EXTRA THE MAGAZINE OF TECHNOLOGY INTEGRATION

Modems Put to the Ultimate Test



SQL Server Roundup PAGE 217

Coming Soon: Ultrafast Megamemory Chips PAGE 185

PORTABL

A STATE OF THE STA

Special Report on Mobile Computing

- **5** Hottest Technologies
- 5 High-End Laptops
- **Essential Travel Tips**

WINDOWS 95 HITS THE ROAD PAGE 145



P120 MILLENNIA PLUS

- · Intel 120MHz Pentium processor
- · 256K Micron SyncBurst" cache
- PCI 32-bit Fast SCSI-2 controller
- 6X SCSI-2 CD-ROM drive, 3.5" floppy
- · SoundBlaster 16 stereo sound & speakers
- PCI 64-bit graphics accelerator (2MB)
- . Tool-Free mini-tower or desktop
- Microsoft Mouse, 101-key keyboard
- MS-DOS & Windows for Workgroups
- . MS Office Pro 4.3 & MS Bookshelf CDs
- A 16MB EDO RAM 1GB SCSI-2 hard drive

• 15"Micron 15FGx, 1280NI, .28mm

B • 32MB EDO RAM • 2GB SCSI-2 hard drive

• 15"Micron 15FGx, 1280Nl, .28mm

\$4.999 (Business Lease \$170/month)

- C 64MB EDO RAM 4GB SCSI-2 hard drive • 17"Micron 17FGx, 1280NI, .28mm

⁵**6,** 999 (Business Lease \$229/month)

D • 128MB EDO RAM • 9GB SCSI-2 hard drive

• 21"Micron 21FGx, 1600NI, .28mm

\$12,999 (Business Lease \$417/month) *Option D not available in desktop

P75 PowerStation

- Intel 75MHz Pentium processor
- · 256K write-back cache, Flash BIOS
- . 4X EIDE CD-ROM drive, 3.5" floppy
- SoundBlaster 16 stereo sound & speakers . PCI 64-bit graphics accelerator (2MB)
- · Tool-Free mini-tower or desktop
- Microsoft Mouse, 101-key keyboard
- MS-DOS & Windows for Workgroups
- A 8MB RAM 540MB EIDE hard drive
 - 15"Micron 15FGx, 1028Ni, .28mm
 - MS Works Multimedia CD

\$1.999 (Business Lease \$71/month)

- B 16MB RAM 850MB EIDE hard drive
 - 15"Micron 15FGx, 1280NI, .28mm
 - MS Office Pro 4.3 & Bookshelf CDs

52,499 (Business Lease \$89/month)

- C 32MB RAM 1.2GB EIDE hard drive
 - 17"Micron 17FGx, 1280NI, .28mm
 - MS Office Pro 4.3 & Bookshelf CDs

53.499 (Business Lease \$119(month)

With 90MHz Pentium Processor..... add \$100 With 100MHz Pentium Processor.... add \$200 With 120MHz Pentium Processor.... add \$500

4100 MAGNUM

- Intel 100MHz-DX4 processor
- 256K write-back cache, Flash BIOS
- . 2X EIDE CD-ROM drive, 3.5" floppy
- . SoundBlaster 16 stereo sound & speakers
- PCI 64-bit graphics accelerator (1MB)
- . Tool-Free mini-tower or desktop
- Microsoft Mouse, 101-key keyboard
- . MS-DOS & Windows for Workgroups

With 66MHz-DX2 Processor.....subtract \$100

- A BMB RAM 540MB EIDE hard drive
 - 14"Micron 14FG, 1024NI, .28mm
 - MS Works Multimedia CD

- \$1.699 (Business Lease \$61/month) B • 16MB RAM • 850MB EIDE hard drive
- - . 15"Micron 15FGx, 1280Nl, .28mm
 - MS Office Pro 4.3 & Bookshelf CDs

299 (Business Lease \$82/month)



June 28, 1994 POWERSTATION



POWERSTATION



April 26 1994 MAGNUM



February 1995 P90 HOME MPC



May 16, 1995 P90 HOME MPC



STELLAR PERFORMANCE

icron is fast becoming the industry leader in personal computer design, engineering and manufacturing. Right off the production line, Micron PCs are receiving awards and critical acclaim for exceptional quality, record-breaking speed and dependable performance. Everywhere you turn, Fortune 500 corporations, mid-size businesses and home offices are discovering the benefits of buying a Micron computer.

P90 PowerServer SMP

- Intel 90MHz Pentium processor
- Dual Pentium SMP ZIF sockets
- 512K write-back cache, Flash BIOS
- Slots: 5 EISA, 2 PCI, 1 EISA/PCI
- PCI 32-bit Fast SCSI-2 controller 4X SCSI-2 CD ROM drive, 3.5" floppy
- PCI 64-bit graphics accelerator (2MB)
- · Full-size tower with 10 drive bays
- Microsoft Mouse, 101-key keyboard
- . MS DOS & Windows for Workgroups
- A 16MB RAM 1GB SCSI-2 hard drive 14"Micron 14FG, 1024NI, .28mm
 - \$3,699 (Business Leuse \$126/month)
- B 32MB RAM 2GB SCSI-2 hard drive • 15"Micron 15FGx, 1280Nl, .28mm
 - 54.999 (Business Lease \$170/month)
- C 64MB RAM 4GB SCSI-2 hard drive 17"Micron 17FGx, 1280NI, .28mm

56.999 (Business Lease \$229/month)

With second 90MHz Pentium processor...add \$799 With Windows NT Workstation CD.....add \$249



THE P75 HOME MPC

Your Best Value in Pentium Power

· indows applications have revolutionized the way you do business and even the way you live. From presentation packages and word processing to financial management and spreadsheets, increased computing speed and processing power have become basic necessities. But when it comes to action-packed games and dynamic multi-media CDs, you need more than just horsepower. Micron's new Pentiumbased Home MPC is your answer! And since it's from Micron, it's not only loaded with power, it's also packed with standard features that the other guys add as extras, which usually means more money. Only the Micron Home MPC features 8MB of Micron RAM; a superfast 4X EIDE CD-ROM drive; and full exploding stereo sound with the

pentium

SoundBlaster™ 16, including speakers and a lightning-quick 14.4 Fax/Modem. And when you buy a Micron Home MPC, you'll also receive Bob, Microsoft's new user-friendly home interface. Microsoft Bob includes eight essential applications--including a calendar, letter writer, checkbook, and more--that are linked together to make everyday computing tasks easy. With Bob around, you'll really get things done! Plus you'll receive fullyloaded Microsoft software packages, Intuit's Quicken Deluxe Edition

CD and trial subscriptions for CompuServe, America OnLine and Prodigy . . . all in one super Micron deal! Virtually redefine your definition of value. Cut loose with some real excitement and check out the Micron Home MPC.

- Intel® 75MHz Pentium® Processor
- 256K Write-back cache, Flash BIOS
- 8MB RAM, 540MB EIDE hard drive
- · 4X EIDE CD-ROM drive, 3.5" floppy
- 14.4 Fax/Modern & WinFax Lite
- PCI 64-bit graphics accelerator (2MB)
- 14" Micron14FG.1024NI,.28mm

- · Tool-Free mini-tower or desktop
- Microsoft Mouse, 101-key keyboard
- . MS-DOS & Windows for Workgroups CD
- Microsoft Scenes: Sports Extremes
- SoundBlaster™ 16 stereo sound & speakers Microsoft Bob CD; Microsoft Works Multimedia CD; Microsoft Encarta 95 CD: Quicken Deluxe Edition CD; Microsoft Dangerous Creatures CD; Microsoft Golf Multimedia CD; Trial Subscriptions for CompuServe, America OnLine & Prodigy.

90MHz Processor..... add \$100 100MHz Processor..... add \$200 120MHz Processor..... add \$500

Micron Electronics, Inc., 900 E. Karcher Road, Nampa, ID 83687 • Mon-Fri 7AM-8PM Sat 8AM-5PM (MT) 208-463-3434 • FAX 208-463-3424 • Purchase Order FAX 208-467-5384
















February 1995 P90 HOME MPC

EXCLUSIVELY FROM MICRON

- · Next Day Shipping on Selected Systems
- · 30-Day Money Back Guarantee
- · One-Year Express Parts Replacement
- · Lifetime Toll-Free Technical Support

800-233-7027

isotronics. Inc. All rights reserved. All prices and specifications subset to change wireout notice Microri Electronics, Inc. cannot be responsible for christians and/or shrows in hypotraphy. Male Your Piece With The Laudier' is a service mark of Microri Discretion, Inc. Inst., their traybe, and Perhotum are repleased statements of the Windows Open are instalments of All-Discretion Accounts. All other company yearbands are trained and investments and All-Discretion. All other company yearbands are responsed invested and company of the control of the Company of the Compa





THE MICRON MILLENNIA

"A full 20% faster than the average 100-MHz Pentium system."

PC World, February, 1995

nd the reason for the Micron P100 Millennia's amazing ability to far outperform the competition? It's exclusive dynamic combination of Micron's EDO

> (Extended Data Out) Memory and SyncBurst™ cache, providing signifi-

cant performance gains over previous memory

designs. Once again, another major break-

through in computing

performance innovation from Micron, the technology leader.

- Intel[™] 100MHz Pentium[™] processor
- 256K Micron SyncBurst cache
- 4X EIDE CD-ROM drive, 3.5" floppy drive
- · SoundBlaster 16 with stereo speakers
- · PCI 64-bit graphics accelerator (2MB)
- · Tool-free desktop or mini-tower
- · Microsoft Mouse, 101-key keyboard
- MS-DOS® & Windows® for Workgroups
- A 8MB Micron EDO RAM, 540MB EIDE hard drive
 - 15" Micron 15FGx, 1280Nl, .28mm.
 - · Microsoft Works Multimedia CD

- B 16MB Micron EDO RAM, 850MB EIDE hard drive
 - 15" Micron 15FGx, 1280NI, .28mm
 - Microsoft Office Pro 4.3 CD & MS Bookshelf CD

52,999 (Business Lease \$107/month)

- C 32MB Micron EDO RAM, 1.2GB EIDE hard drive
 - 17" Micron 17FGx, 1280NI, .28mm
 - Microsoft Office Pro 4.3 CD & MS Bookshelf CD

3.999

"The Millennia is nothing short of the best all-around PC available in the Market today."

PC Magazine, April 25, 1995



PC Magazine Labs tested the leading 100-MHz

Pentium desktop systems and

pentium

came up with an "unprecedented

Winstone 95 benchmark score for the Micron P100 Millennia." The numbers clearly tell the Micron story.



WILL YOUR DEVELOPMENT TEAM TAKE TWO STEPS FORWARD TODAY,

You navigate along a thin line to keep your team on track. Fortunately, for C++ developers creating applications for Windows 95. Microsoft has a core set of products designed to ensure they continue moving ahead.

Microsoft* Visual C++* development system provides a powerful, tightly integrated tool set, including the Microsoft Foundation Class Library: 70,000 lines of pre-built, pre-tested code to give you a head start. With a



SOLKEZHE MANAK





latest tools and technologies, including new features for Windows 95 development. That way, you'll get applications up and running quickly, and Windows 95 ready. Microsoft SourceSafe and Microsoft Test keep your team on course. SourceSafe's project oriented approach to source code control promotes code reuse and management of multiple releases for development teams of any size. Test is an automated testing tool which evaluates applications throughout the development process. Together, they help find errors and regressions while identifying where the problems occurred. By joining the Microsoft Developers Network,

Visual C++ Subscription, three times a year you're updated on the

via quarterly CDs, you'll get in-depth technical information, operating systems and software development kits. Right there on your desktop. More importantly, you can get a pre-release version of Windows 95 operating system and the SDK. These are just part of our line of products and services designed for your development teams. For more information and the name of your local reseller, call 1-800-719-5577, Dept. NYY. We'll even send you a free CD, the Microsoft Roadmap to Developer's Products & Services, describing all our tools and programs. That way, you'll have everything you need to continue in the only direction you want to go.





ONE STEP BACKWARDS?



VOI.-20, NO.6

News & Views

PC MICROPROCESSORS

Chip Wars Drive Down PC Prices......24

Four companies are scrambling to put the fastest and least expensive x86 chip in your PC.

POWERPC

PowerPC Tidal Wave25

Apple and IBM will make major PowerPC-related announcements this spring and summer.

COLOR PRINTING

Color Encroaches on the Desktop28

Over the next several years, technological advances will accelerate the use of color printers.

INTERNET ACCESS

Service Providers Consolidate.....28

The day of numerous, tiny Internet service providers may be over.

PC CONNECTIVITY

Vendors Ride Bus to Better Telephony30

A new Universal Serial Bus that supports a maximum 12 Mbps could become a standard PC connector.

PC PROCESSORS

Pentium OverDrive = Moderate Upgrade30

Intel's Pentium OverDrive processor puts a rocket in your socket, but the upgrade has a 32-bit 486-style I/O busnot the 64-bit bus of a Pentium.

PROGRAMMING

Getting Clear About Fuzzy34

What do pension plans, elevators, and battery chargers have in common? Each is an application of fuzzy logic.

WINDOWS 95

Windows 95 Sees Better Future36

Microsoft says it will work to improve Windows' support for blind users.

NEW PRODUCTS

What's New258

A 100-MHz Pentium notebook; wireless infrared printers from Hewlett-Packard; the latest version of Dr. Solomon's Anti-Virus Toolkit; and more.

Special Report on Mobile Computing

From Here to Mobility BY ANDY REINHARD	100
What you need to know to hit the road.	107
Radio Days BY SALVATORE SALAMON Wireless links are expanding—despite obstacles.	101
Color to Go BY CHRIS CHIN YOCK	115
New display technologies are oming, but LCD is still king.	

Brainy, Brawny Batteries BY GIL BASSAK Battery technology for mobile computing is a crossroads.

You Can Take It with You BY JON UDELL What does Windows 95 offer users on the go?

PDAs Bounce Back BY MICHAEL NADEAU PDAs finally evolve into useful business tools for mobile workers.

159 Tales from the Trip BY RAPHAEL NEEDLEMAN Tips from a savvy world traveler on geiring on-line from anywhere.

167 Red-Hot 100-MHz Portable Peutium BY REX BALDAZO The Tadpole P1000 -screaming performance.

169 RISC for the Road BY DOUG TAMASANIS The SparcBook 3XP-a workstation to go.

Portable Multimedia BY REX BALDAZO Satellite Pro-power at the right price.

Pentium Power Without Sticker Shock BY DAVE ANDREWS 173 The Eurocom-lots of features but short battery life.

Not Flashier, but Faster BY DAVE ANDREWS 175 The Globalist 250P good for heavy-duty number crunching.

Features

THE VIRTUAL OFFICE



Solutions Focus: Not Lost in Space

BY MICHAEL NADEAU Xerox's entire sales force will soon be working from virtual offices.

OPERATING SYSTEMS



Apple's New Operating System

BY TOM THOMPSON Apple completely redesigned its Mac OS to provide a growth path to the future while continuing to support the existing software base.

INTERNET PAYMENT SYSTEMS



Cash on the Wirehead

BY ANDREW SINGLETON Six new payment systems aim to move your money across the Internet.

APPLICATIONS DEVELOPMENT

Windows for Control Freaks

BY PETER D. VARHOL QNX's Photon kernel gives developers welcome control over windowing programming.

NETWORKS



Break Up Your Network

BY BRETT HUSSELBAUGH Dividing your network into two or more parts can boost performance.

Reviews



PAGE 201

131


145

147

171

71

83





State of the Art



MEMORY TECHNOLOGIES

Improve Your Memory

BY RUSSELL KAY Sorting out the dazzling variety of new memory technologies.

Fast, Smart RAM

187 BY PETER WAYNER New chips and new technologies compete for adoption.

Flash Memory Looks Bright 188 Is Cache Losing Its Cachet? 191 192

One Machine, Many RAMs



NETWORKING

Local Air Networks

201

BY REX BALDAZO With roaming-enabled access points, good range, and high throughput, WaveLAN-based wireless LANs are the ones to beat in North America.

MOBILE COMMUNICATIONS

Oracle Hits the Road

207

BY PETER WAYNER Oracle In Motion's agents take over network housekeeping chores, virtually eliminating the wireless performance penalty.

DATA STORAGE

Hands-Off Backup

209

BY BILL LAWRENCE Bundled with Palindrome's automated backup software for NetWare, HP's SureStore Tape 12000e DAT Autoloader can provide weeks of unattended network backup.

FLOWCHART SOFTWARE

Better Business Processes

211

BY DAVID ESSEX Scitor links an optimized spreadsheet to flowchart objects, and—presto!—an instant simulator that most anyone can use.

SPREADSHEETS

Wanted: A Good OS/2 Spreadsheet

215

BY DANIEL GASTEIGER In the OS/2 spreadsheet duel, upstart Mesa 2 has the advanced GUI features that 1-2-3 should have.

SQL FRONT ENDS

Software Roundup: Simple SQL

217

BY CHARLES VOGT SQL front-end tools empower nontechnical managers to make informed, timecritical decisions by giving them direct access to client/server databases.

V.34 MODEMS

Lab Report:

32 V.34 Modems Answer the Call

224

V.34 represents the best and fastest modem technology available today.

NSTL evaluates 32 state-of-the-market modems for throughput, reliability, robustness, and compatibility.

External V.34 Modems-226

How We Tested-228

Pick a PC Card-230

Honorable Mentions-232



WALNUT

More Memory in Less Space 197

BY RICK COOK

Packing silicon wafers tightly creates compact new memory devices



Core Technologies

CPUS

BY BRUCE FAUST Digital's three CPUs bring powerful possibilities

erful possibilities to desktop and workstation systems design.



OPERATING SYSTEMS

BY STANFORD DIEHL Windows 95 will eventually unify a series of graphics APIs—for

video, games, and 3-D using a new set of devicedriver interfaces.



PROGRAMMING

BY TOM THOMPSON This month, we write the event handlers and the dispatch table.

NETWORKS

BY SALVATORE SALAMONE Remote monitoring lets managers

find out what's going on at distant locations.



Opinions

Pournelle:

Privacy and Liberty249

BY JERRY POURNELLE Visits to AAAS's annual meeting and Washington, D.C., highlight Jerry's month.

Books and CD-ROMs: Word Overload, Information Shortage45

BY ANDY REINHARDT, RICH FRIEDMAN, AND EDMUND X. DEJESUS Four books about the Internet, CD-ROMs for learning applications and computer languages, and Nicholas Negroponte's experiences, insights, and predictions.

Commentary:

ATM = After the Millennium . . 306

BY TED PRINCE Don't blindly jump on the bandwagon.

Blasts from the Past41

Highlights from two decades of covering the PC revolution.

Letters on Intel's P6, Microsoft's Bob, and personal quandaries.

Demographic Section ... 200DM 1

Reader Survey.......196

READER SERVICE

Editorial Index by Company
Alphabetical Index to Advertisers
Index to Advertisers by

Product Category 302
Inquiry Reply Cards 170A, 300A
BUYER'S GUIDE 267

Mail Order Hardware/Software Showcase Buyer's Mart

PROGRAM LISTINGS

From BIX: Join "listings/frombyte95" and select the appropriate subarea (i.e., "jun95").

From the UUNET:ftp to ftp.uu.net, log on as "anonymous," and enter your user ID as your password. Type "cd/published/byte" and type "DIR." Files appear in subdirectories by month.

From the BYTE BBS at 1200-9600 bps: Dial (603) 924-9820 and follow the instructions at the prompt.

BYTE (ISSN 0360-5290) is published monthly by Mo-Graw-Hill, Inc. U.S. subscriber rate \$29.85 per year. In Canada and Mexico, \$34.95 per year. European surface mal subscriptions \$60, airmall \$80. Non-European surface subscriptions are payable in U.S. funds that can be drawn on a U.S. bank. Single copies \$3.50 in the U.S., \$4.50 in Canada. Executive, Editorial, Circulation, and Advertising Offices. One Phoenix Mill Lane, Peierborough, NH 03458. Second-class postage paid at Peterborough, NH, and additional malling offices. Postage paid at Winnipeg, Manitoba. Canada Post International Publications Mail Product Seles Agreement No. 246492. Registered for GST as McGrav-Hill, Inc., GST #123075673. Printed in the United States of America. Postmaster: Send address changes and fulfillment questions to BYTE Subscriptions, P.O. Box 552, Hightstown, NJ 08520.

BYTE Contents by Platform

This page presents the articles in this issue according to computing platform.

DOS/WINDOWS

Chip Wars Drive Down PC Prices24

Intel faces strong competition in the x86 arena as four companies scramble to put the fastest x86 chip in your PC in 1996.

An Early Survey of Windows 95 Plans34

BYTE polls vendors on their Windows 95 applications plans.

Windows 95 Sees Better Future......36

Microsoft plans to implement new features in its API and DLL library to improve the support that Windows 95 provides to blind users.

Code Talk: ANSI C Anywhere.....36

If you'd like to start building a library of ANSI C compilers, Archelon's Retargetable Software Tools deserves a look.

You Can Take It with You145

Windows 95, with its Plug and Play support, is built to meet the needs of mobile users.

Oracle Hits the Road207

Oracle In Motion lets you use standard Windows tools to write agents that provide wireless clients with the help they need to overcome client/server bottlenecks.

Better Business Processes......211

A slick flowchart module and cleverly linked spreadsheets make Process Charter for Windows a simulation program for Everymanager.

Roundup: Simple SQL.....217

NSTL evaluates four Windows tools for accessing SQL client/server databases. An easy-to-use Windows front end insulates the business manager from the complexities of the database structure and from having to learn SQL.

Windows 95 Graphics Architecture241

Microsoft has revamped the graphics architecture of Windows with multimedia in mind.

0\$/2

Wanted: A Good OS/2 Spreadsheet.....215

There is a void in the OS/2 spreadsheet market, and Lotus 1-2-3 for OS/2 and Athena Design's Mesa 2 would fill it nicely if only they were rolled up into one program.

MACINTOSH

PowerPC Tidal Wave25

This spring or summer Apple plans to introduce three PCI-based Macs.

Here's a technical description of Copland, the newest version of Apple's OS.

Adding Apple Events to Your Mac Application: Part 2......243

This final installment shows you how to write the event handlers and the dispatch table.

UNIX

Code Talk: ANSI C Anywhere.....36

With Archelon's Retargetable Software Tools you can start building a library of ANSI C compilers for yourself. It's available for DOS, Unix System V release 4.2, HP-UX, SunOS, and Solaris 2.x.

RISC for the Road......169

Tadpole has squeezed a SPARC workstation into a 7-pound travel package.

A Universal Desktop for Unix......200DM 3

CDE (Common Desktop Environment) is a new GUI standard for all Unix systems.

Tickle Makes Developers Smile ... 2000 M 11

Tel (Tool Command Language) and its common extensions offer a combination of features that developers find hard to resist.

Oracle Hits the Road207

Unix-based agents provide the server agent component of Oracle In Motion, an impressive toolkit that largely eliminates the throughput problems of wireless database access.

NETWORKS

Break Up Your Network.....91

Are your workstations standing in line to access the network? Tune your network for peak efficiency.

Radio Days.....107

The move to wireless WANs promises to be much more manageable thanks to expanded service offerings and new development tools.

Local Air Networks......201

We test two wireless LAN systems with roaming-enabled Ethernet access points for connecting notebooks to your LAN.

Hands-Off Backup209

Hewlett-Packard's SureStore Tape 12000e LABS for Novell provides welcome relief for offsite administrators. It combines an autoloading DDS-2 tape drive with highly automated backup software from Palindrome.

Simplifying Remote Management245

While RMon (remote monitoring) has great potential to help network administrators better manage remote-site LANs, RMon technology is not meant to replace traditional protocol analyzers. Here's why.

Commentary: ATM = After the Millennium306

Don't just blindly jump on the ATM (asynchronous transfer mode) bandwagon.

Index

Adaptive computing	36
Alpha	239
Books	45
Color displays	115
Color printers	28
Communications 107,	
161, 201, 207,	
CPUs 24, 25, 30,	
Databases 207,	
Flowcharting	
Fuzzy logic	
Handwriting recognition	
Internet 28, 40, 71,	
Macintosh25, 59,	
Memory185, 187,	
Mobile computing25,	
100, 107, 115, 131, 147, 161, 167, 169,	
173, 175, 201,	
Modems	224
Multimedia	241
Networks91, 107, 2	102
207, 209, 245,	
Operating systems59, 83,	
0\$/2 25,	
Pentium24, 30, 167,	
PDAs	
Portables25, 50, 167,	
171, 173, 175,	
PowerPC	
Programming34, 36,	83,
200DM 11,	243
RAM185, 187,	
RISC 169,	239
Serial buses	30
Smart batteries	
Spreadsheets	
SQL front ends	
Storage	
Unix36, 169, 200DM 200DM 3, 200DM	
200DM 3, 200DM 23,	
Windows 34, 36, 145 2	
211, 217,	
Wireless107, 201,	207
World Wide Web40	, 71

RECORDABLE CD!

The Pinnacle RCD-1000 is 3 Drives in 1

- 1. 2X Recordable CD System
- 2. Double-speed CD-ROM Player
- 3. Tape Backup Replacement



The RCD-1000[™] is virtually 3 drives in 1 - making it the ultimate storage device for only \$1695.

With the flexibility of Pinnacle's RCD-1000, the applications are endless. As a CD Recorder, the RCD-1000 allows you to master your own CD that can be easily transported across town - or to the end of the world. As a double-speed CD-ROM player, it can read virtually thousands of educa-



RCD Backup Utility

tional, multimedia or audio CDs. And, with Pinnacle's own Backup Software Utility, you can now replace your tape drive with a system that provides a more reliable solution and fast random access to your data for only

\$19 per disc, or **3 cents** per megabyte. Each disc holds 650 MB of data, audio and video storage.

The RCD-1000 is perfect for creating and mastering your own multimedia titles, interactive games, or even mixing your own audio CD of your favorite tunes. You can backup accounting records, business plans, charts and graphs, or confidential information on CDs for decades - safe and secure.


The RCD-1000 system is simply the best way to store, archive, distribute and create information. Best of all, it's now affordable - it's recordable!

Pinnacle Micro. The Optical Storage Leader.

All Trademarks and Registered Trademarks of Their Respective Consts

TO REACH THE PINNACLE CALL: 800-553-7070


Tel: 714-789-3000 Fax: 714-789-3150 Circle 81 on Inquiry Card (RESELLERS: 82).






© 1995 Intel Corporation. †Source: (COMP®: A Simplified Measure Of Relative Microprocessor Performance, Intel Corporation, 1992.††The 63-MHz Pentium OverDrive processor for most 50-MHz and 25-MHz land 33-MHz intel486 CPU-based systems will be available later in the year. *Other trade names referenced are the property of their respective holders.

Run your PC faster with the Over





The OverDrive processor is a single-chip CPU upgrade that maximizes the performance of most Intel486" processor-based PCs.



OverDrive processors boost CPU performance as much as 343%, making your software run much faster.



The family of IntelDX2," IntelDX4, and newly released Pentium OverDrive processors gives you several affordable upgrade options for your i486™ CPU-based PC-each of them fully software compatible.



Contact your PC reseller for more information about OverDrive processors, or dial the FaxBack* service at 1-800-525-3019, document #9306. Or call 1-800-538-3373, ext. 295.

Drive processor upgrade. intel.



Take This Job and Lug It





Portable computers: liberator or leash? It depends on how you use them. Don't forget the off switch!

Every now and then when I find myself among new acquaintances,

somebody will lob me a variation of The Question. And they look to me for The Answer.

Question: What are computers going to be like in the future? My close friends know better than to ask me this, because The Question is really an entrée to wax philosophical about all sorts of silly, far-out notions that get most technologists rolling their eyes and looking about for more grounded conversation. Without a time frame to anchor my discussion, you see, when I talk about the future I start talking about implanted computers, discussion databases that the global population has access to (the Internet doesn't yet count), and stuff like that. Out-there concepts, spawned from the time frittered away in youth reading bad science fiction (unlike, say, Mr. Pournelle's good science fiction).

Except we're closer to the future than we might want to admit. None of us at BYTE have implanted computers, but the way some of us take our portables anywhere, they might as well be. Dave Egan, our publisher, has been known to take his portable on vacation, although he had to hide it in his luggage so his daughter didn't see it. (She hates "that thing" that diverts his attention from family.)

My portable goes with me everywhere, too (well, almost everywhere). People ask me how I can do this, and if I ever leave my work behind. They're making a fundamental mistake: The computer is not work. It's just a tool that gives me access to other people. Some of these people are the ones I work with, but others are my friends, my family, and people I haven't even met in person.

Yes, portable technology can act as nothing more than a cruel leash back to the office. But fortunately, every piece of technology we cover in BYTE has an off switch, which we should be liberal in using during moments that require our undivided attention to other, nontechnological matters,

Off switch or no, I'm totally hooked on portable technology. I'm never in one place long enough to get comfortable with wired-in devices (desktop computers, corded phones, cable television), and furthermore, I like being able to compose my E-mail to friends and acquaintances from the relative seclusion of an airline seat (to those of you who've gotten E-mail replies from me, I thank you for sparing me from the tedium of yet another showing of Angels in the Outfield).

And beyond the connectedness I get from having my portable with me everywhere, I get a kick out of portable computers because they highlight real engineering prowess. I like the innovative IBM 701C (Butterfly) keyboard. I like the ridiculous three-way door that covers the PC Card slots on the new Toshiba Satellite Pro (the machine on this month's cover). I even like the little LED bar graph on the Dell Lattitude's lithium-ion batteries—a feature I doubt anyone needs, because one battery is plenty for most users, and you can't see the LEDs when the battery is installed in the computer. You just don't see this kind of attention to detail on many desktop computers, where the engineers have sheet metal to spare and where cleverness of packaging is not a major design consideration.

But to be fair, here's what still nags me about this class of technology: Mostly, it's too bloody expensive. I want all computer users to experience the freedom of untethered technology, but I don't recommend portables for most individuals because you have to give up too many features to take your show on the road. And furthermore, you don't have access to quite the same bandwidth of a hard-wired desktop connection from the Motel 6 in Sedona, Arizona. But that's an infrastructure problem—I'm sure if most hotels had ISDN connections, there would be a flood of ISDN PC Cards on the market.

For those of you who understand the all-consuming addiction to mobile technology, you'll be happy to see our Special Report on Mobile Computing. In addition to covering some of the hottest portable products you can buy today, we also look at what Windows 95 means to the mobile user, and we examine several technologies you can't get for any price, just yet. It all starts on page 97.

Rof Mahr

RAPHAEL NEEDLEMAN, EDITOR IN CHIEF (rafe@bix.com)

Choose the pointing device that works best for you:



TECHNICAL SPECIFICATIONS

- · SL-ENHANCED INTEL 486 DX4-75MHZ OR 486 DX4-100MHZ
- 5.9 LBS, DUAL-SCAN COLOR OR 6.1 LBS, OPTIONAL ACTIVE MATRIX COLOR
- DIMENSIONS: 11.3" X 8.5" X 1.7"
- 4MB, 8MB OR 16MB RAM (EXPANDABLE UP TO 32MB)
- 3.5" 1.44MB DISKETTE DRIVE
- REMOVABLE 260 TO 810 HDD
- VGA DUAL-SCAN COLOR OR OPTIONAL ACTIVE MATRIX. MONOCHROME UNITS ALSO AVAILABLE
- 10-CELL NIMH BATTERY & AC PACK
- SUSPEND/RESUME FEATURE
- TWO TYPE II OR ONE TYPE III PCMCIA SLOT
- INTEGRATED DUAL-BUTTON POINTING STICK, OPTION-AL DUAL-BUTTON 19MM TRACKBALL OR OPTIONAL DUAL-BUTTON TOUCHPAD
- PARALLEL, SERIAL AND PS/2 PORTS
- . 1MB VIDEO MEMORY WITH EXTERNAL VGA PORT
- LCD FLINCTION INDICATOR PANEL
- 14.4 SEND/RECEIVE FAXVOICE/DATA MODEM OPTIONAL
- INTERNAL AUDIO OPTIONAL
- DOCKING STATION OPTIONAL

WinBook XP AT \$1999, IT'S THE ONLY SPEEDING ΓICKET YOU'L NJOY PAYING.

51999

- Intel 486 DX4-100MHz
 - 10.3" dual-scan color display
 - · 4MB RAM/340MB HD
 - . Intel 486 DX4-100MHz

 - · Active matrix color display 16MB RAM/810MB HD
 - 14.4 Fax Modem
 - · DOS and Windows

S Comparable savings on all other WinBook XPs—from our base models to notebooks for the power user. For current pricing and configurations, call 1-800-468-0712.


















February-April 1995, Windhook XP DX4/75 B/125 Dual-scan color







We use only genuine Intel



COMPUTER CORPORATION

Call us today, toll-free 1-800-468-071

Monday-Friday, 8am-9pm EST • Saturday, 9am-4pm Use your VISA, Discover Card, MasterCard, personal check or P.O. with credit approval. U.S. sales only. 30-day unconditional money-back guarantee from date of purchase.

a subsidiary of Micro Electronics, Inc. and fraderwink of Micros Electronics, Inc. The letest install logge is a traderwink of the Intell Corporation. All other belowments and inquisited tradersaria are properly of their expective compositions. All prices and specifications are subject to change without notice or enligation. Prices do not unclude shapping



Introducing the new Compaq ProLinea

normally associated with the word "value." And in creating the latest Compaq ProLinea, we built on that premise—by taking the original apart.

We examined it from top to bottom, from the inside out, looking for ways to improve it. Looking to see what new technologies we could add.

THE LATEST PROLINEA HAS AN

IMPRESSIVE SAVE FEATURE: IT'LL SAVE YOU MONEY,

SAVE YOU TIME, AND SAVE YOUR SANITY.

In the end, we came up with more than a few improvements. Making ProLinea even harder to distinguish from more expensive machines. The fastest processors. Easy upgradability. Simplified maintenance. Features that make it easy to live with on the day you install it, and for years to come.

COMPAQ

It all raises ProLinea to a completely new level. (Of course you'll still find the price within reach.) And that should certainly put your mind at ease.



Traditionally, the phrase "better value" has always meant someone's cut corners to give you a better price. At Compaq, however, we like to take a different approach.

The result is the new Compaq ProLinea: a family of computers that not only offers affordable prices, it pushes technology many steps ahead. Twelve, to be exact:

Number One. Our first improvement is something you'll notice before you

expansion cards and peripherals. And guess what: Compaq has already enhanced this standard with our new TriFlex/PCI architecture—which is built into every ProLinea model.

Number Three. The PCI architecture also boosts the performance of the graphics subsystem. So even if you're working with general productivity applications like word processors and spreadsheets, you can enjoy a crisp, responsive high-resolution display. If

new QuadSpeed drive (along with Enhanced Business Audio). This gives you faster access to the rich and vast references available on CD-ROM today, from national directories to archives of business publications.

Number Six. However large a hard drive may be, there are those who take it as a personal challenge to fill it up. With the new ProLinea PCs, however, we're determined to make that as difficult as possible. You can

LIKE MOST PC BUYERS, YOU'RE

"BETTER VALUE," SO WE'VE CLEVERLY

even buy a ProLinea. You get to choose the processor you want—from very fast (486DX2/50MHz) to blindingly fast (Pentium/100MHz). This way, you don't have to buy more performance than you really need. And it's designed so that you can upgrade whenever you want.

Number Two. You may be familiar with the new standard bus architecture called PCI. Basically, it improves upon the previous technology by expanding the data path to 32 bits and radically speeding the flow of information to

your uses demand more, select 586-class models are now available with higher-performance VRAM graphics.

[Number Four. Forgive the acronyms, but there's also a PCI local bus IDE interface. This not only pays off in improved disk performance, but it supports up to four storage devices. Which means you can easily add another hard drive, tape backup or CD-ROM drive when needed.

Number Five. As long as we're on the subject of CD-ROM, multimedia ProLinea models now come with our

choose a configuration with a disk capacity of 270MB, 420MB or 720MB. Any of which should put you well ahead of your burgeoning files.

Number Seven. ProLinea comes with 8MB or 16MB of RAM, depending on the model. And you can easily expand it to 136MB or 192MB—enough to take advantage of new 32-bit operating systems, run several programs at once and work with spreadsheets the size of Madison Square Garden.

[Number Eight.] ProLinea is filled with features designed to make your life



easier. It's not only pre-loaded with an extensive online help system and automated setup software, it now has redesigned documentation to help you quickly pinpoint information. It's also optimized to run new operating systems like Windows 95, which will make your future computing easier still. Every model supports the Plugand-Play standard that will bring a new simplicity to the process of adding expansion cards. (If you add

Number Ten. The new ProLinea PCs have been designed so you can get inside without any special tools. The system board slides out to accept extra memory or a processor upgrade. The hard drive cage swings out so you can swap disks without reaching into inaccessible, finger-bruising areas. And when you snap in a new Compaq hard drive, you won't have to configure any enigmatic jumpers. When you connect the

become necessary, installing them will be no more difficult than running a software utility and clicking a few buttons on the screen.

Number Twelve. And what about the environment? Using a ProLinea won't by itself repair the ozone layer, but it's certainly a step in the right direction. For the sake of the atmosphere—and everyone who breathes it—our PC manufacturing process is completely CFC-free. And every model is now

PROBABLY SICK OF HEARING

DISGUISED IT AS 12 IMPROVEMENTS.

a new network interface card, for example, ProLinca will sense the change and automatically reconfigure its software to support it.)

Number Nine. You decide exactly how expandable you want your ProLinea to be. You can select a desktop model with three expansion slots and three expansion bays or a model with four of each. Or you can choose a five-slot, five-bay mini-tower model that offers maximum expandability without taking up too

much of your space.

cables, the settings have the good sense to take care of themselves.


Number Eleven. The ProLinea system board now incorporates Flash ROM technology. That means basic system ROM can be updated without major PC surgery. If future system updates

Energy Star-compliant, which means less wasted energy for the planet and less wasted money on your power bill.

These are the improvements that define our approach to value. (We think you'll agree, it's a lot more rewarding than cutting corners.)

In fact, our new ProLinea does an excellent job of expressing a core

belief at Compaq: That is, the smartest way to build better value is to build a better computer.



should ever



EDITOR IN CHIEF Raphael Needleman

Editor in Chief's Assistant: Linda Higgins

EXECUTIVE EDITORS Rich Friedman, Jon Udell

CHIEF OF CORRESPONDENTS Dennis Barker

ANAGING EDITOR Lauren Stickler Thompson

ASSISTANT MANAGING EDITOR Tom Kevan

ough: News Editors: David L. Andrews, Martha Hicks News Editor: Salvatore Salamone San Mateo/West Cor

Senior Editor: Tom Halfhill Senior Editor: Rainer Mauth

PRODUCT REVIEWS

Director: Stanford Diehl Senior Technical Editors: Rick Grehan, Douglas Tamasanis Technical Editors: Rex Baldazo. Selinda Chiquoine, David Essex, Dave Rowell Reviews Assistant: Lisa O'Nell

STATE OF THE ART/FEATURES

Features Editor: John Montgomery Senior Editor: Alan Joch Technical Editor: Russell Kay Senior Editor: Edmund X. DeJesus

SENIOR TECHNICAL EDITOR At Large: Tom Thompson

SENIOR RESEARCHER Rowland Aertker

ASSOCIATE TECHNICAL EDITORS Susan Colwell, Cathy Kingery, Mark Reynolds, Warren Williamson

SENIOR CONTRIBUTING EDITOR Jerry Poumelle

CONTRIBUTING EDITORS Stephen Apiki, Dick Pountain

CONSULTING EDITORS Nicholas Baran, Raymond GA Côté, Trevor Marshall, Stan Miastkowski, Barry Nance, Roberta Poumeile Ellen Ullman, Peter Wayner

EDITORIAL ASSISTANTS

Tammy Grenier, June Sheldon

DESIGN

Associate Design Director/Design & Photography: Sharon Price Associate Design Director/Graphics: Joseph A. Gallagher Production Manager: David R. Anderson Desktop Prepress Manager: Virginia Reardon Designers: Barbara Busenbark, Jan Muller, Donna Sweeney Design Assistant: Cindy Sands

FINANCE AND OPERATIONS
Director: Claudia Flowers

ADVERTISING PRODUCTION Advertising Production Manager: Linda Fluhr Senior Advertising Services Representative: Lyda Clark Advertising Services Representatives: Dale J. Christensen, Karen Cilley, Rod Holden Operations Assistant: Lisa Jo Steiner Advertising Graphics Manager: Susan Kingsbury Graphics Production Coordinator: Christa Patterson

Senior Financial Analyst: Kathleen Deguise Systems Administrator: Peggy Dunham Junior Financial Analyst: Diane Henry Production Assistant/Purchaser: Agnes Perry

MARKETING AND PLANNING

Director: L. Bradley Browne Administrative Assistant: Aria Neukam Marketing Communications Manager: Rob Mitchell Marketing Art Director: Stephanie Warnesky Market Research Manager: William Zhao Copyrights Manager: Faith Kluntz Assistant Manager, Marketing Events: Carol Sanchioni

CERCULATION

Director: Glyn Standen Subscriptions Manager: Paul Ruess Assistant Manager, Lynn Legasse Subscription Source Specialist: Christine Tourgee Newsstand Manager: Vicki Weston Assistant Manager: Karen Desroches Back Issues: Jill Wood Direct Accounts Coordinator: Ellen Dunbar PUBLISHER David B. Egan

Publisher's Assistant: Donna Nordlund

ADVERTISING SALES NATIONAL ACCOUNTS Jon Sawyer (603) 924-2665

NEW ENGLAND Sanford L. Fibish (817) 860-6344 Merle Model (617) 860-6221

MID-ATLANTIC Michael Feinberg (212) 512-4811 Susan Rastellini (617) 860-6265

Mary Ann Goulding (404) 843-4782 Margot Swanson (803) 924-2651

MIDWEST Lori Silverstein (614) 899-4908 Ed Ware (603) 924-2664

SOUTHWEST, ROCKY MOUNTAIN Jennifer Walker (214) 701-8496 Kevin Lary (603) 924-2527

SOUTH PACIFIC Beth Dudas (714) 753-8140 Mark Speros (714) 753-8140 Brad Dixon (803) 924-2574

NORTH PACIFIC Roy J. Kops (415) 513-6861 Susan Werner (415) 513-6862 James Bail (603) 924-2662

INSIDE ADVERTISING SALES Director of Sales Operations: Diane Lieberman Assistants: Susan Monkton, Vivian Bernier

THE BUYER'S MART (1 × 2) and HARDWARE/SOFTWARE SHOWCASE Ellen Perham (603) 924-2598 Mark Stone (603) 924-2695

REGIONAL Brian Higgins (603) 924-2596

Brian Higgins (603) 924-2596

EURO-DECK Joseph Mabe (603) 924-2533

INTERNATIONAL ADVERTISING SALES STAFF See listing on page 301.

PERSONNEL Human Resources Administrator: Patricia Burke Assistant: Fran Wozniak Receptionist: Beverly Goss

MEMBER SERVICES MANAGER

Kevin Plankey

How to Contact the Editors

we welcome your questions, comments, complaints, kudos, and submissions.

MAIN OFFICE: One Phoenix Mill Lane, Peterborough, NH 03458, (603) 924-9281.

San Mateo: 1900 O'Farrell St. #200, San Mateo, CA 94403, (415) 513-6912.

New York: 1221 Avenue of the Americas, New York: 10200 (43) 551 313-691. York, NY 10020, (212) 512-3175. Lexington: 24 Hartwell Ave., Lexington, MA

We welcome your questions, comments.

02173, (617) 863-5100. ozrina, (617) 663-5160.

dermanny-Europe: Liebigsträsse No. 19, 60323 Frankfurt, Germany, +49 69 7140 7123.

ELECTRONIC MAIL: On BIX, send to "editors." All BYTE editors and columnists also have individual

mailboxes on BIX for easy access.

MCI: 250-0135 BYTE Magazine. Many editors also have individual MCI addresses in their

own name.

others: Many editors also are reachable through unnet, AppleLink, CompuServe, and numerous other services.

U.S. fax: Editorial: (603) 924-2550 Advertising: (603) 924-7507 U.K. fax: +44 171 495 6734

Authors: We welcome article proposals and submissions. Unacceptable manuscripts will be returned if accompanied by sufficient re-turn postage. Not responsible for lost manu-

turn postage. Not responsible for now scripts or photos.

Vendern: We welcome news of your new products; please call the News department or the BYTE Lab at the earliest possible date.

We cannot be responsible for unsolicited another teamples. product samples.

ARTICLE REPRINTS:

Arritical Reproductions on customized reprints of BYTE articles, contact Susan Monkton, reprints manager, at (603) 924-2618. (Minimum quantity: 500.)

Subscription Customer Service

Helde U.S. (800) 232-BYTE; outside U.S. +609 426 7676, International subscribers +609 426 7676. International subscribers may also contact our international customer service facility in Galway, Ireland, by calling +353 91 752792 or via lax. +353 91 752 793. For a new subscription, (800) 257-9402 U.S. only, or write to BYTE Subscription Dept., P.O. Box 555, Hightstown, NJ 08520. Subscriptions are \$29.95 for one year, \$54.95 for two years, and \$74.95 for three years in the U.S. and its pressessions. In Canada and Mavico years, and \$74.95 for three years in the U.S. and its possessions. In Canada and Mexico, \$34.95 for one year, \$64.95 for two years, \$67.95 for three years. In Europe, £42 (US\$60) for fast surface delivery, £55 (US\$80) for airdelivery. Non-European countries US\$60 for surface mail, or US\$85 for air mail. Single copy price is \$3.95 in the U.S. and its possessions, \$4.95 in Canada. Foreign subscriptions and sales should be remitted in U.S. funds drawn on a U.S. bank. Please allow six to eight weeks for delivery of first issue. for delivery of first issue.

PHOTOCOPY PERMISSION:
Where necessary, permission is granted by
the copyright owner for those registered with
the Copyright Clearance Center (CCC), 222 the Copyright Clearance Center (CCC), 222 Rosewood Dr., Danvers, MA 01923, to photocopy any article herein for personal or internal reference use only for the flat fee of \$1.50 per copy of the article or any part thereof. Correspondence and payment should be sent directly to the CCC, 222 Rosewood Dr., Danvers, MA 01923. Specify ISSN 0360-5280, \$1.50. Copying done for other than personal or internal reference use without the permission of McGraw-Hill, Inc., is prohibited. Requests for special permission or bulk orders. quests for special permission or bulk orders should be addressed to Faith Kluntz, copy-rights manager, (603) 924-2525. BYTE is available in microform from University Microfilms International, 300 North Zeeb Rd., Dept. PR, Ann Arbor, MI 48106 or 18 Bedford Row, Dept. PR, London, WC1R 4EJ, U.K.

In Copyright © 1995 by McGraw-Hill, Winc. All rights reserved. BYTE and BYTE are registered trademarks of McGraw-Hill, Inc. Trademark registered in the United States Patent and Trademark Office.



Member Audit Bureau of Circulation

BIX Interactive On-line Service

MANAGING EDITOR Christine Taylor

EXCHANGE EDITORS

Amiga Exchange: Joanne Dow Entertainment and Leisure Exchange: Rich Taylor IBM Exchange: Barry Nance Programmers Exchange: Bill Nicholls Professionals Exchange: David Reed Tolerry Exchange: Jerry Pournelle WIX Exchange: Karen Kenworthy Writers Exchange: Wayne Rash Jr.


TECHNICAL ASSOCIATE

BIX, owned and operated by Delphi Internet Services Corporation, is a worldwide, low-cost, on-line information service featuring industry news, downloadable software, powerful electronic mail, previews of upcoming BYTE articles, the full text of published issues of BYTE, and source and/or executable code for BYTE benchmarks and noncommercial software mentioned in feature articles. BIX also offers unmatched "conferences" on virtually every computer-related topic imaginable, where you can share information with thousands of other computer pros. To subscribe via modem, set your communications software to full duplex, 7 bits, even parity, 1 stop bit, and then call (800) 695-4882 or (617) 491-5410, or telenet to x25.bix.com and type "bix" at the USERNAME prompt. At the Name? prompt, type bix.ville. For more information, call (800) 695-4775 or (617) 354-4137 (voice); send a fax to (617) 491-6642; or send Internet mail to info@bix.com.

Founder: James H. McGraw (1860–1948).

Chalman and Chief Executive Officer: Joseph L. Dionne; President and Chief Operating Officer: Harold W. McGraw III; Executive Vice President, General Counsel, and Secretary: Robert N. Landes; Executive Vice President and Chief Financial Officer: Robert J. Bahash; Senior Vice President, Treasury Operations: Frank D. Penglase; Executive Vice President, Publication Services: Norbert Schumacher.

When you raid extra for SGSI but rerformance, this probably masn't what you had in mind.



Aeronics' new 68 Position IDC 0.025 Pitch Ribbon Cable Terminator will give your SCSI bus a boost.

Why does my bus need a boost?

Peripheral devices such as hard drives, CD-ROM drives, scanners, and printers that are interfaced with your computer have connectors manufactured by different companies that are connected to cable made by who-knows-who. Differences in peripheral cabling and connectors create signal impedance mismatches which can cause signalling errors, bottlenecks, and data transmission errors.

Aeronics has the answers.

Aeronics, the originator of Forced Perfect Termination (FPT), has added a new interconnect product to our family of high performance terminators that will drastically improve your SCSI bus



performance. Aeronics' new 68 Position IDC 0.025 Pitch Ribbon Cable Terminator easily clamps onto your ribbon cable with a standard tool and replaces the low performance passive terminators frequently furnished by

peripheral manufacturers. For those active negation drivers that generate higher than normal pull-up voltages that tend to overdrive the SCSI bus, Aeronics has developed the ALT-2ANHC. This new electrical configuration sinks unusual amounts of current due to charged cable capacitance and is available in most of Aeronics' interconnect products.

How does Aeronics boost my bus?

Aeronics' FPT active terminators purposely mismatch impedance higher and lower than the impedance of the transmission line, "forcing" the SCSI bus to operate as if the impedance between the host and peripherals is always matched. Because our terminators provide higher noise immunity, results are seen as improved data integrity, allowing your system to transfer data farther and faster while improving overall SCSI reliability.

Terminate your SCSI bus performance problems once and for all.

Aeronics' advanced terminator technology is available in a broad line of connection and electrical configurations that meet or exceed ANSI SCSI 1, 2, and 3 standards. Our passive, active, FPT, and differential terminators are 100% electrically tested, burned in, and delivered on time. With a minimum MTBF of 87,600 hours (10 years continuous duty), our quality terminators are backed by a limited lifetime warranty.

Aeronics' high performance products leave passive and copycat terminators in the dust. If you want the same performance that high-end OEM SCSI systems have, choose the same terminator from Aeronics and give your bus a boost. Call or fax Aeronics today for the location of the reseller or distributor nearest you.

For off-the-shelf delivery, call TCC at 1-800-TEC CABL (1-800-832-2225).



Turning concepts into reality.

12741 Research Blvd. • Suite 500 • Austin, TX 78759 Tel (512) 258-8040 • Fax (512) 258-8441

Intel's P6

I enjoyed your article "Intel's P6" (April); however, the P6 is not the first chip "intended for large-scale production" with two dies on a single package. That honor goes to the DEC J-11 11/70-on-chip. The J-11 was the first PDP-11 (maybe the first chip of any type) to be able to do register-to-register instructions in one cycle (200 nanoseconds), and it had a four-level pipeline, truly great accomplishments in 1982.

> **Bob Morris** President DSPS Digital Signal Processing, Inc. Carleton University Ottawa, Ontario morris@sce.carleton.ca

I really enjoy the depth to which BYTE explores topics like the P6. I still have a few questions regarding your April Cover Story. On what front-end bus speed (% CPU, % CPU....) does Intel base the P6's performance numbers? Also, I was under the impression that a 100-MHz Pentium really runs at 99 MHz. This would make it easy to use a PLL (phase-locked loop) to create 66 MHz for the main bus. It follows that the P6 would use a 132-MHz clock rate so the main bus would run at 66 or 33 MHz.

> Karl Richards richardk@execpc.com

The P6's I/O (i.e., frontside) bus can be clocked at 1/4, 1/3, or 1/4 of the core speed. The performance estimates from Intel are based on a system that runs internally at 133 MHz and externally at 66 MHz. In other words, 1/2 clock speed. It doesn't make sense to run a 133-MHz P6 at 1/3 or 4-those dividers were included for future P6 chips that will run at faster core speeds. My understanding is that a 100-MHz Pentium actually

runs at 100 MHz, not 99 MHz, and that a 133-MHz P6 runs at 133 MHz, not 132 MHz.

—Tom R. Halfhill

In your April Cover Story you describe the physical dimensions of the current crop of processor chips as "306 mm square." That comes very close to being a foot on a side. We'll

have to redesign all our personal computers just to hold the CPU. This is too much!

Merritt J. Rucher Belen, NM

Intel's

Yes, the size was supposed to be written as "square millimeters," not "millimeters square," but somehow it got trans--Tom R. Halfhill posed.

They're Everywhere

In Tom R. Halfhill's March piece, "The Truth Behind the Pentium Bug," his instructions on how to bruise an integer (page 164) are mind-boggling. I tried the test on several different Pentium machines and they all gave me the binary 10 from the difference of 4.1 and 1.1. When I tried it on our newest Pentium 100, I got the same binary, 10. All our 486 machines gave me 10 as well. I tried a different test I acquired from another magazine and found which systems were using a faulty chip. I wonder if Intel is replacing Pentium chips that are not faulty at all?

> Cesar Quebral Legend23@ix.netcom.com

Integer bruising happens on almost all computers, not just a buggy Pentium. The example I gave was not to reveal whether or not you've got a had Pentium but to demonstrate how integers can get bruised -Tom R. Halfhill on any computer.

Mutant Methods

I found your March Editorial "Mutant Chips," in which you told us not to be overly concerned about the Pentium bug and also implied that we wouldn't want to fly with an airline that was programmed using heuristic methods, to be something of a giant leap from reality. According to published reports, between 40 percent to 60 percent of all pilot-reported faults are

> not corrected at the depot repair shops. These randomly occurring failures (bugs) are generally referred to as CNDs (Can-Not-Duplicates). CND rates usually increase as multiple unrepaired faults accumulate.

> You think we're asking for trouble if we use neural networks; we've got trouble already. If pilots or autopilots rely on the data from the avionics equipment to fly the plane

safely, and half or more of the faults are never fixed, how safe are airplanes really? The diagnostic problem gets worse as avionics become more complex. Complexity demands that we use neural networks and other heuristic methods, if not as the final solution, then to help us figure out a more direct means to sort it all out.

> **Brent Sorenson** Vice President, Research and Development Universal Synaptics Ogden, UT

Bob's Neighborhood

You make the point that users raised on Bob will have certain expectations ("The In-Your-Face Interface" April Editorial). I suggest that users raised on Bob won't have the required skills to figure out realworld applications. Like most kids' toys, Bob will end up forgotten in the closet after several weeks. In fact, if we ever do see users raised on Bob, they will most likely resemble people raised on TV: semiliterate, jingle-humming boobs.

> Sieve Rogers scrogers@winternet.com

People said the same thing about GUIs, the same thing about the command line, and for all I know, the same thing about assembly code. ("The only real way to use computers is in binary!") Computers should be easier to use, not harder. While Bob doesn't suit my personal tastes in interfaces (nor yours, obviously), if it forces programmers to write easier-to-use applications, I'm all for it. -Rafe Needleman

I was browsing in a software store and asked about the huge, rotating yellow smiley face that bore the words "Bob is coming." The clerk was quick to hand me a brochure, and after I read it, I became irked, annoyed, and dismayed—but not surprised. Bob wasn't an intelligent agent. Bob was a kiddie interface that makes an ATM look smart. Many successful GUIs obscure the real functionality of the computer from people in an effort to make the computer easier to use. That is appropriate when the OS can do the bookkeeping, but Windows can't. Windows programs put files in the \windows\system directory without telling you, and when you delete the applications, those files are still there.

We want to hear from you. Address correspondence to Letters Editor, BYTE, One Phoenix Mill Lane, Peterborough, NH 03458; or you can send E-mail via the Internet or BIX to editors@bix.com. Letters may be edited.

Exabyte's new 8mm XL tape drive is the perfect union of capacity and reliability.

- 14 GB capacity compressed
- 1 MB/second transfer rate compressed
- 160,000 hours MTBF
- Extended-length media
- Half-high form factor
- Backward compatible



8mm

4mm

Quarter-Inch

Libraries

Media

Accommodating the new eXtended Length data-grade 8mm media, the EXB-8505XL 8mm tape drive can store 14 gigabytes of compressed data per cartridge. That's nearly two times the capacity of DDS-2 drives. Using the EXATAPE™ 160XL data cartridge with its Recognition System assures users of the highest data reliability and integrity. And this new high-capacity tape drive can read the tapes written on any of the 750,000 8mm tape drives in use today. Seamless integration with

latest-generation 8mm libraries protects your 8mm investment.

EXABYTE

Fogmore information on the Exsbyte office nearest you: The Netherlands (31) 3403-51347,

Germany (49) 69-95-925-220, France, (33) 1-69-41-16-17; United Kingdom, (44) 492-874855; Asia, (65) 271-5531.

C1995 Exabyte Corporation. Estabyte is a registered trademark and "Exabyte is Everywhere" and EXATAPE are trademarks of Exabyte Corporation.

Circle 70 on Inquiry Car (RESELLERS: 71)



The last thing we need is another layer between naive users and Windows.

Stuart M. Pomerantz smpst19@vms.cis.pitt.edu

BYTE: Real Food for Real People

I'm reading my April issue and I am grateful! This issue exemplifies why I originally subscribed to BYTE: articles with meat that explain the technology. I was afraid you were going to become another reviews magazine. BYTE is back to what it was for me: a solid education.

> John Astreides IS Support Systems Gottlieb Memorial Hospital jastra@ais.net

Moving the Rock

Your March Cover Story "New Ways to

Learn" was an excellently conceived, brilliantly executed article and a great service to those of us who slug it out in the process of moving the rock. I need to present the keynote to the umbrella organization for educational leadership here in Maryland, and my task will be much easier by the ripple in the information environment your article caused. I can just hear all the people in school systems

ripping it out, digesting it, and including your ideas in their reports.

Jack N. Cole Columbia, MD

When I read "New Ways to Learn," I was looking for something we could actually

apply in the real world of reduced educational budgets. All I found were expensive alternatives to human contact. Andy Reinhardt suggests the federal government pick up the \$8 billion to \$9 billion cost to connect every school in America to the data highway. Connecting the schools is only the initial cost. Does anyone really believe that this country will provide such funding when most classrooms don't even have a telephone?

Martin Hittelman Los Angeles, CA MartyHitt@aol.com

Proud Papa

I have been a contract engineer for Rockwell-Collins for almost seven years. One of the systems I gave heart and soul to was the Rockwell Pro2000 series described in Christine White's "On-Road, On-Time, and On-Line" in the April issue.

It's rare when the big magazines, such as BYTE, cover such systems, and the gratification I felt while reading about the Pro2000 caught me by surprise. Thank you very much.

Greg Shelton Cedar Rapids, Iowa glshelton@bix.com

The Real Compatibility Test

Sal Salamone's "Compatibility Testing" (April), in which he explains his method of discerning personality traits by studying a person's computer habits, had me a little worried about my software-shopping husband, until I realized there is a fatal flaw in

Sal's theory. In order to determine how a potential mate will treat you, it's necessary to observe his interaction with his hardware, which is, after all, the core of the relationship.

When I applied this new approach, my fears were gone. Although he has had numerous opportunities to purchase a Pentium, my man stands by his Dell 486. All that software he buys for it indicates that he is generous and giving to those he loves. If he feels his computer should have the biggest, highest-quality hard drive, by the same token he'll feel his wife should have the newest, nicest luxury car. If the way he treats his computer is indicative of how he'll treat me, I'll be happy for a long time.

Debi Littlejohn Shinder Little Rock, AR MsSgt@aol.com

Throwing Eunuchs Out of Windows

Just wondering: If I replace Windows with Unix, have I been emasculated or defenestrated?

> David Boyce Cambridge, MA dsb@id.wing.net

FIXES

"The 1995 Readers' Choice Awards" (May) should have listed Intergraph's fax number (page 80) as (203) 730-9441.

In the April Lab Report, the AST Ascentia 910N notebook has a maximum internal screen resolution of 640 by 480 pixels by 65,536 colors, not 600 by 800 pixels by 256 colors, as stated on page 199. The WinBook XP notebook now supports a maximum hard drive capacity of 800 MB, secondary cache is not yet available for it, and its optional 16-bit sound card plugs into the notebook, not into the docking station.

Rick Grehan's E-mail address (April, page 216) is rick_g@bix.com. Lenny Tropiano's E-mail address (page 74) is lenny@icus.com, and his URL is http://www.icus.com/~lenny/.

In the "Whatever Happened to..." article concerning diamond-film hard disks (April, page 32), there is an error in the gender designation of Ainissa Ramirez. He should be she. ■

COMING UP IN JULY

- INTERNET SPECIAL REPORT
 How your company can succeed on the Internet.
- DATABASES

We describe how to perform parallel querying of distributed, enterprise-wide databases.

APPLE'S NEWEST OS

Apple delays Copland to give it a HAL (hardware abstraction layer).

33 ETHERNET SWITCHING HUBS

We test midrange Ethernet "store and forward" plus "cut-through" switching hubs for workgroups and find the most efficient performers.

UNINSTALLERS

BYTE looks at uninstallers for Windows-what they do well and not so well.

Highly informative business applications can also be greatlooking.




OK

ab





Developers: Bet You Haven't Seen Xbase Like This Before.



it's easy to create
Windows applications
with browsers and
editors that design
and manage the
process.

DD

CICL BIOLOGING MAINE BIXTERS



Ission-Critical
Client/Server
costlory-based
Code Compiler
Fully Scalable
lass Libraries
OOP
CA-Visua

With CA-Visual Objects, developing new applications is a sight to behold. Because for the first time, the ease of use of visual programming has been married with the fourth generation power of an Xbase language.

The result is the only application development tool that gives you full object orientation,
GUI support and client/server architectures combined with existing
Xbase technologies and databases.

And the advanced technology of Visual Objects doesn't stop there. The object orientation includes inheritance, polymorphism and encapsulation. And the native code compiler boasts an engine that drives Visual Objects at a speed that's as fast as lightning. Plus, the repository-based interactive development environment includes class browsers, painters, editors and prebuilt classes.

For More Information, Call 1-800-225-5224, Dept. 14500.

Phone soon for a closer look at new CA-Visual Objects. Your mind won't believe what your eyes are seeing.

New CA-Visual Objects

© Computer Associates International, Inc., Islandia, NY 11788-7000. "Light Lib" graphic developed in conjunction with Light Lib" Business for Windows from DFL Software, Inc. All products referenced herein are trademarks of their respective companies.





An Idea Without A Customer Goes Nowhere Fast.

At Advanced Micro Devices, we champion ideas that make a difference to our customers. Ideas we transform into microchips that make personal computer and communications systems perform better. As a result, AMD is Number 1 or 2 in the world in every market where we compete-microprocessors, communications circuits, flash memories and programmable logic. Which is not to say we've crossed the finish line. The truth is, we win when our customers win. That's why our 12,000 people worldwide are racing into the future with a singular vision: If it's a good idea. If it makes a difference. Run with it.



1-800-222-9323 Internet: http://www.amd.com

Circle 124 on Inquiry Card (RESELLERS: 125).

News&Views


PC MICROPROCESSORS

Chip Wars Drive Down PC Prices

Prices will drop and performance will increase as Intel faces some strong competition in the x86 microprocessor arena

TOM R. HALFHILL

our companies are currently scrambling to put the fastest x86 chip in your PC in 1996, and the competition will make lightning-fast PCs more affordable than ever. Even as Intel (Santa Clara, CA) prepares to introduce its sixth-generation CPU this year (see "Intel's P6," April BYTE), the company is also working on fifth-generation Pentiums that will run as fast as 180 MHz. Meanwhile, Intel announced a 120-MHz Pentium in March. Faster versions of the Pentium processor—clocked at 133 and 150 MHz—are promised for the end of this year. In addition, Pentiums clocked at speeds of 166 and 180 MHz are expected to follow in 1996.



A 180-MHz Pentium would likely break the 200-SPECint92 barrier and deliver roughly the same performance as the first P6, which is clocked at 133 MHz. By then, of course, the P6 will be faster, too. Intel plans to introduce a 166-MHz P6 in early 1996 and a 231-MHz version later next year. That would yield an estimated top end of about 350 SPECint92, which would boost the P6 into the stratosphere of the fastest RISC chips.

Leading the charge among Intel's rivals is NexGen (Milpitas, CA), which won a great deal of credibility last year by shipping its first Pentium-class x86-compatible processor, the Nx586. (Compaq recently announced it will use NexGen chips in future PCs.) NexGen says it will match the performance of Intel's 120- and 133-MHz Pentiums by midyear, when it delivers P120 and P133 versions of the Nx586.

NexGen's P120 chip will actually be clocked at about 112 MHz, and the P133 at about 124 MHz, but their performance will be comparable to that of the slightly faster Pentium chips, due to the NexGen chips' more efficient microarchitectures. NexGen's strategy is to match the Pentium's performance while undercutting Intel's prices. The Nx586 currently costs about 13 percent to 20 percent less than comparable Pentium versions.

NexGen's Nx686, a sixthgeneration design, will compete head-to-head with Intel's P6. NexGen says it will introduce the still-secret Nx686 "in the same time frame" as the first shipments of the P6, which are anticipated for late this year. According to NexGen, the Nx686 will match or exceed the P6's performance.

Cyrix (Richardson, TX), another x86 contender, hopes to release by midvear the M1. a 100-MHz x86 chip that promises to deliver 30 percent to 50 percent more performance than a Pentium running at the same clock speed. Cyrix says that a 120-MHz version of the M1. slated for release at the end of this year, will be followed by a 133-MHz chip in early 1996. If Cyrix can meet those goalsits delivery schedules have already slipped-the M1's performance at 133 MHz should reach 200 SPECint92, which is comparable to the performance of the 133-MHz P6 and the 180-MHz Pentium.

Intel's largest x86 competitor, Advanced Micro Devices (Sunnyvale, CA), promises to ship its K5 processor in early 1996. Like the Cyrix M1, AMD's K5 is estimated to be at least 30 percent faster than a Pentium running at the same

clock speed. The K5 will debut at 100 MHz; a 150-MHz version will follow. The 150-MHz K5 should easily exceed 200 SPECint92 and compete well against Intel's 133-MHz P6 and 180-MHz Pentium. AMD says that later in 1996 it will unveil the K6, a sixth-generation x86 processor that will attain 300 SPECint92—performance comparable to that of a 200-MHz P6.

Recent history is a good bellwether of how fast system prices will drop due to all these manufacturing improvements: Pentium systems fell below \$2000 about twice as fast as 486 systems did after the 486 processor was introduced. It's likely that sixth-generation x86 performance will be affordable by 1997.

CHIPS TO DIE FOR

New fabrication plants and process technologies that shrink processor dies allow the development of chips that run faster and at lower voltages without overheating. Smaller dies also let fabricators squeeze more chips onto a silicon wafer, thereby increasing yields and slashing costs.

Intel is already moving the 120-MHz Pentlum chip onto its next-generation 0.35-micron process. Faster Pentiums will be manufactured on this process, too. Slower 60- to 100-MHz Pentiums (and some 120-MHz chips) will still use the older 0.8- and 0.6-micron technologies.

The only other x86 maker that has its own fabrication plants is AMD. Cyrix and NexGen subcontract their manufacturing to other chip makers (Cyrix and NexGen both subcontract with IBM Microelectronics, and Cyrix also deals with SGS Thomson). Intel designed the P6 to run at higher clock speeds to exploit the company's advantages in fab capacity and process technology.

To match Intel's clock speeds, AMD Is working hard to catch up with Intel and move its K5 onto a similar 0.35-micron process. "We're moving to 0.35 so fast that there will possibly be a mix of both [0.5- and 0.35-micron] parts at first," says Drew Dutton, AMD's strategic marketing manager. "In fact, depending on the timing, we may go entirely with 0.35."

NexGen's Nx586 is manufactured on IBM's 0.5-micron process but isn't optimized for it. NexGen hopes to optimize the design and shrink the Nx586 from 192 square millimeters to 118 mm² by midyear so that the chip will run as fast as Intel's 120- and 133-MHz Pentiums. NexGen says it will move the Nx586 onto IBM's 0.35-micron process late this year, which will reduce the die further and allow clock speeds of over 150 MHz. The Nx686 will probably appear on this process as well.

Cyrix-faces the biggest manufacturing challenge. The 100-MHz M1 will debut on IBM's 0.65-micron process, yielding a monstrous die of 394 mm², which is larger than that of any general-purpose CPU. Yields will be so low that analysts wonder how Cyrix will make a profit on the chip. Cyrix says it will decrease the die size to 225 mm² later this year by using five layers of metal instead of three. In early 1996, the M1 will go on another diet, reducing to a much-more-competitive 169 mm² by migrating to IBM's 0.5-micron process. This will also enable clock speeds of over 133 MHz.

—T.R.H.

POWERPC

PowerPC Tidal Wave

his spring and summer, Apple, IBM, and other companies will introduce the first Macs based on the PCI (Peripheral Component Interconnect) bus, the first PowerPC-based ThinkPad, and new PowerPC systems from IBM. In addition, PC manufacturers and peripheral makers will announce their entry into the Power Mac market. Farther out on the horizon is IBM's OS/2 for PowerPC, which is not expected to ship until later this year.

Apple will reportedly introduce three PCI-based Macs, code-named the Tsunami, the TNT, and the Nitro. Apple declined to comment on the systems, but sources say the Tsunami will represent the high end of PCI-based systems and will target high-end desktop publishing and 3-D applications.

With Apple's move to PCI, the options that users will have for third-party graphics accelerator boards should increase. Apple is reportedly developing its own PCI-based graphics accelerator board, but the company will be joined by several others, including Radius and well-known PC peripheral card makers, such as Matrox.

"Power Mac users will get a more competitive mix of products to choose from," says Mary Ellen Power, communications manager for Matrox (Dorval, Quebec, Canada). Matrox's new Millenium board for the Mac will offer QuickTime video, QuickDraw 3D, and graphics hardware acceleration and, like the PC version, will use the new Window RAM memory. Power says that a 2-MB version of the card will cost "under \$500."

The fact that these companies are entering the Mac market at the same time as the debut of Apple's PCI Macs is no coincidence. Vendors say they were already preparing PCI cards for the PC market, and adapting their cards for PCI Macs requires much fewer resources than redesigning for an entirely different bus, such as NuBus. "People are looking at the Mac market to make a little more money," Matrox's Power says. "Doing it without PCI would have required a total redesign." With PCI, the modifications required to bring a card over to the Mac, such as writing a new BIOS, are minor, vendors say. Other companies, including ATI Technologies and Diamond, also plan on introducing new add-in cards for the Mac.

Also, sources say that IBM was expected to introduce in late May a number of high-end PowerPC-based desktops for the business market, using a mixture of PowerPC 601 and 604 chips running at 100 MHz or higher. Because OS/2 for PowerPC is not expected to ship until later this year, the systems will ship sometime this summer with PowerPC versions of AIX and, perhaps, Windows NT.


POWERPC THINKPADS ARE COMING

In addition to PowerPC desktop systems, IBM was expected to announce in May two PowerPC-based notebooks, both of which will be based on the PowerPC 603E chip running at 100 MHz. The systems, which will look like current ThinkPads, will include a CD-ROM, 16 MB of RAM, a TFT (thin-film transistor) screen, and support for business audio. One version will offer a built-in camera for videoconferencing.

But IBM is stymied by the delay of OS/2 for PowerPC, and it's not certain when Microsoft will release Windows NT 3.51, which will support Alpha, Intel, Mips, and, now, PowerPC processors. In early April, Microsoft told vendors the OS would ship in "four to six weeks," says Mark Landrum, project manager for the new Power-Play line, a series of PowerPC 604-based 100-MHz systems that IPC (Austin, TX) expected to release in May. IPC, which had previously sold only PC clones, says its new PowerPlay systems will target CAD, graphics, as well as other high-end applications.

However, vendors entering the NT PowerPC market must contend with a lack of native NT applications, which can't ship until NT 3.51 ships. "Windows NT 3.51 is on track for Q2 release," says Megan Bliss, lead product manager for Windows NT workstations at Microsoft. "I don't want to try to predict beyond that."

—Dave Andrews



RAM (Random Access Memory)

A bare minimum of 8MB RAM is best — 4MB wasn't enough fast year. To run Windows (and Windows 95) you'll need 8MB. RAM will also increase your battery life and improve system performance. All Liberty and ColorBook² systems come standard with 8MB RAM and are expandable to 20MB or 24MB RAM.

Size and Weight

It's a portable PC — the smaller and the less it weighs, the better!

The Liberty and ColorBook² emerge favorably in both areas.

When you're talking portables, you want the biggest, clearest display possible without adding weight or hiking up the price.

A good way to judge screens is to divide the screen size of the portable by its weight. The Liberty has an incomparable screen sizeto-weight ratio of 2.44. This 10.4-inch screen also gives you 23 percent more active viewing area than a 9.4-inch screen and 53 percent more than an 8.4-inch screen. The Liberty's 10.4-inch and ColorBook2's 10.3-inch screens also give you the best value available in a color display.

Look for between three and four hours of battery life depending on the processor and RAM. Batteries based on nickel metal-hydride (NiMH) or lithium ion will give you the best performance. The Liberty gives you up to four hours or more with power management. And it also allows for upgrading to a lithium ion battery.

The better the included software applications, the more the value of your portable PC increases. Pre-installed on all Gateway portables is Microsoft Works for Windows 3.0 or MS Office Professional 4.3. The OAG® FlightDisk® and World Clock software is also included on all Gateway portables.

You'll need a keyboard that's comfortable for you and that's also easy to use. The Liberty is equipped with a large palm rest, and flipout feet so you can adjust the keyboard angle. Pointing devices vary greatly. Again, find one that's easy for you to work with. Gateway's EZ Point integrated pointer is positioned to be comfortable and easily accessible.

Infrared Technology (16)

Extras such as the Liberty's IR technology add even more value to your portable PC. With it you can take advantage of wireless file transfer — this means transferring files between the Liberty and your desktop (or between two Liberty PCs) without cables!

Service and Warranty

Don't get left out in the cold! When you buy from Gateway 2000, you have dedicated portables technical support for the life of your system. Each system also has a 30-day money-back guarantee.

Now that you have all the facts, go ahead and shop around. Then call one of our friendly sales representatives about the very cool Liberty and ColorBook² portable PCs from Gateway 2000.

O 1995 Gateway 2000, Inc. Goreway 2000, black-and-white spot design, "O" logo and "You've got a friend in the business" slegan are registered trademarks, and ColorBook, "Liberty, EZ Point, and TelePath are trademarks of Gareway 2000, Inc. The Intel Inside Logo and Intel are trademarks or registered trademarks of finel Cosporation. All other brands and product names are trademarks or registered trademarks of their respective companies. All prices and configurations are subject to change without notice or obligation. Prices do not include shapping or applicable sales tax.

GATEWAY 2000® LIBERTY™

- 4.2 Lbs., 10" x 8" x 1.6"
- 10.4" DSTN Color Display
- 1MB Video RAM
- Choice of Desktop IR Receptor or External Floppy Drive
- Intel® 486 DX2 or DX4 Processor
- Instant On
- NiMH Battery & AC Pack
- 2 PCMCIA Type II Slots
- EZ Point™ Integrated Pointer
 Removable Hard Drive
- 78-Key Keyboard
- Parallel, Serial, VGA & PS/2® Ports
- Portable Specific Software
- MS-DOS® 6.22 & WFW 3.11
 Microsoft® Works for Windows™ 3.0 or MS Office Professional 4.3**

LIBERTY DX2-50

10.4" DSTN Color Display, 8MB RAM, 340MB HD, MS Works \$2699

LIBERTY DX4-100

10.4" DSTN Color Display, 8MB RAM, 540MB HD, 256K L2 Cache. MS Works

\$3299

LIBERTY DX4-100 Best Buy

10.4" DSTN Color Display, 24MB RAM, 720MB HD, 256K L2 Cache, TelePath™ 14.4 XJACK® Fax/Modem. Extra Battery, Leather Carrying Case, Desktop IR Receptor, External Floppy Drive, MS Office Professional 4.3* \$4499

LIBERTY PROFESSIONAL PACK

MS Office Professional 4.3, PCMCIA TelePath XJACK 14.4 Fax/Modem, Extra NiMH Battery, Leather Carrying Case \$449

**MS Office Professional 4.3 includes Word, Excel, PowerPoint presentation graphics program, and Access database.

COLORBOOK^{2m}

- 10.3" DSTN Color Display
- Intel 486 DX4 Processor
- 8MB RAM (expandable to 24MB)
- 1.5MB Video RAM (includes 512KB cache
- Removable Hard Drive
- 3.5" Diskette Drive
- Integrated 16-Bit Sound and Speaker
- NiMH Battery & AC Pack
- EZ Point Integrated Pointer
- 2 PCMCIA Type II Stors
- 85-Key Keyboard
- Parallel, Serial, VGA & PS/2 Ports
- MS-DOS 6,22 & WFW 3.11
- MS Works for Windows 3.0 or MS Office Professional 4.3*

■ 5.7 Lbs., 11.65" x 8.5" x 1.77" COLORBOOK² DX4-100

8MB RAM, 340MB HD. MS Works 3.0

\$2999

COLORBOOK DX4-100

Deluxe

8MB RAM, 540MB HD, TelePath 14.4 Fax/Modem. MS Office Professional 4.3**

\$3499

COLORBOOK² DX4-100

Best Buy

16MB RAM, 720MB HD, TelePath 14.4 Fax/Modem.

MS Office Professional 4.3**


\$3999



610 Gateway Drive . P.O. Box 2000 . N. Sioux City, SD 57049-2000 Phone 605-232-2000 • TDD 800-846-1778 • Pax 605-232-2023 FaxBack 800-846-4526 • Component Add-On Sales 800-846-2080 Sales Hours: 7am-10pm Weekdays, 9am-4pm Saturdays (CST)



Toll free from Canada 800-846-3609



COLOR PRINTING

Color Encroaches on the Desktop

echnological advances should accelerate the use of color output in both the home and the office over the next several years. An impressive new color printer from Tektronix (Wilsonville, OR, (800) 835-6100; fax (503) 682-7450), the solidink Phaser 340, successfully addresses many of the problems associated with color printers: color print speed, color quality, plain-paper output, and maintenance. Meanwhile, analysts predict the sales of new color ink-jet printers priced at under \$1000 should more than double in the next three years (see the accompanying chart).

The Phaser 340 (\$4995) prints either black-and-white or color documents at approximately 4 pages per minute (compared to 2 to 3½ ppm for color lasers and about 1 ppm for color ink-jets generating four-color output). It prints on almost any type of paper or transparency film, and Tektronix has increased the 340's resolution to 600 by 300 dpi.


The Phaser 340's performance is due to a combination of Tektronix's solid-ink technology and a new internal print mechanism. Color is applied to a high-speed, rotating metal drum. The drum-rotation speed is then reduced, and color is applied to the paper. The result is vibrant color at high speeds.

Unlike printers such as Hewlett-Packard's Color LaserJet, which makes you maintain separate developer and toner cartridges, you only need to refill the Phaser 340's four solid-ink slots.

Users who print mostly text with occasional spot color may prefer to go with a color laser printer, such as Tektronix's Phaser 540, which offers a rated speed of up to 14 ppm for black-and-white text. However, analysts believe the Phaser 340 is a strong new contender. "I

think it's a viable color laser alternative," says Michael Weiss, president of MWA Consulting (Palo Alto, CA), a printing and imaging consultancy.

Vendors are also preparing a new round of ink-jet printers. HP (Santa Clara, CA, (800) 752-0900; fax (800) 333-1917) will likely introduce in June its new DeskJet 660C, an under-\$500 color printer with print speeds of up to 1.5 ppm in color and 4 ppm in black and white. Also, Canon (Costa Mesa, CA, (800) 848-4123) was scheduled to release in late April the BJC-70, an under-3-pound printer with capabilities similar to those of its BJC-4000, for a street price estimated at \$349. In addition, Lexmark (Lexington, KY) says it will release a slew of new color ink-jets this year. And Epson's (Torrance, CA, (800) 289-3776; fax (310) 782-4212) new Stylus Pro XL color ink-jet will offer better flesh-tone and color-transition printing than the current Stylus. It will also print



IDC predicts that, in terms of units shipped, color inkjet printers will become the most popular color solution for the desktop.

on up to an 11- by 17-inch area.

"People are very conscious of color," says Charles LeCompte, editor of the *Hard Copy Observer* (Newton Highlands, MA). "In perhaps three years, more people will have access to color printing than [those who] don't." —Jon Pepper

INTERNET ACCESS

Service Providers Consolidate

he days of numerous tiny ISPs (Internet service providers) may be ending. Many midsize cities have four or more regional Internet providers, in addition to BBSes that offer Internet services. But observers predict there will soon be a consolidation of these providers.

The first steps toward Internet-provider consolidation have already been made in the U.S. On the national level, for example, on-line service CompuServe (Columbus, OH) recently purchased popular Internet software and service provider Spry (Seattle, WA).

Jeremy Allaire, president of New World Media (Minneapolis, MN), an on-line systems and Internet analysis group, says this buy-out is consistent with the revenue-generating models of major on-line services. With the acquisition of Spry, CompuServe will provide full Internet World Wide Web-based access through its net-

work. "CompuServe bought Spry to acquire the software that they give away for free, but the model remains the same," Allaire says. "They make money [by] selling the user a data line."

Meanwhile, long-distance providers and the regional Bell companies are moving into the Internet market. MCI, for instance, recently rolled out its InternetMCI service. Pacific Bell has announced that, in partnership with CompuServe, Intel, Microsoft, and 3Com, it will offer combined ISDN and Internet services. "I think we'll see the vast majority of users accessing the Net through a small set of providers, in the range of 20," Allaire says. The remainder, he adds, will likely survive by providing expertise and infrastructure to local media companies (i.e., TV or radio stations) or businesses that want to set up Web pages. -Steven J. Vaughan-Nichols (sjvn@access.digex.net)

"All in all, this is a must-have package for anyone serious about C++."

PC Magazine

Watcom C/C++ simplifies and accelerates development of high-performance, multi-platform 16- and 32-bit applications. Watcom C/C++ delivers productivity and performance, combining our state-of-the-art compiler technology with an integrated development environment (IDE) and comprehensive set of tools.

"...target a huge range of 16-bit and 32-bit platforms." PC Magazine

Watcom C/C++ supports development of applications targeting an incredible array of 16- and 32-bit PC platforms including: Windows NT, Win32s, 32-bit extended DOS (with royalty-free DOS extender), OS/2 2.x and Warp, Novell NLM, Windows 3.x, DOS and OS/2 1.x.

"The clear cross-platform leader is Watcom C/C++ ..." PC Magazine

The extensive multi-platform support is amplified by the cross-platform capabilities of the IDE and tools, which enable building applications for a wide range of target environments from any of the host systems. Thus, you can standardize on a single host environment and toolset for application development across a wide range of target systems.

"(Watcom C/C++) is also the clear leader in turning out fast, tight code for a huge number of platforms." PC Magazine

Watcom C/C++ advances C++ optimizer technology with a superscalar optimization strategy which uses "riscification" and instruction scheduling to deliver improved performance on 486 and Pentium processors. The compiler can create a single, high-performance executable which runs on 386, 486 and Pentium processors.

"Its excellent performance and very reasonable \$199 price simply add to the luster." PC Magazine

Find it at CompUSA and Egghead or call 1-800-265-4555

Watcom A Powersoft Company PC CONNECTIVITY

Vendors Ride Bus to Better Telephony

new USB (universal serial bus) that supports a maximum of 12 Mbps could become a standard PC connector next year and eventually eliminate the mess of cables found behind today's PCs.

Like other serial-bus standards, such as Access.bus, Apple's GeoPort, and P1394 (also called FireWire), USB allows you to connect multiple devices through a single connection to a PC. But USB's maximum 12 Mbps makes it better suited for CTI (computer telephony integration) applications than Access.bus, which tops out at 100 Kbps. USB will cost less to implement than P1394, and it's

Serial Buses Compared

STANDARD	PEAK BANDWIDTH
Access.bus	100 Kbps
GeoPort	2 Mbps*
P1394	100-400 Mbps
USB	12 Mbps

backed by Compaq, Digital Equipment, IBM PC Co., Intel, Microsoft, NEC, Northern Telecom, and likely other companies in the future.

The most important aspect of USB is its ability to handle multiple isochronous data streams, which means multiple devices can operate concurrently with guaranteed throughput and data latency. Asynchronous operation is possible for devices that don't require guaranteed bandwidth. USB also permits the hot-plugging of multiple devices, such as modems, telephone switches, CD-ROM drives, multimedia audio devices, and tape backup systems, through a single fourwire connector. The interface supports up to 64 devices (one being the host computer itself).

Automatic-configuration software built into Windows 95 (though not necessarily the first release of Windows 95) will provide Plug and Play functionality for these external devices, allowing slotless, low-profile system designs that can be customized by unsophisticated users. USB's promoters say that laptop computers with USB connectors will easily connect through one port to a future generation of standard desktop peripherals without requiring a docking station.

Compaq, DEC, and IBM say they will support USB in future PCs, and NEC and Northern Telecom plan to build USB support into their future telephone devices. USB backers say the first PCs with built-in USB connectors should appear in early 1996. USB support has been promised for, in addition to Windows 95, Windows NT and IBM's OS/2 Warp.

One advantage that USB has over competing standards is its price. Jim Pappas, USB program manager at Intel (Hillsborough, OR), says future PCI (Peripheral Component Interconnect) chip sets from the company will support USB at no additional cost over that of current chip sets. (Texas Instruments currently sells its P1394 physical-layer and logical-layer chips for a combined price of approximately \$30 each in 1000-unit quantities.) Intel will also make USB chips for peripheral manufacturers. Pappas predicts that USB connectors, which will be made by other companies, will cost system manufacturers a mere 35 cents per PC.

Intel officials say USB will likely coexist with other PC peripherals, such as current keyboards, mice, and serial and parallel ports, but they predict that USB will eventually replace all those ports and their associated wires. "We're quite confident we'll have USB on every computer," Pappas says. "And the way you make something universal is to put it on the motherboard."—Matt Trask

PROCESSOR UPGRADES

Pentium OverDrive = Moderate Upgrade

ntel's Pentium OverDrive processor is a compromise design. It puts a rocket in your socket, all right, but the upgrade socket has a 32-bit, 486-style I/O bus—not the faster, wider, 64-bit bus of a regular Pentium. The resulting bottleneck keeps the Pentium OverDrive from delivering as much performance as you might expect (see the accompanying BYTE benchmark table).

Still, it's faster than a 486, and Intel did a few things to compensate for the narrower bus. For instance, the Pentium Over-Drive has twice as much primary cache as a regular Pentium (32 KB versus 16 KB), optimized cache lines, and a 5-to-2 core-to-bus clock-speed ratio that runs the CPU at 83 MHz in a 33-MHz system or at 63 MHz in a 25-MHz system.

To keep the OverDrive cool—it runs much hotter than a 486—Intel strapped a high-reliability fan on the chip. A small TSR program monitors the fan's rpm rate; if the fan slows down or stops, an error message pops up on the screen, and the CPU throttles back its clock speed to prevent a meltdown.

With a street sticker price of about \$400, the Pentium Over-Drive is a reasonable upgrade if your 486 system is otherwise adequate. You will also spend less time upgrading your office if


Pentium OverDrive Yields Modest Gains

The DOS version of BYTE's Native Mode benchmarks shows the performance of a 25-MHz 486 Zeos Pantera upgraded with a Pentium OverDrive chip to be less than that of a 90-MHz Pentium. The Pantera system we tested had a write-back cache. Intel estimates that 486 systems with write-back caches perform about 15 percent faster than similar systems with write-through caches after they have been upgraded. Many older 486 systems have write-through caches, but Intel says that by the end of this year, most 486 systems will ship with write-back caches.

	ZEOS 25-MHZ	PANTERA WITH PENTIUM OVERDRIVE
	486 PANTERA	
Integer index	.216	.704
FPU index	.135	.618

you've kept good records about whose 486 systems are Pentiumupgradable—and which ones are not. But with prices of fullfledged Pentium systems plunging, you might be better off saving your money for a whole new computer.

—T. R. H.



Now you can connect up to three parallel printers to a single network node.

Your office has all kinds of printers, and all kinds of printer configurations, all of which can change daily. And it's your job to hook them all

NOS Compatibility: Novell NetWare; Microsoft* Windows* 95, Windows NT, Windows for Workgroups, LAN Manager; IBM LAN Server; UNIX*: HP-UX, SunOS, Solaris, IBM AIX, SCO UNIX, Ipd; Apple Ethertalk

Management Support: HP JetAdmin print management software enables consistent installation and management of any HP JetDirect connected printer on the network; up to the network. With a limited number of nodes, that can be a big problem.

Fortunately, there's an easy way out—and in. The new HP JetDirect EX Plus3 print server lets you connect up to three printers to the

supports SNMP-based network management software • Flash memory for easy upgrades

- Multiple protocols with automatic switching
 Three high-performance IEEE 1284 ports
 - 3-year return to HP warranty
 HP JetDirect EX and EX Plus3 print servers support all parallel printers
 HP JetDirect cards support HP printers with I/O slots

network, using only one LAN connection. Best of all, it works with any parallel printer, and supports virtually every network protocol and NOS out there.

For fast faxed information, call 1-800-964-1066.* You'll discover that for every problem, there's a solution. At least when it comes to network printing.



New Back-UPS: \$119 blackouts, brownouts




Just don't have the time for power problems on your PC? Don't worry. They'll always make the time for you. It's not if a power problem will occur, but when. Due to household appliances,

poor wiring, bad weather or even other office equipment, power problems are as inevitable as death and taxes. You can't run, but you can hide, behind APC protection.

That's why we've just introduced new models in our award-winning Back-UPS line, now delivering reliable protection for just \$119.





IN THE NEXT THREE MONTHS, MORE THAN 30,000,000 PCs WILL BE HIT BY POWER PROBLEMS...

Who needs power protection? If you use a computer, you do. A study in a recent PCWeek showed that the largest single cause of data loss is bad power, accounting for almost as much data loss as all other causes combined. Every PC plugged into an outlet is vulnerable. In fact, you have better odds of winning the lottery than of escaping the sting of power problems. One study found a typical PC is hit over 100 times a month, causing keyboard lockups, hard drive damage, and worse.

Simply put, if power problems are the least of your troubles, you've got one chance to keep it that way. You insure your car and home with the best policy you can afford. It just doesn't make sense to leave your PC (which is at far greater statistical risk) vulnerable to loss or damage.

WHY A \$119 APC UPS COSTS LESS THAN A \$9.99 "SURGE PROTECTOR" ...

Contrary to most people's belief, a PC alone already has more protection built into it than a low-end "surge suppressor," which is usually nothing more than a well-packaged extension cord. In other words, going without any protection is just as good as underspending on one of the most important PC decisions you'll make.



And since sags and blackouts represent more than 90% of power problems likely to hit your computer, even quality, highperformance surge suppressors are literally powerless to protect you from data loss.



"Don't take chances. Get the ultimate protection... from APC." -PCWorld

"★ ★ ★ Back-UPS should be standard on every desktop ... effective, affordable, designed to last..." -- PC Computing

"Never been cheaper or more convenient. A UPS can pay for itself the first time it saves vour data." -- MacUser



"The clear winner in price performance... it's unbeatable..." -- PC Magazine UK



O 1995 APC, 132 Furgrounds Rd. W. Kingston, El 02893, Back-UPS & PromyChote, are trademarks of APC. Other trademarks are prompted of those moneys, Successfully to change nethods against

protection against and other trials by fire

More than 3,000,000 satisfied customers count on APC reliability that goes above and beyond the call of duty


After a raging fire which took 18 trucks to subdue, Michael Benolkin, director of the Systems Division at Correa Enterprises, Inc. didn't expect much. "While rummaging through the ashes, we heard something beeping. Our four APC units were still in action, while two UPSes from another brand were history. We're still using these same APC units at our new office location - they still work like a charm! We're impressed with the ruggedness, reliability, and product support offered by APC."



Brian Krause, Network Manager for Goodyear Airship Operations, knows how critical APC protection can be." The night of the All-star game a tornado came through our blimp hanger and took out our roof. Our airships demand absolute communication so I protect our local and remote servers with the most reliable protection I can find: APC. APC's PowerChute software shut our server down in an orderly way... closed out all files nice and neathy. When we reconnected, everything came back up perfectly, without a hitch."



Doug Welch learns his reliability lessons well: "While still a Computer Science student, I was at home preparing a large spreadsheet for a final project when Anchorage experienced an all too common 5+ Richter earthquake. If not for my Back-UPS 400 it would have been back to square one! I'm now the Network Systems Manager at Charter College, in charge of three networks. I learned my UPS lesson well back in my student days. I've never been disappointed with APC and the product has had quite a work out."



Faced with a water main break, Mark Conley, Regional Manager of Novell's remote sales office in Detroit was amazed at APC's reliability. "The APC unit was sitting in an inch and a half of water, working just fine, as though nothing was unusual and we lost no data to this disaster. We've used APC here now for at least four years - more than a dozen units are all around the office, and we're well satisfied, so we were even more impressed to learn that the units are amphibious!"



Trial by Water



Back-UPS Award Winning FEATURES

- Unmatched surge/lightning protection for maximum hardware safety
- Site diagnostics automatically spot missing ground and reversed polarity
- LAN signaling allows simple shutdown with interface kits for automatic data protection (400 and above)
- ► User replaceable, hot swappable batteries insure uptime safe disposal. Batteries will last 3-5 years under normal use.
- ▶\$25,000 lifetime Equipment Protection
- 10 minute runtime with specified applications. For longer runtimes choose next largest unit.

Model	Application	Sugg.List
200 NEW	"Green" PCs	\$119
280 NEW	LAN Nodes	\$139
400	Desktop 486/386 systems	\$199
450	Tower 486/386 systems	\$254
600	CAD/CAM workstations	\$359
900	Longer runtime	\$529
1250	Multiple systems	\$689

That's why you need instantaneous battery backup power from an APC Uninterruptible Power Supply to prevent keyboard lockups, data loss, and crashes. With an APC UPS, you get six times the protection of a high-end surge protector for little more than twice the price. And \$119 is much less expensive than false piece of mind. APC UPSs catry up to a \$25,000 lifetime guarantee against surge damage to your properly connected equipment, and are available to suit any application, from network servers and PCs, to fax and satellite systems.

PROTECT YOURSELF OR KICK YOURSELF...

It's been said that there are two types of computer users: those who have lost data, and those who are about to. Prevent the single largest cause of computer problems and join a fast-growing third category: those who protect their PC's

with the most reliable protection they can buy: APC UPSes. So ask for APC at your favorite reseller. At just \$119 an APC UPS is serious protection no serious computer user should be without.

APC has won more awards for reliability than all other UPS vendors combined...











AMERICAN POWER CONVERSION

Call 800-800-4APC

please reference Dept. A2

Tel: (401)789-5735 Fax: (401)788-2797 Compuserve: GO APCSUPPORT Internet: apctech@apcc.com

France: (+33)1.64.62.59.00

Germany: (+49)89 958 23-5

UK: (+44) 1 753 511 022


Ireland: (+35)391 702000

Latin America: (+1)401.789.5735

Japan: (+83)5295 1988

PROGRAMMING

Getting Clear About Fuzzy



The MathWorks' (Natick, MA, (508) 653-1415; fax (508) 653-2997) **Fuzzy Logic Toolkit** (\$895, available for Macs, Windows, and Unix) combines fuzzy-logic modeling with engineering-design tools that integrate with the company's Matlab technicalcomputing environment and Simulink graphical simulation environment.

hat do pension plans, elevators, and battery chargers all have in common? Each is an important application of fuzzy logic, a style of computing that is slowly and, according to experts, inevitably replacing the binary-based processing now found in many of

the world's applications.

"Any application that's logic-based can be fuzzy-based," says David Brubaker, a fuzzylogic consultant for Huntington Advanced Technology (Menlo Park, CA). "There's more fuzzy logic around than you probably think, from your appliances at home, to the car you drive to work, to the heating system in your building," he says. However, Brubaker adds that many fuzzy-logic designers won't discuss their projects, "either because they don't want to give away any competitive advantage or they are afraid of losing sales if their customers found out."

Such fuzziness about fuzzy logic has stifled the market, according to Bonnie Packert, cofounder and executive vice president of HyperLogic (Escondido, CA), maker of Cubi-Calc, one of the first general-purpose fuzzy-logic-design tools. Like many companies in the business, HyperLogic has experienced slow growth. "I think part of the reason is a lack of exposure for fuzzy, especially in the press," Packert says.

However, Market Intelligence Research (Mountain View, CA) says that worldwide fuzzy-logic revenues were \$2 billion in 1994, a number that will reach \$8 billion by 1998. The research firm also says that U.S. and European companies are now taking an active interest in the field, following successful commercial fuzzy projects in Japan.

Fuzzy logic provides a way for computers to deal with the ambiguities of the real world. Rather than using numbers that are always true or not, fuzzy applications can use numbers that are very true, slightly true, or somewhere in between.

FuziWare (Knoxville, TN, (800) 472-6183 or (615) 588-4144; fax (615) 588-9487) holds a patent on using fuzzy mathematics in a spreadsheet. With the company's FuziCalc product, which can import data from Windows-based spreadsheets, you can create scientific, technical, and financial-projection models that use fuzzy logic.

A simple example of an application of fuzzy arithmetic is revenue forecasting, in which you take historical data, such as a previous year's revenue, and project it for future years using three likely growth rates to derive a triangular fuzzy number. You then project revenue by multiplying the base revenue by (1 + the fuzzy growth rate). "Knowing the relative degree of belief across the range is critical information," says Karl Thorndike, president of FuziWare. "Encapsulating that information into a single fuzzy number keeps you from throwing away information each time you do a calculation."

-Randy Cronk

An Early Survey of Windows 95 Plans

It's starting to look like Microsoft will release Windows 95 this August. BYTE recently polled a number of vendors to gauge their Windows 95 applications plans. The following list is not a comprehensive list of functionality; all the vendors we surveyed were still developing applications, and their feature sets were not all finalized at press time. All vendors will support some element of OLE 2.0, as well as long filenames.

Corel ((613) 728-8200; fax (613) 728-9790)

CorelDraw 6. Offers faster redrawing, multitasking, and multithreading; OLE 2.0 automation; and in-place editing. Has a new presentation module that offers 3-D modeling. Also, CorelCAD, a 3-D CAD package for Windows 95, and 32-bit Corel Ventura 6, which offers support for HTML (Hypertext Markup Language) and SGML (Standard Generalized Markup Language).

Delrina ((800) 268-6082; fax (408) 363-2340)

Rebullt 32-bit versions of WinFax Pro and WinComm Sulte. Both offer background communications without the hiccups. They now support call control through TAPI (telephony API), and unified messaging lets you store fax, E-mail, and voice messages in one mailbox.

Lotus Development ((800) 343-5414 or (617) 577-8500)

Windows 95 version of SmartSuite. Includes OLE 2.0 and Information-sharing among applications, including Notes. Team-collaboration tools in 1:2:3 and WordPro (formerly Ami Pro) let you distribute portions of a spreadsheet or document to colleagues via a LAN, Notes, or E-mail; collect comments and annotations; and consolidate them in your final document.

Micrografx ((800) 765-7859 or (214) 234-1769; fax (214) 994-6477)

Picture Publisher for Windows 95. Offers extensive support for multithreading; is 50 percent faster when working with large files and 200 percent faster when applying filters.

Microsoft ((206) 882-8080)

Windows 95 32-bit versions of Excel, Schedule Plus, Word, and other applications. Single-threaded assembly code for Excel recalculation has been hand-tuned for 32 bits, making it 50 percent faster than before.

Stylus Innovation ((617) 621-9545; fax (617) 621-7862)

Visual Voice 32-bit OLE controls, which are environments for developing computer-telephony applications, such as interactive voice response, text-to-speech, faxback, or voice recognition. These OLE controls can be used in any development environment that supports OLE, such as Access, Delphi, Excel, PowerBuilder, and Visual Basic 4.0.

3D/Eye ((800) 764-5237; fax (607) 257-7335)

TriSpectives 1.0, an affordable 3-D product-design and graphics tool for professionals, combines a CAD engine with a GUI.

WordPerfect

PerfectOffice for Windows 95 (which includes WordPerfect for Windows, Quattro Pro, Presentations, InfoCentral, Envoy, and Group-Wise) will offer full OLE 2.0 support and up to a 60 percent performance improvement in some areas due to 32-bit code, code tuning, and more shared code (and, thus, less hard disk access). Other benefits: Long filenames are supported at the OS level, and OLE drag-and-drop support will break down existing walls among applications.



20,000 of the best highresolution photographs chosen from the

millions submitted to Corel!

Royalty free for use in everything from advertisements to presentations!

\$699.90 Verld's Bast Digital Photo-table book and CD-ROM

- ALSO INCLUDES.

 Corel Visual Database Search for specific images from the 20,000 photographs available using descriptive keywords.
- Full Color Reference Manual -Displays all 20,000 photographs.

OTHER COMPREHENSIVE UTILITIES • Corel Photo CD Lab

- Corel Mosaic Visual File Manager Corel Artview Screen Saver
- Corel CD Audio
- Windows Wallpaper & Ripper
- HIGH RESOLUTION 5 resolutions from 128 X 192 up to 2048 X 3072. Each image is approximately 18 megs (uncompressed).

CD-ROMs

20,000 Photographs

- · COLOR FUNCTIONALITY Grayscale, 16 colors, 256 colors or RGB (24 bit).
- EXPORT FILTERS Windows: TIF, BMP, EPS, PCX or GIF. MacIntosh: TIFF or PICT.
- COMPATIBILITY Can be read by any CD-ROM player (XA support not needed). All photographs are in the Kodak Photo CD format.



Volume Sets: Selected from the Corel

Professional Photos collection on CD-ROM!

CD-ROMs

Individual Titles:

- 100 stunning photographic images on CD-ROM.
- · Hundreds of individual titles available.
- · The world's largest collection of royalty free stock photography images.



1-800-238-4437

Please mention code BSZ

*\$US plus applicable takes



\$ ATTENTION \$ PROFESSIONAL PHOTOGRAPHERS!

tu are a professional profesgraphier framesis ing your photographic published in the wo five retroto CD-SOM collection, resease cell C

1-613-728-0826 ext. 85080



1-613-728-0826 ext. 3080

ADAPTIVE COMPUTING

Windows 95 Sees Better Future

indows has been a mixed blessing for disabled computer users. People who are unable to type on a standard keyboard can benefit from Windows and other GUIs like the Macintosh interface. in which a few keystrokes or mouse-clicks can accomplish many tasks. But for blind or moderately visually impaired users, using Windows with adaptive equipment, such as speech, braille, and screenmagnification systems, can be frustrating. And, due to inconsistent programming methods by Windows software developers and a lack of standards, adaptive equipment that verbalizes important information, such as the current position of the mouse cursor, doesn't always work. Microsoft now says it will work to improve Windows' support for blind users.

One near-term solution in which Microsoft hopes to improve Windows' accessibility is by putting its Access Pack of utilities, which aids disabled users, in the Windows 95 control panel. The Access Pack can provide such assistance as holding and locking the Shift keys, allowing mouse movements via the arrow keys or an external adapted switch, and making the screen flash when the speaker beeps. These utilities make a computer more accessible for users with hearing or other physical disabilities.

The company also plans to improve Windows' support for third-party assistive devices. "We plan to provide extra assistance to independent software developers writing accessibility software, give the developers increased access to low-level technical informa-

tion, and evangelize how to make programs more accessible across the board," says Greg Lowney, a senior program manager in Microsoft's Accessibility and Disabilities Group.

Microsoft also plans to implement new features in its API and DLL library to make Windows 95 more compatible with adaptive hardware and software, A Helper.DLL file, which will be released shortly after Windows 95, will expose system information (e.g., the on-screen location of a menu item) to accessibility products through a supported, documented interface. Further out, Microsoft has other plans. "Our intention is to use the off-screen model [OSM] as the basis of a component architecture to provide access to information on the Windows screen," explains Lowney. In the OSM, a database tracks the data that a Windows application writes to and removes from the computer's screen. A screen-reader program queries the OSM to find out exactly what's on the screen at any given time so that it can reliably report this information to a blind user.

People in the disabled community welcome Microsoft's plans but remain wary. "I am impressed with what Microsoft has agreed to do and to consider," says Paul Schroeder, national program associate for technology and telecommunications at the American Foundation for the Blind (Chicago, IL). "But we must remain vigilant to ensure that they and other companies really commit to making computers more accessible for persons with disabilities." -Joe Lazzaro

CODE TALK RICK GREHAN

ANSI C Anywhere

Some time ago, a fellow BYTE editor loaned me his notes and documents from a conference on how to retarget GCC, the GNU C++ compiler. After spending days poring over the materials, I emerged none the wiser, and simply more jealous of anyone who'd succeeded in building his or her own GCC compiler. Apparently, I didn't have the mental stamina required to accomplish this task.

Then I found out about the Retargetable Software Tools from Archelon (Waterloo, Ontario, Canada, (800) 387-5670). I'll say right up front that Archelon's tools build C compilers, not C++ compilers. Furthermore, the software is not cheap: The starting price is \$3495. But you get a set of tools to construct a C compiler, an assembler, a linker, and a librarian for whatever target processor you wish (provided, of course, that the processor is powerful enough). There's also a preprocessor for the compiler's front end and a peephole optimizer for its back end.

Furthermore, the C compiler is ANSI compatible. Archelon's president, R. Preston Gurd, informed me that the company has verified the output with the Plum-Hall suite.

I spent most of my time with the kit working with the C compiler portion. That meant wading through the CIF (compiler information file). The CIF tells the compiler everything it needs to know about the architecture of the target machine, including available registers, which ones can be used for indexing, which one can be used for the stack pointer, whether there's a frame-pointer register, the format of assembly instructions, and addressing modes.

Using these tools, you end up working in two directions at once. On one end is the target processor's architecture. On the other end are the rudimentary operators that the compiler understands. Your job is to connect the two.

For example, one of the compiler's fundamental operators is SUB; its format is "\$dest = \$left - \$right," which means that the SUB operator subtracts the right operand from the left operand and puts the result in a destination operand. Your job is to teach the compiler the assembly instructions it must emit to perform a SUB operation. Of course, a SUB operation can have characters, integers, long integers, or floating-point values as operands; you have to take all cases into account.

I won't kid you; this stuff is not for the squeamish. I recommend that you work through the demonstration files, trying a little reverse-engineering until you get the feel of how the commands in the CIF work. Then bring up your compiler piecemeal—don't try to do the whole thing at once. You can have it output dummy instructions for the operators you're not sure of in the beginning and then complete it all later.

My biggest complaint is that the documentation could stand more work. I appreciated all the Backus-Naur diagrams—they helped me figure out the proper syntax for a command—but more examples, such as a tutorial for an 8088 C compiler, would make the process smoother. Still, if you find yourself working with a variety of processors or custom microcontrollers and you'd like to start building a library of ANSI C compilers for yourself, Archelon's Retargetable Software Tools deserves a look. I worked with the DOS version; versions also exist for Unix System V release 4.2, HP-UX, SunOS, and Solaris 2.x.

Cutting-edge technology has no room for warm, fuzzy characters.

Soft, fuzzy type is great on kid's pajamas and schmaltzy greeting cards. Unfortunately, it also shows up on bills of lading, insurance forms, and legal briefs. That's why we've designed ACE Plus-Adaptive Contrast Enhancement.



It turns soft-edge, low-contrast characters into cold, hard letterforms. And that can actually make scanned documents more readable than the originals. It also makes sure operators don't spend all day scanning documents over and over. We have a brochure that tells you the whole story. For a free copy, call 1-800-SCAN-494.

THE BESTRATED UNIX° SYSTEM.

(OH NO, NOT ANOTHER ONE.)

Recently, IBM was awarded best-rated UNIX system by a noted consultant, D.H. Brown.

Now we're as proud as anyone to be ranked No. l, but we can't help but notice that other companies are being ranked No. l, too. And proudly telling the world.

Which raises a pesky question: If everybody can be ranked No. 1, what should you look for in a UNIX partner?

Good point.

We suggest you look at a number of things. The operating system. Range of applications.

And perhaps, above all, the ability to run your company using the different computers and platforms you already have in place.



Over 10,000 programs from design to data mining.

Something that, you may have guessed, we're no strangers to at

IBM. In fact, at the last Enterprise Management Summit, IBM surpassed all other vendors in

systems and network management. On top of that, our RISC System/6000° and its UNIX operating system, AIX, connect to all hardware systems, including HP, Sun, DEC° and PC LANs, so you'll be able to keep working with your existing business computers.



What's more, RS/6000[™] products extend from notebooks to

high-performance parallel computers, so your investment is protected as your business needs grow. As for software, with

over 10,000 commercial and technical applications, your network can run everything from engineering to accounting to databases such as DB2/6000, CA-INGRES, INFORMIX, ORACLE, PROGRESS and SYBASE.

Not surprisingly, when Kodak Japan needed a UNIX system that could deliver faster same-day service and would scale from their smallest warehouse to the largest, they went with RS/6000.



RS/6000 keeps United Airlines flying on time.

And when United Airlines system aircraft maintenance controllers needed to access critical information instantly and communicate it to a fleet of 550 airplanes, they chose RS/6000 to keep them connected.

The UNIX platform is a very powerful tool. And with our proven RS/6000 system running on AIX, there are hundreds of ways it can help your business stay competitive.

We'll be glad to show you how. Call us at 1 800 IBM-3333, ext. FA101. Or, if you're on the Net, visit our Home Page at http://www.ibm.com. And see for yourself how we stack up.



INTERNET COMMERCE

Caching Could Stall Internet Commerce

technique used by service providers to give their users fast access to World Wide Web pages could stymie the plans of companies who want to rent out electronic-store space on the Internet.

The problem is due to a technique called caching, in which Internet providers cache Web pages to provide fast access to popular ones. Web caching is already used by Internet systems using the CERN (European Laboratory for Particle Physics) Web server in proxy mode as part of firewall security systems. Caching moved to the front of Web publishers' concerns earlier this year when the Prodigy on-line service, based in White Plains, New York, released its Web browser and its caching Web-server software.

Because of its Web caching, Prodigy's 1-million-plus potential Web readers see a faster response time when they access a popular Web site. But since Prodigy's readers are accessing the Web cache instead of the actual Web itself, the reliability of the number of times that users access a specific page

INTERNET INDEX

Estimated number of people who can use interactive services on the Internet: 13.5 million

Percentage of movie ads with Internet addresses in the Boston Globe on February 12, 1995: 8

Number per day of Prodigy users registering to use Prodigy's Web access: 15,000

Price per hour of Web access on Prodigy after the first 5 hours: \$2.95

—Compiled by Win Treese (treese@openmarket.com)

(known as hits) is reduced.

Prodigy's caching scheme is troubling to some Web publishers who rely on accurate page hits to determine the popularity of their Web pages (and, in some cases, to set Web-space advertising rates). "I rely on hit counts to determine whether or not I am posting data that people want to read," says Bob Wyman, vice president of new technologies for Medio Multimedia (Redmond, WA), publisher of a CD-ROM monthly magazine called Medio Magazine. "My business depends on accurate data about user preferences," he adds.

However, Don Tydeman, publisher of NetGuide Magazine (Manhasset, NY), says the use of Web hits is not useful for determining Web-page pricing models because it assumes that the electronic-publishing model is similar to the print model and that readers behave in comparable ways. "That's simply not the way it is," he says. Tydeman adds that the value of a Web page is in the quality of the relationship that exists between the marketer and the customer and the Web's ability to provide both with such benefits as shorter time to market, cost savings, and expert advice.

Other firms are now exploring alternatives to the Web-hit model. Tom Dubois, director of business strategy for Nielsen Media Research (Dunedin, FL), a major media-tracking company, says his firm is investigating several measurement methods, including hit audits, user surveys, and tracking certain Web users and the Web sites they access.

Ken Appleman, Prodigy program manager for the In-

Whatever Happened to ***



Hewlett-Packard's Kittyhawk?

(see "HP Delivers Matchbox-Size Hard Drive," July 1992 BYTE, page 32)

Hewlett-Packard's 1.3-inch Kittyhawk hard drive, which packed about 20 MB of disk storage into a rotating hard drive about the size of a matchbox, was a marvel of miniaturization. The drive's components were so small and precise that HP joined forces with Japanese watch company Citizen to manufacture the drive. But HP discontinued the line last year, citing lower-than-expected sales.

Eric Larson, HP's operations manager for mobile storage, says the company designed the Kittyhawk for use in mobile-computing devices, such as PDAs (personal digital assistants) and small hand-held devices, and nontraditional applications, such as game machines and printers. In 1993, HP tried to remedy one weakness of the Kittyhawk—its low capacity—by releasing a second implementation of the drive that doubled its capacity to 40 MB.

But Larson says the main factor in HP's decision to discontinue the line was weak sales in the subnotebook market. "The subnotebook market had trouble developing and is still in trouble today," he says. "Products didn't come out and were either canceled or delayed."

HP has manufactured the drive in small quantities since 1991 to satisfy its contracts with vendors, but it will end production this summer. According to Larson, HP is applying the knowledge it gained in manufacturing technology and automation during the Kittyhawk project to its factories in Penang, Malaysia, and Boise, Idaho. As far as getting back Into the market with the Kittyhawk, Larson says, "We'll watch and see what happens." —Nick Baran

IBM's Workplace Shell for DOS?

(see "OS/2 Gets Lean and Mean," August 1994 BYTE)

Users who prefer a character-based PC OS will find much to investigate in IBM's new PC DOS 7, including a tape backup facility, a file-synchronization utility, the ability to create compressed drives of up to 2 GB, and many other new attributes. But one feature noticeably absent from this latest version of PC DOS from IBM's Personal Software Products Division (Austin, TX) is the version of the Workplace Shell that was to provide a graphical shell to support task switching, drag-and-drop operation, file management, and other functions for PCs running DOS in real mode. IBM officials say the shell for PC DOS is currently on hold and "may or may not be" ever released.

And what about a new version of MS-DOS? Microsoft officials say the company is currently focused on getting Windows 95 into the channel by August. After that's released, Microsoft will evaluate whether it should further develop MS-DOS. Meanwhile, Novell says that it will no longer release new versions of Novell DOS.

—D. A.

ternet, says that he's aware of the issues lurking behind Web caching, noting that Prodigy is also in the Web publishing business. "Today, you really can't use the number of hits you get for useful financial purposes," he says. "The World Wide Web Consortium [W3C] is aware of the problem, and

Prodigy will work with the W3C to find a solution for it."

It's too early to predict what model (or models) Web publishers will use. However, Web publishers and marketers agree that a metric for measuring the value of Web services will be found. Business demands it.

-S. J. V.-N.

Blasts from the Past



DENNIS BARKER



Like Godzilla appearing on the edge of town, Windows 3.0 finally arrived. But people didn't run away. They ran out to buy it. Jon Udell, who'd worked with beta versions for months, rightly wrote that version 3.0 would change the face of DOS computing: "After years of twists and turns, Microsoft has finally nailed this product." His forecast: "The Windows momentum that has been building is about to become a tidal wave."

Father of computer graphics.

We paid tribute to Ivan Sutherland. As a graduate student at MIT in the 1950s, he developed the SketchPad, You could use It to draw, rotate, and edit primitives, without having to be an ace programmer. Sutherland had created the first CAD program.

"Who Needs OS/2?" That's what we asked on our cover, but that wasn't really the issue. OS/2, which Microsoft still sold at that time, had things Windows didn't, such as a multithreaded architecture and a 32-bit progamming model. And it lacked something: a foundation built on "creaky old DOS." Power users, we said. "will find the move from Windows to OS/2 a natural."

Sun lowered the price/performance curve with its SparcStation SLC, a diskless worksta-

tion priced below \$5000 (12 MIPS, 8 MB of RAM, Ethernet, and a 17inch monitor). "Quite a bargain

for an office running a network of SparcStations."

State of the Art scouted out coming networking technologies: wireless LANs, fiber optics, ATM (asynchronous transfer mode), and zapping data over AM and FM radio.



Trendsetting board of the month: VideoLogic's DVA-4000. By converting analog signals from a TV, VCR, or laserdisc player, the board let you play live video in a window on your VGA screen. We pretended stockbrokers would use it to snag Dow quotes or watch financial news shows.



Programming techniques. Hundreds of pages on languages, libraries, debugging techniques, subroutines, data-flow diagrams, and tricks for the 6502 programmer.

GEM '85 Our West Coast editor John Markoff reported on Digital Research's GEM (Graphics Environment Manager) after attending a seminar for OEMs and programmers thinking of converting to the new GUI. It appeared GEM's biggest competitor

was the Mac OS. GUIs that were in the works for IBMtype machines—Desq, Visi On, and something called Windows-seemed to be jinxed.

ComponentWare '85 "Software-ICs" proposed a plan for building reusable software components. "The notion of objects that communicate by messages is... fundamental to Software-ICs."

The Mindset was a PC clone that did some graphics chores in hardware. and it was swift at running Time

Arts' Lumena paint program. One model had genlock circuitry, so it could interact with video cameras and recorders (shades of the Amiga).

CyberBYTE We officially announced the BYTE Information Exchange, becoming the first magazine to extend into what is now called cyberspace. BIX featured on-line conferences, E-mail, BYTE articles, and the massive collective knowledge of BYTE readers.



On the cover, Robert Tinney "created a visual fantasy on a communications theme. Imagine a network of personal computers where each person's computer is a node." Editor Carl Helmers noted that this "fantasy" network already existed: the phone system combined with modem equipment.

Intercomputer communications was the focus of the issue. Helmers proposed "The Grass

Roots Electronic Post Office"—basically a global E-mail system. "Thus any two people who have a personal computer and a Bell 103-compatible modem

can send electronic messages back and forth."

And Flipper scores the winning touchdown. An article about Al-based personalized news services told this story: A Stanford researcher put in his profile that he would like to see any stories about dolphins. Sure enough, his report included football scores-of the Miami Dolphins.

In the News, June 1985

Lotus and Intel announced an expanded-memory specification for PCs.

At Comdex, Compaq announced 286based Portable and Deskpro models; TeleVideo unwrapped an AT clone that used an 8-MHz 286 (the IBM AT used a 6-MHz chip); Zenith brought out two "portables," weighing 17 and 25 pounds.

Manhattan Graphics released ReadySetGo, once of the first desktop publishing packages.

Microsoft introduced Access-a \$250 communications program, not the database program.





Cartridges returned via:





Call 1-800-962-2708 for Detail. All registered trademarks belong to their respective holders. The Canon Cartridge. In laser beam printers, personal copiers and plain paper fax machines, it's the heart of the desktop publishing revolution that's transformed homes and offices around the globe.

The key components of the imaging mechanism are combined with the toner in an all-in-one cartridge so simple to replace that anyone can do it. Replacing the cartridge ensures the highest output quality. It also makes your equipment virtually maintenance free. It's clean as well as simple, too; so

Please return your there's no need to dirty your hands. spent Canon cartridges.

For output quality and operating convenience, no other system comes close. And here's the point we'd like to emphasize — when the cartridge is returned to Canon, the environment is benefited because landfill waste is reduced.


When returned to Canon, cartridges are carefully disassembled. Reusable parts are painstakingly screened and cleaned. Over 95 % by weight of collected cartridges' parts and materials are used in making cartridges

or other products. The result: It's good for you. It's also good for the earth. Return your Canon cartridges when they are of no further use. Please.

As part of our Clean Earth Campaign in the United States, Canon makes donations to charitable organizations dedicated to environmental issues. Used cartridges are returned under the Clean Earth Campaign via the United Parcel Service (UPS) or Mail Boxes Etc. Shipping costs are paid by Canon, so there's no charge to our customers. Easy shipping instructions can be found in the cartridge box.



For your home or office, choose any of the wide range of products that use Canon cartridges.



Laser Beam Printer LBP-1260

Personal Copier PC320

Electronic Filing System Canofile 510

Fax Laser Class 5000



Not One More Damn Line of Code. Ever.

Apps Today!

See How **LAYOUT** Lets You Build Real, Heavy-Duty Programs Without Writing a Single Line of Code. Free.

PC Week called Layout a "sure thing." We call it a revolution. With over 200,000 users, tons of add-ons, and widespread third-party support, Layout is the only tool that lets you build DOS or Windows

programs by manipulating objects on screen - without writing code. Not just simple programs, but real, heavy-duty, mission-critical applications.

The True Power of Objects

Layout is truly object-oriented, both in the programs it creates, and in how you use it. You start out by arranging objects in a simple diagram, and then add more objects as the program grows, or create new objects by combining existing ones. You can even run your program as you're building it. Data-entry, database, and report formats are all visually designed on-screen.


What Layout Delivers

When you're done, Layout creates real .EXE files, or well-structured and efficient C/C++, Pascal, or BASIC programs. You can even create new objects right in Layout, or even re-use existing source code. Layout supports DOS and Windows, with NT and OS/2 coming soon, and applications written on any of these platforms are automatically portable to the others — including Windows 95 (Chicago).

Visual Power, Incredible Performance

The programs Layout creates are com-

Objects, Inc. is offering a free Windows95 Toolkit with Layout so you can start building tomorrow's programs today!



Layout: the Ultimate Tool

Layout delivers the future for \$299,95, including everything you need to build programs; free, unlimited, technical support; and superb documentation. Call today, join the Layout revolution, and never see code again. Ever.

pletely graphical, even under DOS, and fully support OLE 2.0, DDE, 3D buttons, hypertext links, messaging, creating and using DLLs, and much more. Layout even supports pictures as a data-type! Layout creates very efficient programs they're fast and compact. No 150K "Hello World" programs come out of Layout: it doesn't just spit out pre-canned code like other so-called high-level tools. And now,

Free! LAYOUT APPLICATIONS SAMPLER **☎**800-424-6644



99 Rosewood Drive O Danvers, MA 01923 USA USA 508-777-2800 FAX 508-777-0180 Email info@objectsinc.com Australia 07-855-2333 FAX 07-855-2364

New Zealand 03-343-2150 FAX 03-343-2151

Pricing and Conditions May Vary Outside North America. © 1995 Objects, Inc.

Word Overload, **Information Shortage**

ANDY REINHARDT

iven last year's wave of best-selling books about the Internet, it's not surprising that publishers are cranking out even more titles concerning the information superhighway. The four books reviewed here offer varying degrees of insight about this most nebulous of topics. Unfortunately,

they don't provide deep technical information on gnarly subjects, such as how video servers will accommodate 50,000 concurrent requests for the latest Spielberg movie or whether transac-

tion systems will be able to handle 20 million Super Bowl viewers pressing "Buy" on their TV remotes simultaneously. Three of the titles are generalinterest books. The fourth, Realizing the Information Future, is more of a policy paper.

Of the three general-interest books, Inside the Information Superhighway Revolution by Nicholas Baran is the most informative and best written. In lively, readable prose, Baran provides a good overview of the whole topic, including key players, hardware and software, networking, and content. He also tackles some larger questions, such as privacy, cost, and equality of access. Baran does a good job of explaining in lay terms such concepts as analog and digital, bandwidth, and video-on-demand, and he goes deeper into the technology of the information superhighway than do his counterparts. But even so, expert readers will find the book fairly nontechnical.

For some reason, Inside the Information Superhighway Revolution does not say exactly what the information superhighway is, and it would benefit

from additional graphics to il-

lustrate the layout and architecture of various proposals. I wasn't crazy about the slightly hokey

forward, which appeared to have been tacked on by Baran's editor to illus-

trate whiz-bang futuristic applications. And I found slightly disingenuous Baran's frequent references to "hype" and "buzzwords" about the

information superhighway in a book largely uncritical of its subject. But overall, Baran's book is thoroughly researched and smoothly written.

At the other end of the spectrum is Detour: The Truth About the Information Superhighway by Michael Sullivan-Trainor, a senior editor for Computerworld. Though he is enthused about the subject and has done some research, the writing is unfocused and meandering. Detour is full of information, but it careens from one topic to another and often repeats itself.

Detour's biggest problem may be its title and cover, which misrepresent and overpromise. The title implies that the book is a hard-hitting debunking of infobahn hype, which it is not, and the

DETOUR: THE TRUTH ABOUT THE INFORMATION INSIDE THE INFORMATION REALIZING THE THE INFORMATION SUPERHIGHWAY: BEYOND INFORMATION FUTURE: THE SUPERHIGHWAY INTERNET AND BEYOND **REVOLUTION** SUPERHIGHWAY THE INTERNET Nicholas Baran Michael Peter Otte **National Research** Sullivan-Trainor Council Coriolis Group Books **IDG Books National Academy** ISBN 1-56529-825-X ISBN 1-883577-10-1 ISBN 1-56884-307-0 Press ISBN 0-309-05044-8 \$19.95 \$19.99 \$22.99 \$24.95



SELF-PACED TRAINING

WORDPERFECT 6.0 FOR WINDOWS

ClassAct Multimedia, 1121 South Orem Bivd., Orem, UT 84058, (800) 235-3276 or (801) 221-9400, \$149.95 per title

owever computer-savvy you may be, it's always a daunting task to learn the ins and outs of a major new application or computer language. Every scripting language is different. You have to invest a lot of time and effort to realize the rewards of knowing a powerful new spreadsheet macro language. Even becoming familiar with those everincreasing toolbar icons can be a royal pain.

But when your company decides to standardize on a new word processor or database, you need a relatively painless way to get up to speed quickly. ClassAct Multimedia is producing some well-thought-out training CD-ROMs for major applications, OSes, and computer languages. The material is organized in outline form. Thus, a computer neophyte will be gradually brought up to speed at his or her own pace, and an experienced businessperson can quickly find out how to add, say, shaded, snaking columns to a company newsletter using the latest version of Word-

Not only is the ClassAct material well organized and accessible, it reinforces what you are trying to learn in helpful ways. For example, a pleasant-sounding instructor talks you through the lesson as the program requires you to perform the necessary keystrokes and mouse-clicks to accomplish the tasks at hand. You work directly with the interface of the application you are trying to learn, though the actual application is not required for the training. Quizzes test how much information you've retained.

ClassAct CD-ROMs are licensed on a concurrent usage basis and are networkable. There are training CD-ROMs for most of the best-selling applications, including Microsoft Office 4.2, Novell PerfectOffice 3.0, and Lotus SmartSuite. Also available are Microsoft C++, Visual Basic 4.0, Lotus Notes 3.2 development and administration, and Novell NetWare 4.1. The company promises a version for Windows 95 as soon as Microsoft releases it.

-Rich Friedman

Small investment.



Few things cost so little yet save so much as Software Security's family of superior hardwareor software-based protection solutions. Call 800-841-1316 today to protect the return on your software investment.



6 Thorndal Circle, Darien, CT 06820-5421 (203) 656-3000

Software Security International Ltd. +44-(0)1784-430-060

YOU'VE HEARD ALL ABOU HERE'S WHERE YOU BUY

Novell's UnixWare™ 2.0

has the power to drive your PC to the limit. UnixWare 2.0 is a true 32bit multi-tasking, multi-user graphical operating system. With built-in networking and the ability to run tens of thousands of UNIX, DOS and Windows 3.1 applications, it is the ultimate operating system for your Intel-based PC.



Information Foundation is the leading supplier of UnixWare products. IF also provides a full

range of UNIX tools and

place to come for UNIX

connectivity products for both UNIX and DOS/ Windows systems.

Our service and rock bottom prices

money back guarantee make IF the

-800-GET-UNIX

combined with a no risk 30-day

UNIX PRODUCTS FROM INFORMATION FOUNDATION:

- UnixWare Personal Edition 2.0 Desktop UNIX with graphics & networking ■ UnixWare Application Server 2.0 \$1,135
- Unlimited user UNIX with the "works"!
- UnixWare Software Development Kit 2.0 from \$97 The ultimate development system for UNIX
- LAN Manager for UnixWare from \$895 Seamless UNIX connectivity for WINDOWS & NT
- Accelerated-X from X Inside 599 Get the X power of a RISC workstation on your PC
- Spry Air Connect ternet connectivity for Windows!
- Slackware Professional Linux \$55 PC UNIX for the rest of usi

Call for our complete list of UNIX products!







Information Foundation - GREAT PRICES · SERVICE & SUPPORT · SATISFACTION GUARANTEED

P.O. Box 2821 Evergreen, Colorado 80439 Phone: 303/670-5345 Facsimile: 303/727-7618 E-mail: sales@if.com

edation's product distribution business is owned and ope norks are the property of their respective owners.

Books & CD-ROMs

cover lines suggest that it contains extensive interviews with assorted luminaries, which it does not.

The Information Superhighway: Beyond the Internet is by Peter Otte, an editor for Mobile Office. It was obviously written in a hurry. Though it has a nice, colloquial tone, it's so light that it borders on fluff. Otte takes the broadest view of the three authors, which is to say that he touches on everything from the Newton to home theater design, and from PCMCIA to schoolyard violence. At times, the text veers into silliness.

Realizing the Information Future: The Internet and Beyond is a report authored by a group of distinguished academics and businesspeople called the NRENaissance Committee, convened by the National Research Council in Washington, D.C. It is dry and academic, but it may be the most informative of the four.


The book outlines in great detail the technical issues of the information superhighway and provides a set of recommendations for an Open Data Network. It's a thoughtful, reasonable, and frankly inspiring prescription that leaves behind partisan politics, marketing glitz, and economic considerations. The information superhighway it sketches would be, if implemented, the most democratic, and it would most successfully avoid technical obsolescence.

Andy Reinhardt was formerly BYTE's West Coast bureau chief.

CONVERTING LIFE INTO BITS

BEING DIGITAL by Nicholas Negroponte Alfred A. Knopf, ISBN 0-679-43919-6, \$23

s founder and director of MIT's Media Laboratory, Nicholas Negroponte has had a front-row seat at the conversion of reality into bit streams. In Being Digital, he shares his experiences, insights, and predictions. It's a well-written and engaging book, and if you see the irony in the medium being a book, yes, so does Negroponte.



His analysis of such digital developments as the Internet, cable TV, "digital convergence," computer interfaces, E-mail, CD-ROM, and multimedia will appeal to experts and novices alike. The expert will see many familiar themes that have been playing out in reality, but they're juxtaposed and extended in new ways. Negroponte plays with ideas and insights like glass beads, stringing them together in ways that are suggestive, predictive, and creative. For the novice, I can imagine no more engaging tour guide of the digital technology of the early twenty-first century.

One of Negroponte's main messages is about the freedom of digital representations. This plays out in a number of phrases that pop up like slogans throughout the book. "Bits will be bits." "Information will win out." "Bits know no borders." In his view, there is a kind of Darwinian survival of the fittest, an inevitability to the current state and the future unfolding of technology.

Negroponte's predictions, woven throughout the book, may take five years or 50 years to realize, but there is little doubt that here is the shape—the outline, if not the detail—of the future. Anyone planning to live there should take a peek. ■

-Edmund X. DeJesus

Reflection X is simply better. But why take our word for it?

You be the judge. Try Reflection® X free for 30 days, and you'll see why it's 'simply better.'

You'll discover complete PC-to-UNIX connectivity. Reflection X is the first 32-bit PC X server to include advanced TCP/IP for Windows, award-winning VT320 emulation, and sophisticated applications like FTP client and server and LPR/LPD. All from a single vendor. You'll find Reflection X is easier to use, too, because it takes full advantage of Microsoft® Windows™. We've added features like drag-and-drop FTP and configurable panning. Plus, our intelligent client startup lets you launch X clients automatically—right out of the box!

Reflection X delivers top performance, reliability, and offers outstanding technical support.


So call today for your free 30-day evaluation. Because when it comes to 'simply better,' you know best.

For your free 30-day evaluation of Reflection X, call 800 926 3896

In Europe, call +31.70.375.11.00 Outside Europe, call 206.217.7100



Making PC Connections Count



Or a Globalyst PC&C?

With an AT&T Globalyst, people are free to work together:

Any time. Any place. Any way they want.

(That's what Personal Computing and

Communications—PC&C—is all about.)



AT&T Globalyst features at no extra cost:

☐ MessageFlash™/MailFlash™: send key messages, e-mails to alphanumeric pagers.

☐ AT&T Vistium™ Share Software: work with others on the same file at the same time.

AT&T Virtual Workplace™ features: hardware, software, communications and 24-hour support for mobile users.

□ Call 1 800 447-1124 ext. 1074 for more info, or e-mail us on the

for more info, or e-mail us on the Internet: pcc.info@daytonoh.attgis.com

Intel Pentium™ or 486 • Clock speeds from 50MHz-100MHz 4 PCMCIA Slots • 4MB-192MB Memory • 540MB-2GB Hard Disk



Bringing computing and communications together to help you get, move and use information.



Not Lost in Space

MICHAEL NADEAU

ast September, Xerox gave part of its New England sales force notebooks and kicked them out of the office. The 135 sales representatives, analysts, and managers in the northern customer operations division would never again have permanent space at the regional head-quarters. Instead, each person has a virtual office consisting of a notebook, a modem, a LAN adapter, and Microsoft Office. Xerox won't stop with the Waltham, Massachusetts, office. Within a year, it expects that all 5500 members of its U.S. sales force will work from virtual offices.

Xerox had good reasons for its decision. Salespeople now spend more time in front of customers, and overhead costs have been slashed. But the real catalyst for the change was a legacy system from hell. Xerox's information infrastructure was based on mainframes, some over 20 years old. As the company added more applications and brought more departments on-line over

sneakernet approach." In some cases, he adds, 10 to 20 systems were used to get information requested by one customer.

Although Xerox is not the first company to implement the virtual-office concept, it did so in a remarkable way. Earlier pilot programs in other sales regions uncovered potential problems and pointed to innovative solutions. Those solutions, however, meant a complete overhaul of not only the legacy systems but also the regional facilities themselves. The pilot programs proved that salespeople did not need permanent offices, but it also showed that quick and easy access to information was essential for them to be effective

on the road. The legacy system simply was not able to deliver that type of access.

Xerox closed a regional sales office and pushed the sales staff out on the road—where it belonged



The company's products and services—including printers, copiers, on-demand printing systems, and network consulting—were becoming increasingly

complex. Sales representatives had to spend more time working with clients to understand their needs. But, according to Pittman, they were also spending 30 percent of their time chasing information stored on the legacy system. Consequently, the sales force spent only 40 percent to 50 percent of its time in front of customers. For Xerox to reach all its potential customers, that percentage would have to increase.

"Solutions selling today is much more complex," says Cathy Lewis, a Xerox vice president and former district manager of sales for Xerox's New England North region. She estimates that her region alone has 2000 to 3000 potential customers. Her staff could not reach them all if they spent only half their time

with customers. Rather than hire more people, says Lewis, Xerox wanted to get more out of the staff it already had.

The goal, according to Pittman, was to develop a full marketing and customer database. This database would provide marketplace information, customer profiles, order information, and solution libraries. In short, one centralized data repository would have everything needed by the sales force and other departments, such as manufacturing. Much of the work on this database, which was built using Oracle, has been done. Although it resides on mainframes in the form of a data warehouse, it appears unified to anyone accessing it.



the years, the system grew in piecemeal fashion with undesirable results.

Many new applications came with their own databases, so one application maintained price lists, another processed customer orders, and another tracked inventory. Linking those databases was difficult—if not impossible—even for those running on the same mainframe. Different geographic regions, particularly those overseas, had systems that could not talk to anyone else's.

The old setup, says Bill Pittman, Xerox's corporate vice president and business process manager, "did not allow us to be responsive to our customers. When we did respond, it was with a

Sales personnel can choose any communications package for general use, but to connect to the data warehouse, they use Wall Data's Rumba terminal-emulation software. A Centrum communications server acts as a gateway between the notebook and the mainframe holding the data. Sales-team members have unlimited access to all the product, market-research, and competitive analysis data relevant to their territory. They cannot, however, use the connection to get data on their coworkers' accounts. Contact among the staff is maintained via Microsoft Mail and voice mail.

Productivity was not the only concern. Maintaining the legacy systems was becoming expensive. Also, the end of a lease agreement prompted Xerox's New England branch to adopt the virtual-office plan earlier than expected. The age of the company's old digs meant that rewiring for a new network would be expensive.

Pittman expects Xerox to accrue \$250 million annually from the project. About \$30 million to \$50 million of that will come from cutting leased office space by 30 percent. Most of the 65 district offices were downsized, and about half of the 50 area sales offices were closed. In addition, Xerox saves money by processing customer invoices more efficiently, and fewer people are needed to maintain databases and mainframes. Some people were reassigned, and some were part of a layoff, although Xerox declines to provide specific numbers. On top of that, Pittman foresees a 20 percent gain in sales productivity. When you consider those numbers, the project's estimated \$100 million price tag to implement the client/server network, renovate facilities, and train the staff looks like a bargain.

Before and After

Over 10 years ago, Xerox was one of the first companies to adopt LAN technology companywide, but this proved to be a disadvantage for the virtual-office plan. The existing corporate network could not support the mobile sales force. That network is based on Xerox Star network software and runs Global View terminalemulation software with Xerox Model 6085 terminals and a mainframe.

Although the proprietary network was ahead of its time, especially in its ability to transmit graphics images, it was slow and incompatible with the current industry standards. "We were highly arrogant about [our] technology and tried to protect it," says Lewis. Protecting that system kept Xerox blind to technology that its competitors and customers were using.

All the details of the client/server network that will replace the old network have not been worked out at this writing. It will be based on Novell NetWare 4.1 running an Oracle database engine. The servers will be Sun SolarStation 2000s, and the clients will be mostly Windows PCs and portables with a few Macs.

In Waltham, each virtual-office worker has a Compaq Elite 440C notebook. This system has a passive-matrix color display, a 340-MB hard drive, a Megahertz 14.4-Kbps PCMCIA modem, and a Thomas-Conrad PCMCIA Ethernet adapter. Software includes Microsoft Office, a communications package, a set of Xerox forms, and several megabytes of database files.

The Compaq notebook was not Xerox's first choice. The company planned to use the IBM ThinkPad 750. Pilot programs showed that the ThinkPad was "the first laptop with more than a six-month life span," says Mike Radigan, program manager for Xerox's U.S. customer operations division. However, lack of availability forced Xerox to look elsewhere.

Still, the Elite 440C has a number of features that appeal to mobile workers. Its power supply is internal—there is no "brick" to carry around. The processor, screen, and hard drive are userupgradable. This improves the system's life span and makes service easier. This is important because Xerox does its own service

on the units to reduce costs and minimize downtime. Compaq provided service training and has authorized Xerox to order parts directly. It also keeps a reference model loaded with the same applications that Xerox uses if Xerox calls with a problem it cannot solve itself.

Making It Work

The Xerox experience provides three key lessons for companies thinking about implementing the virtual-office concept. First, do testing to be sure you have adequate equipment and an information infrastructure, and identify potential glitches. Second, give the people involved the training and resources they need. Finally, redesign your facilities to maximize their efficiency.

Xerox's pilot programs quickly brought issues to light that might have meant disaster on an actual rollout. Many of the notebooks from vendors other than Compag and IBM proved to be unreliable. When the tests began, Xerox was also worried about notebook performance and hard drive capacities. The tests told the company just how close existing models came to its requirements.

The speed of the re-

VIRTUAL OFFICE, TANGIBLE BENEFITS

The Problems

- · Selling complex office products and support services requires on-site meetings, but sales representatives didn't have time to meet with the 3000 potential customers in the
- region. · The sales staff spent 30 percent of its time chasing essential product and
- Maintaining the legacy system was expensive.

customer information stored on the

The Solutions

legacy system.

- · Give the sales force notebooks.
- · Close down the central sales office.
- · Develop a centralized, quickly accessible data repository.

The Benefits

· A possible annual payback of \$250 million from increased sales, lower computer costs, reduced office rent, and staff reductions.

Lessons Learned

- · Run pilot programs to gauge equipment and informationinfrastructure requirements.
- Fully train and equip the staff.
- · Redesign your facilities to maximize efficiency.

mote connection was another big concern. It was clear that ISDN availability was too variable and too expensive. Radigan estimated that, for a test in Phoenix, providing ISDN for each participant would cost roughly the same as the notebook. With about 4000 potential virtual-office workers in the company, Xerox decided that fast modem connections over POTS (plain old telephone system) lines would have to do. However, the company continues to evaluate ISDN and other alternatives, such as 28.8-Kbps modems.

What Experts Say About the Virtual Office

Not all companies find success with virtual offices. What separates the winners from the losers often comes down to some basic "dos" and "don'ts."

DON'T force clerical tasks onto salespeople.

"You have now taken somebody with talent and made them into a clerk," says Ken Dulaney, vice president of mobile computing at the Gartner Group (Santa Clara, CA). Xerox's key goal was to have its sales force spend more time with customers. That would be impossible if salespeople took on new tasks. Dulaney suggests that in many cases you will get better results by giving your best salespersons secretaries rather than placing them in a virtual-office environment with inadequate support.

DON'T use mobile technology as a means of cutting costs.

You can't just send off your sales force with modems and notebooks and expect good results, Dulaney warns. Xerox changed its entire information infrastructure, for example, so that its sales force could easily access the data it needs remotely.

Do work harder for better communication.

Important information on products, policies, and key accounts is not easily disseminated in a virtual office. Regular staff meetings to review goals and share information are a must, says Jaclyn Kostner, whose consulting firm Bridge the Distance International (Denver, CO) specializes in helping companies manage the virtual office. "[The sales staff] must be able to reach people in real time," she adds. Kostner recommends giving pagers or cellular phones to key people, requiring the staff to update voice-mail greetings daily, and to frequently check for messages.

DO consciously develop team spirit.

Lack of communication can also diminish the sales staff's morale and effectiveness. Kostner knows of one mobile staff that learned of a coworker's \$10 million sale 45 days after the fact. This angered some people who would have sought advice from the coworker. In situations like this, says Kostner, "learning stays in little puddles." Worse, this situation may promote distrust among a staff. A buddy system, such as the one Xerox used, provides "someone else to share the pain as well as the successes," says Kostner.

To help relieve anxiety about the change, Xerox provided both classroom training and ongoing support for its virtual-office employees. Many of them had never used notebooks or Windows, nor had they ever made a remote connection. "Dialing in was something totally foreign

to them," says Joann Halle, marketing manager for the New England operations. Yet other sales-team members had PCs at home and used modems; some of them even looked forward to the change.

Bob Couch, a sales analyst in the Waltham office, is a prime example. He likes having quick access to information for which he used to drive long distances. Couch has optimized the virtual-office concept further by creating templates in Microsoft Word for all the forms he uses.

After receiving formal training on the new systems and software, each employee who had little experience was assigned a buddy. The buddy was a fellow sales-team member who had more knowledge of computers. During the three-week transition period in Waltham, the buddy was on-call 24 hours a day. If someone had a crisis at 2:00 a.m. while working on a proposal, help was only a phone call away.

The buddies continue to be available as long as they are needed. If a problem is too vexing for a buddy to solve, the Waltham office has a CNA (certified NetWare analyst) on-site. It also has access to a CNE (certified NetWare engineer) provided by systems integrator EDS, which set up the notebooks. To Lewis, the buddy system was a success. She says her staff "feels like they can talk to customers at any level."

Each virtual-office worker has a home office with a phone line and printer, both of which Xerox provides. Xerox gives each employee \$200 to set up a home office. The company has also set up the Waltham office with a classroom that's equipped for videoconferencing. Now employees can get on-site training for new products or procedures without traveling to a central training facility in Leesburg, Virginia, as they did in the past.

Whiteboards and leaning rails in corridors to encourage ad hoc meetings B13 B11 B9 Meeting and demonstration rooms with videoconferencing capabilities B12 Dataports in every office

tham, staff members connect to the network to determine room and equipment availability and to reserve any necessary equipment. A touchscreen located in a lounge provides for up-to-date resource scheduling. According to Connellan, however, this scheduling system is only a trial and might not be deployed companywide.

Where Virtual-Office Workers Meet

Xerox's Waltham office looks and functions like an airport red-carpet lounge for frequent fliers. Both provide an office away from the office for transient workers.

At the Waltham facility, you see rows of phone booths, work cubicles, lounge areas, and dataports everywhere. Strategically placed leaning rails, whiteboards, worktables, and chairs encourage chance encounters among the staff. Thus, information is more easily shared. "Everywhere a person could conceivably sit down, he or she should be able to plug in a laptop and become produc-

tive," says Sean Connellan, who is the manager of strategic planning and operations support in Xerox's corporate real estate organization. The facility in Waltham also has product demonstration areas, meeting rooms, a mailroom, and classrooms for training.

The Waltham building has about 40 percent less floor space than the old regional sales office had, but it still supports the same number of people. However, it does not appear to be cramped at all. Many of the offices are, in fact, empty.

To schedule on-site meetings in Wal-



Less than 50% of all software is paid for! That's right, over half of the software used in the world is an illegal copy. Piracy costs developers billions in lost sales each year. Protect your software.

It's the worldwide standard in software protection.

More developers rely on Sentinel®, from Rainbow, than any other software protection in the world.

And for good reason. Only Sentinel performs where it matters most: giving you the best in quality, reliability and support – with the most advanced technology available.

So whether you're protecting a DOS, OS/2, Windows, Windows NT, Macintosh, UNIX, XENIX, And Application – protect with Sentinel. Protect with confidence.

Call Rainbow for a Sentinel Developer's Kit and a Free copy of "The Sentinel Guide to Securing Software."



1-800-852-8569

SETTINEL Software Protection





RAINBOW

Rainbow Technologies, Inc. World Headquarters: 9292 Jeronimo Road, Irvine, CA 92718 Tel: 714/454-2100 Fax: 714/454-8557 LATIN AMERICA / ASIA 714/454-2100 LK. (44) 1932 570066 FRANCE (33) 1 41 43 29 00 GRMANY (49) 89 32 17 98 0 G1995 Rainbow Technologies, Inc. Sentinel is a registered trademark of Rainbow Technologies. All other product names are trademarks of their respective owners.


ARGENTINA: Agri-Aid, S.A. 54 1 8030536 AUSTRALIA: (DAGPLAN 61 3 590 0455 BELGRUM/LUXEMBURG: £25 32 92 21 11 17 BRAZIL: MIPS Sistems Ltda. 55 11 574 8686 BULGARIA: KSIMETRO 35 9279 1478 CHLIB: Chile/Soft Ltda. 56 2 2327617 CHIRA (Eastern): Shanghai Pudong Soltware Park Development Company 86 21 4371500

CHINA (Northern): C585 86 1 8316524 COLOMBIA: Construdata 57 1 610 8549 CZECH REPUBLIC: ASKON Intl' 42 2 3103 652 GREECE: Byte Computer S.A. 301 924 17 28 HONG KONG: Computers & Peripheral 852 2515 0018 HUNGARY: Polyware Kft 36 76 481 236 IRAN: Gam Electronics 982 122 22374 TRALY: BEI IBEXSA SPA 39 23 31 00535 ITALY: Siosistemi 39 30 24 21074
JAPAN; Giken Shoji Co, Ltd. 81 52 972 8544
JORDAN: CDG Engineening 96 26 863 861
KORBA: Genesis Technologies 82 2 578 8528
LEBANON: National Group Consultaris 961 1 494317
MAINYSA: Estam 5p. Despit M/5 file 86 03 241 1188
MEXICO: Impex Comp., 5A. de C. V. 91 800 66 466
MIDDLE EAST: Noche Inf1 44 81 459 882.2

MOROCCO: Futur & Soft 212 2 40 03 97 NETHERLANDS: IntroCom 31 74 430 105 PHILIPPINES MANASOFT TECH 63 2813 4162 POLAND: HITEX 48 22 41 97 51 PORTUGAL: COMELTA 351 1 941 65 07 SCANDINAVIA: PERICO A75 47 2249 1500 SINGAPORE: Systems Design FE LID 65 747 2266 SPAIN: MECCO 34 3 422 7700

SWITZERLAND: IBV AG 41 1741 2140 SWITZERLAND: Safe Compaid 5.A 41 247 5386 TANAWAN:Evenshine Tech, 886 2 5935201 THAILAND: BCS Int'l 66 2 319 4451 TUNISIA: ASCI 216 1 781 751 TURKEY: BINKEX, Icd. 90 216 348 3508 VENEZUELA: HRT-M Osers 58 2 261 4282

Solutions Focus Virtual Office



Imperfect Success

Xerox has not yet perfected its virtual-office implementation. Perhaps the most significant issue to be resolved is moving from the legacy system. By the time you read this, all the company's U.S. sales operations will have the capability of working from virtual offices. The major European divisions will follow by the third quarter of this year. But Xerox will not shut down the mainframes until next year.

All the "real support" is still in the mainframe, says Pittman. In practical terms, a sales representative connecting remotely won't know the difference between getting data from a legacy mainframe or from a client/server network. The trouble is that some employees with whom the virtual-office workers need to communicate still use only the legacy system. This presents a problem with E-mail. Thus, the Waltham office still maintains some of the old Xerox systems for access to legacy services.

Both the Xerox planners and the virtual-office staff would like to see improvements in the portable systems. Wish-list items include a bigger hard drive (the Waltham staff did not have enough room

to install XSoft's GV-Win, which provides connectivity to the legacy system), a better color display, and a faster modem. In most cases, 14.4 Kbps is adequate. But downloading a bit-mapped form is still too time-consuming.

Smaller problems still abound. Lewis cites the need for people to learn better - E-mail etiquette; some staffers tend to un-

necessarily copy everyone on the E-mail messages they send, clogging up mailboxes. Couch would like to see all sales personnel have a CompuServe or other on-line account. This would give them access to the Internet and to on-line users groups catering to Xerox products, not to mention another avenue of communication with customers.

Down the Road

Xerox is currently examining the next step in its information-system strategy: the implementation of an object-oriented approach to data management. It is too early to know which model or platform the company might use, but Pittman sees some important benefits to using object-based applications.

First, he and Pat Wallington, who is chief information officer and architect of the strategy, expect the upkeep of the ap-

plications to be easier and that local managers will be able to build more of their own reports and applications. The company will also be better able to adapt applications to different geographic needs. But perhaps most important, Pittman sees the object-oriented approach as insurance that Xerox "does not wind up with a new legacy system."

Where to Find

Sun Microsystems Mountain View, CA (800) 786-0404 (408) 276-1931 fax: (415) 969-9131

Compaq Computer Corp.

Houston, TX (800) 345-1518

Oracle

(713) 370-0670

(800) 672-2531

(415) 506-7000

fax: (713) 378-1442

Redwood Shores, CA

fax: (415) 506-7200

Xerox Corp. Rochester, NY (800) 275-9376 (716) 423-5090 fax: (716) 427-5400 Michael Nadeau is the author of the BYTE Guide to CD-ROM (Osborne/McGraw-Hill, 1995). You can reach him on the Internet or BIX at miken @bix.com.



Your workgroups get the HP LaserJet 4V network printer. And you get \$250 off. What a steal!



Under \$2,200*
The HP LaserJet 4V with HP JetDirect card, after rebate. The HP LaserJet 4MV is under \$2,800 after rebate.

For a limited time, HP will take \$250 off the price of either the HP LaserJet 4V with a qualifying HP JetDirect card or the LaserJet 4MV. But savings aside, you just won't find a better solution for the needs of a busy workgroup. First of all, these mid-volume network printers are fast. They clock in at 16 ppm, fueled by a 33.3-MHz RISC-based processor. Each one accepts a wide variety of paper sizes. And, because they feature HP JetAdmin printer

management software, printing will be noticeably smoother for everyone involved. For more information about the printers and the rebate, see your nearest authorized HP dealer.

HP Network Printers
Just what you had in mind.






The difference between running a network and having a network run you.

Ask people who manage networks what they want in a PC server and everybody says the same thing: "Something to make life easier." So here they are—the new line of IBM PC Servers.

Along with the IBM PC Server 300 for small LANs and the 500 for enterprise networks, we introduce the IBM PC Server 320 with increased flexibility for expanding networks, and the 720, a superserver with highly advanced and easy-to-upgrade 1- to 6-way SMP.

So how do they make managing your network more manageable? First, with our new PC Server Start-Up support¹—a part of HelpWare®—you can call us for free for the first 90 days and we'll handle any IBM and non-IBM installation or configuration problems. There's Server Guide, our CD-ROM software that streamlines setup and automatically fine-tunes for optimum performance. And finally, DMI-compliant NetFinity,™ our industry-leading software that manages both your PC server and PCs.²

That's making life easier. For complete details, call 1 800 IBM-4FAX (enter #8361777). Or visit your IBM Authorized Business Partner.



IBM PC Server 300:

Intel® 486DX2/66MHz processor or 60MHz Pentium™ processor, EISA/PCI, 8MB parity memory expandable to 128MB, 728MB hard drive, 8 open slots, 9 bays.

IBM PC Server 320:

Intel 90MHz Pentium processor, multiprocessor enabled, EISA/PCI, 16MB parity memory expandable to 256MB, ECC on SIMM optional, 256KB of L2 cache, SCSI-2 fast and wide, 6 open slots, 9 bays, standard CD-ROM.

IBM PC Server 500:

Intel 90MHz Pentium processor, MCA, 32MB ECC memory expandable to 256MB, 256KB of L2 cache, SCSI-2 fast and wide, 6 open slots, 18 bays for hot-swappable drives, RAID-0, 1, 5 enabled, standard CD-ROM.

IBM PC Server 720:

Intel 100MHz Pentium processor, 1- to 6-way SMP, 64MB ECC memory expandable to 1GB, 512KB of L2 cache and 224B of L3 cache, SCSI-2 fast and wide, 7 MCA/PCI combination slots, 18 bays for hot-swappable drives, RAID-0, 1, 5 enabled, standard CD-ROM.

All Models:

30-day money-back guarantee, 3-year on-site warranty¹ (same-day service on 500 and 720, next-day on 300 and 320).

There is a difference™



No other sound card ever made this kind of uproar.

"Creative Lahs just keeps on improving on the design that made it famous. This latest revision of the Sound Blaster features a host of innovations. For example, it has both a 20-voice FM synthesizer and a 32-voice digital sample playback synthesizer for more realistic MIDI sounds. The QSound feature delivers surround-sound effects to your WAV files or you can choose to enhance them with such effects as stuttering and echo. Lots of useful applications come in the box, too, including the easy-to-use VoiceAssist speech-recognition software and well-rounded TextAssist for text-to-speech tasks."

HOME OFFICE COMPUTATE / JANUARY 1995



"To me, using a computer without sound and music is like driving a Lamborghini without the roar of its V12 engine. The

AWE32 is completely compatible with the whole range of Sound Blasters. The MIDI side of the AWE32 has been enhanced to provide it with the kind of sound you would expect from a professional synthesizer."

"...if sound quality and performance is important, you can't go wrong."

ordinary sound card, the Sound Blaster

OSound to widen and enhance the AWE32 adds stereo effects of sounds."

The Sound Blaster AWE32 has Creative Labs' suite of sound playback and editing software that does the job with admirable simplicity-and the addition of sequencer Cakewalk Apprentice and the presentation program HSC Interactive SE rounds out the bundle nicely. And of course, the Sound Blaster AWE32 is compatible with software written for older Sound Blasters, so it will work on anything from Windows to Doom."



"For flexibility necessary for businessrelated audio, turn to the Creative Labs Sound Blaster AWE32, which stands out with decent sound quality

and excellent software that includes 3D sound and text-to-speech and speech recognition capabilities. its lavish documentation is another welcome feature. The AWE32 gave us the smoothest rides and the best sound in the games we tested."

174 PC WORLD - DECEMBER 1994

SOUND CARDS

Greative Labs has long been the leader in this market, with its Sound Blaster series setting the standard for PC sound. The \$399 AWE32 is the most advanced card in the Creative Labs lineup. It has everything you'd want in a general-purpose audio board."



It seems the Sound Blaster™ AWE32 has the critics buzzing. For the first time, it puts

awesome professional studio sound within the reach of the hungry audiophile. And of course it's genuine



Sound Blaster compatible. So now that you've heard the experts' opinion, how about coming up with one of your own? Simply visit your local

Creative Labs dealer. Or

CREATIVE" multimedia iSs. Creatise

Apple's New Operating System

TOM THOMPSON

ext year, Apple will release System 8.0, a major revision of its Macintosh OS. Codenamed Copland, it supports two diametrically opposed goals: to deliver sophisticated OS services with a growth path to future features, yet run existing Mac software.


It was the Mac's extensive software base that forced Apple's engineers to limit Copland's capabilities in the areas of memory protection and task scheduling. But they were still able to build in sophisticated OS services, such as threads, task and I/O synchronization, hardware abstraction, and virtual memory support.

Copland is a complete redesign of the Mac OS. Like all modern OSes, Copland consolidates all its core OS services into a compact microkernel. This microkernel, along with a completely revamped I/O subsystem, provides powerful OS services without impacting performance. (For an overview, see the text box "Copland OS Features at a Glance" on page 60.)

Copland's microkernel, native OS software, and native applications are packaged as code fragments. Thus, Copland will be released first on Power Macs, CHRP (Common Hardware Reference Platform) systems, and PowerPC-based clones. Apple is still deciding whether to release a 680x0 version. Copland is expected to require 8

MB of RAM and 40 MB of disk space (20 MB for the actual code and 20 MB for a swap file).

Not all of Copland's improvements originate in the microkernel. Other parts of the OS, such as the Finder and portions of the Toolbox, have been enhanced to provide better performance or to improve the UI (user interface). For example, Copland has a scalable UI that can accommodate a user's expertise level. For the programmer, object-oriented interface elements make an application's UI much easier to build.



System 8.0 offers up-to-date OS services. such as limited preemptive multitasking, concurrent I/O, and memory protection

Safeguarding Memory

Copland's 32-bit memory architecture manages a maximum address space of 4 GB. Unlike System 7, Copland partitions this space so that 1 GB is allocated for the OS code, OS tasks, and I/O buffers. The remaining 3 GB is for applications.

Copland sets up a variable-size Cooperative Toolbox Environment space (henceforth referred to as sim-

ply the Cooperative space) where existing Mac applications and portions of the Mac Toolbox execute. The microkernel can create other, independent spaces as required for specialized applications. The PowerPC uses information from its MMU's (memory management unit's) PTEs (page-table entries) to manage memory accesses. Copland programs the PTEs to establish several types of controlled access, each of which is then enforced by the MMU. These controls include write protection, address-space isolation, and execution-mode protection.



Copland OS Features at a Glance

BETTER PERFORMANCE. The first Power Macs achieved their wellknown stability and compatibility by simply executing large amounts of the time-proven 680x0 Toolbox code in an emulator, With Copland, this situation is reversed: It's comprised mostly of native PowerPC code, so calls to the microkernel services benefit directly from the PowerPC's processing speed.

It's important that Copland's device drivers

are reentrant native code. Thus, they provide better raw throughput over what's possible using emulated drivers, and concurrent I/O operations are supported. A native file system boosts file I/O rates, especially for virtual memory. It also offers new capabilities, such as the ability to handle hard drives up to 256 TB in size and individual files up to 2 GB in size. Finally, an improved 680x0 emulator executes the remaining portions of the 680x0 Toolbox code, and any 680x0 applications, significantly faster.

The microkemel also has a preemptive task scheduler that helps overall performance. As with other OSes, this task scheduler juggles task activity so that when one task gets blocked-perhaps while waiting on pending I/O or for access to an exclusively owned resource-other tasks still execute.

This keeps the overall system running efficiently rather than stalling when a program waits for an I/O function to complete, as is often the case with System 7. While the kernel, I/O services, and server programs created by Copland-savvy applications execute preemptively, for reasons of compatibility, existing Mac applications still have to execute cooperatively.

A MORE STABLE OS. The microkernel improves reliability through the use of memory protection, separate address spaces, and user/supervisor execution modes. Again, for compatibility purposes, this memory-protection mechanism has limitations: Applications and nonreentrant Toolbox code reside in a single Cooperative space and can trash one another, but not the entire OS.

Because of the microkemel's modular design, Apple can release portions of the OS for shakedown before Copland ships next year. For example, drivers, network services based on Open Transport, and a faster 680x0 emulator will be released with the PCI-bus (Peripheral Component Interconnect) Macs that are due out this summer. Users can depend on these services' being reliable in Copland because they will sport any bug fixes and performancetuning accomplished during the interval.

AN EXTENSIBLE ARCHITECTURE. This is an outgrowth of Copland's modular design. Portions of the OS can readily be replaced to, say, support a new volume format or an imaging engine without having an impact on other OS services.

In recognition of the fact that third-party vendors often extend the Mac OS in new and useful ways, Copland's microkernel offers a well-documented native patching mechanism. For example, both the new File Manager and the high-level Toolbox supply hooks so that these portions of the OS can be readily extended.

HARDWARE ABSTRACTION. Copland's ship date was delayed so that hardware dependencies could be eliminated from every part of the OS but the drivers. Unlike previous versions of the Mac OS, Copland is not ROM-based: Instead, all the OS and Toolbox code resides in disk files.

Open Firmware, an evolving IEEE standard, is used to bootstrap the computer. This prepares Copland for the new PowerPC system hardware standard, CHRP (Common Hardware Reference Platform), which was jointly proposed by Apple, IBM, and Motorola. (For details, see "New PowerPC Standard Supports Macs," March BYTE.) This hardware abstraction also assists Mac clone vendors: They can readily add custom hardware to their system designs to add value or cut costs without requiring a drastic revision of Copland.

All program code and invariant data (e.g., an interface object, such as an error dialogue string) are marked as write-protected. This feature prevents an errant memory access from corrupting key data or program code. Any such attempt creates a write-protection exception, which is fielded by an exception handler. Copland has a number of default handlers that attempt to make a graceful recovery from such exceptions as addressing errors, illegal instructions, and arithmetic overflows. Special-purpose applications can install their own handlers.

Portions of the OS reside in separate address spaces established by the MMU. This arrangement effectively walls off these parts of the OS from applications. Current System 7 Mac applications must run in the Cooperative space. Certain types of programs, such as extension code and background-only applications that don't make use of the GUI, can be placed in separate address spaces for additional memory protection. In the future, when the Toolbox code is revised for Gershwin (the code name for the next major Mac OS release), Mac applications will reside in their own distinct address spaces, protected from each other.

But not all the OS code and system data can be isolated. Certain information must be shared globally with applications and other OS tasks. Such code and data are protected by the execution-mode mechanism (see the figure "Copland Memory Map" on page 62). Unlike previous versions of the Mac OS, Copland distinguishes among instructions executing in the processor's user or supervisor mode. (System 7 also made this distinction when running virtual memory, but it was only to support the page-faulting mechanism.)

The microkernel, I/O services, and device drivers operate in supervisor mode (which is also known as privileged mode), while applications run in user mode. This arrangement restricts memory accesses so that only privileged code, such as the microkernel, has the ability to modify system data structures.

Applications can access this data, but only indirectly by invoking a kernel service through an API call. These calls, which use the PowerPC's exception mechanism, are fast and efficient. In combination with write protection, this arrangement lets applications have read-only access to globally shared data structures.

The most vulnerable section of memory is the Cooperative space, where applications reside. It offers no memory-space isolation or execution-mode protection. Apple's engineers made it this way so that this area would resemble the current System 7 run-time model and thus provide an environment where existing applications can run.

While the Cooperative space cannot pro-

POWER PUBLISHING!

Corel VENTURA 5 beats PageMaker and QuarkXPress in InfoWorld

(see below)

The tool bar provides quick access to commonly used features.

> Wrap text around irregularly-shaped graphics.

Use multicolored fountain or fractal fills to create unique effects.

Use Corel PHOTO-PAINT 5 (Included) to create and modify bitmapped images.



Presets enable quick formatting of page elements.

The Index Entries roll-up allows you to generate Indexes automatically.

Define and modify cross-references interactively.

Drag and drop images directly into your document using Corel's visual file manager.

Corel VENTURA 5 ... "unparalleled power and flexibility" ...

"Corel has done some fine work in improving and recasting VENTURA into a robust page layout program with impressive capabilities.

Windows Magazine, January '95

"Newcomers to this desktop publishing package will find unparalleled power and flexibility in building and modifying large and complex documents.'

PC Magazine, February '95



You can upgrade to Corel VENTURA 5 if you own one of the following:

PageMaker FrameMaker **QuarkXPress PagePlus** Microsoft Publisher any previous registered version of VENTURA.

"FrameMaker, QuarkXPress, and PageMaker can't beat the level of formatting and typographical control offered by VENTURA's paragraph-based style sheets—a boon when your document requires a complex structured format."

PC\Computing, January '95

"Appropriate for documents of all lengths, VENTURA offers templates to get started quickly, better text formatting, and prepress capabilities."

Home Office Computing, January '95

Corel VENTURA NUMBER ONE in PUBLISHING!

Product 3.5" disk version	S.L.P. (US\$)	Score
Corel VENTURA 5	\$595	6.8
QuarkXPress	\$895	6.7
Aldus PageMaker	\$895	6.2
InfoWorld, Report (Card Rating M	arch 20, '95

Includes Corel РНОТО-PAINT 5



"Corel VENTURA delivered a convincing

CorelDRAW will easily get used to the DTP

recommended even to beginners..."

program. The user friendly VENTURA can be

performance. Users who are already familiar with

Competitive upgrade **CD-ROM version** US\$ plus applicable taxes

All product names are trademarks or registered trademarks of their respective companies.



Call now for faxed literature! 1-613-728-0826 ext. 3080 Document #1122

Feature

vide memory-space isolation or execution-mode protection, it offers limited memory protection, Recall that all native program code, regardless of its address space, is write protected. A wild access into a native application's codeor into the Toolbox code residing in this spacecauses an address exception. In such a case, Copland's exception handler terminates the offending application.


An errant application can trash another application by altering its data structures, since such information can't be marked as read-only. A misbehaving application can also corrupt data used by the Toolbox code residing in the Cooperative space. In the latter situation, the Cooperative space terminates and you lose all your work inside the applications. But you can restart the Cooperative space, and-because of the memory pro-

tection—the OS itself, any network sessions, and the state of the file system are still intact. Any special-purpose background applications living in separate address spaces, such as a database engine, are also safe in such a situation.

This design compromise shields the Copland OS and native applications from most malfunctioning programs. A program would have to precisely hammer a small range of key data addresses to damage another application. In the worst possible scenario, it could only bring down the Cooperative space. This a major improvement over the current situation, where all of System 7's code and all applications are wide open and vulnerable to a stray memory access.

A New Run-Time Model

Copland sports a threaded run-time architecture for the microkernel and various parts of the OS. A thread, an independent course of execution, has its own stack and registers. It relies on resources obtained by the parent process, such as memory or access to an I/O device. Copland threads are similar to Unix Mach threads, but they are called tasks in Apple parlance. (The remainder of this article will use the Apple term.) Copland's task scheduler schedules



tasks preemptively according to priority and time intervals.

Copland tasks are typically part of a team, which makes them similar to Unix Mach processes. A team is composed of one or more tasks and other kernel resources. Only the tasks within a team execute, while the resources supply the data required by the tasks. An address space can be occupied by multiple teams, such as the Cooperative space. However, to help implement Copland's memory-protection strategy, tasks within a team can't migrate to other teams, nor can teams move between address spaces.

A Copland process, as in System 7, is a thread of execution that represents an application started by the Process Manager. However, while a System 7 process has only a single thread of execution, a Copland process uses a team, which consists of a main task, resources, and any other tasks started by the main task.

An application's main task can create secondary tasks, which can be scheduled preemptively as long as the secondary tasks don't make use of the GUI or the Event Manager. The restriction for not using such calls is that these Managers, especially QuickDraw, still have nonreentrant code and thus can't be used in a

preemptively scheduled task. These secondary tasks can manage network, disk-I/O, or computationally intensive tasks while the main task handles the main event loop that processes user events.

The cornerstone to the new memory-protection and reentrant-code capabilities discussed thus far is the Power Mac's runtime architecture. It's based on shared libraries of code fragments that are functionally similar to DLLs. This is radically different from how System 7 resides in memory: a monolithic code block that must stay RAM-resident. Because each of Copland's services is resident only while in use, applications can use more of the 8 MB of RAM that Copland occupies.

When you create a codefragment shared library, you can specify how its global data is to be shared. The Code Fragment Manager, the part of the OS re-

sponsible for managing code fragments, calls the microkernel to program the PowerPC's PTEs as it loads and unloads code fragments. A shared library's data can be per-context (i.e., each team has its own instantiation of the global data), privilegedonly (i.e., the data is readable by all teams but can be altered only by privileged-mode code), or made up of systemwide globals, which are accessible and writable by all tasks.

On Schedule

The nerve center that coordinates all of Copland's activities is its preemptive task scheduler. Only those tasks that are written in reentrant code and that make use of reentrant Toolbox Managers can be scheduled preemptively. The reentrant Managers include any kernel services, the new File Manager, the Device Manager, the Apple Event Manager, all network protocols, and a new memory Manager called the Pool Manager (just to name a few).

Therefore, a task that makes use of I/O or networking services, or one that performs background processing, such as a database search or floating-point computations, can be preemptively scheduled. However, any task that makes use of the System 7 Memory Manager, the Event

Imagine a broad range of high performance drives for every systems' need.



Conner's
Filepro
Performance
3.5-inch disk
drives deliver
the capacity
for today's
demanding
systems.

Conner makes it a **Reality**.

The race is on. And Conner leads the way with a broad range of high performance disk drives for high-end workstations, servers and RAID systems. Consider the Conner Filepro Performance 1080, 2105, 2107 and 4207. With 1, 2 and 4 GB capacities, these drives are ideal for today's most demanding system needs—like video, CAD/CAM and other high performance applications. With a data transfer

Model:	CFP1080	CFP2105/2107	CFP4207
Capacity:	1 GB	2 GB	4 GB
Average Seck Time:	11.0 msec.	9,0 msec.	9.5 msec.
Data Transfer Rate:	55.4 Mb/S	73.1/87.4 Mb/S	87.4 Mb/S
RPM:	\$400	5400/7200	7200
Interface:	Fast SCSI-2 Fast-Wide SCSI	Fast SCSI-2 Fast-Wide SCSI	Fast SCSI-2 Fast-Wide SCSI
Warranty:	5 years	5 years	5 years


rate of up to 87.4 Mb/S and an average seek time of 9.0 msec., Conner's Filepro Performance family offers one of the highest levels of performance in the industry. Combined with an industry leading MTBF up to 1,000,000 hours and backed by a 5 year warranty, they provide the winning combination of capacity, performance and reliability available in today's high performance market. Plus, the Filepro Performance drives come in FAST SCSI-2 and FAST-WIDE SCSI interfaces.

What's more, we're continually expanding this family of cost-effective, high performance disk drives to fit your growing system needs—now and in the future.

So call Conner today at 1-800-6-CONNER. And take the fast path to a new world of high performance storage solutions.

The Storage Answer.
Circle 115 on Inquiry Card.





Manager, or QuickDraw can't. The scheduler arranges these tasks to execute just one at a time to satisfy the nonreentrant nature of these APIs, as shown in the figure "Copland's Architecture" above.

Typically, an application's main task contains the calls to WaitNextEvent() and-by way of the Window or Dialog Manager-to QuickDraw, and thus has a limited execution schedule. WaitNext-Event() calls kernel services, which synchronizes the team's data with the main task.

A main task can create other, secondary tasks that have the ability to execute preemptively as long as they avoid use of nonreentrant Toolbox code. In addition, it's up to the programmer to use the main task to enforce data synchronization among other tasks. But the new File Manager and Device Manager API calls provide a completion notification mechanism-either by posting a new type of event or setting a semaphore—that notifies the main task when an I/O operation concludes. The kernel provides a variety of synchronization services, ranging from semaphores to a sophisticated message system that can pass blocks of data between tasks that have different privileges and reside in different address spaces.

The task scheduler has 31 priority levels. Priorities deal with such details as realtime data handling (e.g., video and sound), responding to an application's user interface, network activity, and background tasks. The scheduler is smart enough to resolve scheduling conflicts brought about by lower-priority tasks having exclusive access to kernel resources.

While this design has its limits, the major win here is that it allows System 7 applications to continue to run. While these applications execute cooperatively, the kernel and most OS services execute preemptively. As a result, no longer does the system halt while an application tracks your mouse position in a menu, as is the case with cooperative multitasking under System 7. Instead, menu tracking continues, and so does kernel, networking, disk I/O, and other tasks.

Performance Improvements

It's a tribute to the might of the PowerPC processor that Power Macs deliver ample performance, even though more than half of System 7's OS and Toolbox code is 680x0 code running in an emulator. Copland, despite the overhead that the kernel services exact, should run faster, because 95 percent of it is native code.

For example, Copland integrates native versions of QuickDraw GX and Power-Talk, its collaboration software. The remaining 5 percent of the OS uses 680x0processor-specific code, such as the Segment Loader. It doesn't make much sense to do a native implementation of these parts of the OS. A faster 680x0 emulator uses dynamic recompilation rather than static execution to boost the speed of this code, as well as any 680x0 application running on the system.

To improve memory performance, a new pointer-based Pool Manager provides faster

70 entry points, while the old File Manager had more than 150. The new API calls don't use parameter blocks; instead, they use smaller logical data structures that carry shared data between file-system calls for better efficiency. The File Manager also uses reentrant code, so tasks can have concurrent file I/O operations in progress.

Copland's virtual memory subsystem is faster, more robust, and always active. It doesn't interfere with overall system performance because it's smarter and more flexible about memory paging. Under System 7, a swap file representing a fixed memory partition had to be built at boot time. Under Copland, a swap file is built only when the Process Manager launches a new application. This way, the swap space can be disjointed files on the hard drive, and it need only be as large as the combined memory demands of the OS and any running applications. This arrangement also reduces memory fragmentation. As in the native version of System 7, file mapping is used to reduce I/O to and from the swap files.

Hardware Independence

Copland's ship date was delayed by at least six months so that a HAL (hardware abstraction layer) could be added. The HAL hides the hardware details from the kernel code so that the code can be written without any dependencies on a particular machine configuration. To this end, Copland no longer requires Mac ROMs to function. Instead, a set of bootstrap ROMs use the Open FirmWare boot process to locate the start-up drive, load Copland into memory from a disk file, and transfer control to it.

This design departure was necessary to support CHRP and clone systems that sport



5 MINUTES TO FREEDOM

INSTANT INTERNET ACCESS



Forget on-line services; InterRamp connects you directly to the Internet. That's the BIG difference.

In less than 5 minutes, you'll have access to MOSAIC, Gopher, WAIS, Veronica, Archie, ftp, E-Mail, NEWS and other hot Internet applications. You have the entire world-wide Internet at your fingertips.

lust a few clicks of your mouse, you're connected.

All applications are automatically configured for immediate use. It's that SIMPLE.

We're so sure you'll love Instant InterRamp, we'll let you try it absolutely FREE without any obligation.

All you need is a computer and a modem; we'll send you the Instant InterRamp software.*

Also, PSI offers high-performance LAN Internet solutions for your organization. Ask our sales representative for more information.




CALL NOW FOR FREE DEMO 1.800. PSI. 0852

PREFERRED CUSTOMER NUMBER #00140



- FAXBACK INFO: 1.800.fax.psi.1 INTERNET E-MAIL: interramp-info@psi.com World Wide Web: http://www.psi.net DOWNLOAD THE SOFTWARE FROM THE INTERNET: http://www.psi.net/interramp/
 - FTP: ftp.psi.com/liramp/inetcham/
- * Restrictions apply, FREE trial requires credit card for verification purposes only. Performance Systems International, Inc. 510 Huntima Park Daive Herndon, VA 22070 USA ©1995 Performance Systems International, Inc. PSINet and the PSINet logo are registered trademarks. All other trademarks and service marks are used with their permission and remain the property of their respective ownes. [Rev. 2/10/95]

Feature



The new Standard File dialog box, presented by Navigation services. Notice the nested folder hierarchy in the window.

a diverse array of hardware. Adding a new type of device to Copland means simply adding a new device driver rather than a modification to the OS. For example, to add a low-cost PC keyboard to its design, a Mac-clone vendor provides a keyboard-driver file. Inside this file is driver code that consists of two parts: one that's hardware-specific, and one that hooks into Copland's abstraction layer. The latter portion mediates communications between the Mac OS and the hardware-specific part of the driver.

A Name Registry provides a certain level of hardware abstraction and driver-design consistency while providing device control. The Name Registry is an object database that stores information about the various devices that register themselves with Copland. It also provides for dynamic driver loading and unloading, which is necessary for devices that can be hotswapped, such as PCMCIA cards and PowerBooks intended for docking.

Last but not least, Copland uses Open Transport to implement network services. Open Transport is based on network standards from the X/Open Group, including the XTI (Transport Interface) and the DLPI (Data Link Provider Interface). Apple's engineers used the Streams standard from Unix System V for the protocol environment.

Open Transport thus provides network services through a single set of APIs that let applications transparently access network services using multiple protocols. Open Transport implementations of the AppleTalk and TCP/IP protocols have

been completed, and IPX and serial communications protocols are currently in the works. Open Transport uses native drivers for maximum performance.

Easily Extendable

To allow Apple and third parties to extend Copland's features in the future, a new, well-documented, patching API is available. The functions of this new patching API shift from the 680x0-processor-specific, A-trap table to the processor-neutral, transition-vector mechanism used by the Code Fragment Manager. Transition vectors consist of pointers that aim at the entry points of a shared library's functions.

This mechanism shift confers two advantages. First, patch code won't incur the overhead of a context shift between processor-instruction sets when a switch occurs into the emulated 680x0 environment and back. This overhead wasn't significant when the bulk of the OS was still 680x0 code, but it becomes substantial with Copland, which is chiefly native code.

Second, the transition vectors provide finer granularity over what's patched and can supply bookkeeping information. For example, many A-trap entries actually dispatch to several Toolbox functions. To patch the file Open() function, with the old patch API you had to patch the file system's entry point (FSDispatch()) in the trap table and then filter all uses of this call until you received an Open() request. This method was prone to failure and could introduce unwanted side effects in all the functions called through that entry point. With the new patch API, you patch only

the Open() function. The bookkeeping information can be used by a developer to order or disable patches for debugging purposes.

Finally, parts of Copland offer hooks to facilitate patching. The virtual memory subsystem uses backing objects, which are abstract entities that make up part of the page-fault mechanism. Normally, backing objects are registered with the OS and simply map sections of physical memory to swap files. However, a third-party vendor might modify a backing object's behavior so that a page fault referenced by it becomes an I/O request. This I/O request then compresses the data and writes it into a memory cache, mimicking the operation of Connectix's RAM Doubler utility.

The new File Manager allows extensions, so it can be enhanced and new foreign volume formats can be supported. It also provides notification events so that when a change occurs in the file system (e.g., a Type III drive card is removed from a slot), the OS and applications can respond to the change.

A New Look

So far this article has concentrated on Copland's infrastructure. However, there are visible changes to the UI as well. Some of these changes assist the user, while others make the programmer's job simpler.

For instance, some existing Toolbox Managers have been enhanced to make it easier to use certain interface elements. For example, the Menu Manager now has built-in support for tear-off menus and sticky menus, which formerly required extensive patching to implement. The Menu Manager also lets the user hide the menu bar or add a permanent menu (i.e., one that's present in all applications).

The Window Manager now provides floating and modal windows as standard fare. It also introduces new features, such as multidirectional window sizing and background patterns within the window's content area.


The Dialog Manager and Control Manager now offer active feedback during mouse tracking (which is essential for live document scrolling). It now also lets the user chose dialog box items via keyboard input.

In System 7, the interface elements used by these Managers (e.g., a window or a menu) consisted of stand-alone resources known as definition functions, or *defProcs*, with only one entry point. To implement a custom control or window, you had to write your own defProc resource.

For compatibility, Copland supports existing custom WDEF, CDEF, MDEF, and

Indy Modeler workstations come standard with: Silicon Graphics® Indy™ 133MHz R4600™ 64-bit processor, 168 hard disk,

For the easiest 3D modeling available anywhere, follow these instructions closely.



Don't add any expensive, new memory boards or graphics accelerators. Forget the sound cards and display drivers. Skip the file viewers, plot spooling, and antialiasing software too. Just switch on an indy Modeler™ workstation from Silicon Graphics.

It's instant 3D modeling at your fingertips—from the people who invented solids modeling. You'll see that even our low-cost systems are embarassingly faster and easier to run than the most lavishly equipped PCs. (And UNIX® works. It always has.)

Simply put, when it comes to 3D, Indy Modeler is the replacement for the PC.

amaii" electronic maii, and the Indigo Magic" user environment. The Indy Modeler workstation is priced at 88,995, with other options available, until June 80, 1995,

Go farther today, Call now for the new Indy Modeler video and the name of your nearest reseller at 1-800-800-7441, Dept. D440, or find our home page on the World Wide Web at http://www.sgi.com.



COPLAND HOT SPOTS

It's normal to expect some software-compatibility problems due to subtle changes that are introduced in a new OS release. Since the application run-time architecture has undergone sweeping changes under Copland, you might anticipate major compatibility problems. However, Copland supports the old run-time environment and APIs along with the new ones, so such problems might be minimal—at least on paper. The matter won't be settled until Copland ships, but we can identify the potential problem areas. Possible culprits are listed below and are arranged in order from best-behaved to worst-behaved.

- Applications that make heavy use of network communications, such as mailers, group schedulers, and softwarecontrol packages. That's because Copland uses Open Transport to implement protocol stacks and network services. Also at risk are telecommunications applications, since Open Transport manages serial communications protocols. But because Open Transport will be released this summer, software vendors will have an opportunity to revise their programs. The bottom line: Expect to
- use the most recent version of these applications with Copland.
- Drivers. The revised driver architecture is bound to create some problems for vendors and users alike. The PCI-bus Power Macs to be introduced this summer will be a proving ground for the native implementation of PCI drivers. However, Copland's memory-protection scheme and the need for reentrant code could create new problems. The bottom line: Make sure the PCI card or new driver
- extension is Copland-compatible.
- Extensions and Control Panels with initialization code.
 Since Copland uses a native patching mechanism, an initialization-code resource that patches the old A-trap table simply breaks. Also, there will be many problems arising out of such code being loaded into disparate address spaces. The bottom line: Prepare to pony up the cash to upgrade all your favorite Extensions and Control Panels.

MBDF defProc resources. But Copland improves the situation with an object-oriented interface architecture based on the SOM (System Object Model). Instead of using defProcs, SOM helps implement Mac OS interface elements as IDOs (Interface Definition Objects). An IDO has multiple entry points, one per method. A programmer can write a custom IDO by subclassing it from a base IDO, thereby causing it to inherit all its desired behaviors. The programmer then quickly adds custom behavior by writing code to override certain methods.

Important here is the fact that, while QuickDraw is not reentrant, IDOs are. These new interface objects thus pave the way toward a future OS based on a reentrant imaging engine.

Also important, text is handled by an abstract data type known as a *text object*. Text objects remove the limitations of C or Pascal text strings and provide the means for manipulating multibyte foreign languages. Text objects use a Unicode converter to handle conversions between different-language text encodings. They also provide for a smooth migration to complete Unicode text encoding in a future OS release.

Copland provides several new Managers to handle the system from the user's perspective. An Appearance Manager provides new human-interface components—such as sliders, a progress indicator, and an expansion triangle—that formerly required extensive programming to implement. It also provides new APIs that draw interface elements, such as bevels, for these components.

A Navigation Services Manager supplies new standard file dialog boxes that expedite the selection of files, applications, folders, and volumes. Its behavior can be easily extended so that this window can act as a file viewer or be used to browse other data containers (e.g., a mailbox or archive) rather the file system (see the screen on page 66).

From the user's point of view, some of these interface benefits are obvious. Others aren't so obvious but are just as useful. For instance, the Finder is now multithreaded, so you can handle several different file operations, such as copying several files simultaneously, launching other applications, and emptying the trash, all at once.

Copland's UI is now scalable, which means that its appearance and behavior can be tailored to the user's expertise level. While details are still sketchy, Copland should closely resemble At Ease to a novice user, where items such as hard drives and the Trashcan are hidden from view. An expert user can have the familiar Finder

Desktop layout, with all its hard drives, remote servers, and Power-Talk mailbox.

Copland's scalable UI means that as a user gains experience with the Mac, he or she can apply skills learned at the novice level toward the more advanced UI environment. This isn't the case with Microsoft's Bob, where the interface skills gained by a user don't translate to using Windows.

The Best Gets Better

Copland provides a much-needed revision of the Mac OS. It offers speed, reliability, and modern OS services through its native code, preemptive multitasking, I/O concurrency, and memory protection. The compromises made in task scheduling and memory protection are reasonable ones, particularly since they protect your software investment by allowing existing software to run. Reliability shouldn't be a concern, because parts of Copland, such as the emulator and PCI (Peripheral Component Interconnect) expansionboard drivers, will be field-tested


in staged phases of the Mac OS releases.

In the inevitable comparison to Windows 95, we have to say that Copland is better. It offers Windows 95 services while still providing better features. Some of these features, such as network support through Open Transport and the use of Open Firmware to implement plug and play for expansion cards, are based on industry standards.

Furthermore, Copland offers hardware abstraction, a feature currently found only in Windows NT. This capability will help foster a growing clone market without incurring the compatibility nightmare of supporting diverse hardware—a problem that delays the release of Windows 95.

While these are important technical issues, there's also the issue of the user who'll be sitting in front of the machine. Copland's scalable UI ensures that experts and novices alike can use a Mac to their best advantage.

Tom Thompson is a BYTE senior technical editor at large with a B.S.E.E. degree from the University of Memphis. He is an Associate Apple Developer and author of Power Macintosh Programming Starter Kit (Hayden Books, 1994). You can reach him on AppleLink as "T.THOMPSON" or on the Internet or BIX at tom_thompson @bix.com.



At Lexmark, we don't limit top-of-the-line features to our top-of-the-line printers.

The new Optra family is the first full line of networkready, desktop laser printers capable of true 1200 x 1200



dpi*printing. Each Optra laser printer, from the extremely affordable 12 ppm Optra R to the NetWore extremely powerful 16 ppm Optra Lxi, delivers

four times the sharpness of ordinary 600 dpi printers.

No matter which option you choose, our breakthrough MarkVision[™] printer utility is standard. Users and LAN managers can control and configure every Optra on the network, and monitor job statistics, right from Windows" or Macintosh workstations.

PostScript Level 2 and enhanced PCL 5 emulations are also standard. Which means that every Optra prints incredibly sharp graphics and beautiful, crisp text from virtually any of your applications.

All this value and innovation from Lexmark, a former division of IBM. For more information, call us at 1800 891-0399, ext. 232.

Thanks to the new Optra family, you can choose the best printer, rather than the best compromise.



ADVANCING THE ART OF PRINTING



*1200 dpi requires additional memory for complex fiés. Lexmark products are manufactured under the ISO 9002 approved quality process. This Energy Star emblem does not represent EPA endorsement of any product or service. Lexmark, Optia and MarkVision are trademarks of Lexmark in International, inc. NetViere is a migistered trademark of Novell, inc. Windows is a trademark of Microsoft Corporation. Macintosh is a registered trademark of Apple Computer, inc. PosScorpic is a trademark of Adobe Systems Incorporated, which may be registered in ordain jurisdictions. PCL. as registered trademark of Hewholf Packerd Company, © 1986 Lexmark International, inc.



We've Made Network Faxing Easy and Affordable

Delrina has put the benefits of network faxing within your reach. Meet Delrina WinFax PRO for Networks¹¹ 4.0 – the easy, affordable way to share fax modems and telephone lines across your network.

The benefits of WinFax PRO for Networks are enormous. Save the expense of buying individual fax modems and telephone lines. Make your people more productive, by letting them fax directly from their own PC. And, WinFax PRO for Networks is so easy to use and implement that you can have your entire group up and running in no time.

Easy to Use. Network faxing is now as easy as printing from your PC. Using the world's best-selling, most award-winning fax software, WinFax PRO" 4.0, you can send faxes directly from any Windows application. Then, choose any fax modem on your LAN or let WinFax PRO for Networks select one for you. To send a fax to a group of people,



New Delrina WinFax PRO for Networks 4.0

WinFax PRO for Networks will even use up to four modems at once. And because everything takes place in the background, you can continue working while you fax.

Affordable. WinFax PRO for Networks is the most affordable solution for groups of up to 50 people. You don't need a dedicated fax server. Start off with a few users sharing one fax modem and grow until everyone in your department is faxing. To expand, simply add more fax modems – up to four per server and 16 per workgroup, with as many workgroups per LAN as you need. To add more users, simply purchase affordable 10, 25 and 50 volume user packs.

N. America: 1-800-598-8679 Germany: +49/89/64 19 22-0 U.K.: 44(0)181-207-3163 France: 33.1.46.94.80.40

Compatible. WinFax PRO for Networks also integrates with your existing hardware and software. It supports over 600 popular fax modems. It works with all popular networks including Novell NetWare," Microsoft Windows for Workgroups® 3.11 and Artisoft LANtastic." Plus, it routes faxes using all popular e-mail packages like Microsoft Mail™ (MAPI), Lotus cc:Mail™ (VIM) and all MHS-compatible systems. If you don't have e-mail, simply forward faxes directly to another WinFax PRO user over your network.

Call Today! The benefits of network-based faxing are now within your reach. WinFax PRO for Networks gives you an easy and affordable way to put faxing where it belongs—on your network.

Call now for information or to upgrade from WinFax PRO or see your local dealer.









Defrina, WinFax PRO and WinFax PRO for Networks are trademarks of Defrina Corporation and its affiliated companies. Microsoft is a registered trademark of Microsoft Corporation. All other product names are trademarks of their respective owners. © 1994 Defrina (Canada) Corporation, All rights reserved.



Cash on the Wirehead

ANDREW SINGLETON

barter, currency, and signed checks and vouchers—simply don't work in cyberspace. Making payment possible across the Internet—and the WWW (World Wide Web) in particular—is the goal of a new breed of electronic payment systems that are just now coming into use.

This article examines six of these commercial Internet payment systems and describes their strengths and weaknesses. Each is quite different from the others, and each is appropriate for certain types of applications but ill-suited for others.

Debit and Credit

All systems for making payments—digital or otherwise—fall into one of two different classes: debit and credit. In a debit system, you gather your money up front and then spend it. In a credit system, you spend the money first and pay the bill later. Payment systems based on gold, paper currency, traveler's checks, and instant-debit ATM (automatic teller machine) cards are debit systems. Checks, charge accounts, and credit cards are credit systems.

Just as cash and credit coexist in today's business climate, both exist in the digital world as well. *Digital cash* is the digital equivalent of a cashier's check or a bearer bond (i.e., a token or note issued and signed by a bank or other institution with its name, a ran-

dom and unique identifying note number, and the amount of money represented). Users can buy these notes from a bank (which makes this a debit system) and then redeem them later for real cash. Although users can make digital copies of such notes, a bank redeems each note number only once.

Digital credit is similar to the credit systems used in the business world. The main difference lies in the incorporation of digital time stamps and signatures that build auditability and account-



You can't do business on the Internet if you can't pay your bills or get paid. Here's how.

ability into the system and replace the paper trail that's no longer there.

With such a system, the payer creates a voucher record that contains a description of the transaction, the names of the payer and the recipient, the date and time of the transaction, and the amount to be paid. The payer signs this voucher with his or her private key. Using a public key, the recipient of a voucher can read the record and verify that it was signed and obliged by the possessor of that private key. The recipient can then submit the voucher to a

clearing system and have legal grounds for collecting payment.

An Infrastructure in Place

The infrastructure for electronic-payment systems already exists: the major credit-card processors (e.g., American Express, MasterCard, Visa, and Discover), ATM networks, and the ACH (Automated Clearing House). Credit-card business involves a three-part processing system. Banks provide credit and billing

The Outlook for Digital-Cash Systems

iven the variety of approaches in the six systems examined here, network merchants have a lot of payment-service options. Which ones will thrive—or even survive? Here are a few predictions.

- Servers will accept a variety of payment methods. (Translation: They'll take your money any way they can get it.)
- WWW browsers with built in public-key signatures will be used. Encryption and digital signatures are needed, but dedicated payment software has a firewall problem. There will be a steady increase in password-capturing software.
- Credit-card companies will begin using network payments in a big way. Their operations are global, and they already have you signed up. These companies will eventually offer corporate billing and debit transactions, as well as consumer credit billing. Right now, they're just biding their time, hoping to get their systems right the first time.
- Digital-cash rollouts will be slow. A major security flaw in many digital-cash schemes, including E-cash, is that somebody who embezzles a bank's private key can create counterfeit cash. The cost of this would probably be borne by the bank. Of course, this prospect makes banks extremely wary.
- It will be quite a while before payment services make money. At a 1 percent margin after clearing, BYTE estimates that each service will have to process \$200 million per year—far more than the total volume for 1994—to support a data center and customer-service operation.
- Time-sharing will make a comeback. Why bother to buy, install, and maintain a complex application when you can just attach and go? Rent, don't buy; do it from your laptop. Payment services will support an explosion in creative new information services.

to the customers. Third-party processors provide verification and collection mechanisms for merchants who accept credit cards. And international networks, such as Visa, connect the processors with the banks for collection. This system is complex, but it's already in place and extends nearly everywhere. Charges to merchants typically run 2 percent to 3 percent of the total transactions made, plus 20 cents per transaction.

Several credit-card processors intend to offer their services to merchants on the Internet. The credit-card system is truly international, able to accommodate transactions in a wide variety of currencies and reconcile them in the banking system. This gives it a big advantage on the Internet.

The ACH is a U.S. interbank mechanism in which local banks submit payments to a database and the Federal Reserve transfers the money overnight. This is the manner in which direct-deposit payroll works. ACH transactions are inexpensive (less than 15 cents each) and can be generated by a computer. They will become popular for clearing online payments, although ACH works only between U.S. bank accounts.

Debit-card networks allow an ATM to instantaneously deduct money from your account and transfer it to another bank as payment. The banks pay 50 cents per transaction for this. Banks require both a physical card and a password (known as a PIN) before issuing payment. When the obvious existing security issues are resolved, these same networks will have the ability to issue online payments.

Nothing prevents private citizens and corporations from maintaining accounts for their customers and issuing payments from those accounts. Most on-line services pay their content providers in this way, and it may evolve into a significant banking role as these institutions offer payment servers for their accounts.

The Mechanics of Payment Systems

An on-line payment transaction generally involves three

parties. The customer pays, the merchant receives the payment, and a bank does the accounting, making sure that money from the customer ends up in the merchant's account. In a peer-to-peer system, users can act as both customers and merchants. For the purposes of this discus-

sion, a payment service can act like a bank even if it's not legally considered to be one.

The customer runs client software. This might be a WWW browser, such as Mosaic; an encrypting browser, such as Netscape or Mosaic with S-HTTP (Secure Hypertext Transport Protocol); or a

dedicated payment client.

The merchant runs merchant software on its server to request and process payments. In many cases, the merchant software is integrated with a WWW server. A payment server is the bank's POP (point of presence) on the network. To execute a real-time transaction, the merchant generally forwards information to the payment server, which authorizes the payment and credits the merchant's account.

Security and Privacy

Security issues are critically important in any digital-payment mechanism. The most common way to authenticate a user is to ask for a password. Because it's easy to read messages as they traverse the Internet, most commercial services encrypt passwords before sending them, using the new generation of WWW browsers. These include Netscape (which uses SSL [Secure Sockets Layer] encrypted protocol) and Mosaic derivatives (which use S-HTTP).

Unfortunately, even encrypted passwords aren't secure if they are used more than once. Ultimately users may be forced to rely on the use of *hardware tokens*—typically, credit-card-size devices that can generate unique one-time passwords or securely maintain encryption keys.

To ensure security, financial messages—whether they're payments, credit-card numbers, or digital signatures—must remain confidential and be impossible to alter without detection. Most systems currently in use maintain some kind of paper trail that can be used to check and audit transactions; equivalent capabilities must be a part of any viable on-line payment system. Current cryptographic mechanisms can provide these features.

Privacy is a related but more controversial issue. In this age of mammoth databanks, many people think that it's time to draw the line. Some believe that digital financial transactions should be, in principle, just as anonymous as cash transactions and that it's nobody's business—certainly not the merchant's, the bank's, or the government's—where people spend their money. This goal can be achieved with existing digital cryptographic technologies, but only some electronic-payment systems currently make use of them.

The Internet's First Payment Systems

BYTE recently surveyed six different commercial systems from Cybercash, Digicash, First Data/Netscape, First Virtual, Open Market, and Wave Systems. This list does not include what may well become the two biggest guns on the payment-services battlefield—the joint

Since We Introduced The Complete COBOL Solution, Thousands Have Off-Loaded Our Competition.

From New York to the Netherlands. companies are replacing their incomplete COBOL solutions with the one that's fully loaded. CA-Realia® II Workbench.

The reason is simple. CA-Realia II Workbench is the most comprehensive COBOL client/server solution in the industry. One that provides an unsurpassed list of benefits and features which include: the world's fastest PC COBOL compiler, a GUI

CA-Realia II Workbench Other COBOL Competitors Feature Fully integrated, intuitive programmer's workbench Debug both PC and mainframe-based Fast compiles and efficient execution Complete single-vendor solution Supports Windows and OS/2 Foundation for GUI Client/Server COBOL development with open DBMS access

The competition simply carri compete with CA-Realia II Workbench.


What's more, CA-Realia II Workbench includes a complete mainframe CICS emulator for no extra charge. And, all the features of the workbench apply to CICS programs as well as batch.

So whether you're in a Windows or OS/2 environment, CA-Realia II Workbench provides complete integration with your host-based

systems. Which means unlike some other COBOL solutions, your programming choices are never limited

For A Self-Running Demo And A Free Copy Of The Secret of COBOL Maintenance, Call 1-800-434-REAL, Dept. 26500.

And join the thousands of companies who've already decided that





editor and an interactive GUI debugger for code executing on a PC or mainframe, and integrated lifecycle management. Plus a COBOL-intelligent program analyzer that's

the smartest thing you've ever seen.

ventures announced by Visa/Microsoft and MasterCard/Netscape. Neither is due to be available until late this year, and neither is well defined at present. But the six services examined here are close enough to real-world deployment that a realistic evaluation of their implementations and prospects is possible. The fundamental features of each system and details on how it works are summarized in the table "Digital-Cash Systems Compared" on pages 76 through 78.

Cybercash

Cybercash proclaims that "the bank is our customer" and anticipates that all its transactions will be passed directly to a real bank. Thus, customers will talk to the bank. not to Cybercash, for customer service. As this article was being written, Cybercash had scheduled a pilot project with Wells Fargo Bank for March, with service available to the public in May.

Cybercash software should work well as a bank interface by providing a portable ATM for home banking. The debit version could prove to be an excellent mechanism for funds transfer, bill paying, and peer-to-peer payments. But the initial credit-card version is less appealing. The customer must enter a credit-card slip for each transaction, and there's no mechanism for subscriptions. With Cybercash, as with credit cards, merchants are liable for fraudulent transactions. BYTE rates Cybercash as fair to good for one-time catalog sales, but only fair for information sales.

Digicash Ensures Privacy

Digicash is the most radical—and possibly the most significant—player in the payment-services game. Founder David Chaum has invented and patented a form of digital cash, called E-cash, that offers privacy ments are recorded electronically, the notion that an electronic payment system doesn't have to invade your privacy will be

very important, almost a human right."

The E-cash software is convenient and fun to use. As a peer-to-peer payment mechanism that allows individuals to exchange payment with anyone anywhere on the globe, without paying high fees or giving up privacy, E-cash empowers the individual. It sounds great, and BYTE believes it could work.

Because no banks have yet signed on to the E-cash system, it's difficult to evaluate its suitability. Close attention will certainly be paid to its progress. The software is currently being tested with play-money cyberbucks.

First Data/Netscape: Business as Usual

First Data, the biggest U.S. credit-card processor, and Netscape Communications, one of the hottest commercial vendors of WWW software, have teamed up to offer credit-card authorization. The mechanism is actually a minimum modification to the phone-based credit-card payment systems now in use. Instead of calling in a creditcard number to a merchant, a customer types the number onto an HTML (Hypertext Markup Language) form, and the client takes advantage of Netscape's built-in encryption to send it to the merchant server. The product is currently in use at Marketplace MCI. Both the Netscape server and the First Data processing service are first class, but the union of these two organizations does not add much value.

Also, the product's requirement of a dedicated phone line adds significant expense. Merchants with encrypting Netscape or S-HTTP WWW servers can install inexpensive card-authorization soft-

ware, such as IC-Verify, for less than \$500 and work with the creditcard processor of their choice. Moreover, users already send their card numbers to merchants. And, while simple, this product's mechanism inherits all the security flaws of the current credit-card payment system. It's clearly an interim product, and thus BYTE rates its suitability as only fair.

Merchants and customers should instead look forward to Netscape's venture with MasterCard, in which MasterCard will place a payment server on the Internet. This will eliminate the merchant's need for a dedicated phone line. Also, a payment server on the Internet will increase security for customers, since signed credit-card slips will go directly to the payment server for authorization without revealing customer information to the merchant.

First Virtual: Try Before You Buy

First Virtual is a unique credit-card processor because of its try-before-you-buy approach. The system, already in operation, is designed primarily for vendors selling information and other "soft" goods. The Virtual in the name refers to a unique company organization: The principals all work in different states, and the phoneresponse and Internet-server maintenance are contracted out to companies in vet other states. Company principals claim that the virtual organization and its simple, voluntary payment system are well suited to the decentralized culture of the Internet.

The First Virtual service is a simple way for a merchant to process credit-card transactions. It requires no special WWW browser, infrastructure, or merchant processing account. And the merchant start-up fee is only \$10.

Unfortunately, the system, with all its passwords and insistent E-mail, is also somewhat inconvenient for the customer to use. The payment schedule is uncertain, the sign-up mechanism is automated and clunky, and the "virtual" concept doesn't seem to support a real service organization. For suitability to WWW information sales, BYTE rates First Virtual as fair.

Open Market: Full Service on the Web

Open Market is a startup company dedicated to building Internet stores and the payment services to support them. Its system

is entirely WWW based and exploits the HTTP standard to its fullest. The system is currently in operation for internal use by the Open Marketplace WWW servers.

Unlike some other providers examined here, Open Market views itself as a service company that's willing to handle customer accounting and billing as well as development. Open Market's is the only payment server to provide customer service, subscription accounting, charge aggregation, scalable security, and businessto-business accounting.

The implementation is clever and convenient, with the downside being that the

for the buyer. Says Chaum, "When all pay-

Cybercash

Reston, VA (703) 620-4200 fax: (703) 620-4215 E-mail: info@cybercash.com http://www.cybercash.com/

Digicash by

Amsterdam. The Netherlands +31 20 665 2611 fax: +31 20 668 5486 E-mail: info@digicash.nl http://www.digicash.nl/

Digicash, Inc.

Palo Alto, CA (415) 321-0300 fax: (415) 321-0322

First Data/Netscape (800) 638-7483

fax: (415) 528-4140 E-mail: sales@mcom.com http://www.mcom.com/

First Virtual

(800) 570-0003 fax: (619) 282-6567 E-mail: info@fv.com http://www.fv.com/

Open Market, Inc.

Cambridge, MA (617) 621-9500 fax: (617) 621-1703 E-mail: webmaster@ openmarket.com http://www.openmarket.com/

Wave Systems

New York, NY (212) 755-3282 fax: (212) 755-3436

Where

Discover The New World Of Content-Driven Navigation



AnchorPage Fully Automates Concept Extraction And Hypertext Anchoring Of HTML Documents.

AnchorPage uses semantic and syntactical analysis to "read" HTML documents and extract the significant concepts from them. AnchorPage then builds four *Synopsis Views* of the document and links each view's entries with the corresponding passages in the original document.

This provides your end users with four different methods of referencing the content of each document, so they can quickly determine if it has the information they're looking for *before* they invest the time in downloading it.

The *Table Of Contents View* presents the overall document headings and subheadings in outline form. This allows users to see the overall shape and content of the document at a glance.

The Abstract View presents significant concepts in the order in which they appear in the original document. This allows users to view the concepts in the context of surrounding ideas.

The Concept View presents these same concepts arranged alphabetically on the basis of the key words they contain. This allows users to search for an important term or phrase (e.g., taxes, social security) and immediately see the context in which the term is discussed.

The *Phrase View* presents an alphabetical list of all the key terms and phrases of the document, whether or not they happen to appear within the discussion of a significant concept. This view is both briefer and more all-inclusive than all others, and allows users to quickly skim for key terms that may point to the information they are looking for.

Website administrators can offer as many of these options as they choose, along with any combination of hypertext jumps linking them to one another and to the original document.

This results in fully referenced, fully linked document content that makes your information quickly and easily accessible to your user.



Internet Demonstrations. To try AnchorPage for yourself, visit the ICONOVEX home page on the World Wide Web (http://www.iconovex.com). Or call ICONOVEX for more information, 1-800-943-0292 or 1-612-896-5100. Or write: ICONOVEX Corporation, 7900 Xerxes Avenue South, Suite 550, Bloomington, MN 55431.

Circle 108 on inquiry Card (RESELLERS: 109). ©1995 ICONOVEX Corporation

AnchorPage Benefits For Website Administrators:

•Fully automatic process, from analyzing text to placing hypertext links to producing Synopsis Views.

*Fully customizable, both in the amount of detail in the Synopsis Views you choose to present and in the appearance of the final pages.

•Files can be stored anywhere on your system.

*Documents are segmented for faster download times.

*No modification to existing website pages is necessary. AnchorPage won't affect the structure or organization of servers.

*High speed. AnchorPage analyzes single or multiple documents at very high speed without human intervention.

*Satisfied users make for a popular website. Helping them find information quickly, easily, and reliably assures repeated visits.



	CYBERCASH	DIGICASH
Credit- or debit-based?	Credit-based now; debit is planned.	Debit.
Customer software	Cybercash plans to distribute free client software with which the user can transmit credit-card charge slips and debit authorizations and view some account information. Typically, a Cybercash client runs on the same workstation as a WWW browser.	Digicash is a peer-to-peer system, so merchants and customers can use the same client software that Digicash distributes for free.
Merchant software	The merchant receives a free software library to build and parse Cybercash messages. The merchant's Internet server calls this library to request payment.	Most merchants need the text-based version of the software so that the can integrate it into their Internet servers.
How customer pays	The initial Cybercash implementation supports only credit-card payments. The customer types a credit-card number into a charge slip that pops up in the Cybercash window; this charge slip is forwarded to the merchant's credit-card processor. Cybercash also intends to support debit and peer-to-peer transactions through Cybercash accounts.	The customer buys E-cash from a participating bank. The customer can pay with an account transfer or with E-cash received from other custom. The E-cash client keeps files of encrypted digital-cash tokens (called "coins") and provides a graphical interface that allows the client to buy, send, and receive money and review the transaction log.
How merchant is paid	With credit-card transactions, the merchant gets paid by a participating credit-card processor. With debit transactions, money appears in the merchant's Cybercash account after a one-day clearing period.	The merchant calls the client software over the Internet (technically, the client acts as a server) and asks for payment. The merchant redeems each E-cash token with a payment server at the issuing bank, which transfers money to the merchant's account. All payments are final; the merchant need not budget for challenges.
How a transaction is handled	The customer connects with a participating merchant via a WWW browser. When the customer presses the RPAYS button on a form, the merchant server sends a message that invokes the Cybercash software and asks for money. A window pops up, asking the customer to either authorize a debit transaction or fill out a credit-card form. The client software signs and encrypts the form and sends it to the payment server. The payment server forwards the information to the merchant's credit-card processor (for credit) or to the customer's bank (for debit) for authorization. The payment server signs and encrypts an authorization token and sends it back to the customer's client software, which sends it back to the merchant.	The customer buys E-cash coins for his or her digital wallet and then starts a WWW browser or other Internet software. When a merchant wants payment from the customer, the merchant's server sends a payment request to the client software. The E-cash client software pops up the customer approves the payment, and the client software sends E-cash coins to the merchant. The merchant then connects with the bayment server and sends the coins to the bank. The bank checks the note numbers and signature, redeems them by transferring money to the merchant, and sends back a verification message. It's possible for the E-cash client software, running in a tiny window, to have a policy to authorize transactions automatically.
Support for small micropayments	Cybercash intends to support large transactions for both hard goods and bill payments, as well as debit micropayments for small units of information.	Yes.
Accounting services or capabilities	None, All authentication, subscription accounting, and cumulative billing must take place on the merchant's server. Cybercash only clears the eventual payments.	Digicash provides no accounting. By collecting receipts, and possibly to auditing the redemption of notes, however, a business can impose accountability on E-cash.
Cost per transaction	Cybercash charges a fixed fee per transaction, with no percentage add-on. For credit-card authorization, the charge is 5 cents, to which the credit-card processor adds its customary fee, often 2 percent plus 20 cents. The Cybercash charge for a debit transaction is 30 cents, with no processing fee. The company intends to bring down the cost of Cybercash debit transactions.	Digicash is a development company, not a payment-services company It will charge the banks that sell E-cash some type of licensing fee, al- though details are still unknown. Customers and merchants will pay a transaction fee to the bank. As a pure debit system with no collection problems, E-cash should be noticeably less expensive than credit-care clearing.
Risks to merchant and customer	Cybercash accounts earn no interest and cost the customer float. Under "card-not-present" rules (similar to those for telephone sales), the merchant is liable for fraudulent credit-card transactions. There is currently no mechanism for handling disputed debit transactions, so presumably the customer assumes all the risk with those.	Lost or stolen E-cash can't be recovered, nor can payments to un- scrupulous merchants. Because a note is untraceable, all notes in circulation must be voided if the issuer's key is embezzled. The custor gets a signed receipt from the merchant, but payment is final and can be reversed if the merchant fails to deliver. The customer loses the flo with E-cash.
Security and privacy	The client software includes RSA public-key encryption; the user unlocks the private key with a password when the software starts up. The customer's bank receives detailed information on each transaction, but a customer can remain anonymous to the merchant except for IP address. The Cybercash client can be installed as a viewer in the WWW browser; in the future, this will allow the merchant to request money through a firewall. The client will also use HTTP proxy services to communicate across a firewall.	A customer can remain anonymous to the merchant except for IP address. A client creates notes with a random note number and an amount, and a bank signs them. When a bank gets a note for redemption, it checks for a valid signature and an unredeemed note nun Neither the bank nor the merchant knows who bought a particular note but the customer can go to the bank and find out who redeemed the nor this is known as one-way HTTP privacy. The current technique does work through firewalls. Digicash plans to offer its own proxy software.
Special hardware	None.	None.
Suitability for applications	Well suited for home banking and catalog sales. Poorly suited for WWW information sales.	Target market is information sales. E-cash is efficient for small transact and is well suited for transferring funds. Governments have valid concabout the use of E-cash for money laundering, gambling, and other prohibited activities.
Problems	A customer must enter a credit-card slip for every transaction and forgo the benefits of subscriptions and cumulative billing.	No bank has yet stepped forward to self E-cash.

OPEN MARKET	WAVE METER
Credit.	Debit.
The Open Market payment server works with any WWW browser.	Requires dedicated software for browsing Wave-encrypted information. The software uses the Wave Meter API to perform decryption and metering appropriate for the application.
The merchant integrates functions from Open Market into its WWW server. These functions create payment URLs (uniform resource locators) for forwarding to the payment server. Open Market also sells its own S-HTTP server, which works with its payment server.	The merchant designs custom applications software using the Wave API.
Currently, the customer must pay with a credit card. Open Market intends to support direct corporate billing as well.	Customers "buy" money in advance by starting a communications program and entering credit-card information. The communications program calls Wave Systems and downloads credits to the Wave Meter chip.
The ACH (Automated Clearing House) transfers payment to the merchant's account.	When a customer calls up Wave Systems to get more credit, the Wave Meter chip downloads usage information, and Wave Systems pays the merchant.
A transaction begins when the merchant server sends the customer an HTML (Hypertext Markup Language) document containing a button with a payment URL. This URL contains the payment server's address, an item description, the merchant's name, the price, and a secret key signature. When the user presses the button to invoke the payment URL, it goes to the payment server rather than to the merchant. The payment server then begins an authentication dialogue with the customer. When the payment server finishes authorizing the transaction, the server issues a redirect to the customer's browser, instructing it to contact the merchant server with an authorization URL. The merchant server then releases the product.	When the customer wants to use a particular item, the browsing software performs a transaction with the Wave Meter, which retrieves a secret key and subtracts money from the credit accumulator. The processes of charging and decrypting can be hidden from the user.
The Open Market server will aggregate small transactions into \$35 credit-card charges, making it suitable for low-value information sales.	There is no per-transaction charge, so the Wave Meter is suitable for small- valued transactions.
The Open Market payment server intends to offer authentication, subscription verification, and the purchase and verification of temporary subscriptions. Open Market intends to offer business-to-business direct billing in the future.	The Wave Meter has counters and clocks for subscriptions and can meter software rentals. A planned Novell NetWare server-based product will consolidate bills for all LAN users, with individual credit limits and client bill-back codes. This will be especially useful in law firms.
Merchant costs are 3 percent plus 20 cents per transaction, plus setup fees.	Wave Systems charges the merchant a negotiable rate, currently 20 percent to 40 percent of the total revenue.
The merchant assumes the risk of fraud.	The customer "buys" money in advance and loses the float. Losses are borne by both the customer and the merchant. If a machine goes out of service before the customer uses up the credit in the Wave Meter, the customer loses. If the customer stops using the service or the machine, or if communications fail, the merchant loses the revenue to Wave Systems.
Asks for passwords and other information, so an encrypting browser is recommended. Open Market currently supports S-HTTP encrypting browsers. Open Market receives detailed information on each transaction, but a customer can remain anonymous to the merchant except for IP address.	Wave Systems keeps a detailed record of all transactions. This information can be distributed to the merchant.
None.	A Wave Meter must be installed on a local machine or on a local Novell NetWarnetwork.
The system is intended for sales of both hard and soft goods.	Target market is pay-per-use information distribution via encrypted CD-ROM, satellite or FM broadcast, and daily downloads. Also suitable for software distribution; enterprise licensing; and pay-per-play, CD-based games.



	FIRST DATA/NETSCAPE	FIRST VIRTUAL
Credit- or debit-based?	Credit.	Credit.
Customer software	The customer must have the encrypting Netscape WWW browser, which is free for noncommercial distribution and \$39 per copy for commercial use.	No special software is required. Interested parties can use any WWW browser and E-mail reader with First Virtual. To sign up for an account, users call an automated telephone center that takes their credit-card information.
Merchant software	Merchants must have the encrypting Netscape Commerce Server (\$5000) and First Data interface software. With the current implementation, the merchant must run a dedicated phone line to First Data's processing center, which costs several hundred dollars per month.	The merchant must integrate a set of free communications routines with its server.
How customer pays	A credit-card charge is assessed for each transaction.	The customer can pay via credit card or via ACH transactions, which are authorized when a voided check is sent in.
How merchant is paid	The merchant gets a normal bank transfer from First Data.	The merchant gets paid via an ACH transfer to its bank account.
How a transaction is handled	The merchant makes up an HTML form that contains information about the transaction. The customer enters a credit-card number on the form and returns it to the merchant's server with Netscape's built-in encryption. A script running on the merchant's server forwards the credit-card information (as a standard authorization transaction) over a dedicated phone line to First Data's credit-card-processing center. When the charge is authorized, the rest of the transaction proceeds.	The merchant initiates a transaction by displaying a WWW form that asks the customer for his or her unencrypted, unsecured password. The merchant software forwards the password and a description of the transaction to the First Virtual payment server. The customer then receives E-mail from First Virtual asking for authorization. The customer can reply with Yes, No, or Fraud. If the client replies No, he or she isn't billed, but a high percentage of No responses gets the customer kicked off the service as a freeloader if the customer replies Fraud, he or she does not get billed. However, his or her account is then deactivated, and he or she must call to obtain a new password.
Support for small micropayments	No.	No.
Accounting services or capabilities	Additional modules in the Netscape server, which are announced but not yet available, should provide subscription accounting and billing.	None.
Cost per transaction	Costs are identical to the merchant's existing card-not-present processing fees.	First Virtual charges the merchant 2 percent plus 29 cents per transaction.
Risks to merchant and customer	The merchant assumes all risk.	The merchant assumes all risk. For this reason, First Virtual suggests that the service is most suitable for information sales, where the cost of distributing nonpaid products is negligible.
Security and privacy	Uses secure HTTP with Netscape. The Netscape server provides password-based access restrictions. There is no privacy; the merchant receives all the customer's purchase and credit-card information.	First Virtual receives detailed information on each transaction, but the customer can remain anonymous to the merchant except for his or her IP address.
Special hardware	None.	None.
Suitability for applications	Well suited for catalog and subscription sales.	Target market is sales of software, low- to moderately priced information, and information subscriptions.
Problems	Poor security for users; expensive for merchants.	The payment schedule is uncertain, the sign-up mechanism is automated and clunky, and the "virtual" concept doesn't seem to support a real service organization.

customer must interact with the payment server on every transaction. BYTE rates this product's suitability as good.

Wave Systems: Like a Vending Machine

Wave Systems' Wave Meter, now in beta testing, represents a totally different, hardware-based approach to digital cash. It includes a chip that you install in your computer. You download money to the chip, which then meters it out as you spend it.

Wave Systems, a five-year-old public company, was founded by Peter Sprague, chairman of chip maker National Semiconductor. According to Sprague, "we follow the vending-machine model." The Wave Meter can be used to sell information, software licenses, or software time.

The Wave Meter is also good for metering and unlocking information that arrives on encrypted one-way media, such as CD-ROM and satellite or FM broadcast. But the complex Wave Meter system is not competitive with central payment servers, and therefore BYTE rates its prospects and usefulness as poor.

Winners and Losers

These six systems take a wide variety of approaches. As mentioned earlier, each has applications where it's especially well suited, but each also has its limitations and may not work so well for other purposes.

Furthermore, these digital-cash systems are quite literally in their infancy. None has enough of a track record to guarantee

its future. And we have yet to see what some of the important players, including the major credit-card organizations, plan to do. Finally, the evolving nature of commerce on the Internet also means that a system that works now may become impractical next year.

These are all serious obstacles that digital-cash systems must overcome. But we can be certain that good solutions will indeed appear. After all, the cyberspace community needs to get on with business.


Andrew Singleton is president of Money.Com (Cambridge, MA), a provider of financial information services on the Internet. You can reach him on the Internet at andy@payment.com or on BIX c/o "editors."

C L A R I Y

If You Think Vivid Clarity
Sounds Underpriced,
You'll Be Absolutely
Overwhelmed When
You See What A
Developer's Dream
It Is.

Tired. Tired. Of no iterative development for client/server. Of weak prototyping. Of complex data organizing tools. We know you are. We've been there.

That's why we decided to do something about it. Create Vivid Clarity.
So you can do something about it.
Order Vivid Clarity.



The first 5000 copies are going for the let's-get-acquainted price of \$149. No kidding. That's all. For all of this:

- · Easy, rapid visual modeling
- User views prototype prior to coding
- User modification without re-coding
- Automatically generates prototype in PowerBuilder
- Completely configurable DDL generation
- Generates to/Reengineers from Oracle, Sybase, ODBC
- OLE automation-fully open
- Object Gallery-browse for executable and reusable objects
- Bridges CASE to client/server
- Windows based
- Functionally robust for corporate use
- Easy, easy, easy

Hey, we're not asking for a big commitment here. Try Vivid Clarity for 30 days. If you don't go bonkers over it, send it back. At \$149, the refund isn't going to kill us.

All it takes to place your order is one card — Visa, MasterCard or American Express (preferably your own). And one call — 1-800-654-3249 ext. 3507.

Don't delay. When those 5000 go, the price goes to \$495. (Kids to feed.) Plus, isn't it about time you were able to turn chaos into Clarity faster than you can say "cool"?

InTek.

1-800-654-3249 ext. 3507

1-404-815-5283 ext 3507

AX 1-404-239-1723

We'd like to expose you to the Next-Generation of PC client/server computing. For free.

(SEE BOTTOMLINE FOR DETAILS.)



D1995 Oracle Corporation. All rights reserved. Oracle is a registered tradecurk. Oracle Town Spirming and handling not technique.

DOWNLOAD ORACLE WORKGROUP/2000 OFF THE INTERNET AND TRY IT FREE FOR 90 DAYS.

Oracle Workgroup/2000 is the

applications

one thing you need to build a

easier than

PC-based client/server system.

ever before.



To tost drive Workgroup/2000, just log on. http://www.oracle.com/

day trial or

register for our

free seminar.

With powerful and easy-to-use

But we're not asking you to take

http://www.oracle.com/

Oracle Workgroup

databases,

our word for it. We're ready to

prove it. Log onto Oracle's Web

and tools, Oracle Workgroup/2000

Proof that you can. middleware

page and download Oracle


makes building and installing

Workgroup/2000 for a free 90

Oracle Workgroup/2000[™] includes:

- Oracle7 Workgroup Server[™]
- Personal Oracle7™ for Windows
- Oracle Objects[™] for OLE And coming soon:
- Oracle Radio Agents™
- Oracle Power Objects[™]





What Makes HASP the Best **Protection Your Software** Can Get?

"Aladdin's HASP has helped us increase our revenues by providing us with extremely reliable and user-friendly protection for our software. In addition, Aladdin's service and technical support are simply first class."

Frank LaMonica, Chairman, Vibrant Graphics

"Quark/QSS has chosen HASP and MacHASP to protect QuarkXpress® in our most demanding markets, because we believe that Aladdin's products meet the high standards of reliability, compatibility and security required for these markets."

John MacMonagle, Purchasing Manager, Quark/QSS



"Aladdin's HASP gives our customers the key to protecting their investment in software development."

David Assia, CEO, Magic Software Enterprises Ltd.

"We have been most impressed with the quality of the HASP keys, as well as with the excellent support provided by Aladdin. We have tried a number of protection methods, but for ease-of-use, cost, and reliability, we keep coming back to HASP."

Jeremy du Plessis, Director, Indexia Research









■ Australia Contab 3 8985685 ■ Benelux Aladdin Benelux 08894 19777 ■ Czech Atlas 2 766085 ■ Chile Micrologica 2 222 1388 Berendsen 39 577300 • Egypt Zeineldein 2 3604632 • Finland 10-Systems 0 870 3520 • Germany CSS 201 278804

■ Greece Unibrain 1 6856320 ■ Haby Partner Data 2 26147380 ■ Japan Athena 3 58 213284 ■ Korea Dae-A 2 848 4481 ■ Mexico SiSoft 5 5439770 New Zealand Training 4 5666014 Poland Systhem 61 480273 Portugal Futurmatica 1 4116269 Russia Aladdin R.D. 095 9230588 ■ South Africa D Le Roux 11 886 4704 ■ Spain PC Hardware 3 4493193 ■ Switzerland Opag 61 7169222 ■ Talwan Teco 2 555 9676 ■ Turkey Mikrobeta 312 467 7504

Since 1984, thousands of leading developers in over 60 countries have chosen HASP to protect their software. Why? Because HASP's security, reliability, and ease-of-use led them to a simple conclusion: HASP is the most effective software protection system available.

LISTEN TO THE EXPERTS:

In all the products we tested, except the HASP, we could see through the encrypting and questioning procedures... and crack them.

CT Magazine (Germany)

MemoHASP: ...of all the protection devices tested is without any doubt, the one which combines the best features.

PCompatible (Spain)

Trying to crack a program... that was protected utilizing all of HASP's features - is like searching for the Holy Grail.

Micro Systems (France)

PC dongles... come with varying claims as to their transparency. The majority suffer from problems when a printer is connected... the HASP-3 is not affected...

Program Now (UK)

Of all keys tested, HASP is the most ambitious one... the quality of HASP manufacturing seems excellent. PC Compatible (France)

MacHASP is an optimal protection method, for the programmers... and for the users...

Bit Magazine (Italy)

Software piracy is costing developers over \$12 billion a year in lost revenues. To date, over one million HASP keys have been used to protect billions of dollars worth of software worldwide.

Call us today to find out how HASP can help increase your revenues.

1-800-223-4277

The Professional's Choice

North America Aladdin Software Security Inc. Tel: (800) 223 4277, (212) 564 5678

Fax: (212) 564 3377 E-mail: sales@hasp.com

Intl Office

Aladdin Knowledge Systems Ltd. Tel: 972-3-537 5795, Fax: 972-3-537 5796

E-mail: aladdin@aladdin.co.il

United **Kingdom**

Aladdin Knowledge Systems UK Ltd Tel: 01753-622266, Fax: 01753-622262

Aladdin France SA Tel: 1 40 85 98 85, Fax: 1 41 21 90 56

Circle 61 on Inquiry Card.

Windows for Control Freaks

PETER D. VARHOL

friend of mine is searching in vain for the Zen of Windows. He seeks a way to magically fit together all the individual and often disjointed pieces of Windows programming into a coherent whole. This enlightened programming model would yield an intuitive feel for Windows applications design. APIs would be simple details that you look up as you need them.


His search has been futile because the Windows programming model is

fundamentally incoherent. He'd have far more luck if he turned his attention to Photon, the new windowing environment for QNX, where coherence is as natural as the air on Mt. Fuji.

Photon gives developers a great deal of control over how processes respond to events. Best of all, this control is built into the architecture rather than being something that a developer must

add, as in Windows. The Photon windowing model depicts processes and events that programmers must take into account when developing applications for a windowing system (see the text box "The Photon Architecture" on page 84). This type of control is important for specialized applications ranging from a handwriting-recognition program for PDAs (personal digital assistants) to applications for data acquisition and process control devices.

Photon is an optional module for QNX, a Posix-compliant real-time OS (see "QNX Forges Ahead," October 1994 BYTE). In about 650 lines of code, the 10-KB QNX microkernel performs IPC (interprocess communications) locally and over a network, process scheduling, and interrupt redirection. You need only about 14 system calls to access these services. QNX is a message-



s,

Photon lives for event-driven applications for PDAs, process control, and data acquisition.

passing OS that doesn't distinguish between local and remote messages. This is one feature that makes it an excellent distributed OS.

Photon is built on these same principles. The Photon microkernel is a resource manager that creates a graphical event space and manages regions and events in that space. The Photon microkernel is about 24 KB of code plus 40 KB of data. Extra components, such as shared libraries and drivers, might increase the amount of code and data to about 250 KB. The Photon Window Manager adds 24 KB of code and 48 KB of data.

In addition to Photon, QNX offers as an option a full X11R5 implementation of the X Window System, with the Motif window manager, scalable fonts, and font server. X uses the QNX message passing for communication between QNX kernels and uses TCP/IP for communication with other X servers.)

QNX runs its device drivers as user processes, which means you can dynamically load drivers when you need them. For example,

The Photon Architecture


tem that waits for the user (or sometimes the system) to send a signal; it then redirects the signal to the appropriate process or processes. Photon developers control whether and how

various processes respond to the same events. This control is a characteristic of Photon's architecture rather than being something that a developer must add. The Photon microkernel is also compact: about 24 KB of code plus 40 KB of data.

Process Regions
Application processes own regions that enable applications and device drivers to interact with the Photon event space.
Applications and drivers differ only in how they respond to and generate events.
Every region has two properties that determine how it responds to events—

Every region has two properties that determine how it responds to events—sensitivity and opacity. If a region is sensitive to an event, the process that owns the region collects a copy of the event. If it's insensitive, the event is ignored, if the region is opaque, the event is clipped, or possibly changed in some manner (see the "Clipped Regions" icon). If transparent, the event passes through the region unaltered.

A region may be both sensitive and opaque, which allows the owning process to act as a filter. Such a process might collect a connected sequence of pen events: After a touch pen writes a word, the process performs handwriting recognition and then generates the equivalent keyboard events in the event space. Apple's Newton does handwriting recognition, but not with such a coherent model of operation.




Why the Photon Programming Model Is Important

t makes windowing programming and windowing behavior more consistent by depicting the behavior of processes and events important to programmers. By contrast, the Microsoft Windows programming model is less coherent. A process (each individual window) doesn't normally receive an event unless it's the active process (the one closest to the user). If you want other processes (other windows in the same application) to respond to events, Windows requires you to find a way to do this. The active window may collect an event and then pass it on to other windows, like prospectors panning for gold. If the first

prospector (the process) finds a gold nugget, he or she keeps it; if it is fool's gold, he or she throws it back into the stream for the next prospector. Implemented in a process-by-process manner in Windows, this type of solution is natural behavior in Photon.

drawn on screen.

Event control like this is important for a handwriting-recognition program in a PDA or for data-acquisition and process-control applications. For example, you might want a user-initiated event to change the visual image of an instrument control and also have that event let a process-control driver send a signal to an electronic control.



Programmer's Notes

rogramming for Photon centers on initially positioning a region, telling the Photon microkernel which types of events are relevant to the region and then dispatching based on the event received. Photon consists of a single X Window System-like API. The API may consist of four separate libraries: graphics; a Pho-

ton Window Manager, which is optional; AppBuilder, a visual C-code application development environment; and widget, the user-interface component. The windows manager can automatically control windows and regions created by applications. The window manager creates icons, and resizes and repositions process regions within event space.

Photon and X may require a mouse driver, and X may need to access a CD-ROM drive. To load these, you simply type Mouse msoft </dev/serl for a Microsoft serial mouse, and Fsys. Aha4scsi for an Adaptec-compatible SCSI CD-ROM drive. The drivers load into user space, find the devices, and make them available to the system. Running drivers in the user space provides MMU (memory management unit) protection for user processes. Also, you can use a full screen source code debugger to debug device drivers. You might think that running device drivers in user space causes unacceptable performance penalties, but we haven't noticed any problems with the QNX applications we have built.

Photon is remarkably easy to install for a Unix-like product. We just loaded the requisite drivers from the command line, called the install program on the floppy or CD-ROM drive, and launched the program. Because QNX runs everything as a process, we only had to rebuild the kernel when we upgraded the base OS.

How easy is Photon to use? The first time we used Photon, its application-builder module wouldn't launch. But after taking a quick trip through the Photon documentation, we discovered that we had to run Photon in Super VGA mode. We then simply returned to the QNX command line, ran the Super VGA driver, and returned to Photon.

Windows for the Masses

If programmers use the Photon model depicted at left, there should be no question about the behavior of their process in response to events. Furthermore, programming becomes more straightforward because the model is consistent and easily extensible without much effort. Our experience with Photon backs that up: We wrote a resource-scheduling application in only about 100 lines of code.

While it is natural to compare Photon to a general-purpose windowing system like Windows, the comparison may be a poor one. Photon is not designed for general-purpose use, and it has fewer APIs than Windows or other known systems. The Photon event model may not be widely usable in general-purpose computing. Imagine a transparent process that automatically passes mouse-clicks through to other applications. Without controlling or even knowing about the behavior of all running applications, such a process can wreak havoc.

Photon is designed for an application environment that is more controlled than a Windows application environment. A Photon programmer of one process should know

Get That Data

hoton can be useful for real-time display of data in data acquisition applications and for process control. Using the AppBuilder visual-application designer, you can write an application that intercepts events coming in asynchronously and displays them graphically in any desirable fashion.

Because the default QNX scheduler lets you schedule real-time events, data acquisition can be real time. (If you don't like the default scheduler, you can write your own—it runs in user space). Photon is capable of updating the display faster than the display's refresh rate. This is a waste of CPU cycles, because it has to wait for the display to update before you can see any changes. Thus, it makes sense to constrain Photon data acquisition events to correspond to the display refresh rate (e.g., 72 Hz).

Process control can work in reverse. As data comes in and is displayed, events can be generated in the other direction. You can generate a touchscreen or light-pen pointer event, to which a control process is opaque. The control process translates the light-pen event into an appropriate control signal, which Photon then transmits out through a port to an instrument that can respond to it.

what other processes are running under the windowing system. Therefore, events for one process will not be mistakenly intercepted by others.

But the behavior of processes in Photon defaults to the opaque value of the opacity property (see the "Process Region" icon on page 84), so under normal circumstances, it behaves like Windows or X (Photon defaults to Motif window manager).

If you want to do something unusual, you have to adjust the properties of the processes. For example, in a process control application, you might want a series of different processes to simultaneously receive the same mouse-click signal. In this instance, you probably don't also want to run Photon as a general-pur-

pose windowing system.

Photon need not run on the same system as its processes. Some developers are even running Photon under Windows on separate systems simply by passing process events to and from the Photon manager, which runs as a Windows process.

Photon uses a coherent model of process interaction in an event-driven environment. If your benchmark is Windows or a general-purpose windowing system, you can appre-

ciate QNX and Photon as being small and elegant operating environments for processcontrol and real-time

QNX\$795
Photon ...\$95
QNX Software Systems, Ltd.
Kanata, Ontario, Canada
(800) 676-0566
(613) 591-0931
fax: (613) 591-3579
Http://WWW.QNX.com
FTP.QNX.com:/pub/papers
Circle 978 on Inquiry Card.

systems. As Photon develops, we may see it appear on more desktops as an alternative windowing system. ■

Peter D. Varhol is chair of the graduate computer science department at Rivier College in Nashua, New Hampshire. You can reach him on the Internet or BIX at pvarhol@bix.com.



SEE WHT'S MSSNG FRM YR CMPRSSD IMGS?

Genuine Fractal Quality."

CD-ROM publishers—get the blg picture!

Compress PC images down to 1% of their original size... Maintain image quality...Get fast decompression. See for yourself how a major publisher puts over 10,000 images on a CD-ROM. High quality images come

up in seconds—no special hardware required—with Fractal Compression.^{5M}

Let's discuss details.

No artifacts, no pseudo color, no Gibbs effect. High image quality at *any* resolution. Fractal Compressionst from Iterated is the *quality* compression technology.

Improve your image. Call today.

Join Microsoft, Grolier and other powerhouse CD-ROM publishers. Let Genuine Fractal Quality[™] improve *your* image. Call today for a free demo disk.

Call (800) 437-2285 now! (+1) (404) 840-0310 Fax (+1) (404) 840-0806




"WE SELECTED FRACTAL TECHNOLOGY AS THE BEST OVERALL MIX OF COMPRESSION, IMAGE QUALITY AND SPEED."

—MICROSOFT MULTIMEDIA PUBLISHING GROUP



YOU CAN USE A SPREADSHEET TO ANALYZE DATA. OR YOU CAN USE CORNERSTONE.



Access, analyze, visualize and present – all in Cornerstone's integrated environment.

Introducing Cornerstone for Windows. The fastest path to the answers you need.

A spreadsheet wasn't designed for exploratory data analysis. So it's not the quickest and easiest way to turn data into information.

Cornerstone for Windows, however, gives you the power

to swiftly access, analyze, visualize and present data. All in an integrated environment that delivers the answers you need – faster and easier than any spreadsheet can.

BBN/Cornerstone™

To get things moving, send for your free Data Kit. It's got details on Cornerstone, user application stories and Data Analysis: New Tools for Expanding Needs, a special report from the Seybold Group. For your Kit, call 1-800-331-2266 or fax the coupon

today. And pick up the pace of your data analysis.

GET MOVING!

Rush me my free Data Kit! Fax this completed coupon to 1-508-429-8395. Email: Cornerstone@bbn.com.

NAME
TITLE
ADDRES
CITY
PHONE

COMPANY

ADDRESS

CITY STATE ZIP


Call BBN Software Products 800 331 2266 ext. 130


© 1995, BBN/Cornerstone Software Products Corporation. Cornerstone is a trademark of Bolt Beranek and Newman Inc. Windows is a trademark of Microsoft Corporation.


ZEOS Can Ship Today!

Tired of waiting and waiting for your new PC? Wait no more. With our special *Computers Now!* program many of our award-winning and most popular packages can be shipped the same day you call.

It's As Easy As:







Our Guarantee To You:

If we accept your order for immediate shipment and fail to ship your system under the conditions outlined, we will ship it at our expense as soon as it is ready.*

Need A Bigger Monitor?

We can upgrade your *Computers Now!* desktop or vertical system with a larger monitor—and still ship it the same day you order!*

Buy With Confidence

Not only are you getting a ZEOS PC fast, you're getting a fast PC. ZEOS has earned dozens of top industry awards for power and performance, besting the competitors time and time again. With an awesome price, ZEOS computers *are* your best value.

That's not all. ZEOS gives you the best support in the business—for an even better value.

In fact, ZEOS has earned seven *PC Magazine*Readers' Choice for Service & Reliability awards. And ZEOS was the first to provide 24-hour toll-free technical support—365 days a year—for quick and accurate answers to all your technical questions.

To order your high-performance PC, call a ZEOS Systems Consultant today at 800-554-5226.



Pantera™ 486DX2-66 **\$1645**

Pentium-60 **\$1895**

Pentium-75

Package #2:

- ➤ 8MB RAM
- ➤ 850MB local bus IDE hard drive
- ➤ 4X CD-ROM drive, 3.5" 1.44MB floppy drive
- Diamond Stealth 64 PCI local bus graphics card with IMB DRAM
- ➤ I4" SVGA color monitor
- ➤ 6-bay desktop case
- ➤ MS-DOS 6.2, Windows for Workgroups, Microsoft Mouse



Pentium-60 \$2095 Pentium-75 \$2145

PanteraTh

Discovery™ MM:

- ➤ 8MB RAM
- ➤ 528MB local bus IDE hard drive
- ➤ 4X CD-ROM drive, 3.5" 1.44MB floppy drive
- ➤ Stereo sound card and speakers
- ➤ 14,400 bps send/receive fax modem
- Diamond Stealth 64 PCI local bus graphics card with 1MB DRAM
- ➤ 14"SVGA color monitor
- 6-bay desktop case
- ➤ MS-DOS 6.2, Windows for Workgroups, Microsoft Mouse
- ➤ Lotus SmartSuite





Top Gun:

- ➤ 8MB RAM, 256K SRAM cache
- ➤ 850MB local bus IDE hard drive
- ➤ 4X CD-ROM drive, 3.5" 1.44MB floppy drive
- ➤ 14,400 bps send/receive fax modem
- ➤ Diamond Stealth 64 Video PCI local bus graphics card with 2MB VRAM
- ➤ 15"SVGA color monitor
- ➤ 6-bay desktop case
- ➤ MS-DOS 6.2, Windows for Workgroups, Microsoft Mouse
- ➤ Lotus SmartSuite

*Orders must be for Computers Now! configurations; we've listed just a sampling here. Since we continuously update this list of configurations, please call to confirm your system as on the list. This offer is good only as long as these pre-built systems remain in stock. Monitor upgrades available as long as monitors remain in stock. Other ZEOS systems and configurations take slightly longer—about a week. Credit curs are subject to authorization. Orders must be received by 1 p m. Central Time, N-F.

Purchase orders are subject to approval. Business leasing programs smallable. All prices, specifications and availability are subject to change without notice; call to confirm these and warranty details. Prices do not include shipping. All products and company names are trademarks of their respective holders. ZEOS and Contends are registered trademarks; Computiers Novil is a registered servicemanic Z-Card is a servicemark. Ambra, Partera and ZEOS Meridian trademarks of Micron Electronics, Inc. © 1995 MEI. ZEOS International, USI Industrial Bhrd., Minneapolis, MN 55413 USA. Micron Electronics, Inc. is a publicity traded company (NASDAQ symbol: MUE1).



Pantera™ 486DX2-66 \$2145 Pentium-75 \$2445 Pentium-90 \$2595

Package #3:

- ➤ 16MB RAM
- ➤ 1GB local bus IDE hard drive
- ➤ 4X CD-ROM drive, 35"1.44MB floppy drive
- Diamond Stealth 64 PCI local bus graphics card with IMB DRAM
- ➤ 15"SVGA color monitor
- ➤ 6-bay desktop case
- ➤ MS-DOS 6.2, Windows for Workgroups, Microsoft Mouse
- ➤ Lotus SmartSuite



Pantera™ Pentium-75 \$2545 Pentium-90 \$2745 Pentium-100 \$2895

Hottest:

- ➤ 16MB RAM, 256K SRAM cache
- ➤ 1GB local bus IDE hard drive
- ➤ 4X CD-ROM drive, 3.5" 1.44MB floppy drive
 ➤ Diamond Stealth 64 Video PCI local bus graphics card with 2MB VRAM
- ➤ 15 "SVGA color monitor
- ➤ 6-bay desktop case (Pentium-75) 10-bay vertical case (Pentium 90 & 100)
- ➤ MS-DOS 6.2, Windows for Workgroups, Microsoft Mouse
- ➤ Lotus SmartSuite



Pantera™ Pentium-75 \$2745 Pentium-90 \$2895

Discovery Plus:

- ➤ 16MB RAM, 256K SRAM cache
- 850MB local bus IDE hard drive
- ➤ 4X CD-ROM drive, 3.5" 1.44MB floppy drive
- ➤ Stereo sound card, high-power speakers w/subwoofer
- 14,400 bps send/receive fax modem
- Diamond Stealth 64 PCI local bus graphics card with 1MB DRAM
- ➤ 15 "SVGA color monitor
- ➤ 6-bay desktop case
- MS-DOS 6.2, Windows for Workgroups, Microsoft Mouse
- ➤ Lotus SmartSuite





Pantera™ Pentium-75

\$2995 Pentium-90 \$3145

Best MM:

- ➤ 16MB RAM, 256K SRAM cache
- ➤ 850MB local bus IDE hard drive
- ➤ 4X CD-ROM drive, 35" 1.44MB floppy drive
- ➤ Stereo sound card and speakers
- ➤ Diamond Stealth 64 Video PCI local bus graphics card with 2MB VRAM
- ➤ 17 "SVGA color monitor
- ➤ 10-bay vertical case
- ➤ MS-DOS 6.2, Windows for Workgroups, Microsoft Mouse
- ➤ Lotus SmartSuite



Pantera™ Pentium-90 \$3695 Pentium-100 \$3845 Pentium-120 \$4145

Best MM Supreme:

- ➤ 24MB RAM, 256K SRAM cache
- ➤ 1.2GB local bus IDE hard drive
- ➤ 4X CD-ROM drive, 35" 1.44MB floppy drive
- ➤ Stereo sound card, high-power speakers w/ subwoofer
- ➤ Diamond Stealth 64 Video PCI local bus graphics card with 2MB VRAM
- ➤ 17 "SVGA color monitor
- ➤ 10-bay vertical case
- ➤ MS-DOS 6.2, Windows for Workgroups, Microsoft Mouse
- ➤ Lotus SmartSuite



Ambra™ 486DX2-66 \$1345

Package

- ➤ 8MB RAM, 128K SRAM cache
- ➤ 528MB hard drive
- ➤ 3.5" 1.44MB floppy drive
- ➤ On-board VESA local bus video
- ➤ 14"SVGA color monitor
- ➤ 4-bay desktop case
- ➤ MS-DOS 6.2, Windows for Workgroups, Microsoft Mouse



Meridian™ 400C 486DX2-50

\$2595 DX4-100 \$2995

Package

- ➤ 8MB RAM
- ➤ 350MB IDE hard drive
- ➤ External 35" 1.44MB floppy drive
- ➤ 14.4 PCMCIA fax/modem
- ➤ 7.9 "dual-scan color VGA display
- ➤ Custom leather carrying case
- ➤ Extra battery
- ➤ MS-DOS 6.2, Windows for Workgroups
- ➤ Lotus Organizer
- ➤ 7.8" x 10.2" x 1.7", 3.9 lbs.

For active matrix display, add \$700



Meridian™ 800C 486DX2-50

\$2695 DX4-100

\$3095

Package #3:

- ➤ 8MB RAM
- ➤ 528MB IDE hard drive
- ➤ Internal 3.5" 1.44MB floppy drive
- ➤ 14.4 PCMCIA fax/modem
- ➤ 10.3" dual-scan color VGA display ➤ Custom nylon carrying case
- Extra battery
- ➤ MS-DOS 6.2, Windows for Workgroups
- ➤ Lotus Organizer
- ➤ 8.9" x 11.7" x 1.9"; 6.3 lbs.
- For active matrix display, add \$800



Meridian™ 850C Pentium-75 \$3995

Package #2:

- 16MB RAM, 256K synchronous SRAM cache
- ➤ 528MB IDE hard drive
- ➤ Internal 35" 1.44MB floppy drive
- ➤ Integrated stereo sound
- ➤ 10.3" dual-scan color SVGA display
- ➤ Custom nylon carrying case
- ➤ Extra battery
- ➤ MS-DOS 6.2, Windows for Workgroups
- ➤ Lotus Organizer
- ➤ 8.9" x 11.7" x 2.1"; 6.8 lbs.

Fax Orders: 800-362-1205 or 612-362-1205. Phone Orders: Outside U.S. and Canada: 612-362-1212, Government: 800-245-2449, ZEOS Information Systems, Inc. GSA #GS00K94AGS5176. Purchase Orders, MasterCard, VISA, Am Ex, Discover, Z-Card, COD and leasing programs.

800-554-5226 24 Hours a Day • 365 Days a Year



Data Express: Rugged Removability

Data Express, a family of durable removable carriers, houses a hard disk or DAT (Digital Audio Tape) device, adding up to 36GB plus the many

benefits of storage removability to your PC or workstation. Data Express is available internally; mounting into your computer system drive bay, or externally; housed in steel enclosures and equipped with a fan and power supply. Data Express boasts an industry leading 25,000 insertions for long lasting removability. Constructed of steel and equipped with superior ventilation, Data Express provides the peripheral cooling needed when using large capacity devices.

Data Silo: Durable External Housing



Kingston's Data Silo is a family of stand alone external storage enclosures for half-height or full-height 5.25" or


3.5" SCSI peripherals. Data Silo is available in versions to house one, two, four, or nine SCSI devices simultaneously providing the utmost flexibility for storage expansion, disk array environments, and peripheral integration. Each Data Silo is equipped with its own power supply and fan and constructed of 100% steel, making Data Silo the most durable external storage enclosure available today.

Storage Versatility



Kingston's Data Silo four and nine bay units provide ideal drive stacking features for use in disk array environ-

ments. Data Silo also houses Kingston's Data Express products, which provide all the benefits of storage removability including data security and portability.



Industry-Leading, Five-Year Warranty

Every Data Express and Data Silo
comes equipped with a
comprehensive five year
warranty and free technical
support. Designed specifically

for PC and workstation users, Data Express and Data Silo provide unsurpassed storage flexibility and quality.

Every Product 100% Tested

Kingston guarantees the highest quality available by testing every product prior to shipping.

Information At Your Fingertips

To get the facts on Data Express and Data Silo, call our convenient RAMFax fax on-demand service toll-free and request

ALLEGAL FREE
(800)435-0056

© 1994 Kingston Technology Corporation. All Trademarks and Registered Trademarks are of their Respective bolders. Kingston Technology is a registered trademark of Kingston Technology.

document number 8310. For immediate assistance, contact Kingston's Storage Products group at:

(800) 435-0670

Kingston

THE INSIDE NAME IN UPGRADES

Kingston Technology Corporation 17600 Newbope Street, Fountain Valley, CA 92708 (714) 438-1850 • Fax (714) 438-1847

Break Up Your Network

BRETT HUSSELBAUGH

our network is probably considerably less efficient than it could be. Dividing it into smaller subnets can significantly enhance performance in most cases. Segmentation is one of the most important but least understood aspects of a highly tuned network.

To segment a network is to divide it into two or more physically independent competition domains. Consider the figure "Network Segmentation" on page 92 which shows a token-ring network before and after segmentation. In its original, single-domain configuration, all seven nodes had to compete for the single token serving the network.


Now look what happens when the network is segmented into three separate competition domains, or rings-one for the server, one for three workstations. and one for the other three workstations. After segmentation, the worst-case scenario is three workstations competing for a token, and there are three tokens serving the network. Of course, you have to add an extra piece of equipment—the bridge that connects the three rings. Network segmentation requires one or more internetworking devices, such as a bridge, a packet switch, or a router, to connect the segments into a single logical network.

The Bandwidth Misconception

Network performance is most com-

monly quantified in terms of bandwidth. However, using bandwidth techniques to predict network performance is fraught with inadequacies. (See "Misusing Bandwidth" in the December 1994 BYTE.) One particular problem with bandwidth is its failure to take competition into account.

For example, say you have a new network application that you want to roll out to 40 users, although you don't expect more than 10 to ever be using it simultaneously. Before you install it, however, you want to make sure that the application won't




By dividing your network into smaller. interconnected segments, you can increase throughput by reducing competition

overload the net and bog down total throughput of your 16-Mbps token ring. So the first thing you do is to take a series of measurements with a network analyzer, and it tells you that one workstation will demand an average throughput of 51.2 Kbps. If you're still thinking in terms of bandwidth, you can make the following calculations:

10 simultaneous workstations \times 51.2 Kbps = 512 Kbps $512 \text{ Kbps} \times 8 \text{ bits per byte} = 4.096 \text{ Mbps}$

4.096 Mbps requires only 25 percent of a 16-Mbps bandwidth

Therefore, you conclude that your 16-Mbps token-ring network will comfortably sustain the required traffic. Unfortunately, bandwidth doesn't tell the whole story. Keep this example in mind, and later on we'll compare it to a far more effective method for predicting network performance.



Competing for Queue Space

Queuing theory is a branch of mathematics that grew out of telephone traffic studies conducted at the beginning of the twentieth century. It is used extensively to model packet-switched as well as circuit-switched networks. Because it handles the probabilistic nature of communication systems, queuing theory is an effective tool for network analysis.

In its simplest form, a queue is nothing more than a place where things can wait their turn for service. The line at the bank and a network computer's incoming-packet buffer are both examples of queues. A queue will have one or more servers (not to be confused with file servers), which are processes that move items through the queue. One or more tellers, for example, deal with customers in the bank line, and one or more operating-system processes will service the incoming-packet buffer.

We can further describe a queue in terms of two rates—the rate at which new things appear in the queue for service (λ) , and the rate at which things are serviced or removed from the queue (μ) . As λ exceeds μ —that is, as new items appear faster than they can be serviced—the queue will begin to lengthen. If λ continues to exceed μ ,

the queue buffer will eventually be filled, and any additional new items presented for service will be rejected.

We can model a network as a large, distributed queue. The figure "Distributed M/G/1 Queue—Token-Ring Segment" shows the concept graphically. Packets


wait in a number of packet buffers that are distributed among the various active nodes until the network can service them. The queue's server here is the network's access methodology. In the case of a token-ring network, therefore, the queue's server is the token itself.

Competition occurs on a network because, in general, only one node may transmit on the media at any given time. As competition increases, therefore, each node spends more and more time waiting for the token, until we reach a point at which the wait time becomes far greater than the time actually spent transmitting. Using queuing theory, we can quantify the time spent waiting on the media.

Modeling the Network

In analyzing the effects of competition on a segment, we'll focus on token-ring networks. CSMA/CD (Ethernet) performance usually degrades sharply as competition is raised, giving the network administrator highly discernible notice that segmentation is required. Token-ring performance, on the other hand, degrades more gracefully, and it might not be readily apparent that performance can be significantly improved. By modeling token ring as a queuing system, we can study the effects of competition and discover the influence of other parameters, such as packet size. (This example is somewhat simplified. We don't consider either early token release or such windowing methodologies as packet burst.)

We will consider a token-ring segment as a queue model that has the following characteristics: Markov arrival statistics (also called Poisson distributed), generally distributed service times, and a single



ost of today's client/server development tools force your applications to be driven by the outward appearance of things.

It's akin to putting in all the walls, windows and doorways of a building before the foundation and support beams are in place. You can build a small cottage that way, but certainly not a skyscraper.

The same principle holds true for client/server application tools. Especially if you are working with multiple databases and extremely large communities of users.

Which is why you should consider evaluating our powerful, 2.0 version of Enterprise Developer.

front-end screen
or graphic, you can
put all of your
business rules and
all of your data
models in place first.

Then our SCALE
C++ objects provide
you with all of
the transaction
structures
required
for your

graphical

development tool sets. The bottom line is scalable, robust, enterprise-wide applications in record time.

So don't settle for a client/server development tool set that's just a facade.

Call and enroll in our

Symantec Enterprise Developer ensures that your client/server applications won't end up as great looking front-ends that are unable to stand up to the stresses of the real world.

IS YOUR CLIENT/SERVER DEVELOPMENT TOOL JUST A FACADE?

ENTERPRISE DEVELOPER 2.0. FOR THE FASTEST DELIVERY OF ROBUST ENTERPRISE-WIDE APPLICATIONS.

Unlike other client/server tools, Enterprise Developer 2.0 isolates the many complex components of client/server development in its own unique SCALE™ architecture.

The foundation of this new architecture is a business model repository that centralizes and stores your logical data models, the data locations, and all of your business rules separately from the presentation services.

So before you ever design a

interface, delivering the complex logic that would take months to

ENTERPRISE DEVELOPER 2.0.

SCALE REPOSITORY
Business Model: reverselforward engineer
logical data models from your databases.
Store business rules for all of your clientl
server applications, View data models
through interactive E-R Diagrammer.

Database Trigger Express: optimize performance by partitioning business rule logic between client and servers through generation of database triggers.

SCALE C++ OBJECTS
Leverage the information in the
business model to derive the master
detail processing, business rule
enforcement, multi-user access,
transaction integrity and data caching
behavior for each application.

VISUAL ENVIRONMENT RAD is fostered through our active business model repository and a high level of default processing, shrinking development from months to weeks. Enterprise Developer Evaluation Program where you can examine the structural superiority of our new Enterprise Developer for yourself.

Then get ready to develop robust, client/server applications that have the structural integrity to really scale across the enterprise.

CALL 1-800-488-9914.

Ask for Ext. 9AP1 and request Enterprise Developer Evaluation Program information. U.S. only. In Canada, call 1-800-667-8661, extension 5518. In Australia, call 2-879-6577.



Symanux: is a registered trademark and Enterprise Developer and SCALE are trademarks of Symanics Corporation. All other brand names or trademarks are the property of their respective to holden. For information in the U.K., call 1628-592222. © 1995 Symanics Corporation. All rights reserved.

SYMANTEC

MANAGING THE ENTERPRISE.

Circle 96 on Inquiry Card.

Feature

queue server. (Thus we call this an M/G/1 queue.) Poisson arrival statistics means that packets reach the network from the individual network nodes in a fairly random fashion. Generally distributed service times (as used here) means that, once a packet is granted access, the transmission time follows a uniform statistical distribution. Simply stated, this means that we'll consider that all packets are the same size.

We can determine the wait time in an M/G/1 queue using the following equation, which you'll find in any book on classical queuing theory:

$$E[T] = \frac{1}{\mu - \lambda} \left[1 - \frac{\lambda}{2\mu} (1 - \mu^2 \sigma^2) \right]$$

Where

E[T] = average wait time

μ = packet service rate, in packets per second

λ = packet demand rate, in packets per second

 σ^2 = variance of packet size distribution

We adapt this equation to the token-ring model by appropriately defining the rate at which packets are generated for transmission on the segment (λ) and the rate at which packets are serviced (μ)—that is, accepted for transmission, transmitted, and the token freed. We define these parameters as follows:


$$\lambda = 2a\lambda_{\mu}N_{\mu}$$

$$\frac{1}{\mu} = \frac{10N_p}{f_s} + N_u t_d$$

Where

 λ_u = source rate per user, in packets per

 N_{ij} = number of inserted users



Here data-transfer efficiency increases, because far fewer transmissions are required to move the same volume of data. Therefore, the network is stable right up through 100 inserted stations. However, once we get to 50 stations, the wait time begins to exceed the transmission time.

a = percentage of inserted users wishing to transmit simultaneously

 N_p = average number of bytes per package

 f_s = signaling rate in bits per second

 t_d = time delay due to inserted station, in

We need the factor of 2 in the equation for λ because, in most client/server environments, every packet from a client must be answered by a packet from the server. Also, the factor of 10 in the equation for μ accounts for the 8 bits per byte, plus an additional 1.25 factor for packet overhead and other node delays in the system.

Applying the Model


How can these equations help us tune our network? They can tell us how many segments to divide our network into, and how many nodes to put on each segment, based on parameters that fit the needs of a particular network.

The first thing to do is decide what level of packet demand we're interested in, along with a figure (expressed as a percentage of the total) that represents the number of stations actively transmitting on a network segment. We can plug these numbers into the equation and plot the results against the number of inserted stations on the segment.

Let's look at an actual example, shown in the figure "Small Packet, High Composite Rate." This models the same situation as we used earlier in the bandwidth analysis. In this case, we're showing a 512-Kbps throughput demand placed on the network by a composite set of nodes. The packets are uniform in size, but small, at 256 bytes. Notice how the length of time each node must wait for a token builds to roughly 6 ms before going negative at approximately 20 inserted stations. This means each packet spends 47 times as long waiting for the token as it does actually transmitting its data.

And what does it mean when the wait time goes negative on the plot? In fact, it becomes mathematically undefined at that point, which means that the real-world network becomes unstable and begins to drop packets. This analysis suggests that, if we want to achieve any kind of reasonable performance, we need to limit any segment that we're asking to carry 512 Kbps using 256-byte packets to no more than five inserted users.

This is a significantly different conclusion than we got from our bandwidth analysis, which suggested that a 16-Mbps token ring would easily sustain 512-Kbps throughput for 10 users. The discrepancy occurs because the bandwidth-centric




This illustrates a 512-Kbps throughput demand that a composite set of nodes places on the network. The 256-byte packets are uniform but small, and the waiting time for a token builds to roughly 6 ms before going negative at approximately 20 inserted stations. At that point, the real-world network becomes unstable and can drop packets.

magine roaring through the development process in a fraction of the time it takes with Microsoft Visual C++ or Borland C++. All you need is new Symantec C++ 7.0 with full support for Windows 95 Preview Program, Windows NT 3.5, Windows 3.1 and DOS.

THE FIRST TRULY OBJECT-ORIENTED C++ ENVIRONMENT.

Symantec C++ 7.0 is the only C++ that lets you architect and navigate your application with a dynamic Class Editor and graphical Hierarchy Editor. This



6.0 - the world's fastest linker.

For building great Windows

and Debugging Environment (IDDE) provides the most powerful debugging

ARCHITECT. NAVIGATE. BUILD. DEBUG. NEW SYMANTEC C++ 7.0 IS THE FASTEST WAY TO DO IT ALL.

great new system incrementally parses your C and C++ code and displays an up-to-date structural model of your program without compiling. But that's only the beginning. It also lets you modify any class's inheritance graphically. Plus it automatically locates any class implementation, and much more!

THE NETBUILD REVOLUTION.

Now you can build applications faster than you've ever imagined. With the new NetBuild," you can automatically distribute the build process over multiple computers on your LAN, dramatically reducing build times.

In addition, AppExpress,™ Class-Express,™ and ProjectExpress,™ give you Wizard-like functionality to boost your productivity.

And to make your link-cycle lightning-fast, there's new 32-bit OPTLINK® resources easily, we've added ResourceStudio – the new OLE 2.0based resource editor that supports the widest range of Windows resources including Windows 95.

POWER DEBUGGING FOR WINDOWS 3.1 AND NT.

Symantec's Integrated Development

CLASS EDITOR AND HIERARCHY EDITOR dramatically increase your productivity.

NETBUILD

distributes the build process across networked resources for the fastest build times.

SUPPORT FOR WINDOWS 95 Preview as well as Windows NT 3.5, Windows 3.1 and DOS.

APPEXPRESS, CLASSEXPRESS AND PROJECTEXPRESS automate time-consuming tasks.

OPTLINK® 6.0
is the fastest linker in the world.
IDDE WITH 16 AND
32-BIT DEBUGGING


for Windows 95 beta, NT 3.5 & Windows 3.1

Inspector View, hardware watchpoints and low-level debugging.

features including Thread View,

Of course, all of these productivity-boosting tools are integrated with a language that supports key standards like ANSI C++ (exception handling, templates and RTTI) and NT structured exception handling. And unlike Borland, Symantec supports MFC and includes it free.

In short, no other C++ lets you do it all this fast. Call the toll-free number below and see for yourself.



SYMANTEC.

analysis fails to consider the effects of competition. And as we can see, those effects can seriously reduce performance by having the workstations waste considerable time just waiting for access to the

Now, let's consider another case, where we have the same composite throughput demand as before, but we've increased the packet size to 2080 bytes. The results are shown in the figure "Large Packet, High Composite Rate" on the previous page. Notice the difference. Data-transfer efficiency has been greatly increased, since far fewer transmissions are required to move the same volume of data. The result is a stable network right up through 100 inserted stations. Even here, however, although the network is stable, once we get to 50 stations the wait time begins to exceed the transmission time, indicating unacceptable performance. Thus, if we wanted to segment this network conservatively, we'd keep each segment down to, say, 30 to 40 workstations.

One obvious point is that competition is greatly influenced by the number of transmissions per second, but hardly at all by the volume of data to be moved. Therefore, when considering competition, it's important to think of throughput in terms of packets per second, not bandwidth utilization and certainly not bytes per second.

Drawing Conclusions

The analysis technique that we've just described should be used primarily as a qualitative aid in understanding just how sensitive network performance is to segment competition. Like all models, this one is based on certain assumptions, but there appears to be a high degree of correlation with observations of real-world

We can draw several conclusions from studying this model. First, increasing competition on a network segment increases each user's average waiting time. Since more time is spent in simply waiting for the token, less time is spent in transmitting. Competition has the effect of limiting the amount of available bandwidth that can actually be used.

Second, simply upgrading older workstations with newer technology can create a competition problem where none previously existed. The newer technology is faster and can send out packets at a higher rate. This will create more competition on that particular segment and can result in slower network performance. When upgrading workstations on a large scale, therefore, don't forget to budget for addiWe might almost consider competition to be a parasite that feeds on available bandwidth. It robs a network of usable bandwidth by causing nodes to waste considerable time just

sitting around, waiting for the token to arrive.

tional network segmentation and the connecting hardware needed to link the new segments.

Software makes a difference, too. Rolling

out a new application can also create a competition problem. It all depends on how the application uses the available packet payload and on how much data it needs to move. For example, some database applications move data based on the record size of the tables being accessed. For small data records, this can result in very inefficient data transfer and create a significant competition problem.

Software packages that use a windowing technology, such as packet burst, on a LAN or any other shared media can create a serious competition problem. Windowing technology allows a series of packets to be sent in rapid succession, with only a single required response from the destination (typically a server). This can quickly boost competition. For other types of applications, the normal, internal node-processing delays on the server and workstation actually help to limit competition.

One of the most subtly difficult things to understand about network segmentation stems from the seemingly intuitive observation that, since all traffic is generally directed to the same server, it eventually has to funnel down to the single segment that's occupied by that server. So why bother to segment the network? From a simple, bandwidth-analysis perspective, there's no clear advantage, and segmentation cannot be justified. The bandwidth argument suggests that even with multiple 16-Mbps segments, they eventually have to feed into a single 16-Mbps segment to reach the server. Thus the fastest that data can move is 16 Mbps, and any gains the network might have earned from parallelism will have been

But we have already seen that such bandwidth-centered arguments fail to take competition into account; their simplicity is deceiving. We might almost consider competition to be a parasite that feeds on available bandwidth. It robs a network of usable bandwidth by causing nodes to waste considerable time just sitting around,

> waiting for the token to arrive. Segmentation, on the other hand, serves to limit competition and thus allows more efficient use of the available bandwidth.

A Continuing Concern


There's no simple, cookbook methodology for determining how to segment a network, and how big each segment should be, because there are so many factors at work. Our recommendation is to measure your current network traf-

fic with a sniffer or other network monitoring device, then perform your own analysis similar to the one described above, using throughput and packet-size data that reflect your own network conditions. This will yield a rough measure of whether or not your network can benefit from segmentation and will indicate the maximum number of workstations you should place on any given segment.

Segmentation is also an important ongoing maintenance function that you constantly have to keep in mind when tuning your network. Any given network segment can become overloaded for a variety of reasons: adding new clients, upgrading older technology, rolling out a new application, or introducing windowing or other new technologies. And once a segment is overloaded, competition can drive its performance down dramatically.

So analyzing competition and segmenting your network isn't something you can do just once and then forget about. Periodically, you need to reexamine the way your network is segmented and make sure that individual workstations aren't spending too much of their time waiting in line.

Brett Husselbaugh is president of Tobek Computer Systems, a small LAN consulting firm in Dallas, Texas. He holds a master's degree in electrical engineering, with emphasis in telecommunications, and has analyzed many large LANs. You can reach him on the Internet at wbretth@aol.com or on BIX c/o "editors."



New and improved technologies are finally breaking down the barriers that impede the progress of mobile computing



Radio Days

The wireless infrastructure that will make mobile computers ubiquitous is incomplete, but it's slowly maturing.

PAGE 107



Color to Go

LCDs will likely remain dominant for the next few years, despite flirtations with new screen technologies.

PAGE 115



Brainy, Brawny Batteries

Smart batteries and new chemistries promise longer lives for tomorrow's mobile devices.

PAGE 131



PDAs Bounce Back

Although significant obstacles remain, PDAs are gradually evolving into practical business tools.

PAGE 147



ALL NOTEBOOKS GO THROUGH HELL. **GET ONE THAT SURVIVED IT.**



"***** **Best Overall** PC Computing **Torture Test**

Presenting the unshockable Dell* Latitude XP™ notebook. Recently back from PC Computing's Notebook Hell and winner of the Best Overall Award in the Annual Notebook Torture Test.

For ten weeks they baked, froze, dropped, even spilled hot coffee on thirteen notebooks. They analyzed useability. They scrutinized portability. They measured battery life.

In the end, the Dell Latitude XP notebook was the only one to receive the coveted Five Star rating. And the magazine remarked, "the Latitude [XP] braved our durability tests with nary a scratch - surviving in better shape than any notebook we tested." Then they pronounced it, "the best travelling six-pound machine you'll find."

So, as you're looking for a notebook that can withstand the rigors of the daily grind, call us. We'll send you the indestructible Dell Latitude XP. The notebook you can put through hell. And then back on your desk.



DELL LATITUDE XP IntelDX4™ 100MHz System

- 9.5" Active Matrix Color Display • 16MB RAM/810MB Removable HDD
- · 3 Year Warranty

\$5198

Product Code #600039 (Pictured System)

DELL LATITUDE XP IntelDX4 100MHz System

- · 9.5" Dual Scan Color Display
- 16MB RAM/524MB Removable HDD · 3 Year Warranty

\$3998

Product Code #600050

DELL LATITUDE™ IntelDX475MHz System[‡]

- 9.5" Dual Scan Color Display
 8MB RAM/340MB Upgradeable HDD
 Second NiMH Battery*—\$99 more
- · 1 Year Warranty†

\$2299

Product Code #600041

DELL LATITUDE IntelDX4 75MHz System[‡]

- 9.5" Dual Scan Color Display
 4MB RAM/260MB Upgradeable HDD
 Second NiMH Battery" \$99 more
- · 1 Year Warranty†

\$1999

Product Code #600035



(800) 247-5531

MONDAY-FRIDAY 7AM-9PM CT • SATURDAY 10AM-6PM CT • SUNDAY 12PM-5PM CT KEYCODE #01024 • CANADA* CALL 800-387-5755 • MEXICO CITY* CALL 800-228-7811

FROM HERE TO

ANDY REINHARDT

s long as there have been mobile computers, there have been compromises. It is simply not possible to provide all the capabilities of a full-powered desktop system in a package small and light enough to carry comfortably. The history of mobile system design has been about choosing which features and functions to sacrifice in favor of others.

However, those compromises are gradually disappearing. For example, surging yields and falling costs of activematrix LCD screens have made high-quality color laptops almost commonplace. Indeed, thanks to greatly improved passive-matrix LCDs, color screens now constitute the baseline. IBM doesn't expect to produce any monochrome ThinkPads after 1995.

Power-conserving CPUs, augmented by sophisticated power management schemes, are driving top-of-the-line performance into notebook-sized packages. Hard drive and memory configurations are almost the same in desktops and portables. And nearly all mobile systems come with built-in pointing devices.

Even some seemingly insurmountable design hurdles are giving way to clever solutions. Consider the keyboard problem, for instance. Because human fingers aren't getting any smaller, how do you provide a full-size keyboard in a package the size of a

subnotebook? IBM engineers came up with an ingenious answer in the ThinkPad 701C "Butterfly"—a keyboard that unfolds when you open the lid.

One indication of how small the gap between desktop and mobile systems has become is that Compaq engineers reportedly refer to notebooks as DFEs, or desktop functional equivalents. This nickname also reveals another truth, in the opinion of analyst Richard Shaffer: The only successful portable systems today are extensions to existing desktop architectures. Virtually all the radically different mobile devices introduced over the past three years—especially PDAs (personal digital assistants)—have failed to find their promised markets. Except for inexpensive organizers, such as the Sharp Wizard, no hand-held devices have established themselves in the marketplace.

The lukewarm reception for pen-based computers reinforces the belief that users won't accept too many compromises. Pen-based technology is still evolving, however, so dozens of companies both large and small continue to work on pocket-size devices that differ radically from conventional QWERTY-based laptops.

Today, the main difference between portable computers and deskbound systems is price. This isn't likely to change soon, because portables require rugged construction, miniaturized parts, LCD screens, and other components that make them cost more than their higher-volume commodity desktop cousins.

> The biggest technical challenges facing mobile computers today are the demands for longer battery life, better displays, and a broad-based wireless communications infrastructure. In addition, engineers are striving to improve user interfaces and provide better data sharing between portables and desktops.

The Grand Challenges

The holy grail of portability is a system that runs on batteries long enough for a round-trip flight from New York to Singapore. If today's notebook computers relied entirely on solidstate components and didn't

have backlit screens, that goal wouldn't be out of the question; rechargeable batteries have improved significantly over the past few years. But the recent addition of large-capacity hard disks, LCD backlighting, color screens, megabytes of RAM, high-powered CPUs, and even such accessories as CD-ROM drives and stereo speakers are draining the batteries more quickly than ever.

Because battery technology is fairly mature and improving slowly, the most recent gains are coming from better power management. The latest portables know how to power down their hungriest components during idle periods and even scale back the CPU speed between keystrokes. One of the most interesting advances is the so-called "smart" battery that uses its own microprocessor to monitor and manage the

There's not much left that mobile computers don't do as well or better than desktop systems. And when the remaining challenges are solved, mobile technology will significantly change the face of computing.

MOBILITY

rates of discharge and recharge. Smart batteries last longer and provide users with more accurate predictions about running and charging times.

Another, less obvious advantage is that smart batteries hide the complex charging characteristics of a battery from

the host computer. This gives the engineers greater latitude when designing the power subsystem, and it provides a growth path toward emerging battery technologies.

One of the real surprises of the last few years has been the unexpectedly rapid arrival of lithium-ion and lithium-polymer batteries. Lithium ion had been used for years in tiny, nonrechargeable camera batteries, but techniques for safe recharging were developed only recently. Lithiumpolymer, still a lab experiment five years ago, is on the verge of arriving in commercial products, Zinc-air cells, which are based on an older technology, are just beginning to achieve their potential. too. Author Gil Bassak in his piece, "Brainy,

Brawny Batteries," describes these and other developments in mobile power systems.

Better than a CRT

Active-matrix LCD screens began showing up in portables about four years ago, but they were devilishly hard to manufacture and, hence, expensive. Now companies such as Sharp and Hitachi, and the Toshiba/IBM joint venture Display Technologies are cranking out millions of panels a year,

and the difference in price between active- and passive-matrix screens has dropped to less than \$1000.

It is now availability, not cost, that is holding back the universal adoption of active-matrix screens. To meet the growing demand for color portables, vendors are turning to

improved passive-matrix panels. In "Color To Go," author Chris Chinnock explains how manufacturers are inventing new techniques for enhancing the quality of passive screens, such as the "active addressing" technology from Motif, a joint venture of Motorola and In Focus Systems.

For the foreseeable future, LCDs will continue to deliver the best combination of price and performance. But some alternatives are beginning to appear on the horizon. Among these are different types of silicon that could be used to fabricate higherperformance, higherresolution displays. Other contenders include FEDs (Field Emission Displays), which are like flat CRTs, and AMEL (active-matrix electroluminescent)

panels. None of these, however, is expected to show up in mass-market portables for several years.



The dream of mobile computing will be only partly realized if "anytime, anywhere" data communications isn't made more practical. This is especially true for hand-held devices. Some analysts are convinced that the limited acceptance of PDAs has a lot to do with their limited capabilities for



Special Report Mobile Computing

wireless communications. They think PDAs should be designed as wireless communications devices that can also compute instead of as pocket-sized computers that have some ability to communicate.

Over the past three years, two trends have strengthened the support for communications in mobile systems. The first is that an increasing number of notebooks offer internal data/fax modems capable of speeds as fast as 14.4 Kbps, eliminating the need to carry an external modem. (Often, however, the internal modem is still an extra-cost option.) The second trend is the rising popularity of PCMCIA slots and user-installed modem cards. These two developments are making it easier to get on line while traveling on the road.

Adding a modem solves only half the problem, of course. The greater challenge is tapping into a communications infrastructure that is not very accommodating to mobile computers. The wired telephone system is admirably ubiquitous, but plugging wires into phone jacks is a hassle and chains you to a wall. Wireless connections appear more attractive, but the infrastructure is nowhere near as mature as the wired phone system.

The first and most obvious contender in wireless communications was analog cellular, because it is so widely available. But the early round of products was relatively expensive, slow, and unreliable. This provoked users and vendors to consider other approaches, such as private packet radio networks and the promising CDPD (cellular digital packet data) standard, which interleaves short data packets into the breaks between analog cellular calls. Companies such as Motorola laid out grand road maps for their PCMCIA wireless modems, and analysts made bold predictions of market growth.

But instead there has been a resurgence of interest in analog cellular, fueled by the arrival of new technologies such as AT&T's ETC (Enhanced Throughput Cellular) protocol. The undeniable advantage of analog cellular is that it's here now and is relatively familiar and easy to use. This is partly because it is circuit-switched and connection-oriented, like the wired phone system, so it works with your existing communications software and applications. Also, if you've already got a cellular account, you needn't subscribe to another service for data communications.


Meanwhile, the growth of other wireless options continues, but at slower rates than predicted. The Ardis and RAM Mobile Data packet radio networks have attracted enormous attention and serve many customers, especially in vertical markets. But because they're proprietary and not yet universally available, they haven't become broad-based, horizontal solutions. CDPD is finally emerging, but it's too early to assess its cost efficiency or acceptance. In "Radio Days," BYTE news editor Salvatore Salamone discusses these services and the efforts underway to bridge their differences.

Two additional technologies hold promise for the future. One is PCS (Personal Communications Services), the swaths of bandwidth recently opened up and auctioned off by the U.S. Federal Communications Commission. PCS devices and services will compete with cellular phones, and the competition could drive down prices for all forms of wireless communication. However, PCS won't be widely

available for several years, and even when it is, service providers will probably focus their early attention on voice traffic rather than the more specialized market for data traffic.

The other essential communication technology of the future is software agents. (See "The Network with Smarts," October 1994 BYTE.) In IBM's proposed Intelligent Communications services, for example, agents that "live" in the network represent your preferences, so you can transparently connect to services using a variety of protocols and devices. Software agents hide specifics of the network from users, reducing the complexity of dealing with different services and providers. They can also route and filter messages, minimize traffic and connect time, convert data among different formats, and help users locate services on the network. Middleware tools such as Oracle in Motion will simplify the job of developing WANaware programs.

In the world of wireless communications, standards are growing up from hardware and down from applications. In the future, you'll be able to buy a single PCM-CIA card that will support different modulation schemes and transparently connect itself to a variety of services. Applications will talk to the networks through common APIs and network agents will do the bulk of your work—allowing you to focus on your job, not on the business of connecting and transmitting data.



Hanging On to Pens

Pen computing was undoubtedly overhyped, especially considering the state of the technology a few years ago. But the idea remains compelling, because not even IBM's clever Butterfly solves the problem of squeezing a usable keyboard into a computer that's small enough to fit in your pocket. Despite the many false starts, pen computing has a future.

A few companies are still plugging away: Apple is establishing the Newton MessagePad as a vertical-market tool; Magic Cap-based PDAs, such as Sony's Magic Link and Motorola's Envoy, are slowly gaining a toehold; and Palm Computing's Graffiti recognition engine has been a surprise hit.

For some people, PDAs have a certain psychological appeal because they refashion the computer as a true consumer device,

an able assistant and trusted electronic buddy. Although PDAs will gain from the same technological advances that benefit laptop computers, the problems they face are multiplied. Battery life, display quality, component costs, communication links—all are bigger challenges for hand-held devices.

In "PDAs Bounce Back," Michael Nadeau outlines the prospects for handheld systems. The bottom line, however, is that PDAs aren't going to be ready for prime time for a few more years. Only then will the right combination of technologies exist to break through psychological and economic barriers and propel PDAs into the mass market.

The eventual success of PDAs will dramatically alter the mobile landscape. Laptop computers that run desktop-class OSes will still exist, of course, but they'll be more oriented toward intensive computing tasks, as PDAs take over some of their duties. Indeed, for many people, a PDA might be all the computer they'll ever need.

If you came late to the first personal computer revolution, stick around. The flourishing power of mobile technology offers innumerable opportunities for users and vendors to embrace new standards and create a truly new paradigm of personal computing.

Andy Reinhardt is BYTE's former West Coast bureau chief. You can reach him on the Internet or BIX at areinhardt@bix.com.



Introducing the Apple MessagePad I20.

Put your office in the palm of your hand.

The new Apple® MessagePad™ 120 offers better screen clarity, more memory, and connectivity to both Windows™ and Macintosh® computers, so it's never been easier to manage your business away from the office. Just look what you'll get with a MessagePad 120 (2 MB configuration only):

- Pocket Quicken[™]—the powerful personal finance software (with coupon redemption*)
- Notion: The Newton List Manager—to help you organize and prioritize
- External modem—lets you send faxes and send/receive e-mail
- PowerNeWS[™] for staying in touch with world events**
- NewtonMail[™] exchange e-mail with subscribers of on-line services**

Free software & modem!
A value of over \$200.***


Get an Apple MessagePad 120 today. For more information on Newton software solutions and cellular capabilities, or for dealers nearest you, call 1 800 909-0260.



*Coupon is included in the MessagePad 120 box. **New subscribers receive service and usage at no charge for the first month. ***Value is based on the combined suggested retail price of the products included with purchase.

1995 Apple Computer, Inc. Minglist reserved. Apple, the Apple logo. Macintosh, and Newton are registered trademarks of Apple Computer, Inc. MessagePad, the Newton Logo, and Newton Mail are trademarks of Apple Computer, Inc. Windows is a trademark of Microsoft Corporation. Poor Quicken is a trademark of Intrut, Inc. Notion is a trademark of Intrut. Inc. Notion is a trademark o

IT'S AS FINELY TUNED UNDER THE ROOF



In designing the Galant LS, we strived to create a car that excelled in every respect. It offers more interior room

than Accord EX or Altima GLE.* And with an available Luxury Package, there's plush leather trim, an 8-speaker


INTRODUCING THE LUXURIOUS

Mitsubishi/Infinity® audio system, plus meaningful luxuries like a power driver's seat you can adjust four ways, and a

NEW GALANT LS.

security system with remote keyless entry. There's also an exclusive feature called Mitsubishi HomeLink[®], which lets you operate security gates, garage doors, even house lights, all as you pull up your driveway.¹ Powering the Galant is a confident 141-horsepower^{**} engine, with a very smooth automatic transmission. Anti-lock brakes are available, and dual air bags are standard. And, the Galant S starts at \$14,349, while the Galant LS with Luxury Package is \$23,164.¹¹ Probably why *Road & Track* said, "It's without question, a lot of car for the money."***To which you'll surely add, "A lot of *finely tuned* car for the money." For the Mitsubishi Motors Dealer nearest you, call 1-800-55MITSU.







FPS 60: MAXIMUM DIGITAL VIDEO PERFORMANCE.

- 2 video inputs VHS, S-VHS and Hi8 (NTSC, PAL, and SECAM)
- 1 video output VHS, S-VHS and Hi8 (NTSC, PAL, and SECAM)
- High Quality M-JPEG digitizing of all fields (60 NTSC / 50 PAL)
- Studio quality (4:2:2, 24bit True Color)
- Scalable overlay: full screen/full motion even at high resolutions (up to 1280x1024)
- Framegrabbing (in all standard graphics formats)
- Single Monitor Solution: Preview your picture on your PC monitor in overlay!
- FAST Installation: fast and easy via software; no feature connector, no jumpers. MCI/VfW-compatible
- Includes software for nonlinear video editing on hard disk
- Pluggable MPEG Extension (optional)

The right solution for frame-accurate Digital Video Editing, video integration in professional presentations, animation recording, multimedia applications and "edutainment" (Interactive Games, VideoCD, MPEG1-Video).



Radio Days

SALVATORE SALAMONE

onnecting to the office from remote locations is certainly easier than it used to be-many hotels catering to business travelers have added dataports to the phones in their guest rooms, and most airport terminals have public phones with modular jacks. But there are still numerous occasions when a wired modem connection is impractical or impossible: if you're visiting a client's office that has a digital PBX, for example, or if you spend much of your workday in a vehicle.

Mobile workers who have experienced the liberation of cellular phones are now demanding the same freedom for their digital communications. The most common need for a wireless link between a mobile worker and the office is to exchange E-mail. But many companies would also like to use wireless networks to connect outbound employees with corporate data and applications stored on the network servers, minicomputers, and mainframes in the home office.

The expansion of wireless communications from E-mail and fax to remote data access will take some time. One study estimates that by the year 2000 about 25 percent of cellular data users will still be using wireless connectivity only for personal communications (E-mail and faxing). The rest of the market for cellular data services will be split among several distinct types of users (see the figure "The Changing Mobile Market" on page 108).

For example, service technicians need access to technical documentation or warranty information at customer sites. Delivery and inventory workers need to transmit information gathered about packages or products. And then there are the professionals who require a full mobile office that provides access to remote applications, data, and personal communication services.

The companies that are trying to address this market face a number of obstacles (see the text box, "Wireless Applications Stumbling Blocks," on page 108). Perhaps the most serious problem is that low-bandwidth connections still plague wide-area wireless communications. In many areas, wireless networks are limited to data transfer rates of only 4.8 Kbps, which is much slower than the 14.4- or 28.8-Kbps connections now taken for granted with wired modems and analog phone lines. Wireless WANs look even worse when compared to wireless LANs, which typically deliver transfer rates of 1 to 2 Mbps.



Even if you're willing to settle for low throughput rates, there are still vast areas of the country (albeit mostly rural) that aren't covered by wireless services at all.

Another problem is the lack of standards. Businesses are often dismayed to discover they must use different

wireless modems and develop multiple versions of the

same remote-access software just to access all the different wireless services. To compound this difficulty, some enterprises must

develop their wireless applications to run on a wide variety of mobile platforms-everything from PDAs (personal digital assistants) with limited memory and processing power to Pentium-based laptops that rival high-end desktop systems. And as mentioned before, those mobile devices are increasingly expected to handle a lot more than just E-mail.

All these issues have kept most organizations from deploying wireless applications in any broad manner. Two notable exceptions are United Parcel Service and Federal Express, which use special wireless software and thousands of mobile computers to track all their packages in transit.

Fortunately, some recent developments should make it easier to create and deploy wireless applications. Wireless network providers are boosting their maximum throughput rates, new standards are coming with digital cellular networks, and there is a growing number of middleware products that should ease the chore of developing wireless

Many obstacles still hinder wireless communications, but expanded service offerings and new development tools are helping

applications or adapting existing applications to wireless use.

Improved Services

Wireless services are available in virtually every major city in the U.S.-about 90 percent of major metropolitan locations have coverage, according to industry sources. And some kind of wireless service is available in about 30 to 40 percent of the rest of the country. All together, about 80 percent of the U.S. population can get access to wireless networking.

Currently there are four major wireless choices:

- The existing cellular phone network is the most familiar method, because all you have to do is connect an analog modem to a cellular phone jack.
- CDPD (cellular digital packet data) is offered by the large telecommunications service providers, including AT&T, Bell Atlantic Mobile Systems, Nynex, GTE, Southwestern Bell, McCaw Cellular, and
- · RAM Mobile Data is a service of Bell-South Mobile Systems and RAM Broadcasting.
- · Ardis is a joint venture of Motorola and IBM.

The two leading providers, Ardis and RAM Mobile Data, are constantly expanding their coverage into new sections of the country. That trend is likely to accelerate, thanks to increased competition from CDPD networks.

Less than a dozen cities had CDPD service by the end of 1994. But in January, the CDPD Forum announced that 20 additional cities-including New York, St. Louis, Dallas, and San Diego-would have commercial CDPD service by April. Carriers are expected to announce commercial CDPD services for the top 50 metropolitan areas during the first half of this year.

Despite this progress, CDPD still has quite a bit of catching up to do. Ardis-a two-way, store-and-forward, packet-based wireless network—is available in every

state now and reaches more than 80 percent of the U.S. population.

However, don't get caught in a numbers game. Though the established service providers offer more extensive coverage, they may not cover the geographical regions in which your organization's mobile workers need to The Changing Mobile Market roam. Wireless data services are springing up from the cores of metropolitan areas and expanding outward. much in the way cellular phone networks began to spread. This is a logical way for services to grow, but it may no fit the needs of organi zations that wish to pro-

with access to corporate resources from far-flung locations.

vide their mobile workers

For instance, it's not hard to imagine a field service technician at a customer site in a rural area who needs access to technical documentation stored on the LAN back at the office. This is an excellent application for wireless communications. but before a company can rely on it, wireless data services must be deployed across broad regions of the country.

13%

25%

45%

Breaking the Speed Barrier

Another challenge for the wireless data industry is to overcome the traditionally low bandwidths of wide-area communications. Early users had to accept 4.8-Kbps connections, which seemed frustratingly slow compared to wired modems. Ardis now offers speeds of 19.2 Kbps in most large cities, though smaller cities are still limited to 4.8 Kbps. CDPD services and RAM Mobile Data also operate at 19.2 Kbps.

Some service providers hope to carve out a niche market for higher-speed wireless services. For example, Metricom plans to introduce a 100-Kbps wireless service in five U.S. cities (Atlanta, Boston, Chicago, Seattle, and Washington, D.C.) by the end of this year. Metricom already offers a 77-Kbps service in parts of Silicon Valley.

Most users want the highest speed available when connecting from the field. When two wired modems or fax machines establish a link over an analog phone line, they automatically negotiate the fastest com-

> mon speed they can support. After the link is negotiated, away you go. Ideally, wireless connections would work the same way. If Metricom's 77-Kbps service were available, your wireless device might choose that. If not, maybe it would route your connection through

By the year 2000, mobile workers will enjoy much more access to remote data and applications. That's in contrast to today's mobile market, in which wireless communications are primarily used for F-mail

Source: McLaughlin & Associates (Chicago)

a CDPD link at 19.2 Kbps. And if you're in a small town and neither service is available, perhaps it would fall back on the 4.8-Kbps Ardis network.

Unless you've got a trunkload of wireless modems, however, your chances of accomplishing such a feat are small. Each type of wireless service requires a different type of modem. Even though all the major wireless networks-including Ardis, CDPD, and RAM Mobile Data—operate in adjacent parts of the 800-MHz to 900-MHz frequency bands, they each use different modulation and transmission methods. That means users must have a different proprietary modem to tap into each service.

And that was no joke about a trunkload of modems. Until recently, wireless modems were about the size of a brick. Carrying several of them wouldn't be practical for most people.

In March, the first PCMCIA wireless modems were introduced at the Mobile '95 show in San Jose, California. Both IBM and Motorola exhibited radio modems in the form of PCMCIA Type III cards. IBM also announced a modern that supports both CDPD and circuit-switched cellular service in a single device, providing mobile users with access to two wireless options. However, it's still a far cry from the level of standardization that lets you connect any wired modern to any modular phone jack and place a call over any local or long-distance telephone network.

There is, at least, some movement toward standardized command sets and common APIs for wireless modems. The PCCA (Portable Computer and Communications Association) has defined a set of extensions to the traditional TIA-602 AT (Hayes) modem commands. Any wireless modem, regardless of the service to which it's connected, can use these extensions.

In addition, the PCCA and the WINSock Forum are developing wireless extensions for the two most common network adapter drivers: NDIS (Network Driver Interface Specification) and ODI (Open Data-Link Interface). Their goal is to specify common APIs that will make it easier to run LAN-based applications over

Wireless Applications Stumbling Blocks

- · Wireless networks must support increasingly complex applications
- Low throughput rates
- Support for a wide variety of mobile platforms
- · Service not ubiquitous
- Lack of standardization

Lost Your Modem Cable? Push The XJACK® Connector, Not The Panic Button.



Losing an external modem connector can be stressful. Unless you buy a modem that doesn't require one.

V.34 and the XJACK* connector



In the PCMCIA slot, XJACK pops out for use and back in for travel.

Only Megahertz offers a V.34 modem with the XJACK* connector built in. It simply pops out at the touch of a finger and hooks to any standard RJ-11 phone cord — an especially convenient feature considering the hassles of trying to find or replace proprietary external connectors.

Our connector is not only convenient, it's durable, too. Independent tests have proven the XJACK connector more dependable than all other PCMCIA connectors.

Save time, save money

Our 28,800 bps speed means more productivity for users and less time on phone lines. Which means less money tied up in data transmission. And because it is based on the ratified V.34 standard, you can be assured of the most reliable connections possible.

Megahertz modems also have the future built in with Flash ROM and Flash DSP upgradeability. Getting updates is as easy as downloading it from the Megahertz BBS at 801-320-8840.

So choose the only V.34 modern with the XJACK connector. And never panic over lost cables again.

For more information about the Megahertz V.34 modem, call 1-800-LINKING, ext. 4316.

Ethernet-Modem



Callulas Madas



Ethernet Adapter



Megahertz offers a complete line of industry-leading mobile connectivity solutions.





9 Where

Ardis

Lincolnshire, IL (708) 913-1215 fax: (708) 913-4700

CE Software Inc.

West Des Moines, IA (515) 221-1801 fax: (515) 221-1806 F-mail: cesoftware@mcimall.com

ConnectSoft

Bellevue, WA (800) 234-9497 (206) 827-6467 fax: (206) 822-9095

GTE Telecommunications Atlanta, GA (404) 391-8000

IRM

Armonk, NY (800) 426-3333 (914) 765-1900

Metricom, Inc.

Los Gatos, CA (800) 556-6123 (408) 399-8200

Motorola, Inc.

Wireless Data Group Schaumburg, IL (800) 233-0877 (708) 576-1600 fax: (708) 576-0710

Oracle

Redwood Shores, CA (800) 633-0596 (415) 506-7000 fax: (415) 506-7200

Racotek, Inc.

Minneapolis, MN (612) 832-9800 fax: (612) 832-9383

RadioMail Corp.

San Mateo, CA (415) 286-7800 fax: (415) 286-7801 E-mail: info@radiomail.net

RAM Mobile Data

Woodbridge, NJ (908) 602-5500

Xcelinet

Atlanta, GA (800) 322-3366 (404) 804-8100 fax: (404) 804-8102

wireless networks.

Wireless applications would be network-independent, so users could link their computers to any network. A single user could have access to several networks, or multiple users in different locations could have access to whatever services are available in their regions. In all cases, the same access methods would be used for any particular application.

Tightening Integration

Several vendors-including Motorola, CE Software, Oracle, Racotek, and Xcellnetare concentrating on middleware that more tightly integrates existing applications with wireless networks. Their goal is to minimize the liability of restricted bandwidth.

For example, Oracle in Motion is a network-independent tool that lets a company develop Windows-based wireless applications. It uses agents to reduce the backand-forth packet traffic that is common with LAN-based client/server software. In this case, Oracle in Motion uses an agent on the LAN to query a host.

Some of this middleware makes existing Windows applications compatible with wireless networks. For example, Radio-Mail Connection for Windows-developed by RadioMail and ConnectSoftprovides mobile messaging capabilities for Windows users. It's actually a wireless version of ConnectSoft's E-Mail Connection. With help from products like this, companies don't necessarily have to develop new wireless applications from scratch. Many existing applications can be used with little or no modification.

Thanks to new middleware, standardized command sets, common APIs, expanded geographical coverage, and improved transfer rates, the move to wireless WANs should be a much more manageable task.

Salvatore Salamone is a BYTE news editor based in Manhattan. You can reach him on the Internet or BIX at ssalamone@bix.com.

ere's a small piece of big news for everyone wbo

computes away from the office.

Pereos," the maximum mobile storage

device, bas arrived.

Now, if that doesn't make your eyes bug out, then you baven't arrived at home, at a botel, or at 30,000 feet, only to discover the data you need is back at the office.

never a problem. Because now you can take every-

bling -files, applications, utilities, presen-Lations and more - right along with you.

Pereos weighs less than ten ounces,

attaches to any parallel port on any PC, runs

for months on a pair of standard AA batteries and stores the equivalent of 868 floppies on a

cartridge the size of a postage stamp.

With Pereos, baving all the right stuff right now is It also comes complete with powerful data manage-

Which Would you rather carry around,

this cartridge or

868 floppies?

(Hint: the cartridge is far more

reliable)

ment software that locates and synchronizes your files and makes backup a breeze.

Call 800-328-2779 We'll explain bow bigb speed

data transfer makes Pereos the bandy way to move files from desktop to desktop - no network required.


DATASONIX

© 1995 Datasonix. Pereos is a registered trademark of Datasonix Corporation.



A Gigabyte of Data in the Palm of Your Hand.

Two Functions. One Card. Zero Hassles.



The Ethernet-Modem from Megahertz

No one understands the advantages of a combination Ethernet and modem card better than Megahertz. After all, it means one less thing to carry (or lose). One source for service and support. And only one PC slot required for simultaneous modem and Ethernet connections.

If you expect more from the company that has sold and supported more PCMCIA modems than all competitors combined, Megahertz won't disappoint you. Our single-

Now you can use your modem

and access your Ethernet network from a single PCMCIA slot.

minded focus on the mobile computer user has given us the ability to virtually eliminate card/notebook incompatibilities. Megahertz has also developed innovative solutions to common connectivity problems. Like a unique cable system that removes any confusion between modem and Ethernet connectors.

Additionally, our Ethernet • Modem offers low power consumption, saving battery life. And intelligent installation, making initial set-up fast and easy.

Call us for more details. Or visit our web page at http://www.xmission.com/~mhz.

You'll find that the Megahertz Ethernet • Modem doesn't just combine functions, it eliminates hassles.

V.34 Modem


Cellular Modem



Ethernet Adapter



Megahertz offers a complete line of industry-leading mobile connectivity solutions.











Introducing The First Notebook To Maximize The Pentium's Full Potential.

When the rush was on to introduce a notebook with a Pentium™ processor, Texas Instruments decided to do what others thought couldn't be done.

We created a notebook that maximizes

Pentium performance by integrating full PCI bus architecture in our TravelMate 5000.

And for flexible connectivity, we designed a way to allow external access from the PCI bus to the latest peripherals.

It was a challenge we addressed for two simple reasons: to give users true desktop Pentium performance for faster running software and expansion capabilities for investment protection.

So now you have a notebook with smoother full-motion video and enhanced 3-D graphics. In addition, we designed the TravelMate 5000 to take advantage of the "plug and play" capabilities of Windows 95° when it becomes available.

But our engineers didn't stop there.

We added a second lithium ion battery without sacrificing size, weight or eliminating a floppy drive.

In addition, wireless communication with other notebooks and desktops is very quick and easy with our integrated infrared capabilities.

The TI TravelMate 5000. For more information on what others thought you couldn't do with a notebook, simply call 1-800-TI-TEXAS (e-mail: 2ti@msg.ti.com).

EXTENDING YOUR REACH





Warranty may vary from country to country. Contact your local TI office for details. Batteries and options are covered by a one year limited warranty. "Depending on model. TravelMate and "Extending Your Reach" are trademarks of Texas Instruments. Windows 95 is a registered trademark of Microsoft Corporation. Pentium is a trademark and the Intel Inside logo is a registered trademark of Intel Corporation. © 1995 TI.

MORE DISK SPACE.

Uninstall

FROM THE PEOPLE WHO BROUGHT YOU MORE MEMORY.

Have you ever tried to clean up your system?
Then you know that removing all of the
Windows™ apps, files and system components
you don't want in order to make room for the things
you do want is next to impossible.

Unless you have the right tool.

With Quarterdeck's new CleanSweep™ at your disposal, you can safely unclog your system and free up megabytes of precious disk space with the greatest of ease.

A DISK IS A TERRIBLE THING TO WASTE.

So before you blow a bunch of money on a new drive, grab your mouse and ask CleanSweep to analyze a program for you.

The long list of system files, DLLs, VxDs, Help files, .ini files, add-ons and other stuff that pops up on your screen will give you a pretty good idea

of how much disk space you've been wasting.

And since all those files are scattered all over

your system, they're *very* hard to find. Which is why CleanSweep comes equipped with exclusive Helper Technology that understands the bizarre installation habits of popular Windows programs.

TO DELETE. OR NOT TO DELETE.

CleanSweep knows more than just where to look for the maximum number of files. It also knows what to do when it finds them.

And what not to do.

Since uninstalling the wrong file—say, a shared DLL—can disable other programs you use daily, CleanSweep uses SuperLinks to track files that are needed by multiple applications.

perform trial runs to see how much disk space you're about to gain.

Which is just the sort of ingenious functionality you'd expect from Quarterdeck, the folks who brought memory management to millions with the legendary QEMM.®

LEAVE NO FILE UNTURNED.

To really get the most out of CleanSweep, you'll want to use it to track down and delete duplicate, backup, archive, help and bitmap files.

Not to mention unneeded system components such as graphics drivers, fonts, wallpaper, system files and screen savers.

But before you can do any of this, you'll need to see your nearest reseller.

Or call us at 800-354-3222.

Wherever you buy
CleanSweep, if you're not
thrilled, you can return it within

30 days for a full refund. No questions asked. Don't worry. CleanSweep uninstalls itself.



It also lets you view any file, confirm every action, undo anything you've done and even



Color to Go

CHRIS CHINNOCK

obile-computer screens are roughly midway through a transition from monochrome to color. Five years ago, color screens on laptops were quite rare; five years from now, they will be not only commonplace, but taken for granted. Monochrome displays might still be offered on the lowest-end laptops in the future, and palmtop devices will cling to monochrome displays for a while longer. But for the most part, color screens will soon be the accepted standard, just as they are on desktop systems.

User demand for larger and brighter color displays seems relentless, and it poses great challenges for the designers who struggle to cram these screens into smaller and lighter mobile systems (which users also expect to run longer on a battery charge). Newer display technologies could prove to be their salvation, but LCDs still have plenty of room for improvement and will continue to dominate the market for the immediate future. As new display and materials technologies evolve, prices will drop, and innovative combinations could lead to new categories of mobile-computing products.

LCD Is King

Today's LCDs are essentially valves that regulate the amount of light emitted from an internal backlight. This light passes through several layers of polarizers, liquid crystal materials, and color filters. A screen image is controlled by a grid of electrodes that determines how much light passes through each grid point, or pixel.

AMLCDs (active-matrix LCDs) have a transistor at each pixel site, while PMLCDs (passive-matrix LCDs) don't. These transistors provide better control over the light that passes through the grid, enabling more vivid colors and faster updates without ghosting. This is particularly important for multimedia applications that use motion video. (See the table "Comparing Today's LCD Technologies" on page 122.)

Notebook computers represent a significant portion of the mobile-computing market, and both types of LCDs are almost universal in these systems. Passive displays cost less, of course, so they're generally found in lower-end notebooks. Active displays are likely to cost about twice as much as their passive counterparts for several years to



come (see the figure "LCD Price Trends" on page 118).

Up to now, the vast majority of AMLCDs have been manufactured in Japan. High-volume manufacturing capacity is rapidly expanding—not only in Japan, but also in Korea and Europe. (The U.S. has only a

Although some new display technologies for mobile computers are on the horizon, LCDs are likely to dominate for years to come

few low-volume factories.) This expansion in Asia and Europe is being encouraged by the maturity and stable demand of LCD technology. "Customers have finally realized that active-matrix displays can do the job," says Dave Kuty, display project manager at Apple. "They have moved past the 'needing improvement' phase to the 'acceptable' stage."

Sieve Depp, manager of home electronics and the subsystem technical and applications lab at IBM Research, agrees. "The development of AMLCDs is beginning to look like silicon's. There's a technology road map showing what levers you pull at what time. That's a sign of a reasonably robust technology."

With so much money and brainpower being invested in AMLCDs, suppliers expect to make progress in all aspects of production: screen quality and size, power consumption, weight, and cost.

"The primary emphasis this year will be to shift the 10.4-inch VGA-resolution [640- by 480-pixel] screens to SVGA [800 by 600 pixels] and to add more bits of color," says Joel Pollack, senior product marketing manager at

FEDS: WAIT A FEW YEARS

FED (field emission display) technology is another emerging display technology that's challenging LCDs. However, FEDs must demonstrate clear advantages over LCDs if they hope to gain wide market acceptance. Some developers believe the low power, wide viewing angles, and good image quality of FEDs will make them an attractive alternative. But others think the relentless advancement of LCDs may be too much to overcome.

An FED is essentially a flat CRT. But instead of using a single electron gun to scan a phosphor-coated screen, an FED has a grid of individually addressable electron emitters on a flat substrate. A second transparent substrate contains colored phosphors. Each emitter pixel is addressed with electrical signals that trigger the emission of electrons, which react with the phosphor screen to generate colored light. The ultimate goal is to produce a CRT-quality image in a flat package that consumes little power.

Several varieties of FEDs are now under development by different companies (see the box below). The most popular approach is to fabricate thousands or millions of tiny cone-shaped structures that emit electrons when voltage is applied. Some FEDs add voltage grids that help focus the electrons and increase voltage

levels. Developing the materials, architectures, and manufacturing expertise to fabricate these electron emitters is one of the major challenges facing FED developers.

The advantage of using higher voltages is that it will let FEDs work with existing CRT phosphors. Lower-voltage approaches rely on the development of new phosphors that can operate efficiently and with long lifetimes at reduced voltage levels. There have been several recent advances in this area.

The discovery a few years ago that certain types of diamond films are excellent electron emitters is also helping to fuel FED development. Researchers are looking for ways to improve the quality of these films and make them easier to manufacture.

Several companies are expected to demonstrate prototype FEDs this year, but that doesn't mean mass production is imminent. As IBM's Steve Depp points out, "From our experience in the AMLCD [active-matrix LCD] area, once good prototypes are demonstrated, it's about 2½ years before they show up as actual products in quantity. It takes time to build a factory and establish other aspects of the infrastructure. Consequently, I think we're talking about mid-1997 before we see FEDs in any reasonable volume."

FED Developers

Canon

Tokyo, Japan, and Lake Success, NY

Coloray

Fremont, CA

FED Corp.

Hopewell Junction, NY

Futaba

Chiba City, Japan, and Plymouth, MI

Micron Display Technologies

Boise, ID

Pixel International Rousset, France

Raytheon Quincy, MA

SI Diamond Technology

Houston, TX

Silicon Video

Cupertino, CA

Texas Instruments

Dallas, TX

Sharp Electronics. "We are also talking about offering an 11.3-inch-diagonal display toward the end of the year."

There are many technical challenges involved in improving AMLCDs. For example, to pack more pixels into the same area, manufacturers are reducing the size of the transistors and line widths and are moving toward self-aligning photolithographic techniques. They are also developing improved fabrication processes and better test and repair procedures.

Many manufacturers are now on their third generation of fabrication equipment.

The latest equipment reduces the number of steps required in the manufacturing process, resulting in faster, cleaner, and more uniform processing. The latest equipment can also process larger glass substrates. This permits more (or larger) displays to be processed on a single substrate. All these factors help to improve yields and reduce costs.

At the same time, both weight and power consumption are decreasing. "Today's 10.4-inch AMLCD is 11.5 mm thick, weighs 500 grams, and consumes 2.9 watts of power," explains Pollack. "By next year,

we intend to get that down to 8 mm thick, weighing about 400 grams, and consuming less than 2 watts of power."

Many technical improvements are driving this progress, including more efficient backlights, better optical light guides, and more transmissive color filters. But the best gains appear to come from shrinking the transistors. This allows more light to pass through the LCD, so the screens can be brighter and also use less power. "A few years ago, I would have thought we were getting to the point of diminishing returns for AMLCD, but I now see steady progress being made throughout this year into next [year]," says Pollack.

The Future of Passive-Matrix

As mentioned earlier, passive displays still cost less and consume less power than active displays, so they're expected to command a considerable market share at the lower end of the notebook market. They will also dominate the market for low-cost hand-held devices. But as AMLCDs advance rapidly along the price/performance curve, manufacturers of PMLCDs will have to match those gains to remain competitive. Although they can take advantage of many of the same advances in manufacturing and materials as AMLCDs, the manufacturing techniques for PMLCDs are quite different.

For example, PMLCD manufacturers must pay special attention to the thickness of the cell gap through which liquid crystal material flows, which is located between the two sheets of glass that form the display. Preparing the glass surfaces for this material is a particularly delicate process because any small variations are clearly visible on the screen.

It has taken some time for the Japanese manufacturers to solve these difficult problems. But as they gain better control of their processes, new options become available. For instance, a technique known as electrically controlled birefringence, or ECB, can produce a color PMLCD without filters. If the cell gap is precisely controlled, it's possible to obtain various colors by applying different voltages. This wasn't feasible before, due to variations in the thickness of the cell gap.

"Now Japanese manufacturers are routinely holding this thickness to 0.1 micron, which is actually flatter than the glass itself," says Apple's Kuty. "While ECB is still in the research phase, if we can get adequate speed and some color capability, this technology might make an excellent ultra-low-power reflective display in a few years."



Dataproducts' Typhoon 8 is the ultimate desktop printer. With resolution, full-bleed 11" x 17"

imaging, Adobe PostScript® Level 2, PCL 5 and cameraready faxing, the Typhoon 8 takes laser printing to incredible new heights.

Leave your network printing problems behind.

stunning, typeset-quality 1200 dpi The Typhoon 8's patented Virtual Printer Technology (VPT^{IM})

> handles multiple protocols and provides custom settings for up to 64 users on your network!

So get up to speed.

At \$5,199, we've broken the price barrier to the next level of printing. Call us today for the ultimate in printing performance.

1-800-980-0374 Ask for free print samples!



Taking your printing needs by storm

@ 1995 Dataproducts Corporation. Dataproducts and Dataproducts with its associated logomark are registered trademarks and Typhoon and VPT are trademarks of Dataproducts Corp. PostScript is a registered trademark of Adobe Systems Inc.

Circle 216 on Inquiry Card (RESELLERS: 217).

Another challenge faced by makers of passive displays is the limited number of addressable lines in the LCD grid. To overcome this, most manufacturers are adopting a dual-scan approach that adds a second set of drive electronics to the screen.

Low contrast is yet another problem. Some liquid crystal materials yield high contrast, but at the expense of slower response. For example, rapid mouse movements cause the cursor to "submarine" (i.e., temporarily disappear), and ghost images ruin the playback of motion video.

New addressing schemes may be able to solve these problems. For example, Motif, a joint venture of In Focus Systems and Motorola, will soon introduce passive displays that use a new technique called active addressing. This scheme updates the LCD rows semirandomly under the control of a special ASIC.

"Our first generation of products will carry a 30 percent to 35 percent price premium over traditional passive-matrix displays, but this buys you display performance that is near active-matrix levels," says Motif vice president Kevin Cornelius.



Motif has lined up an impressive array of strategic partners, including Asahi Glass/Optrex, Kyocera, Standish Industries, and Tottori Sanyo. Together, they'll promote active addressing in the market-place. Motif will supply ASICs to its partners and receive display panels in return. All the involved parties can then combine the ASICs and panels to assemble their final products. (In late March, In Focus an-

nounced that it would buy back almost half of Motorola's shares in Motif and that Motorola expected to sell its remaining Motif shares. At press time, it was unclear what effect this would have on the rollout of Motif's active-addressing technology.)

Other novel addressing schemes are likely to appear. Arithmos, a West Coast semiconductor start-up, is reportedly working on a passive-matrix technique called "transform addressing." In Japan, Asahi Glass is developing a method known as MLS (multiline selection). Motif's Cornelius says that MLS and active addressing are complementary technologies. "Both

schemes increase response time and contrast, but MLS does not have a discrete gray-scale capability, which is necessary for displaying video images," he notes.

Another interesting addressing scheme, which is currently under development at Positive Technologies, has been dubbed adaptive scanning by company president Robert Hotto. "In standard passive-matrix addressing, each pixel is updated approximately 30 times per second, row by row," he explains. "But adaptive scanning modifies this update rate, customizing it for each row or group of rows. Higher-intensity pixels, or pixels that are changing

Active-Matrix EL Displays

Like FEDs (field emission displays), EL (electroluminescent) displays are emissive devices. Instead of modulating a backlight, as LCDs do, EL displays produce their own light by applying voltage to a phosphor. The advantages of EL displays include their rugged construction, ability to operate in an extended temperature range, and low power consumption. In addition, EL displays are the only ones that are completely solid-state.

Working with a team that includes Kopin and the David Sarnoff Research Center, Planar America is currently developing an AMEL (active-matrix electroluminescent) display. Each pixel site on this display has its own transistor, an approach that seeks to achieve the same advantages as Kopin's single-crystal LCD process (see the main text for details about this process). All the drive

electronics and pixel transistors are fabricated in a modified silicon foundry. Phosphors are then deposited directly onto these electronics.

"AMEL fabrication requires only a single substrate," explains Ron Khormaei

of Planar America. "This eliminates the assembly and alignment of two substrates, which is required for all other flat-panel technologies."

AMELs may be well suited to HMDs (head-mounted displays) and portable-computing devices that require screens with low power con-

sumption and extended operating-temperature ranges. That's why the military is interested in this technology. In fact, the U.S. Army is making preparations to flight-test an AMEL-based HMD next winter. Development is still in its early stages, however, and moving from prototypes to volume manufacturing will take time and money. Planar recently received a \$29 million contract to develop manufacturing processes that will allow pilot

production of AMEL screens. The company hopes to begin sampling monochrome VGA displays and 640- by 512-pixel color displays by next summer.

Developing a bright and stable blue phosphor has long been an elusive goal for Planar. However, the com-

pany recently announced a breakthrough in this area. While the first samples are targeted primarily for high-performance military devices, Planar is also eyeing opportunities for HMDs and other applications.

- rugged construction
- ability to operate in an extended temperature range
- low power consumption
- only completely solid-state displays



Now available in a notebook.



Power and portability are no longer mutually exclusive. Now you can have both with an Intel Pentium[®] processor-based notebook. In fact, all of today's most demanding desktop software including office suites, multimedia and 3-D graphics, now runs just as great on your notebook.



It's A Classic Combination




Dad always said to look for superior quality at the best value. Like the classic car he handed down to you, your new Gateway 2000® P5-100 Best Buy is custom built with hardware meant to last. You'd be hard pressed to find a better combination of quality, performance and features at such an incredible value.

Gateway's P5-100 Best Buy couples its fast 100MHz Intel Pentium processor with 8MB RAM, giving you a solid PC performance. Built with the future in mind, the substantial 1GB hard drive provides vast storage space. Sure Dad probably wouldn't have used "proactive design" to describe a product that would serve his needs down the road, but it was something he understood.

Built today for tomorrow's technology, this power-packed PC features the revved-up performance of a 4X CD-ROM drive, providing you with true full-screen, full-motion video. The 15-inch Vivitron monitor is based on Sony® Trinitron® technology and combined with a 64-bit, 2MB PCI graphics accelerator, it'll give you a screen display with crisp, clean images and vivid color.

The P5-100 Best Buy comes standard with Microsoft Office Professional 4.3 which includes Word 6.0, Excel 5.0, PowerPoint® 4.0 presentation program, and Access® 2.0 database, along with MS-DOS 6.22 and Windows™ for Workgroups 3.11.

Gateway 2000 can build a computer system to meet your specific requirements at unbeatable prices. While AM/FM radio



and fuel injection aren't customization options available from Gateway, an installed network card, 4X three-CD changer, multimedia kit and many other PC peripherals are. And the seven-bay desktop case can be easily modified with additional drives or peripherals.

Yes, Dad could've bought a standard sedan in 1957, but this baby was a real steal and loaded with options. He'd be proud that you demand the same from your PC. You know it's a classic piece of machinery, and priced at just \$2,499, the Gateway 2000 P5-100 Best Buy is the only logical choice.

Call Gateway today and ask about the incomparable values on all our PC models.

P5-100 BEST BUY

- Intel® 100MHz Pentium™ Processor
- 8MB RAM
- 256K Cache
- 1GB 10ms IDE Hard Drive
- PCI Enhanced IDE Interface
- 64-Bit PCI Graphics Accelerator MS-DOS® 6.22 & WFW 3.11 with 2MB DRAM
- 4X CD-ROM Drive
- 3.5" Diskette Drive

- 15" Vivitron[™] Color Monitor
- 7-Bay Desktop Case
- AnyKey® Keyboard & MS Mouse 2.0
- Microsoft® Office Professional 4.3, Bookshelf® and Money 3.0
- 3-Year Limited Parts Warranty



rapidly—due to fast motion, for example—are updated more frequently than slow-moving or static areas. This smart-addressing method essentially optimizes the pixel-update rate to conform to the type of imagery being displayed."

Adaptive scanning works for both passive- and active-matrix LCDs. Positive Technologies is working on ways to use the technique in automotive displays as well as in hand-held computing devices for package-delivery services.

Additional advancements may come from experiments with new kinds of materials, such as *guest-host* liquid crystals. With these, dye is added to the liquid crystal to increase contrast. Some of these displays dramatically boost the brightness of the screen without the use of polarizers. When used in a passive-reflective mode, they consume little power, sometimes in the range of 50 milliwatts. Guest-host liquid crystals work with both active- and passive-matrix displays.

Ferroelectric LCDs have been under development for a long time, especially at Canon. However, product introductions have been delayed for more than 10 years because of persistent problems with manufacturing and the mechanical instability of the liquid crystal material. Although prototypes are once again expected to appear this year, they face a skeptical audience.

"Ferroelectric LCDs require different driving electronics," says Apple's Kuty. "You just can't replace an active-matrix [display] with them. Unless they have some real advantage over active-matrix, people will be reluctant to invest the engineering time in them."

Emerging Markets

Today, the vast majority of mobile-computing devices are notebook computers, along with personal organizers and a few thousand PDAs (personal digital assistants). The market is likely to expand in coming years as new technologies enable the production of high-resolution displays

that measure 3 inches (diagonal) or less. These displays will be the visual interfaces for communications devices designed to be carried around or even worn on the body. This market is just now emerging and could become quite significant in five years.

For example, HMDs (head-mounted displays) are being touted as a new kind of interface for some types of

portable computers. These aren't the fullimmersion goggles associated with virtual-reality systems, but rather a single eyepiece that obscures only part of the user's field of vision. While these systems can be used for traditional applications, such as spreadsheets and word processors, new uses include the display of such things as technical manuals, blueprints, exploded diagrams, and even video clips that show how to, say, repair complex machinery (see the photo).

When HMDs are linked to voice-activated computers worn on the body, the result is a system that gives workers handsfree access to volumes of information from almost anywhere. For instance, a helicopter-repair technician equipped with an HMD wouldn't have to lug a heavy technical manual to the top of an aircraft to work on the rotor blade. Technicians working in cramped quarters could view schematics right on the repair scene, possibly even getting advice from a supervisor monitoring the situation through a small video camera and a wireless communications link. Factory workers could view a virtual template that helps them assemble com-



Small, high-resolution LCDs will enable a new class of head-mounted displays that give hands-free access to volumes of technical data.

plex components. CPSI and InterVision are among the companies developing systems for these types of applications.

New kinds of projection devices are coming, too. There's already a clear shift under way from CRTs to LCDs for projection panels. Most of today's projection devices are merely peripherals for laptop or desktop computers, but a few are starting

to acquire some computing capabilities of their own. For example, In Focus Systems already offers a projector with a built-in floppy drive that doesn't have to be tethered to a computer to show a presentation.

Communications devices will benefit from improved display technologies as well. Portable phones will probably integrate small displays and enough computing power to enable the user to view E-mail messages, news bulletins, and other information.

The first device to explore this territory is the Simon, which was introduced last year by BellSouth Cellular and designed by IBM. The Simon is a combination cellular phone/PDA that includes an x86-compatible CPU, a fax modem, a PCMCIA Type II PC Card slot, 11 built-in programs, and a 4½- by 1½-inch touch-sensitive LCD screen. Better displays will almost certainly lead to more hybrid devices like the Simon.

New Types of LCDs

By experimenting with different types of silicon, manufacturers are now producing new LCDs that have greater resolution than

DISPLAY TYPE	COLOR QUALITY	VIDEO RESPONSE	CONTRAST	PRICE	POWER
Active-matrix	0000	0000	0000	High	00/0000
Passive-matrix	00	0	00	Low	00/0000
Active-addressing	000	000	000	Moderate	00



The information you need is out there. But how do you find it when it counts?

Introducing Profound," the online service that quickly pinpoints what you need to know.

Truckloads of new articles, reports and statistics emerge every day — information that's vital to your job, your industry and your investments. But who has time to extract the crucial facts? Now Profound's revolutionary InfoSort™ system can deliver the precise information you want. Just point and click and Profound scans millions of documents in seconds.

The most comprehensive business database ever.

Access resources from the world's leading publishers, many of which aren't available anywhere else. News from over 4,000 newspapers, periodicals and news wires from Reuters, The Associated Press and others. Over 40,000 research reports from publishers like Frost & Sullivan and FIND/SVP. Reports from Dun & Bradstreet, Standard & Poor's and Smith Barney. Current stock and commodity prices. All accessible through your Windows†-based PC and modem for only \$19.95 a month. Includes graphics and Adobe†† Acrobat†† software.


Custom Alert™ automatically informs you about exclusive news on your world.

Pick the topics that really matter to you – a client's business, the competition, your personal investments. Then, every time you open up Profound, a list of the latest and most relevant news articles and research reports will be waiting for you.

Let us prove to you how valuable timely information can be, free.*

Call 1-800-688-5583 and request your free software today. You'll get your first month's subscription at no charge. Plus five free hours of online time.





before, as well as improved electrical characteristics. Some of these LCDs are better suited for the tiny displays in miniaturized devices, while others show promise for the full-size, direct-view screens on laptop systems.

The AMLCDs used in today's laptop computers are fabricated with amorphous silicon. This type of silicon requires discrete ICs for the off-screen electronics, which increases the display's weight, bulk, cost, and power consumption. These ICs are made in traditional silicon foundries from single-crystal silicon, which has excellent electrical characteristics. Another type of silicon is poly-silicon, which isn't as efficient as single-crystal silicon but

is better than amorphous silicon.

All the on-screen transistors and offscreen electronics that are made for displays out of single-crystal silicon and polysilicon can be fabricated simultaneously on a single substrate. This not only improves reliability and cuts costs but also offers some performance advantages. The result is a display with lots of pixels in a small area.

One company that's trying to commercialize single-crystal LCD technology is Kopin, which recently established a plant for mass production. "Right now we are shipping 1½-inch VGA monochrome display toolkits that allow systems designers to evaluate the displays, but 1280- by

Apple Computer, Inc.

Cupertino, CA (800) 776-2333 (408) 996-1010 fax: (408) 996-0275

Arithmos

Santa Clara, CA (408) 982-4480 fax: (408) 982-4481

Asahi Glass Co.

Tokyo, Japan +81 3 3218 5250 fax: +81 3 3287 1047

BeliSouth Cellular

Atlanta, GA (800) 746-6672 (404) 705-1880 fax: (404) 717-2111

CPSI

Find

Where to

Fairfax, VA (703) 631-6925 fax: (703) 631-6734

IBM Research

Yorktown Heights, NY (914) 945-3000 fax: (914) 945-2141

In Focus Systems, Inc.

Wilsonville, OR (800) 294-6400 (503) 685-8888 fax: (503) 685-8887

InterVision

Raleigh, NC (800) 850-2556 (919) 850-2511 fax: (919) 850-0562

Kopin Corp.

Taunton, MA (508) 824-6696 fax: (508) 822-1381

Kyocera

Kyoto, Japan +81 75 592 3851

Matif

Wilsonville, OR (503) 682-7700 fax: (503) 682-7036

Motorola, Inc.

Northbrook, IL (708) 480-6842 fax: (708) 205-3872 E-mail: g10839@email.mot.com

Optrex

Tokyo, Japan +81 3 5688 8265 fax; +81 3 5688 8270

Optrex America

Plymouth, MI (313) 416-8500 fax: (313) 416-8520

Planar America

Beaverton, OR (503) 690-1100 fax: (503) 690-1244

Positive Technologies

San Diego, CA (619) 457-5151 fax: (619) 457-4646 E-mail: postech@powergrid.electriciti.com

Sarif

Vancouver, WA (206) 750-0242 fax: (206) 750-0244

David Sarnoff Research Center

Princeton, NJ (609) 734-2000 fax: (609) 734-2221

Sharp Electronics

Mahwah, NJ (800) 237-4277 (201) 529-8200 fax: (201) 529-8413

Standish Industries

Lake Mills, WI (414) 648-1000 fax: (414) 648-1001

Tottori Sanyo Electric Co.

Tottori, Japan +81 857 21 2001 fax: +81 857 21 2034

What makes SAMTRON MONITORS such a great value?

QUALITY

Producing high quality monitors is our only business. In fact, our commitment to quality has been



recognized by the leading testing facilities in the U.S. According

to the NTSL lab report in the January 1995 issue of BYTE magazine, "The Samtron SC-728SXL earned the best overall image quality rating". In their December 1994 issue,

Windows Magazine wrote "It's not often that high




INDOWS quality comes at a midrange price. But Samtron's SC-728SXL,

with its truly flat 17-inch screen is an exception. Right out of the box, the quality of this 17-inch monitor was apparent."

TECHNICAL SUPPORT

Our commitment to quality doesn't end when you buy a Samtron monitor. Our professional Customer Service Representatives are available for unlimited technical





WARRANTY & SERVICE

Every monitor

Samtron manufactures is backed by a 3-year Parts and 2-year Labor Warranty, Samtron "STAR" Service Centers guarantee your satisfaction by offering 48-hour turnaround warranty service*.

SC-728SXL

FULL LINE SELECTION


If your needs call for the impact of a 20" display, or the versatility of a 15" flat screen, our product line offers a full selection of high-quality monitors ideal for use in any application.



SC-528UXL 15" 0.28 Dos Pisch 1280 x 1024 (60 Hz) MPR II



17" 0.26 Dat Pitch 1600 x 1280 (60 Hz) MPR II Mac Compatible



SC-208DXL 20" 0.28 Dos Pich 1600 x 1280 (60 Hz) MPR II Mac Compatible



MONITORS WITH STARPOWER"

18600 Broadwick Street Rancho Dominguez, California 90220 Tel: (310) 537-7000 Fax: (310) 537-1033

Technical Support: (800) SAMTRON





"STAR Service Century available to U.S. Customers only. The EPA Energy Sta does not represent EPA endorsement of any product or service. Specifications subject to without nation. Screens are simple



AnthroCart's!

AnthroCarts will knock your socks off! Imagine how great it'll be when you find the perfect furniture for your equipment — just the right size, tough as nails construction and dozens of accessories.

And you'll find our service so real and responsive, you'll get a kick out of ordering direct!



Lifetime Warranty

Call for a free catalog!



Adjustable for all sizes.



Lots of choices.

800-325-3841

e-mail: sales@anthro.com



10450 SW Manhasset Drive Tualatin Oregon 97062 Phone: (503) 691-2556 Fax: (800) 325-0045

GSA contract no. GS-OOF-5040A. Available for OEM applications. Prices from \$159.00 Anthro, AnthroCart and Technology Furniture are registered trademarks of Anthro.

Special Report

1024-pixel displays will follow soon," says Jeff Jacobsen, Kopin's vice president for business development. "Last May, we received an ARPA contract to demonstrate an AMLCD with 2560 by 2048 resolution. No one has done anything like that before," he adds.

LCDs based on poly-silicon have many of the advantages of single-crystal-silicon LCDs, but their poorer electrical characteristics may prevent them from achieving the highest density displays. The viewfinders in camcorders often use this type of LCD.

Manufacturers such as Hitachi and Seiko-Epson are large-volume suppliers of poly-silicon LCDs, but that situation is changing. Camcorder manufacturers recently established their own poly-silicon lines, so outside suppliers are looking for new market opportunities, such as HMDs and projection devices. Hitachi and Seiko-Epson have increased the resolutions of their viewfinder displays and, along with Sony, are now sampling VGA-resolution products. A U.S.-based company named Sarif (a joint venture of In Focus and the David Samoff Research Center) was recently formed to commercialize poly-silicon displays.

Other companies are developing new technology for larger, direct-view displays based on poly-silicon. Current fabrication techniques use a high-temperature process that requires expensive quartz substrates, because the heat would warp a flat glass panel. Consequently, the goal is to find a low-temperature process. ARPA is currently funding this development in the U.S. "It will be two to three years before low-temperature processes are commercialized, but pilot line production might begin within 18 months," explains ARPA program manager Dave Slobodin.

Display technology is evolving rapidly on many fronts. And each advancement potentially enables the development of new kinds of mobile-computing devices. Although it's difficult to predict what these devices will look like, or even what they will do, today's mobile computers stand to benefit as well. As Sharp's Pollack puts it, "In five years, I think we'll be looking at a whole new paradigm in display technology. Displays may look the same, but it won't be today's technology."

Chris Chinnock is a technology writer based in Norwalk, Connecticut, who specializes in emerging and cutting-edge technologies. He can be contacted on the Internet at 76061.3671@compuserve.com or on CompuServe at 76061.3671.



Best Value! Best Features!









	DISE OF USE				
•	"Drag and drop" symbols	•	•	•	
•	Symbol auto-connect	•		•	
•	Auto-resize symbols to fit text	•			
•	On-screen text and line editing	•	•	•	
•	On-line interactive tutorial	•			
	Spellchecker	•			
	Symbol substitution	•	•	•	
	•				



DIAGRAMMING FEATURES

	DINGIDE IIII TO TENTONES			
\triangleright	OLE 2.0 server		•	•
-	Create customized symbols	•	•	•
-	Draw symbols		•	
-	Save customized symbols to library	•	•	•
-	Open multiple symbol libraries	•	•	
•	Diagram linking	•	•	•
•	Create custom line arrows	•		
-	Works in layers	•	•	
-	Rotate objects	•	•	
•	Mirror objects	•	•	

CorelFLOW is the fast, easy way to organize and communicate your ideas with flowcharts, diagrams, schematics and more!




NETWORK READY!

Floating Smart Symbol Libraries provide quick access to over 2,000 "drag and drop" symbols.

Connect symbols automatically as you draw with over 30 customizable connector styles.

Edit text directly on screen and add impact using any of the 100 TrueType fonts.



Link symbols to other CorelFLOW diagrams or other applications.

"Drag and drop" files directly from any OLE 2.0 compatible application.

Add flair to your diagrams with any of the 1,000 clipart images and 1,000 photo images included.

"Inside and out, CorelFLOW is a beauty."

PC Magazine, November 1994



1-800-333-3330 \$69-99*

COREL
Call now for faxed literature!
1-613-728-0826 ext. 3080
Document #1054

"US\$ plus applicable taxes.

OUR NEWEST SERVERS ARE DESIGNED TO GIV

SOLID SUPPORT. As you'd expect from the world leader in networked servers, we've engineered our newest models to reliably serve in a NetWare environment.

EARLY WARNING SYSTEM. Compaq Insight Manager monitors hundreds of server components and warns you when problems are merely a possibility.

FLEXIBLE CONFIGURATION. SmartStart revolutionizes the setup process, automatically configuring and optimizing NetWare on your server.

FEWER ACHES AND PAINS. Compaq servers are backed by our three-year on-site warranty and free access to our 24-hour help line (with additional plans available).

MOVES INFORMATION FAST. Compaq's TriFlex/PCI architecture builds upon the new PCI standard, for even higher performance.

PREVENTS UNNECESSARY STRAINS. Our Pre-Failure

Warranty** replaces major parts at no cost — before they

can interrupt a group's critical work.

People are born with one. Businesses have to build them from scratch. To help you assemble the most reliable information backbone, Compaq announces a new generation of servers. They're all designed to faithfully serve the demands of workgroups and departments — from the expandable ProSignia line to the business-critical ProLiant family (with up to four Pentium processors). And they're all engineered to do what every

YOUR COMPANY THE THING IT NEEDS MOST.





Fig. I Backbone

profitable business demands: keep running. Compaq's CD-based SmartStart ensures a smooth, integrated installation, and our Insight Manager constantly monitors for potential problems—which, if encountered, are covered by the Compaq Pre-Failure Warranty. For more information, call 1-800-853-9518 or visit our Web site at www.compaq.com. We can help you get the performance you need. As well as the support.



Times like these make you glad you own a Proxima[®] Desktop Projector.[®]



PROXIMA

THE DESKTOP PROJECTION COMPANY

This purchase recessary to error. Void where prohibines. Sweepstanes extres must be received by 8(3195, For compiler rates, call 1-300-799-331) ext. 111

Denktop projection system reclusies a Priscrate Dealstop Projector 2600 and your choice of either a Microsoft Projector 5400 or an ISM Trient-bot 75500. Resid vision 315,000

Main Officio Hard Carella Pick Drives, San Diego, CA 82(21-220), (819) 457-5500, FAX (519) 457-6407, European Office Horsanineg 24 6191 PX Seels, The Noterheimon's -311-4560 246, FAX -311-43-49 201

Priscrate and Cyclosis are applicated Sectionals of Priscrate Composition Collection Collection (Collection) Collection (Colle

It all comes down to tomorrow's presentation.

You've been there many times before.

The night before the big presentation.

You want to make last minute changes.

But there's no time to make new slides or transparencies.

Presenting the Proxima Desktop
Projector 2800. It's a whole new way of
looking at presentations. It connects
directly to your PC or Macintosh and
allows you to project anything on your
computer screen onto a large screen or
wall. Everything from simple charts to
full-motion multimedia presentations.
Plus, Proxima's unique Cyclops' interactive
pointer system lets you control your
software from anywhere in the room.

Best of all, the Proxima Desktop Projector 2800 is easy to set up and use. Find out how owning one can help you be more professional and more successful than ever before.

Call 1-800-799-3331, ext. 111, for your free information kit and enter to win a \$15,000 portable Desktop Projection System!

System

Brainy, Brawny Batteries

GIL BASSAK

n the continuing quest to extend the operating time of their mobile computers, manufacturers are finally getting smart—smart batteries, that is. And more powerful batteries, too.

Thanks to sophisticated electronics and power management subsystems, these new rechargeable batteries promise to live longer, better lives. Equally important, they can predict their own useful operating time with unsurpassed accuracy, ending the guesswork that has long plagued users. Smart batteries began appearing in notebooks from

Compaq and IBM in 1993, and they're coming soon to many other systems.

In the past, you judged batteries by sheer electrical capacity alone. The stronger the battery, the longer it could run between charges. Obtaining a longer battery life boiled down to increasing the battery's size or reformulating its chemistry. To be sure, advances in chemistry continue to bear fruit. But the performance of existing battery technologies can be significantly improved by integrating smart electronics that report the battery's precise charging status, temperature, age, and chemistry.

Armed with this information, a mobile system can accurately predict how much longer the battery will last and adjust its power management tactics to squeeze more work out of the battery's remaining capacity. You see a "fuel gauge" that shows almost exactly how much battery time remains, and you have more options for extending that time.

When a smart battery finally runs out of juice, it also knows how much recharging it needs. This extends the overall life of the battery and keeps the mobile computer running at maximum operating capacity.

Starting from Strength

Intelligence notwithstanding, a battery's fundamental strength starts with its chemistry. For that reason, battery makers are hard at work inventing and refining better rechargeable cells. And that work is paying off. Eclipsing the once-dominant nickel-cadmium batteries are NiMH (nickel-metal-hydride) and lithium-ion cells. Lead-acid, which is a popular chemistry for rechargeable batteries in other devices, has a doubtful future in mobile computing. Rechargeable alkaline batteries probably won't play a major role in laptop computers, but they could prove useful in



smaller devices.

For years, nickel-cadmium has been synonymous with rechargeable batteries for portable tools and electronics. But because cadmium can be hazardous if the spent batteries are not disposed of properly, nickel-cadmium batteries have lost ground to cells built with the newer NiMH chemNew chemistries linked to advanced power management systems are producing much more efficient batteries

istry. NiMH batteries create fewer disposal problems and have at least 20 percent more *volumetric energy density* (i.e., energy for a given volume). NiMH batteries enjoy a service life that's about 40 percent longer than nickel-cadmium batteries.

What's more, nickel-cadmium is a mature technology, with faint prospects for further advancement. NiMH batteries, which were introduced six years ago, should continue to improve for years to come. For example, new spongemetal NiMH cells from Panasonic are said to deliver up to 150 percent more power than comparable nickel-cadmium batteries.

These strengths have not been lost on systems designers, who are adopting NiMH cells as the battery of choice for today's mobile computers. For power tools and other consumer devices, nickel-cadmium batteries are still a mainstay. They are less prone than NiMH batteries to damage from high charge and discharge rates.

Lithium-ion batteries are gaining favor, too. They deliver about 50 percent more volumetric energy density than NiMH batteries and about 80 percent more gravimetric

energy density (i.e., energy per unit of weight). Also, lithium-ion cells have a low rate of self-discharge: 10 percent per month, compared to 25 percent or more per month for NiMH batteries. And lithium-ion cells do not suffer from the so-called memory effect that shortens the operational lives of nickel-cadmium and (to a lesser extent) NiMH batteries.

The memory effect occurs when a battery is repeatedly, but not fully, discharged. Over time, the battery begins to "remember" those partial cycles, causing the output voltage to drop well before the battery is fully drained. To prevent this from happening, most nickel-cadmium and NiMH batteries should be fully discharged before recharging.

Although lithium-ion batteries are the rising star in mobile computing, a potential problem is that lithium is highly reactive, posing safety concerns. Early versions were sometimes known to ignite or explode. In addition, some lithium-ion cells lose their capacity after repeated charge-and-discharge cycles. Still, lithium-ion's high energy density makes it an appealing mobile technology. These batteries are showing up in such notebooks as the Latitude XP from Dell, the HiNote from Digital Equipment, and the T3400CT Portege from Toshiba.

For smaller devices such as palmtops and PDAs (personal digital assistants), rechargeable alkaline batteries show some promise. They fall somewhere between NiMH and lithium-ion batteries in terms of volumetric and gravimetric energy densities. Available in AA and AAA sizes, they are well suited to the moderate power requirements of palmtops and PDAs. Rechargeable alkaline batteries can work alongside standard alkaline cells, have a

five-year shelf life, and—like lithium-ion batteries—have no memory effect.

Looking ahead, two more battery chemistries are appearing on the horizon: lithium-polymer and zinc-air. Both have been under development for years and have commercial potential.

It is claimed that lithium-polymer cells offer twice the gravimetric energy density

and 50 percent more volumetric energy density than lithiumion batteries. Such high energy densities help offset lithiumpolymer batteries' main drawback: a useful life of only 150 discharge cycles. In contrast, nickel-cadmium batteries can last up to 500 cycles; NiMH batteries, 300 to 500 cycles; and

lithium-ion batteries, 500 to 800 cycles.

Zinc-air cells have two to three times as much gravimetric energy density as nickel-cadmium and NiMH chemistries, and about one-and-a-half times the gravimetric energy density of lithium-ion cells. In terms of volumetric energy density, however, they lag behind most other types of batteries. That's because a zinc-air cell requires more airflow, so it tends to be rather boxy and bulky. Engineers find it more difficult to fit zinc-air batteries into the tight quarters and sleek styling of to-day's laptops.

As with lithium-polymer batteries, zincair cells suffer from limited discharge cycles—if fully discharged, they'll endure from 25 to 50 cycles. And recharging can take as long as 10 hours. Still, zinc-air's

high energy capacity yields longer run times between charges, so fewer cycles are needed over the battery's service life. In terms of total useful life, therefore, zincair is competitive with the other types of cells.

AER Energy Resources recently announced that it is developing a zinc-air battery for Hewlett-Packard's color Om-

niBook 600. AER says the battery will run from 10 to 15 hours per charge and withstand about 50 cycles if fully discharged. However, because most users will probably recharge the battery before it is fully discharged, they'll get as many as 200 cycles, according to AER. And there's no

penalty for recharging a partially discharged battery, because zinc-air cells don't exhibit the memory effect.



Getting Smart

To make the most of a battery's inherent capacity, engineers are moving beyond chemistry to intelligent electronics. These smart batteries integrate microcontrollers that monitor and communicate information about the battery's past and present operating states. This information includes output voltage, temperature, and current drain (both instantaneous and average).

Having these details, a smart battery can accurately predict its operating life and recharging time under a given load. The computer's power management software can read this data to display a fuel

BATTERY TYPE	GRAVIMETRIC ENERGY (WATT-HOURS/KILOGRAM)	VOLUMETRIC ENERGY (WATT-HOURS/LITER)	STRENGTHS	WEAKNESSES
Nickel-cadmium	40 to 50	80 lo 125	Delivers high current output; relatively tolerant of overcharging; withstands up to 500 charging cycles.	Mature technology with little room for improvement; cadmium is environmentally troublesome; noticeable memory effect.
NIMH	50 to 60	100 to 170	Environmentally safer than nickel- cadmium; somewhat less memory effect; 300 to 500 charging cycles.	More easily damaged by high charging currents or overcharging
Lithium-ion	80 to 100	220 to 240	Higher energy than nickel-cadmium and NiMH; no memory effect; 500 to 800 charging cycles; low self-discharge rate.	Susceptible to damage from overcharge and overdischarge.



Introducing ABC FlowCharter 4.0. The reigning business graphics heavyweight.

When it comes to creating high-quality business diagrams, new ABC FlowCharter 4.0 gives you ultimate power,

flexibility and control. The program is loaded with four fully-integrated modules specifically designed to meet the demands of the business graphics user. Whether you need to create complex flowcharts for TQM and BPR,

analyze your statistical data, or simply pull together clean, colorful presentation charts in a matter of minutes, ABC FlowCharter 4.0 can help you accomplish your

mission. Only ABC FlowCharter 4.0 features automatic line crossovers, intelligent line routing and data fields.

FEATURES	ABC FlowCharter	Visio 3.0	CorelFLOW2.0
Intelligent line routing	*		
Automatic add/delete shapes	*		
Automatic line crossovers	*		
Data fields	*		
OLE 2.0 automation	*	*	
Royalty free flowchart viewer (ABC Viewer™)	*		
Statistical Process Control Charting (ABC DataAnalyzer**)	*		
21 pre-defined diagram templates (ABC SnapGraphics™)	*		

And those are just a few of the features we've added to make your life easier. Right now you can get ABC Flowcharter 4.0 for as little as \$99.95 upgrade. And you can upgrade from any business graphics program you already own. No other program

gives you such complete power for so little. If you want to settle for less, it's your business. Contact your favorite reseller or call 1-800-877-3040.

MICROGRAFX'








*U.S. SRP (\$149.95 Canadian) for users of any Micrografx product or any version of the following competitive products: Visio, CorelFlow, AllClear, Flowcharting 4, EasyFlow, or other diagramming software. Copyright 1995© Micrografx Inc. All rights reserved. All trademarks are owned by their respective companies.

INTRODUCING THI PREVENT STICKER SHOCK



Satellite[®]

T2100CT & T2105CT*:

- 8.4" dia, color TFT-LCD active matrix display
- 350 Million Bytes (=330MB) HDD
- 8MB of RAM expandable to 32MB

T2100CS & T2105CS*:

- 10.4° dia. color dual-scan STN display
- 350 Million Bytes (=330MB) HDD
- 4MB of RAM expandable to 28MB

T2100 & T2105*:

- 9.5" dia. monochrome display
- 260 Million Bytes (=250MB) HDD
- 4MB of RAM expandable to 28MB

ALL MODELS

- 1486 DX2/50MHz, 3.3v
- Integrated math coprocessor
 3.5° floppy disk drive
- 8KB of cache

- Two stacked PCMCIA (PC Card) slots (two Type I-II or one Type III)
- AccuPoint "integrated pointing device
- Optional Port Replicator
- Under 7 lbs.
- Plug and Play connectivity
 NiMH battery with Toshiba MaxTime* Power Management
- Pre-installed software: MS-DOS', Microsoft Windows' and Fn-esse
- Toll-free technical support —
 7 days a week, 24 hours a day








NEW SATELLITE. AND FUTURE SHOCK.



Built-in power supply: Engineered for ultimate portability, there's no bulky external AC adapter to carry – this slim power cord is all you need.



Connectivity and expansion: Two stacked PCMCIA slots (two Type I-II or one Type III) give you plenty of room to grow with data/fax modems, networking adapters, hard drives and more.





Multiple display options: Choose from Toshiba's renowned active matrix color, dual-scan color or monochrome displays. You get a system that's right for your taste, budget and applications.

The New Satellite® T2100 Series. Introducing the affordable notebook computer that comes complete with a future. Packed with features usually reserved for much more expensive machines — fast processor, large hard drive, AccuPoint™ integrated pointing device and built-in AC adapter — the value is clear. Add to this, your choice of large color or monochrome displays, Plug and Play expansion capabilities and an optional Port Replicator, and the new Satellite becomes the only computer you'll need for years to come. Call 1-800-457-7777 for your nearest dealer.

In Touch with Tomorrow
TOSHIBA

†12100 Reseller prices may differ. All prices and specifications are subject to change. Shipping, handling and applicable sales tax not included *T2100 Series products are sold at selected retailers as 1210SCT, 1210SCS and 1210S, with additional pre-installed software.

©1995 Toshiba America Information Systems, Inc. The Intel Inside Iogo is a trademark of Intel Corporation. All products indicated by trademark symbols are trademarked and/or registered by their respective companies.

gauge that's accurate to within 1 percent or 2 percent.

As a result, you get the most work out of your machine without getting caught with your voltage down and vital files unsaved. You can even set alarms that sound when the remaining operating time reaches, say, 5 minutes.

In contrast, the fuel gauges commonly displayed by today's mobile computers give only a rough indication of the remaining operating time. They draw their conclusions from output voltage alone, a measurement that is skewed by complex interactions among such variables as the battery temperature, electrical load, construction of the cells, type of chemistry, and usage history of the battery. As a result, today's systems warn you that power is low and force a shutdown before the battery is fully depleted. As much as 20 percent of the battery's capacity may still remain.

Smart batteries can also figure out how much time they need to reach a full charge and how much longer a recharge will take

if you're using the computer at the same time. Some smart batteries communicate with a similarly smart charging system to tailor the voltage to the battery's requirements. The result: more efficient charging and longer service life.

Additional savings are possible with savvy power management subsystems. For example, if the computer detects a power surge-perhaps because a disk drive is spinning up to speed—a smart battery can alert the system to reduce power elsewhere, perhaps by dimming the screen momentarily or slowing the processor clock. You also get more working time because of the lowered discharge rate, and the reduction in the average current drain pushes the battery to operate at higher efficiency.

Wielding Power

Clever power management, with or without the benefit of smart batteries, is essential for extending battery life in portable computers. That's why power management functions are now integral to the CPUs, supporting chip sets, and BIOS firmware that are at the heart of the latest mobile computers. These subsystems monitor the computer's

activity, throttle its system clock, and control power to the screen, disk drives, and other devices. Even on the desktop, the latest green PCs are adopting these techniques to meet the U.S. government's Energy Star guidelines.

In mobile computers, the power management subsystems take a more aggressive approach because they're balancing operating time against performance. The better ones let you set these priorities by adjusting sliders and other controls. You can select a power management strategy biased toward maximum operating time, peak performance, or anything in between. Smart-battery technology simply extends this flexible power management to the battery and its charging system.

Compaq introduced smart batteries in its LTE notebooks in 1993, and IBM began using them in its high-end ThinkPads at about the same time. Apple, which is another major laptop vendor, put smart batteries in its PowerBook 500 series last year. Canon recently announced that it would combine smart batteries with ad-

vanced power management in a pair of laptops scheduled for introduction this spring and summer. By the end of the year, at least a third of all new notebooks will include smart-battery technology, estimates David Heacock, marketing manager at Benchmarq Microelectronics, a company that makes chips for smart batteries.

High-end PowerBooks have two battery compartments; one of them accepts an optional PCMCIA-card cage. Each NiMH battery integrates a tiny processor card that communicates important variables to the power management subsystem, which is called EverWatch. Either the user or the subsystem can cut power consumption by spinning down the hard disk, dimming the screen, or slowing the clock speed of the computer's 68LC040 CPU. As these changes are made, the onscreen fuel gauge indicates the precise effect on battery operating time.

Another bonus you get with smart batteries is that the computer can adapt itself to more advanced battery chemistries in the future. As new batteries are developed,

> their integrated controller chips will supply different information to the computer's power management and battery-charging subsystems, thereby adjusting the operating-time calculations and charging characteristics.

> Canon's new laptops will offer similar features, but with one exception: Their smart batteries could become as widely available as the AA penlight batteries that are used in your Walkman. The reason for this is a proposed standard that could eclipse the proprietary designs that are typical of most batteries for today's mobile computers.

AER Energy Resources, Inc.

Smyma, GA (800) 769-3720 (404) 433-2127 fax: (404) 433-2286

Apple Computer, Inc.

Cupertino, CA (800) 776-2333 (408) 996-1010 fax: (408) 996-0275

Benchmarq Microelectronics, Inc. Carrollton, TX

(800) 966-0011 (214) 407-0011 fax: (214) 407-9845

Find

2

Where

Canon Computer Systems Costa Mesa, CA (800) 848-4123 (714) 438-3000

Compaq Computer Corp.

Houston, TX (800) 345-1518 (713) 370-0670 fax: (713) 378-1442

fax: (714) 438-3099

Duracell Bethel, CT

Bethel, CT (800) 431-2656 (203) 791-3274 fax: (203) 791-3273

Energizer Power Systems Gainesville, FL

(904) 462-3911 fax: (904) 462-6210

IBM Personal Computer Co. Somers, NY (914) 766-1900

Intel Corp.

Santa Clara, CA (800) 548-4725 (408) 765-8080 fax: (408) 765-1821

Microchip Technology

Chandler, AZ (800) 437-2767 (602) 963-7373 fax: (602) 899-9210

National Semiconductor Corp. Santa Clara, CA (408) 721-5000 fax: (408) 739-9803

Opti Computer, Inc. Santa Clara, CA (800) 398-6784 (408) 980-8178 fax: (408) 980-8860

Panasonic Communications & Systems

Secaucus, NJ (800) 726-2797 (201) 348-7000 fax: (201) 392-4441

Phoenix Technologies, Ltd. Norwood, MA (800) 452-0120

(800) 452-0120 (617) 551-4000 fax: (617) 551-3725

SystemSoft Corp. Natick, MA (508) 651-0088 fax: (508) 651-8188

Custom Designs

Mobile-computer vendors generally prefer to use custom-designed batteries because it allows them more freedom to match the batteries and the power management subsystem to the particular requirements of the mobile system. These proprietary designs can prove to be expensive and risky, however.

Every time the battery is modified, the changes affect all the phases of product development, including systems design, manufacturing, inventory, and distribution. An unforeseen problem, such as the shortage of a

Fastest Modem Communications

Now Close-Up, two-time winner of PC Magazine "Editors' Choice" award for remote communications software, has a brand new version that lets you view & control other PCs by modem - just as if you were there!

Why Is Close-Up So Fast?

Close-Up learns as it works. It uses AI

(Artificial Intelligence) to compress all

mark tests (see WinBench 95 chart).

Windows video function calls. That's why

Close-Up does so well in Windows Bench-

Close-Up uses its revolutionary Photo-

graphic Memory so that once Close-Up has seen all or part of a Windows screen, it's

memorized. Then as screens change, Close-Up only transmits new unmemorized data. Incredibly, with this technology Close-Up gets faster & faster the longer you use it.

"Version 5.0 Close-Up was fast, but Version 6.0 has even better Windows performance and added features to keep it ahead of the pack."

- PC Magazine, July 1994

WinBench 95 Ver 1.0 by Ziff-Davis Labs Tests Remote Windows Speed

The graph on the right shows the speed of the three leading remote control programs when transferring Windows

screens. As you can see, Close-Up handles more pixels faster, meaning you spend less time waiting for Windows screens to transfer.

WinBench scores (average of 10 runs): Close-Up 209,270 pcAmpwhere 122,600 101,900 Reachout

Close-Up saves time & money by allowing you to connect between PCs running DOS or Windows, eliminating the need to switch between products when connecting to different PCs.

150,000

pixels per second

200,000

100.000

Expert System Makes Communications Easy

You don't have to be a communications expert to get the results of one. Close-Up has an Expert System that automatically analyzes system components and configures your system for maximum speed.

Non-Intrusive Technology

Unlike most remotes, Close-Up's installation does not modify any of your sensitive Windows files, including the SYSTEM.INI and WIN.INI files, allowing Close-Up and your PC to run at optimal levels.

Use Close-Up and Your Fax Software on One Modem



Save money by using just one modem with Close-Up and your fax software. Simply click the Close-Up sleep icon. What could be easier!

50,000

risk free offer


Try Close-Up 6.0! If you're not absolutely convinced that Close-Up 6.0 is the fastest remote program, we'll give your money back! Order Close-Up Host & Remote, a complete system for only \$199.

Upgrade your competitive communications program to new Close-Up 6.0 Host & Remote now for only \$6995.

We invite you to reproduce this test. Moderns: Hayes OPTIMA 288 V.FC. Computer. (Host) Gateway, (Remote) Micron, Pentjums 90Mbz, 32MB RAM, 128KB RAM cache, 500MB HD, IDE controller, no hardware disk cache. Video: (Host) STB

Eightspeed IMB VRAM, (Remote) Dammard Stealth 64 2MB VRAM. 800 x 600 pouels, 16 colors. Super-VGA DRV 11/199.75 Hz.
MS-DOS 622, SMARTDRV 2MB cache. WinBench 95 is available on Ziff-Pavis Publishing Co. Windows trademark of Microsoft Corp.

*60 day money-back gourantee if purchased directly from Nortun-Lambert. Offer expires 9/30/95. All proces in 25 Dollars. Prices oxclude shipping.















Circle 227 on Inquiry Card (RESELLERS: 228).















© 1995 Norton-Lambert Corp

Connect Modems To <u>Any</u> Office Phone

with

KÖNEXX[™]

PROBLEM:

Digital, PBX, and multiline phones in offices, hotels, etc. are not compatible with your PC, Mac, or Notebook computer modem or fax/modem. This incompatibility can potentially damage your modem or require installation of expensive dedicated lines.

SOLUTION:

The KONEXX Konnector 111 connects your fax/modem to the digital, PBX, or multiline office phone allowing data transmissian up to 28.8 Kbps (V.34). No need for expensive dedicated lines or searching for an analog (RJ-11) jack. Now you can communicate through your office phone with a fax/modem; using KONEXX.

The KONEXX line of Konnectors and high speed acoustic Kouplers will get you connected, where you need it, when you need it!

Call 1-800-275-6354

UNLIMITED SYSTEMS CORPORATION, INC. 8586 Miramar Place, San Diego, CA 92121 Phone: (619) 622-1400 Fax: (619) 550-7330

Special Report Mobile Computing

key component, can bring manufacturing to a dead stop. And you may have a hard time finding the right battery to fit your computer, especially after the model is discontinued.

An industry standard for batteries could minimize these risks. Critical components would be readily available from suppliers who are eager to sell to a broad alliance of companies. You would have less trouble finding replacement batteries, and the additional competition should reduce prices.

However, some mobile-system vendors are reluctant to adopt an industrywide standard that neutralizes their competitive edge in battery technology. A standard that's too rigid might also restrict their flexibility to experiment with advanced designs. For these reasons, proposed battery standards are often viewed with caution—if not outright suspicion.

Nevertheless, Intel and Duracell have proposed a pair of complementary standards that are known as SMBus (System Management Bus) and SBD (Smart Battery Data). Together, these two proposals map out a relatively lowcost and reliable plan that would allow mobile-computer makers to add smart-battery technology to their systems.

In the approach from Intel-Duracell, the two-wire SMBus carries clock signals, data, and instructions to a smart battery, an SMBus host, a smart-battery charger, and other devices. The SMBus specification allows for any type of battery, regardless of its chemistry, voltage, capacity, or physical package. And it's designed to work equally well in single- or multiple-battery systems.

The SBD specification defines a wide variety of battery-related information that can be carried over the SMBus, including battery characteristics, manufacturer data, the current state of charge, low-power alarms, predicted and measured discharge rates, and control, status, and error messages This information originates from logic and memory chips embedded within the battery.

The SMBus isn't meant just for smart batteries. Modeled after Philips Semicon-

ductors' I²C communications bus, it's really a general-purpose communications channel that can share power management information with any number of devices. These devices can supply their model designations and part numbers, save their states immediately before a power-down event, indicate errors, accept control parameters, and answer requests about their status.

By carrying messages on a standard bus instead of on individual control lines, the SMBus can reduce the number of pin-outs on the battery and other power management components, reducing costs. It's also easier to add devices to the bus.

SBD feedback improves battery charging, too. When connected to AC power, the charger adjusts its output in response to periodic messages from the battery about its charging requirements. The battery can

notify the charger if it detects a problem, such as over-charging, high voltage, or high temperature. In this way, the battery—regardless of its chemistry, construction, or condition—controls its charging cycle.

Gradually, the Intel-Duracell proposal is gaining supporters. Chip makers such as Benchmarq and

Microchip Technology have announced that they will supply system components, as have BIOS makers Phoenix Technologies and SystemSoft. Canon is the first major system vendor to announce support for the standards.

However, most of the vendors are for the moment watching and waiting. Still other companies actively oppose the idea. One chip maker, Opti Computer, objects to paying royalties for using the SMBus. Apple says the SMBus would require a time-consuming and software-intensive redesign of its PowerBooks. The standards will probably appeal most to smaller vendors, who lack the resources to develop their own smart batteries and power management subsystems.

Duracell also wants the industry to adopt five standard sizes for smart batteries similar in concept to the standard batteries (i.e., D, C, AA, AAA, and 9-V) that are used in other consumer devices. However,



They used to say you had a healthy glow.



You're healthier without the glow.

Here's something you may may be harmful to your monitors hour after hour, self, your family or your emissions. With that in TCO, the **strictest** Swedish

not know ... certain monitors
health. When facing some
you may be exposing youremployees to unhealthful
mind, ViewSonic has adopted
standard, for many of our new

monitors, including our new ViewSonic 17GS. This standard is more stringent than the older MPR-II or Energy Star™ guidelines. The unique benefits of TCO certification include substantial reductions in heat emissions, power consumption and decreased exposure to electromagnetic fields.


The high performance ViewSonic 17GS 17-inch (15.7" diagonal viewable area) monitor includes all you want and expect from such a superior product — like a maximum resolution of 1,280 x 1,024, low 0.27mm dot pitch, refresh rates as high as 160Hz and *Plug & Play +* for compatibility with Microsoft's Windows'95. Plus it has OnView' controls for simple on-screen adjustments and set-up. With ViewSonic's Super Contrast CRT you can expect sharp, bright, unsurpassed screen images. All of this, plus it's right for your budget!

To offer attractive pricing for their systems, many computer companies integrate lower quality monitors providing less emission protection. You have a choice. Demand the quality, performance and **safety** available from ViewSonic now!



Product	ViewSonic 17GS	ViewSonic 17GA	ViewSonic 17PS
CRT (Viewable)	17" (15.7")	17" (16.0")	17" (15.7")
Dot Pitch	0.27mm	0.27mm	0.25mm
Plug & Play +	YES	YES	YES
TCO Certified	YES	YES	YES
Max Resolution	1,280 x 1,024	1,280 x 1,024	1,600 x 1,280
Built in Speakers		YES	











Tel: (800) 888-8583 Ext. #269 or (909) 869-7976 Fax: (909) 869-7958

Call FaxSonic at (909) 869-7318 (fax-on-demand) Request Doc. 151 (17GS), 150 (17GA), 153 (17PS) Applelink: VIEWSONIC Compuserve: 73374, 514

All products and trademarks are brand names of their respective companies. The three bird logo is a registered trademark of ViewSonic Corp. Specifications subject to change without notice.

Network Data & Fax | Special Report

- Dial-out & Dial-in Modem Sharing & Pooling
- No TSRs Under Windows
- **Supports High-Speed Modems**
- **Complete Management Console**
- **Integrated Network Security**
- **Supports DOS INT-14 Applications**





From anywhere

on the network


- **Works with Windows Communication Applications**
- Windows NT Server 3.5, Netware, NetBIOS, & TCP/IP Networks



"WINport is a great buy!"

DONE RIGHT!

Windows, Windows for Workgroups, and Windows NT Clients



- Store-and-Forward Fax Gateway
 - No TSRs
 - Inbound Routing
- Real-Time Send & Receive Logs
 - Annotation
- Network Attachments & Phonebooks
- Windows NT Server 3.5, Netware, NetBIOS, & TCP/IP Networks

You've told us you what you want in an ideal modem sharing and network fax world. Here are the results. WINport 5.0 and FAXport 5.0. Each module is better than ever with easier installation, comprehensive administration, and support for more networks and more modems.

Purchase WINport and FAXport independently, or integrate them for a complete network fax and data solution.

LANSource 1-800-677-2727, (416) 535-3555, Fax (416) 535-6225 LANSource UK Tel: +44 1954 782 799 Fax: +44 1954 782 796



Copyright (c) 1993 LANSOURCE TECHNOLOGIES INC. All rights reserved. LANSource, WINport, and BAXent are trademarks of LANSOURCE TECHNOLOGIES INC. All other trademarks are property of their owners. Developer tested only. Novell makes no warranties with respect to this product.

140 BYTE JUNE 1995

Circle 245 on Inquiry Card.

vendors may be reluctant to accept this idea, too. Mobile-computer designers tend to leave the battery for last, assigning a higher priority to the overall shape and size of the computer, along with styling and ergonomic considerations. As a result, it's the space that remains after the other components are designed that defines the battery's exact shape.

As every laptop owner knows, today's batteries are anything but standard. Users will welcome Duracell's proposal if it doesn't impair performance. But battery design is an important decision that most system vendors would rather reserve for themselves.

At the Crossroads

To make it easier for system vendors to custom-design their own smart batteries, National Semiconductor and Energizer Power Systems, which is a division of Energizer Battery, have teamed up to offer an alternative. National Semiconductor supplies the electronics, and Energizer supplies the battery, which generally includes its own microcontroller. Thus, system vendors will save money because they don't have to start from scratch to make a custom design.

This partnership reflects a growing choice of discrete and chip-level circuits for power management and battery intelligence. For example, National Semiconductor also offers a smart-battery controller called the NeuFuz LMC6984. Using socalled neural-fuzzy logic, this controller is designed to optimally charge most types of rechargeable batteries without the need for more complex charger circuits.

It's becoming quite clear that battery technology for mobile computing is at a crossroads. If system vendors can be convinced that easy access to standard, lowcost batteries will help sell their laptops, they will be more amenable to the Intel-Duracell proposal. Otherwise, they will cling to the competitive advantages of proprietary batteries.

Dale Stolitzka, a senior applications manager at National Semiconductor, sees both camps thriving in the immediate future. "Companies that want a unique design will use custom batteries," he says. "Those driven by low cost and aiming for broadest market appeal will opt for standard sizes." ■

Gil Bassak is a freelance technical writer and journalist in Ossining, New York. You can reach him on America Online at GLBassak, on CompuServe at 72230,3526, or on the Internet or BIX at editors@bix.com.



Free Yourself!

Get the wireless PC Remote[™] today and never be tied to your keyboard and mouse again.



- No more stiff neck and back from hunching over your desk to use your keyboard
- Reduces finger fatigue with unique two-thumb design
- Intuitive layout makes it simple to use



Call Now, To Order 1-800-555-1205 Only \$99



30 day money-back guarantee

"With Envoy I don't get 'stuck' in meetings. I send and receive messages, right at the conference table. No post-meeting backlogs. Envoy levels out my workload. I love it!" Introducing Envoy® and Marco®: the first family of Wireless Communicators which offer fully integrated, two-way wireless connectivity to almost any E-mail address worldwide.

"Battling backlogs of faxes, E-

Messaging is "exquisitely easy" (InfoWorld), "seamless and reliable" (MacWeek). A message often costs less than a postage stamp — whether you're sending it to 1 person or 100.

"Envoy thinks like I do. Sounds weird, but while I'm physically at one meeting, I'm part of three or four others going on in my Envoy! I'm E-mailing, I'm faxing, I'm wireless, man!"

No matter how positive the reviews, or how many users swear by their

Envoy or Marco wireless

only one way to find out

if they're right for you:

try one. Call us, We'll

point you to a local dealer and send you
an information kit. And if you purchase
an Envoy or Marco within 90 days of calling us,

we'll send you a free leather carrying case (a \$79 value).

Call 1-800-894-7353 or E-mail us on the Internet at http://www.mot.com/wdg/ for more information on these products. And remember. No wires. No limits.

Circle 226 on Inquiry Card.



grove

The Envoy on the General
Magic Magic Cap™ platform
is packed with time-saving
features accessible with the tap

of an icon - no manual required.

Send text and handwritten messages via radio,
phone/fax or infrared. Let 'smart agents'
automatically reschedule meetings, update
addresses, etc., while you get on with business.





Using the Newton

platform, Marco

emphasizes wireless

connectivity to network applications like

desktop E-mail and corporate databases.

"Marco finally brings









Searching For The Best Multimedia Pentium Notebook?

CHECK OUR REFERENCES.



BYTE Magazine has just chosen NOTEBOOK the Sceptre

Soundx Multimedia Pentium Notebook BEST


OVERALL after head-tohead comparisons with the best notebooks available.

You'll find excellence in every product Sceptre produces. That's why, year after year, we continue to win performance awards from the industry's toughest critics.

Add your voice to the growing list of satisfied Sceptre users. Call

1-800-788-2878 for the dealer nearest you.

- INTEL 78/90-MHZ PENTIUM PROCESSOR
- 10,4" DETN/TFT WITH 256 COLORS
- FOI BUG TO INGREASE HOD SPEED
- FULL-RIZED, BE-KEY POSITIVE-TOUGH KEYSDARD WITH ENHANGED FEEL AND RESPONSE
- BUILTHN STERED SPEAKERS AND
- BIDE USES 256K CACHE TO MONITOR
- 6.3 POUNDS: 10.9" x 8.6" x 1.7"
- INFRARED BERIAL PORT





EXCELLENCE FOR ALL THE WORLD TO SEE

© 1995. SCEPTRE Technologies, Inc. All Rights Reserved. All product and brand names are trademarks or registered trademarks of their respective companies.

You Can Take It with You

Windows 95 keeps up with users on the go

JON UDELL

hen Microsoft began designing Windows 95, the handwriting was already on the wall: Portable PCs would soon begin to displace desktop systems, acting as home computers and road machines. Windows

95's Plug and Play supportwith dynamically loadable and unloadable VxDs (virtual device drivers)-anticipated the needs of the user who yanks a PC off the company network, pounds out a speech on an airplane, arrives at the conference

hall just in time to print it, and jacks into the company network at the end or server machine and at of the day from the hotel.

The best way to reach this state of perpetual motion will be to use a dockable laptop. Punch the eject button, and you trigger a flurry of activity as Windows 95 negotiates with applications to release their hold on files and devices, and then un-

loads drivers. Dock the PC, and everything comes back. (Caveat: I've seen this done but haven't tried it myself.) Everyone will want to do this, but everyone doesn't have a docking station.

What does Windows 95 do for nondockable portables? On the hardware side, it handles the hot swapping of PCMCIA cards (as does OS/2 Warp), and it can monitor battery power and react to suspend/resume events. There's also a hardware profiles manager (again, à la OS/2 Warp) that can prompt you at boot-up time to choose between, say, an office configuration and a remote setup. Even with all this flexibility, though, you can still reboot more often than you like-as when you change your IP address. Windows 95 isn't as dynamic as NetWare.

Shiva helped Microsoft integrate PPPbased dial-up networking into Windows 95, and the results are impressive. From home, I can dial the office and run three protocols (IPX/SPX, NetBEUI, and TCP/IP) and two clients (Novell and Microsoft), navigating the full panoply of re-

> sources on our network. Negotiation of communications settings, a problem in earlier beta versions, was smoother in the current Beta 3. Resource browsing, however, remains maddeningly slow. Microsoft

Windows 95's mail client, now called Microsoft Exchange, uses the LAN when you're in the office and dial-up networking when you're elsewhere. A nifty remote preview feature lets you scan message headers and specify which to retrieve. Users of nondockable portables will appreciate its ability to fetch messages nondestructively-that is, without altering the state of the post-office message store.

Why do that? If you operate separate home, office, and road PCs, you know that managing multiple local message stores leads to vexing synchronization problems. If you can't avoid these problems by consolidating everything into a multipurpose PC, it's handy to let multiple PCs share one post-office account without stepping on each other's toes. I used Exchange to re-

> motely access both my Microsoft Mail and CompuServe accounts.

> Mobile users will appreciate Windows 95's deferred-printing capability. You can print to a network printer when you're off-line. When you reconnect, Windows 95 finds the printer and prompts you to complete the job.

> You can use the Windows 95 Briefcase to help synchro-

nize files between your portable PC and a desktop or server system. You might, for example, keep a PIM (personal information manager) data file on a server to share it with others and include it in the nightly server backups. If you drag a copy of the file to your portable's Briefcase, it can move the file back and forth for you. When you're leaving the office, a Briefcase update copies from the server to your portable. When you return with new PIM data in the Briefcase, another update ef-

fects the reverse transfer.

Update My Briefcase ? X The following files need to be updated. To change the update action use the right mouse button to click the file you want to change. In \\Rhapsody\Frut, **
Unmodified 3/28/95 1:50 PM 1/31/95 10:08 AM In Baelcase In \\Rhapsody\Fnut 1/31/95 9:33 AM 3/28/95 1:50 PM In \\Rhapsody\Frut Unmodeled 1/31/95 1:27 PM 3/28/95 1:51 PM Update Cancel

The Briefcase (above) helps you manage files that sometimes live on a desktop other times travel with you on a portable PC.

Wizards (right) make it easier to navigate the forest of dialog boxes involved in the configuration of dial-up networking. Note that "Internet" is now a supported PPP server type, which means you can establish a dial-up connection to an IP service provider as well as to the office LAN.

> says its protocols are "slow-link aware," which helps make data transfer more robust. What would also help would be improved client-side caching, so that laboriously retrieved directory listings need not be refetched.

> I had to dial in to a Windows NT machine because the Windows 95 remoteaccess server in the previous beta version had vanished in Beta 3. It will be available separately, and that's a relief to corporate IS managers. If they were suspi-

cious of Windows 3.11's peer networking, they'll be terrified of deploying thousands of Windows 95 systems, each of which could be a security risk.



FYTE ApraNT 35 1(555)555-55.


F PRUSPY Dropold

DK Cancel

P IOPAP

Jon Udell is BYTE's executive editor of new media. You can reach him on the Internet or BIX at judell@bix.com.











The ultimate mobile computing solution.

We designed the Model 7108 Mobile Field Computer System specifically for use in moving vehicles—where harsh operating conditions are the norm. The 7108 is built to take shock, vibration, and high temperatures—it's even water resistant!

Planes, trains, and automobiles.

Perfect for use on land or sea, or in the air—even test vehicles used by automobile and tire manufacturers, the Model 7108 Mobile Field Computer System can handle conditions that would destroy ordinary PCs—in fact, it makes those systems look like they're standing still!

Rush The Info To Me!

Name:

Company:

Address:

City, ST, Zip:

0.1

Phone:

Fax this ad directly to: 713-541-8226. We'll show you the best route to mobile field computing!



1-800-627-8700

Fax:713-541-8226 Int:713-541-8200 Internet: sales@texmicro.com

PDAs Bounce Back

MICHAEL NADEAU

all them what you like—PDAs (personal digital assistants), personal communicators, organizers, palmtops, or hand-held PCs—but sooner or later, you'll almost certainly be using a small computing device to communicate and manage information. Even today, in what might be considered the primeval era of PDAs, they help thousands of users keep track of schedules, maintain todo lists, and serve as mobile nodes for exchanging data in remote locations. Mobile workers are using PDAs to

gather sales statistics, retrieve information from on-line databases, and keep in touch with their home offices via paging services or even cellular phone networks.

So why, after years on the market, have PDAs failed to take the world by storm? Unfortunately, they are still products of an immature technology. While they can perform the above tasks and more, they're relatively inefficient, or prohibitively expensive, or both. Some companies that were planning to introduce PDAs have postponed their projects, and others (e.g., Eo) have vanished from the market.

But the good news is that PDAs are evolving rapidly. Prices for both systems and services are dropping. User interfaces and hardware designs are growing better suited for important tasks. Desktop connectivity—which was at first almost nonexistent—is widely available and much more sophisticated. Battery life is improving. More development tools are available and software is multiplying. Perhaps most significantly, wireless communications services are becoming more affordable and widespread.

Cost Controls

Today, price is still a major barrier to the proliferation of PDAs. A general-purpose PDA with integrated land-line and wireless modems will cost you \$1000 to \$1500. That's not cheap, but nearly two years ago such a device (the Eo Personal Communicator 440) cost nearly \$3000.

Personal organizers have dropped in price as well. The street price of the Casio Z-7000, for example, has dipped from \$700 to \$400. The industry consensus is that sales will surge when prices hit between \$600 and \$700 for a device with two-way wireless communications and between \$200 and \$300 for a less communicative PDA.

A few key components are keeping PDA prices high. LCD screens are a relatively costly item—as much as \$30



per unit. Because each PDA requires its own unique display, vendors can't take advantage of the economies of scale that notebook vendors enjoy. After the LCD, the most expensive component in a PDA is usually RAM. The less memory the PDA needs, the more control its designers have over system cost and size. For this reason, many PDA applications and

some OSes are written in assembly language to conserve as much memory as possible.

The purchase price of a PDA often pales, however, when compared to the user's long-term cost of subscribing to a wireless communications service. RadioMail (San Mateo, CA), a provider of E-mail and other wireless services, charges \$39 to \$139 per month for access to the Ardis radio network. The lowest fee in that range allows you to send up to 100 messages of 240 characters each per month. Additional messages cost 21 to 36 cents each.

If you add paging services, connections to on-line services such as CompuServe, or access to information downloads such as stock quotes, your monthly bill escalates. On the bright side, many of these services were unavailable or more expensive when PDAs first appeared a few years ago.

Form Follows Function

PDAs are very diversified, and they'll probably become more so in the future, although this is a matter of debate.

Slowly but surely,
PDAs are evolving
into useful business
tools. High prices
and an inadequate
wireless
infrastructure
remain obstacles.

Special Report Mobile Computing

Some observers think each important function will spawn its own small, inexpensive, specialized device. Others believe that improved technology and economies of scale will eventually allow a few general-purpose PDAs to adequately and costeffectively perform many different tasks.

"Each hardware manufacturer has different ideas about what they want to build," says Gordon Mayer, CEO of GeoWorks (Alameda, CA), which supplies GEOS to several PDA vendors. Those ideas seem to depend on the historical hardware and application focus of the company (see the table "The Wide Variety of PDAs").

For instance, Motorola (Schaumburg, IL) is a leading communications company, so it's no surprise that its Envoy and Marco

systems emphasize E-mail and wireless connectivity. Cellular-phone vendor Nokia (Salo, Finland), which recently bought a stake in GeoWorks, is planning several cellular-based PDA-like products for the consumer and business markets.

Communications-based devices such as the Marco are expensive (\$1000 or more) and are aimed at a relatively small group of business users. The personal organizer applications they include have a strong slant toward communications. For instance, the Magic Cap software from General Magic (Sunnyvale, CA) can automatically pull E-mail information from its address book when you send a wireless message.

Large Japanese consumer-electronics companies (e.g., Sharp and Casio) tend to

sell devices that emphasize universal tasks, such as scheduling, note-taking, and to-do lists, instead of wireless communications. Their personal organizers offer nearly all the communications options of, say, Motorola's Envoy, but only as relatively expensive add-ons that seem more like an afterthought. For the most part, these organizers are not as versatile as the PDAs from Apple (Cupertino, CA), Sony, Motorola, and a few other vendors.

Traditional computer companies like Hewlett-Packard (Palo Alto, CA) tend to place a higher priority on making their hand-held devices compatible with desktop PCs. The HP 200LX has a QWERTY keyboard, uses MS-DOS, and comes with the LapLink file transfer utility from Traveling

The Wide Variety of PDAs



Apple Newton MessagePad 120



Casio Z-7000 Personal Digital Assistant



Fujitsu PoqetPad Plus



Hewlett-Packard HP 200LX

os e	Newton Intelligence	GEOS	MS-DOS 5.0	MS-DOS 5.0
CPU	20-MHz ARM 610	NEC V20-based	16-MHz NEC V30	7.91-MHz 80C186
I/O ports	serial/LocalTalk, IR	serial, IR, headphone jack	serial (two), IR, keyboard	serial, IR
Standard RAM/ROM	1 MB/4 MB	1 MB/4 MB	2 MB/2 MB	1 MB/3 MB
Standard communications	none	none	none	none
Optional communications	modem, radio modem, pager	modem, cellular modem, pager	modem, radio modem	modem, radio modem cellular modem
Expansion	one Type II PC Card	one Type II PC Card	one Type II and one Type III PC Card	one Type II PC Card
Input	stylus	stylus	stylus, optional keyboard	QWERTY keyboard
Desktop connectivity	optional	optional	optional	yes
Battery	alkaline AA or nickel-cadmium	alkaline AA	nickel-cadmium	alkaline AA
Weight	1 lb.	1 lb.	1.77 lbs.	11 oz.
Dimensions (inches)	8 by 4 by 1.2	6.8 by 4.2 by 1	10 by 4.6 by 1.5	6.3 by 3.4 by 1.
Base price	\$599	\$499.95	\$1275	\$549

Note: Not every hand-held computing device is listed in this table, of course; however, it does represent the broad variety of devices. The proliferation of widely different hardware designs and OSes is reminiscent of the early days of desktop computers.

Software (Bothell, WA). A full range of communications options is also available.

Expect many more variations of these basic archetypes to appear in years to come. What you won't likely see are many PDAs larger than the currently available offerings, "People want products that look like a notebook [PC] or something you hold in your hand," says Ken Dulaney, an analyst with the Gartner Group (Santa Clara, CA).

Tweaking the User Interface

These varied approaches to hardware design and basic functions also dictate the limits of the user interface. Ideally, perhaps, users wouldn't have to confront more than one general type of interface on the different computers they use. But it is proving impractical to design a common user interface that's scalable from small pocketsize devices to larger hand-held units to full-size desktop systems. Some vendors, such as Apple, strongly believe it's preferable not to try-it's better to design a fresh interface that's optimized for PDAs rather than cling to desktop standards that are more appropriate to large screens.

Even among small mobile devices, however, there's enough variety to make userinterface design a challenge. An interface that works on a palm-size PDA might fail on a pocket-size pager.

Microsoft (Redmond, WA) has been struggling for years to make a version of Windows that fits on a PDA. That project, known as WinPad, is on a back burner.

Attention has shifted to object-oriented OSes such as GeoWork's GEOS, Apple's Newton Intelligence, and General Magic's Magic Cap, which are inherently suited to small devices.

For one thing, these OSes are more modular, so the user interface can be modified for different classes of devices or vertical markets without rewriting other parts of the OS. Changing the interface of a conventional desktop OS requires either a major overhaul or the addition of a shell program-not a desirable alternative for PDAs, where memory is at a premium.

GEOS goes the farthest in decoupling the user interface from the underlying kernel. It supports a generic interface, which is common to all GEOS applications, and



Rewriting Handwriting Recognition

DAVID ESSEX

he Doonesbury strip. It haunts every conversation about hand-writing recognition—and also serves as a milestone that marks where the technology has been and where it needs to go. When cartoonist Garry Trudeau ridiculed the Apple Newton's comical mangling of simple phrases, he gave voice to the public's unspoken verdict on the fledgling PDA market: Sorry, but your act isn't ready for prime time.

As a result of the Doonesbury debacle, the leading developers of handwriting-recognition software learned two lessons: do a better job of recognizing handwriting and do a better job of managing users' expectations. Developers say that users shouldn't expect a computer to recognize writing that even a person can barely recognize.

Selling into vertical markets helps, as Apple has learned by repositioning the Newton MessagePad. Pen-based computers deployed by a corporate MIS department are more likely to be accompanied by training, as well as the expectation that users must learn to work with the devices. Vertical-market applications are also more likely to involve the frequent use of forms, where constrained text entry greatly simplifies the difficult task of recognition.

PDA developers have also learned to downplay the emphasis on handwriting recognition as a key component of the user interface. The latest designs make use of point-and-tap selections and digital ink (unrecognized drawing and jotting stored as bit maps). But digital ink needs more memory and disk storage—which PDAs tend to have in short supply.

Perennial Challenges

Although the key issues are almost all software-related, some hardware chal-

lenges remain. The ice-like surfaces of LCD screens on early pen computers caused people to write less legibly than usual, and the weight and thickness of the stylus did not always mimic those of traditional pens. In response, we're starting to see writing surfaces with more friction from vendors such as Cal-Comp, as well as redesigned styluses. Hardware vendors are also working to minimize parallax (i.e., how a user perceives the separation between the writing point and where the point appears on the digitizer).

Meanwhile, research aimed at improving recognition continues. There are two broad approaches: the method of throwing many specialized algorithms at basic pattern recognition (a trend also observed in AI programs, such as neural networks and expert systems); and application of contextual and grammatical post-processing, which is common in speech recognition.

Most first-generation recognizers compared each newly written character to a set of similar ones. Now, research is focused on using computational and statistical methods to spot deviations from the model characters. An example is the process of analyzing the different ways of writing an uppercase A, as explained by John S. Ostrem, vice president of R&D at Communication Intelligence (Redwood Shores, CA), the maker of PenDOS and Handwriter.

The right downstroke of the A might end at the bottom, or it might barely pass the crossbar. To account for such differences, recognizers use a technique called *elastic matching*. By measuring perhaps six or eight Fourier coefficients plotted between representative points on both the unknown and reference char-

Lexicus Longhand

Lexicus Longhand

Software recognizes

software recognizes

Recognizes recognizes

Recognizer recognizer

Recognizer recognized

Ressuizes

Lexicus Longhand uses neural networks to recognize raw images and pattems in cursive handwriting, it compares unrecognized words to a 25,000-word dictionary and uses statistical methods to generate a list of best guesses from which you pick the intended word. Lexicus says the process takes only 1 or 2 seconds and that overall recognition exceeds 90 percent.

acters, an elastic matching algorithm calculates whether the coefficients fall within a permissible range. One study found the resulting error rate to be half that of linear (nonelastic) matching.

Grammatical and contextual analysis methods try to guess the likelihood of certain letters or words occurring near each other, based on language rules. If the pattern-recognition algorithms are uncertain about the identity of a Q, for example, a contextual analyzer might check the next character to see if it's a U and is at the beginning of a word. When the algorithm exceeds a particular confidence threshold, the recognizer interprets the character in question as a Q.

Lookup dictionaries have also become standard fare. They are frequently augmented by contextual algorithms or are narrowed to domains relevant to the user's special interests. A vendor, Lexicus (Palo Alto, CA), claims the dictio-

N_NO_OP_PO_QR_RS_S T_T U_U V_V W_WX_X Y_Y Z_Z

Palm Computing's Graffiti requires users to learn a modified version of the alphabet. When combined with Caps Lock and a separate numbers key, Graffiti purportedly achieves close to 100 percent accuracy.

nary in its Longhand cursive handwriting recognizer correctly guesses an unidentified word about 80 percent of the time (see the screen). Users choose their intended word from a list of candidates.

Using so many advanced techniques at once requires greater CPU power and memory capacity than is typical of today's hand-held devices. Accordingly, complicated neural-net approaches like those in Longhand work only on larger pen computers. Developers expect low-cost, high-speed RISC chips such as the StrongARM from Digital Equipment and Advanced RISC Machines to bring these advanced techniques to smaller devices.

Palm's Alternative

Another approach is Graffiti, a crossplatform recognition engine from Palm Computing (Los Altos, CA). Graffiti requires users to print with a simplified version of the English alphabet. All but six of the 26 letters are the same as their traditional uppercase and lowercase equivalents. The rest are generally based on parts of traditional characters (see the figure at bottom left).

The idea, says Palm Computing, is to make each character more distinguishable so that it won't be confused with others. (A special shift key lets you specify numerals.) Recognition is reportedly close to 100 percent, and Palm says that most people become competent with the new alphabet in about 20 minutes.

However, Palm's competitors—and many users—are skeptical about the idea of adopting a new alphabet. They believe that the computer should adapt to the user, not the other way around.

Most developers continue to concentrate on the challenge of recognizing existing writing styles. All they ask is to be judged by a fair benchmark. "If you write something and no one else can read it, don't expect a computer to," says Madeline Duva, Communication Intelligence's director of business development. "These things are not magicians."

David Essex is a BYTE technical editor for reviews. You can contact him on the Internet or BIX at dessex@bix.com.

a specific interface, which is left to the discretion of the developer. An abstraction layer separates and translates between these two interfaces. Mayer calls this "the most innovative piece of our technology."

Magic Cap's pictorial user interface will not scale down as easily to small pocket-size devices. The Newton's emphasis on handwriting recognition similarly limits its scalability (although the latest Newton applications rely less and less on freehand text entry). Both interfaces are more easily scaled upward; in fact, General Magic has announced plans for a Windows version of Magic Cap.

User interface design for PDAs is closely intertwined with the method of user input. Styluses are fairly standard, but for now, PDA vendors are avoiding handwriting recognition. Not only is it too unreliable, but the recognition engines also tend to hog processing power and memory. One promising alternative, however, is a recognition engine called Graffiti from Palm Computing (Los Altos, CA). Graffiti is available for Newton, Magic Cap, and GEOS systems (see the text box, "Rewriting Handwriting Recognition").

Connecting to the Desktop

Every PDA vendor is beefing up its desktop connectivity in response to user demand. "By far, the most important kind of communications is to talk to the desktop conveniently," says Randy Palmer, U.S. product manager for palmtops at HP.

Virtually all PDAs provide some means of exchanging files with PCs or Macs, but few provide this capability as a standard feature. That's not likely to change soon. Although many users want desktop connectivity, others avoid it and "dedicate a certain task to a certain device," says the Gartner Group's Dulaney. Adding file transfer features to PDAs to accommodate some users would increase prices and consume precious memory for all.

Even when the desktop connectivity gap is bridged, users face the problem of data synchronization. Most people want desktop connectivity as a means of simplifying data input; it's easier, for instance, to enter names and addresses into a card file with a desktop keyboard than with a stylus or a tiny PDA keyboard. But later, when you're on the road, you'll probably add some new records to the address book on the PDA. Now you've got two different versions of your address book—one on the PDA, and another back home on the desktop. Somehow you've got to synchronize the data.

As more businesses deploy PDAs among their mobile workers, group tasks

Unleash your Pentium/Alpha!

Microway's NDP Fortran & C|C++ are the only 32-bit compilers which take full advantage of the Pentium and Alpha's dual numerics units. They run on DOS, UNIX, OS/2, NT and OS/F. To get RISC numeric performance from a Pentium or Alpha you need to schedule your code and use Superscalar optimizations. In his Jan. '95 Dr. Dobbs article, S. Fried describes how to get 35 megaflops from a Pentium using NDP Fortran. The Alpha version of NDP Fortran hits 88 megaflops running on OS/F or NT systems or on DOS using Microway's new ISA add in card. Put our compilers or Pentium, i860 and Alpha systems to work for you today. Call for white papers on Pentium, i860, or Alpha Code Generation, OS/2 or our Pentium FDIV fix, now!

i860/Pentium/Alpha SuperComputers

BX Series Pentium/Alpha/i860 Workstations -Microway's workstations and industrial PC's come configured with DOS, OS/2, UNIX, From....\$2195

Gigacube Three to six QuadPuters - Up to 24 i860's for \$50K! Computational Server runs NFS.

Number Smasher -860 Up to 80 megaflops, does 1024 FFT in just .9 ms, From......\$2995

QuadPuter-860 Four 40 MHz i860's plus shared memory equals 320 megaflops.....\$11995

ArrayPRO/XP™ - 100/200 megaflops, 400 MB/Sec memory, 80 and 33 MB/Sec DSP Interfaces.... \$8995

Number Smasher Alpha 100+ megaflops - this ISA Superscalar add in card runs on DOS or UNIX. It uses T8 links for parallel processing. From \$5995

NDP Compilers

Microway's family of 32-bit compilers run on DOS, OS/2, NT, UNIX, and OS/F generating code for the Intel 386, 486, Pentium, i860 and DEC Alpha.

NDP Fortran™ is a full F77 with complete VMS, F66, DOD, and MS extensions.

NDP C|C++TM runs in K&R, ANSI and C++ modes and generates the highest quality numeric code of any 32-bit C compiler.

NDP Pascal™ is a full ISO Level 0 translator. DOS releases includes VCP1, DPMI, NDPLink,

VM, NDPLib and GREX-Microway's bit mapped graphics library. The 486/Pentium version adds 486/Pentium code generation, Clearview, the MGX vector graphics library, and DPMI DOS Box support for demand paging and GREX.

Call for UNIX, OS/F and NT pricing. NDP Fortran 90 extensions to NDP Fortran...\$295

Microway

Research Park, Kingston, MA 02364 USA (508) 746-7341 FAX (508) 746-4678 Call for Germany, India. Indonesia. Israel Japan, Poland, Russia and U.K.

WHEN IT COMES TO CD-ROM.. WE WROTE THE BOOK


BYTE Guide to CD-ROM, Second Edition by Michael Nadeau Includes One CD-ROM Disc \$39.95 USA ISBN: 0-07-882104-5

Now Fully Revised & Expanded!

This Exclusive CD-ROM Package Includes
• Sound Clips and Clip Art
• Samples of CD-ROM Applications
• Multimedia Authoring Tools

Part buyer's guide, part standards guide, and part trouble-shooter, the BYTE Guide to CD-ROM, Second Edition discusses all aspects of this burgeoning technology so you can take full advantage.






BYTE Guide to Telescript by Cronder Concepcion and Paul Staniforth \$29.95 USA ISBN: 0-07-882119-3 Available June



BYTE Guide to OpenDoc by David Berkowitz \$29.95 USA ISBN: 0-07-882118-5 Available September



BYTE Guide to Optimizing Windows 95 by Craig Menefee and Lenny Bailes \$29.95 USA ISBN: 0-07-882120-7 Available September



Available now at your local book and computer stores or call 1-800-822-8158. Use your American Express, VISA, Discover, or MasterCard.

AT NATIONWIDE STORES

BEST BUY

HENAPLAY

SOFTWARE FIC

TAYLORS

WALDENBOOKS

SUPER CROWN Arlington Taylor's Technical Books PH: 817-548-TECH

University Co-Op PH: 512-476-7211

Taylor's Technical Books PH: 214-239-TECH

Houston Brown Book Shop PH: 713-652-3937 FAX: 713-652-1914

VIRGINIA Blackshum University Bookstore, Virginia Tech PH: 703-231-5991 FAX: 703-231-3410

Vienna Computer Literacy Bookshops PH: 703-734-7771 FMAH . sales@tc.clbooks.com

WASHINGTON Bellevue **University Bookstore** PH: 206-646-3300 FAX: 206-646-3340

Pullman Students Book Corporation PH: 509-332-2537 FAX: 509-332-8239

Seattle Tower Books PH: 206-283-6333 FAX-206-285-2188

Tower Books

PH: 206-473-3362 FAX: 206-473-9141 WISCONSIN Madison University Bookstore

PH: 608-257-3784 FAX: 608-257-9479 Milwaukee

University of Wisconsin Milwaukee PH: 414-229-4201 FAX: 414-229-6194

AI ARAMA Madison Madison Books & Computers PH: 205-772-9250

ADIZONA Phoenin Computer Library PH: 602-547-0331

FAX: 205-461-8076

CALIFORNIA Berkeley Cody's Books Inc. PH: 800–479-7744 in CA

Citrus Heights Tower Books PH: 916-961-7202

Cupertino Computer Literacy Bookshops PH: 408-973-9955

UCD Rookstore University of California PH: 916-752-2944

Las Angeles **ASUCIA Students Store** PH: 310-206-0763

Mountain View Printer's Inc. PH: 415-961-8500

Palo Alto Printer's Inc. PH: 415-327-6500

Stanford Bookston PH: 800-673-2348

Sacramento Tower Books 1600 Broadway PH: 916-444-6688

San Francisco Stacey's Professional Bookstore PH: 800-926-6511 EMAIL: staceysbk@aol.com

San Luis Obisno Earthling Bookshop PH: 805-543-7951 FAX: 805-543-8488

Santa Barbara Chaucer's Bookstore PH: 805-563-0010

UCSB Bookstore The University of California Santa Barbara PH: 805-893-2082

Sunnyvale Computer Literacy Bookshops PH: 408-730-9955

COLORADO University Book Center CU Boulder PH: 303-492-6411 FAX: 303-492-0421

Colorado Springs The Chinook Bookshop PH:719-635-1195 FAX-719-635-0792

Bibão Tek PH:303-534-3460

Longmont
United Techbook Co. PH:303-651-3184

CONNECTICUT Yale Co-Oc PH: 800-ELI-YALE FAX: 203-772-3665

FLORIDA Construction Bookstore PH: 904-378-9784 FAX: 904-378-2791

GEORGIA Atlanta Oxford Bookstore FAX-404-364-2729

HAWAII Honoluli, University of Hawaii PH: 808-956-4338 FAX:808-956-4323

HINOIS **Naperville Books and Bytes** PH-708-416-0102

MARYLAND College Park Maryland Book Exchange PH: 301-927-2510 FAX:301-209-7118

Charlesbank Bookshops PH:617-236-7442 FAX:617-236-7418

Burlington PH: 617-273-2919 FAX:617-273-2499 EMAIL: books@ softproeast.com

Camoridge Quantum Books FAX: 517-577-7282 EMAIL: quanbook@world.std.com

Newton Highlands New England Mobile Bookfair PH: 617-527-5817 FAX:617-527-0113

MICHIGAN Kalamazoa Western Michigan University Bookstore Western Michigan University PH: 616-387-3930 FAX: 616-387-3941

BYTE/OSBORNE BOOKS ARE AVAILABLE AT THE FOLLOWING LOCATIONS FAX: 603-643-5170

NEW JERSEY New Brunswick Rutgers University Bookstore PH: 908-246-8448

NEW MEXICO Albuquerque Page One, Inc. PH: 505-294-2026

NEW YORK Village Green Bookstore PH: 716-884-1200 FAX: 716-884-3007

Books Revue PH: 516-271-1442 FAX: 516-271-5890

New York City Benjamin Books PH: 212-432-1103 FAX: 212-432-1104

Coliseum Bookstore PH: 212-757-8103 FAX: 212-489-0929

J & R Computer World PH: 212-732-8600

McGraw-Hill Bookstore PH: 212-512-4100 FAX: 212-512-4105

New York University Computer Store PH: 212-998-4591

Campus Connections (RIT) PH: 716-475-2504

Village Green Bookstore 1954 West Ridge Road PH: 716-723-1600 FAX: 716-723-1669

Village Green Bookstore 716 Monroe Avenue PH-716-461-5380 FAX: 716-461-9333

Syracuse University Bookstore PH: 315-443-1654

OHLO Cleveland **Business Outreach** PH: 216-348-1744 FAX: 216-348-0375

Lima Readmore 217 Flanders PH: 419-225-5826 FAY-419-225-5537

Readmore's Hallmark 3330 W. Elm Street PH: 419-225-5826

Youngstown Youngstown State University Bookstore PH: 216-742-3589

OREGON Beaverto Powell's Bookstore at Cascade Plaza PH: 503-643-3131 FAX: 503-641-1554

Eugene Book Mark PH: 503-484-0512 FAX: 503-484-3130

Portland Powell's Technical Books PH: 503-228-3906 FAX: 503-228-0505

PENNSYLVANIA Davlestown Village Green Bookstore PH: 215-230-7610 FAX: 215-230-7615

Erie
The Erie Book Store PH-800-252-3354

Philadelphia Bookstore of the University of Pennsylvania PH: 215-898-4900 FAX: 215-898-6997

Book Center University of Pittsburgh PH: 412-648-2321 FAX: 412-648-1902

Paperback Booksmith PH: 717-346-9162

RHODE ISLAND Providence Brown Bookstore FAX: 401-863-2233

Special Report Mobile Computing

such as scheduling and updating sales reports will become increasingly important. To avert chaos, everyone has to be working with the latest version of the schedule or the database. So PDA vendors and developers are working on better file transfer and data-synchronization tools.

For example, Psion (Concord, MA) is introducing PsiWin software for the Psion Series 3a Palmtop computer. The Palmtop files appear in their own volume on the Windows desktop, and you can transfer files by dragging and dropping.

Expected to ship in May, Psion's Psi-Win will include many file translators for preserving attributes while transferring Psion files to many word processor, spreadsheet, database, or scheduling applications. PsiWin will also include a Windows PC version of the Series 3a's data application, which will let you create entries using the PC's full-size keyboard and transfer them into your Psion Palmtop. In a future release, Psion plans to add a Hot Thinking feature to automatically reconcile data within the files. IntelliLink's (Nashua, NH) IntelliLink connectivity software has a similar feature that offers a graceful way to resolve duplicate agenda appointments: IntelliLink lets you send data between your desktop PC and PDA at the file level. IntelliLink supports several PDAs, including ones from Casio, HP, Psion, Tandy, and Sharp.

If your PDA and desktop machine have PCMCIA PC Card slots, you could solve this problem merely by swapping storage cards back and forth. Intelligent driver software could perform any necessary file conversions, and your PDA data would appear as just another hard drive on your desktop. Several vendors make PC Card cages that work with desktop PCs.

Extending Battery Life

Another challenge is building a PDA that can run for days or weeks on a fresh set of batteries. But measuring a PDA's battery life is tricky. People don't use PDAs like desktop computers; they tend to turn portable devices on and off more fre-

quently, using them for brief periods of time. It makes little difference, therefore, whether a device gets 10, 50, or even 100 hours of continuous use. What does matter, says GeoWorks' Mayer, is that users get "unconscious" battery life. In other words, the PDA must run long enough so that users can recharge or replace the batteries at convenient, regular intervals.

Most PDAs sold today have backup batteries that preserve stored information even when the device is turned off. But adding components such as radio modems, cellular phones, or pagers can drain the main batteries much more quickly. Better power management is still a top design goal.

New battery technologies such as the optional lithium-ion cells in Sony's PIC-1000 are part of the answer, but what's more important is designing hardware that's less power hungry. "Power management is a distinctive art," says Mike Lundgren, U.S. market development manager at Apple's PIE (Personal Interactive Electronics) division. That art includes higher integration of system logic into ASICs, lower-power components, and better power management software (see "Brainy, Brawny Batteries" on page 131).

CPUs are doing their part, too. Motorola's Dragon I 68349 CPU draws only 300 milliwatts of power at 16 MHz; when idle, its power consumption drops to under 1 mW. Casio's Z-7000 uses an 8086-class processor and provides excellent battery life—although it has been widely criticized for its poor performance.

One remaining obstacle is that Type II PC Cards and controllers are 5-V components, but most PDAs use 3.3-V parts. A 3.3-V PCMCIA design is in the works, but PDAs that use them are at least a generation or two away.

GEOS 3.0 INTEGRATES COMMUNICATIONS

GeoWorks's GEOS is one of the smallest general-purpose OSes available, needing only about 1.6 MB of ROM and 512 KB of RAM. It is optimized for low-cost, power-sipping, x86-compatible CPUs, and it provides developers with flexible options for designing user interfaces. Until now, however, GEOS's support for communications has lagged behind other PDA-oriented OSes (e.g., General Magic's Magic Cap and Apple's Newton Intelligence). GeoWorks aims to change that with GEOS 3.0.

GEOS 3.0 adds a critical data communications layer atop the core OS. That layer includes a mailbox library, a socket library, transport drivers, and fax capability.

The mailbox library provides a systemwide inbox/outbox that streamlines the delivery of messages between applications or devices. Those messages can be E-mail letters, desktop file transfers, or faxes. The mailbox can hold messages and defer transmission until it recognizes that a transport driver has become available. For example, you could make a change to your calendar, store the change in the mailbox, and later use an infrared or wired link to record that change on a colleague's PDA or desktop computer.

Two-way communications channels are provided by the socket library. GeoWorks borrowed its socket API from BSD Unix; protocols include TCP/IP using SLIP and PPP and the IrLAP (Infrared Link Access Protocol) subset of the IrDA (Infrared Data Association, Walnut Creek, CA) standard. Geoworks says full IrDA support will be available later. This library allows a developer to build communications capability into an application without knowing how a given protocol works. The transport drivers handle the actual transmission and reception of messages, and they also provide a user interface for sending and formatting the messages.


GEOS 3.0 supports Class 1 and 2 fax using either 1-D or 2-D compression. The fax transport driver is integrated with the mailbox library, which means that GEOS 3.0 can defer fax transmissions and automatically receive incoming faxes.

Other improvements include simultaneous support for multiple languages and improved memory management.

Communications: The Driving Force


Most people agree that the key ingredient in moving PDAs into the corporate big leagues is two-way wireless communication. As mentioned before, the relatively high cost of wireless service is still an issue. However, the removal of other barriers could render this moot. Those barriers include a confusing lack of wireless standards, an incomplete wireless infrastructure, and no critical mass of wireless devices (see "Radio Days" on page 107).

Wireless data transmission methods range from analog and digital cellular to several flavors of packet radio, with satellite microwave on the horizon. No PDA vendor is betting the farm on any one of them. Motorola comes closest with its hefty investment in the Ardis packet radio



Find the manual, find the other manual, read them both to get the information to fix your printer.

Or click on the CompuServe icon.



They'll connect you to experts from nearly every hardware and software vendor and to helpful and informed CompuServe members. So you can go online, ask questions, and get answers from a world of technical knowledge and expertise — and the people who are ready to share it.

But helping to keep your computer running isn't the only thing CompuServe makes easier. We have more than 2,000 other places to go and things to do. Access to and from the Internet is easy on CompuServe, too, and we were the first online information service to add an interactive multimedia enhancement: CompuServeCD.

CompuServe. It's all here waiting for you.



Just a click away.

Free Membership Kit°

Join CompuServe now. Just call I 800 487-4838 and you'll receive:

- A free membership kit. CompuServe Information Manager software for DOS, Macintosh, Windows, or OS/2.
- 2) One free month of over I20 popular services, a \$9.95 value.
- 3) A \$25.00 usage credit to explore other extended services.

CompuServe

The information service you won't outgrow.

Circle 214 on Inquiry Card.

Special Report Mobile Computing

Where to Find

Apple Computer, Inc. Cupertino, CA (800) 538-9696 (408) 996-1010

Ardis Co. Lincolnshire, IL (800) 652-7347 (317) 843-9375

Casio, Inc. Dover, NJ (201) 361-5400 fax: (201) 361-3819

Fujitsu Personal Systems, Inc. Santa Clara, CA (800) 831-3183 (408) 982-9500 fax: (408) 496-0609 General Magic Sunnyvale, CA (408) 774-4000 fax: (408) 774-4010

GeoWorks Alameda, CA (510) 814-1660 fax; (510) 814-4250

Hewlett-Packard Co. Corvallis, OR (800) 443-1254

IntelliLink Nashua, NH (603) 888-0666

Motorola Wireless Data Group Schaumburg, IL (800) 894-7353 Palm Computing, Inc. Los Altos, CA

(415) 949-9560 fax: (415) 949-0147 **Psion, Inc.**

Concord, MA (508) 371-0310 fax: (508) 371-9611

RadioMail Corp. San Mateo, CA (800) 597-6245 (415) 286-7800

Sharp Electronics Corp. Mahwah, NJ (800) 237-4277 (201) 529-8200

fax: (415) 286-7801

Sony Electronics, Inc. Park Ridge, NJ (800) 556-2442

network, but the Marco and the Envoy can accommodate virtually any wireless transport. The universal strategy is to support every form of wireless (usually with third-party options) while keeping the hardware and system software flexible.

No wireless system as yet offers full coverage of the U.S., and the dream of a unified, global wireless infrastructure is years (perhaps decades) away. This forces some users to choose a wireless service based on availability rather than features or price.

PDAs that support two-way wireless communications will become more viable as more of them enter the field. It's similar to the burgeoning popularity of cellular phones; as more people use them and become more reachable away from their regular phones, there's more reason for other people to go cellular. The same thing will happen when more people become reachable via E-mail on their wireless PDAs.

The next communications feature likely to be built into PDAs, according to several sources, is two-way paging. Dulaney estimates the cost of goods to the manufacturer at about \$25, which translates into an additional \$75 in the retail price of a PDA. He believes that the added functionality would more than make up for the additional cost: "[Paging] is more valuable than [bundling Lotus] 1-2-3."

When will all these pieces come together so that PDAs can enter the business mainstream? Vendors are optimistically predicting this will happen in 1996 or 1997. But Dulaney expects them to flounder for at least the next three years. During that time, he expects OSes and hardware to mature to the point where PDAs can finally meet the expectations of most users.

Michael Nadeau is the author of the BYTE Guide to CD-ROM, Second Edition (Osborne/McGraw-Hill, 1995). You can reach him on the Internet or BIX at miken@bix.com.

PORTABLE STORAGE, FAST AND SIMPLE



PLUGGER®

Plugger is an external hard drive that connects directly to the parallel printer part. Ideal for data storage, additional copacity, backups, file transfer or software installation. Plug the shackproof hard drive to the printer port and your PC has an additional volume (D:\eta.). Share it among all your PCs! It's so partable, you'll never be without your data.

Interface : parallel port Capacity : 120 MB to 810 MB

Access : 12 ms

SHUTTLE®

Shuttle portable systems connect directly to either a SCSI port or printer port, thus avoiding costly controller cards and installation hassles. No need to open your PCs. Technologies include; Tape, DAT, Optical, CD-ROM and SyQuest. Software for: DOS, OS/2, Windows, Novell, Unix and Apple. Shuttle is the fastest parallel + SCSI storage solution you can buy!


Interface : parallel port + SCSI Capacity : 100 MB to 10 GB

Speed: up to 95 MB/min. (SCSI), 25 MB/min. (parallel port)

Call today for product information, reviews or the nearest dealer.

Computer Connections USA 2 1-800 438 5336, 617 271 0444 - Computer Connections Germany 2 02102 93010 - Computer Connections France 2 1 39 880688

Computer Connections Holland 2 070 3209409 - Computer Connections Swiss 2 31 3027760 - Memory Technology UK 2 734 771 588



Up and away on the Information Highway!

ONLINE NAVIGATION



TRAFFIC INFORMATION



EMERGENCY SERVICE



ONLINE SERVICE



Mobile Assistant I™

- a multifunctional device for mobile communications, traffic and information management. It brings together all the latest technology such as radio modems, satellite navigation and computer power to give you the best service you can expect.

Mobile Assistant ITM is intended for professionals in areas such as: Freight Carriers • Field Service Organizations • Field Sales Organizations • Rental Car Agencies • Police- and Fire-Departments • Emergency Road Service • Hazardous Materials and Security Transports • Public Transportation Systems.

- Wireless Communication Computer
- O GPS, Computer, Modem
- O Just 6-Keys
- Car Radio Size
- O Supported Networks: MODACOM/ARDIS-MDBITEX/RAM - GSM/CDPD

FLEET-MANAGEMENT




ELECTRONIC TOLL COLLECTION





Germany Headquarter: Bruckmannring 32 • D-85764 Oberschleißheim • Tel: + 49-89-31 57 19-0 • Fax: + 49-89-3 15 91 46 • USA: Tel: 1-800•784•RAID



Maybe you can't please all the people all the time, but programmers and managers alike say they're happy they use QNX for real time.

POSIX Plus Performance

QNX is a certified POSIX OS, so any UNIX® OS programmer can become productive in no time. You get the standards you'd expect from any open-systems OS (e.g. ANSI, TCP/IP, the X Window System), but with the performance you'd see only with dedicated realtime executives (e.g. 5 µsec per context switch on an 80486).

One OS Fits All

QNX's modular, microkernel architecture lets you easily scale the OS to fit your platform – cash registers, PDAs, robotic

controllers, instrumentation, whatever. Programmers won't waste time learning a new OS for every project. And managers won't have to make another OS buying decision. Speaking of buying, QNX can cut the cost of your runtime systems, because you pay for only the OS modules you use.

Time-Saving Tools

From the optimizing Watcom C/C++ compiler to our codegenerating GUI builder, QNX's rich development environment can help you deliver better software sooner.

The Bottom Line

Realtime programmers like working with QNX. Managers like succeeding with QNX-based products. And end users like using them. Looks like QNX pleases all the people

To find out more about the leading realtime OS for PCs, call

in real time.

800-676-0566. EXT. #1006



The Leading Realtime OS for PCs

- Leading in Experience (Realtime OS for PCs since 1981)
- Leading in Innovation (Microkemel distributed OS for PCs since 1984)
- Leading In Market Share (QNX outselfs every other realtime DS for PQs).

QNX Software Systems Ltd., 175 Terence Matthews Crescent, Kanata, Ontario, Canada K2M IW8 Tel. 613-591-0931 Fax: 613-591-3579 Internet: info quax.com
European Division: 17 Bishops Court, Church Road, Bishopstoke, Hampshire, SO5O 6PE, England Tel:(+44) 0703 611800 Fax: (+44) 0703 641153

© QNX Software Systems Ltd. 1994. QNX is a registered trademark of QNX Software Systems Ltd. All other trademarks belong to their respective owners.

Tales from the Trip

RAPHAEL NEEDLEMAN



Boston, Massachusetts. I'm setting up my new Boston apartment, and the Nynex guy who was here to install a sec-

ond phone line has just left. I need to get my E-mail. So I run a phone cable from my modem to the wall outlet, add the right phone numbers to my communications program, click on the send/receive button, and walk away. Easy.

At BYTE's far-flung bureaus and at most hotels, it's the same story. Those little RJ-11 phone jacks are a conduit for my communications back to the BYTE home base in Peterborough, New Hampshire. Thanks to E-mail, my portable computer, and a PCMCIA modem, I'm never out of touch for very long. My traveling road kit consists of a Dell Latitude XP with a Megahertz X-Jack modem, a sixfoot phone cable, a phone-line splitter, a small Swiss army knife, and a Mini Mag flashlight, all packed into a single briefcase. It's a little too heavy for my shoulder, but it contains everything I need to connect from almost anywhere—and I even have some room left in my case for papers and magazines.

However, I've had a few experiences when the basic road kit wasn't enough. So I've been gradually adding gizmos to the bag over time, as well as keeping a log of tips and tricks I've learned on my trip down the data highway.




United Airlines flight 33, Boston to San Francisco. I

notice that the seat-back phones have RJ-11 jacks. I plug in and

try to connect. No joy. After a dozen different combinations of computer-dialed and manually dialed credit-card and access-code combinations, I call for help. I ask the AirPhone operator, "Do these phones work with modems?" The response: "They will very soon, sir." Unfortunately, not before I land.

Fortunately, the gentleman sitting next to me is in the printing business. We have



a delightful discussion about the future of magazine publishing.

Lesson learned: The presence of an RJ-11 jack does not guarantee a usable phone line.

Later that day. Washington Square Inn, San Francisco. A typical hotel experience. The phone in the room doesn't have a modem port and the phone cable is stuck—the little tab on the modular plug has been snapped off. I have two options: Use the Swiss army knife to pry the cord out of the phone, or crawl under the bed and try to connect my computer to the phone jack on the wall. I opt for the latter. I plug the splitter into the wall, then plug both the phone and the modem into it. In ten minutes, I'm sending E-mail. No problem.

Lesson learned: Modern hotel design dictates that the phone jack shall be placed It's a poor worker who blames his tools. On the other hand....

in the darkest, most inaccessible place in the room. Bring a small flashlight.



San Francisco International Airport, United Airlines Red Carpet Club. The yearly fees to this little oasis are worth it. The

lounge has an entire wall with little cubicles, each equipped with its own phone, modem jack, and AC power outlet (hidden above the desk, under the fluorescent light). All I have to do is program my

Special Report Mobile Computing

dialing string with my phone card number, and I'm in business.

Lesson learned: Airline clubs are worth the money because they have phones with data jacks. Sign up for one.



IBM's conference center in Raleigh, North Carolina. During a break in a seminar on ATM, I go to the phone bank.

There are several Rolm phones with standard RJ-11 cables plugged into the wall. I disconnect one and plug in my old but trusty Megahertz X-Jack modem. But when I try to dial, I get nothing, not even a dial tone. Hmm. Maybe it's a nonstandard phone line. No big deal, I can wait for my E-mail.

Later that night, at my hotel, I can't get on line. "No dial tone," says the modem. I try everything, but it's no use. My Megahertz has gone to the great bit-bucket in the sky. Apparently, plugging the analog modem into the digital Rolm system earlier that day was not a good idea—the higher voltage of the digital system blew out the Megahertz dialing relay.

Fortunately, an associate lends me a PCMCIA modem (a Gateway Telepath). It works just fine; I don't even have to tell

my communications programs about the change. When I get back to the office, the nice folks at Megahertz send me a replacement X-Jack modem, this one with

the new "digital line guard" feature to protect it from high-voltage melt down.

Lesson learned: Don't plug your analog modem into a PBX system.



Northwest Airlines flight 727, Boston to Minneapolis. This plane has seat-back phones that look newer than the ones I tried

on United, and they have an encouraging label stuck on them: "This phone modem-compatible." It takes me about 15 minutes to come up with the right combination of access and dialing codes, but it works. I'm doing E-mail from a plane! True, I have wires and credit cards strewn all over the tray table, and I'm spending \$2.50 a minute to exchange messages with people who could very well wait another 3 hours to hear from me. But next time I have to dash off a message from the air, I'll know how.

Lesson learned: E-mail from an airplane is expensive and complicated, but on the right airline, it actually works.



Hyatt Regency, Irvine, California. The phone in my room has a modem jack (a plus), but there's an ominous placard on

the desk: "Modem and computer users: For best results, set modem speed to 1200 baud." Sure enough, I can't connect at faster speeds—the hotel's digital phone system apparently compresses the signals and ruins high-speed modem tones. What's worse, the Hyatt's phone charges are outrageous, which means that for every minute I waste running at 1200 bps instead of 9600, I'm spending a fortune.

Lesson learned: Avoid the Hyatt Regency in Irvine.



San Francisco International Airport, Gate 89. This is the farthest you can get from the Red Carpet Club and still actually

be in the airport. Naturally, most of my San Francisco flights leave from here. My flight is delayed for maintenance reasons, but we're advised not to stray from the gate; the plane could board at any minute. Nearby is a futuristic AT&T 2000 pay phone with a keyboard and an inviting little blue RJ-11 jack. I have to try it.

I perch my Dell Latitude on top of the phone and get to work. Half an hour later, after perfecting some carefully orchestrated acrobatics that involve lifting and replacing the handset and pressing the right buttons at the right times, I finally make a connection. Meanwhile, the airplane mechanics are still waiting for a part.

Lesson learned: AT&T 2000 public phones have convenient modem jacks, but using them is decidedly inconvenient.



Philadelphia airport, US-Air terminal, b e t w e e n

flights. This place is a dump. The run-down terminal has peeling paint, no coffee shop, no airline club, and

none of the magic AT&T 2000 phones. But I've been on airplanes all day, and I have another long flight in front of me. I need my E-mail. Fortunately, on this trip I'm carrying an Apex Mobile Plus Cellular-compatible modem instead of my Megahertz. I connect it to my Oki 1150 cellular phone and dial up the home office in a snap. This modem interfaces perfectly with the phone and can double as a land-line modem when I'm near a phone jack.

Lesson learned: Cellular modems are a great backup to regular land-line connections.

Later that day. USAir flight 2451 from Philly to Burlington, Vermont, This plane has a very intriguing setup: a smallish LCD panel mounted on the seatback and a groovy little phone handset in the seat. In addition to the usual phone keypad, the handset even has an alphanumeric keypad and an RJ-11 jack. But the LCDs are discouragingly blank and the system isn't turned on. When I pull the handset out of its holder, a bright orange wire pulls free of the phone. When I land, I kiss the ground.

Lesson learned: Carry a soldering iron on USAir.




Jack Daniels Motor Lodge, Peterborough, New Hampshire. I often stay here when I'm working at BYTE's headquar-

ters. But since my last visit, the JD has replaced its phone system with some awful new digital setup. My Megahertz won't function.

Just for kicks, I run back to the office and grab a product I've had for a while: the Konexx Model 111 handset adapter. It installs between the phone's handset and the phone base, and also plugs into my

modem. But I still can't get the computer to dial for me; I have to dial the phone manually. It seems that cc:Mail supports manual dialing quite nicely (it sets up everything for you and even flashes a message on the screen reminding you what number to dial), but my other programs don't. I have to enter a new dialing string (ATX1DT)

that tells the modem to just pick up the phone and wait for a connection. Then I have to dial all the access numbers myself. Too much work!







Performance

Just about everyone is singing the praises of the new Tadpole P1000. That's because the P1000 is the first notebook designed from the ground up to fully optimize Pentium™ performance. With 100MHz of pure Pentium power, it out-performs every other notebook on the market. And with built-in features such as a PCI bus to take Pentium power to the limit and 256KB Level 2 write-back cache, the P1000 could even upstage your desktop.

For the performance of a lifetime, the P1000 was designed to change with your needs. Removable SCSI-2 hard-disk drives are available with capacities up to 810MB, memory is upgradable up to 128MB of RAM using industry-standard SIMMS, and the Pentium processor can be factory-upgraded to tomorrow's even faster processors.

If you're on the road to stardom, the P1000 is the perfect vehicle for graphics intensive applications, software demonstrations, and multimedia presentations. Its 10.4" active-matrix TFT true color screen.

1MB of video RAM, and 16-bit SoundBlaster CD-quality sound will "wow" small crowds. For larger audiences, the P1000 supports resolutions up to 1024 X 768 on external displays and projectors to inspire standing ovations for your brilliant performances.

And unlike other notebooks bound in plastic shells, the P1000 has real staying power. It's the only one cast in a magnesium alloy case — making it highly durable, yet elegant and lightweight.

If you would like the P1000 to make a curtain call 1-800-232-6656 today for more information!





United States: 512 219 2200 Fax: 512 219 2222 United Kingdom: 01223 428200

Fax: 01223 428201 France: 1 60 86 27 92 Fax: 1 60 86 27 89

Intel Inside and Pentium Processor Logos are trademarks of the Intel Corporation. All other trademarks used herein are the property of their respective corporations. ©1995 Tedpole Technology.

Don't Be the Only One Using FORTRAN 7.7

You look around and discover everyone is making the move to LAHEY FORTRAN 90. Except you. You're using Fortran because it is proven, portable, and the best language for numerically intensive programs. But why 77? With Lahey Fortran 90, you can run your FORTRAN 77 programs FASTER and take advantage of the new language features in 90.

Array expressions, more intrinsic functions, structures, pointers, better array handling, and modules are just a few of the reasons to move to Lahey Fortran 90. Use these and other features to build new, faster executing 32-BIT applications with fewer lines of code. But even if you are not writing new code, the design and speed of Lahey Fortran 90 are reasons enough to switch.

Lahey's innovative compiler design combined with Intel Corporation's highly OPTIMIZED code generation technology produces a language system optimized from the chip up. Lahey Fortran 90 is the fastest PC Fortran on the Pentium-over 18 Mflops on a 90 MHz (SP Linpack). And, you get all the TOOLS found in our award-winning (ahem) FORTRAN 77 language systems: editor, debugger, profiler, librarian, make, linker, video graphics. and Phar Lap's royalty-free DOS-Extendereverything you need to write or port 4GB programs. Add to this our decade of writing PC Fortrans and free technical support. So, don't be the last one using FORTRAN 77. make the move to Lahey Fortran 90.



\$895 Call 800 548-4778 for more information on our Fortran language systems



702 831-2500 Fax: 702 831-8123

Special Report Mobile Computing

Lesson learned: With the help of flexible comm software, a handset adapter can thwart an innkeeper's nefarious plans to lock you out of his phone system.



Mulligen, Germany. Several BYTE staffers are staying in a small guest house for the duration of the CeBIT computer

show this week in Hannover. There's only a single phone for 17 of us. A bad start to the week.

After examining the guest house's phone wiring, we find that the cable has a completely unfamiliar connection at the wall end, but a somewhat ordinary-looking phone connector at the other (the

plug is the same size as an RJ-11, but has six contacts instead of four). I volunteer to try it first.

I plug the phone cable into my modem. The modem's speaker emits a dial tone, but I can't dial out: the switchboard at the guest house doesn't seem to recognize American touch-tone signals. I try old-fashioned pulse dialing. That doesn't work, either.

Luckily, I've planned ahead: There's a Konexx Model 204 acoustic coupler in my travel kit. Remember the old 110-bps acoustic modems from the 1970s? The Konexx works on the same principle, but it uses Velcro straps instead of suction cups to attach its speaker and microphone to the phone handset. The maximum data rate varies, depending on the phone. I got 14,400 bps when I tried it back home on my office phone (an AT&T Merlin), but I'm getting only 2400 bps on the German

guest house phones. Still, it works. Soon I retrieve my E-mail, and a line forms behind me for the use of the phone and the coupler.

Lesson learned: Acoustic couplers aren't obsolete. In a pinch, they'll let you get on line from almost anywhere. Worth carrying.



Hannover, Germany. At the CeBIT show, the BYTE booth has three phone lines: one for voice, one for fax, and one for

data. The phones don't have RJ-11 jacks, and the wall has the same odd-looking connectors we encountered at the guest house. Fortunately, a resourceful

> but guiltless associate has swiped the required cable from a meeting room at a local hotel. (Memo to Hotel Latzen:

Please send me the bill; I'll pay up.)

One end of the cable goes into the wall, the other into the modem. Suddenly I'm dialing out with no trouble at all-this phone line even recognizes American touch-tones. The only difference is that the German dial

tone is different, so I have to set my modem to "blind dial" (the Hayes command is ATX1).

Lesson learned: It can be advantageous to travel with quick-fingered associates of low moral character.



Back at my office in Peterborough, New Hampshire. According to my schedule, I'll be in town for two solid weeks. It

> will be a welcome change of pace. While the traveling is both educational and exciting, my batteries are drained. And that's not just the ones in my laptop.

Final lesson learned: Plug and play is a joke, but if you have the wherewithal, you can get your E-mail from almost anywhere.

Raphael Needleman is BYTE's Editor in Chief. You can reach him on BIX or the Internet at rafe@well.com.

Apex Data (cellularcompatible modems) Pleasanton, CA (800) 841-2739 (510) 416-5656 fax: (510) 416-0909

Dell (portable computers) Austin, TX (800) 289-3355 (512) 338-4400 fax: (512) 728-3653 E-mail: info@dell.com

Megahertz (modems) Salt Lake City, UT (800) 527-8677 (801) 320-7000 fax: (801) 320-6020

Oki Telecom (cellular phones) Suwanee, GA (800) 554-3112 (404) 995-9800 fax: (404) 822-2704

Unlimited Systems Corp. (Konexx couplers) San Diego, CA (619) 622-1400 fax: (619) 550-7330 E-mail: konexx@aol.com




Demand NexGen's Nx586. Processor. Superior Performance. Unbeatable Price.

Now, you don't have to settle for a Pentium™ processor-based PC. Because there's a tough new kid on the block that delivers superior power and performance... for a lot less money.

It's the NexGen Nx586 processor. Manufactured by IBM Microelectronics.™ With patented RISC86™ microarchitecture that outperforms the Pentium processor, megahertz for megahertz. It's fully compatible with your DOS and Windows™ applications. And it's absolutely available right now.

So just call one of the PC suppliers listed below and ask for it by name. The Nx586 processor by NexGen. Don't buy a PC without it.



Absolutely Available Right Now. Don't Buy a PC Without It!

Nx586 processor-based PCs are available from the following PC suppliers. Call the PC supplier of your choice and ask for NexGen's Nx586 processor by name.

La Iolla, CA 619-452-5540

Aberdeen Montebella, CA 800-552-6868 **ACP Superstor**

Santa Ana. CA 714-558-8813 Add Tech Computer Inc. Somerset, NJ 908-805-0900

Adlays Corporatio Santa Clura CA 800-423-4797

602-321-46-10 Alaris

AlS Computers Turson AZ Fremont, CA 800-317-2348

Lodi. NJ 201-778-0707

Alpine Com Center, Inc. 815-229-0200

American Dist Corp. Sunmyale CA

408-245-1580 Aquarius ASI 510-656-3465

ASA Competers, Inc. Santa Glara, CA Balillo's Inc.

Albuquerque, NM 505-883-7511 **BCM Byslams** Chula Vista, CA

610_420_105

San lose, CA

800-531-74-17 City Computer Rockville, MD

Compu-Telt Richardson, TX 800-994-0221

608-831-1165

Temecula, CA 909-699-3577

stor Die Mart Greenwood, IN 317-889-7220

Computer Parts Plan San Marcos, CA 619-741-1700

Computer Reso 800-662-0034

619-268-8856

Beaverton, OR 503-626-3511

714-777-9095

Data Storage Marketing Inc. 800-543-6098

Direct Wave Inc Ontario, CA 909-460-2999

Deracom Com Irving, TX 800-551-9000

Fry's Electron 408-741-1770

714-378-4400 FYI Computer S 513-753-1831

Bataway USA, Inc. 303-438-5500 Globe Comp

800-467-0011

Systems Corp. Richardson, TX 800-852-0614

Laitres Inc. San Jose, CA 408-321-9488

Liuski interne 516-454-8220

Lucky Comput 800-805-5825

Mandi Cerpore 916-858-1377

Maximus Monrovia, CA 800-394-6299

Norrepes GA 404-449-8630 Micro Equip Norcross, GA 404-447-1726

Micro Shender Mers A7

Salt Lake City, LIT

Products.

Sunnyvale, CA 800-961-1200 Net Computer International

214-386-9310 **Hexal Systems** 609-371-0003

Michrix Corporation 201-947-2220

Omni-Tua Houston, TX 713-784-9191

Orientec Corp of El Monte, CA 818-442-1818 PC Concents

214-328-2888 PC Express, Inc. Richfield, MN 800-937-1100

Centers

Eaglewood, 00 303-771-8030 PC Systems West Palm Beach FL

407-640-0811 PC Workers 206-641-4141

Plates Pocket 206-575-0939

RAM, Inc. Denver, CO 303-433-7094 Regals, Inc.

813-623-3402 S.LL Radio Strack Truth or Consequences VM 505-894-3442

Sourceror Syst 619-779-1818 Systems Desi Committees

San Diego, CA 619-537-5737

Burlingame, CA 800-800-5550

908-247-6000

TAP

The Missing Byte 713-782-5557

Ther Computers, Ltd. Albuquerque, NM 505-881-0077

Top Date Sunnyvale, CA 800-888-3318

US Micro Express, Inc. Believue, WA 800-874-5505

US Microtock Milpitas, CA 408-433-5522 Quebec, Canada 1-800-VEC-3433

Chatsworth, CA













© 1995 NexGen, Inc., Rx656 is a registered trademark and R15C86 and NexGen are trademarked Hexilen, Inc. Pentium is a trademark of Intal Corporation. Intel is a registered trademark of this international Business Machines Corporation. All products mentioned herein are trademarks of their respective companies. If you'd like to find out about respirit

Now Everyone Can Have The Superior Monitor.



Photo Credit: Peter John Griffiths/Time-Life Books



If you've always wanted a top performing monitor, now is the time.

Run, don't walk to your nearest dealer to get a premium 17" Nanao monitor at the best price you've ever seen. Which is

why hard working graphics pros around the world are picking up our new T2·17TS and F2·17EX monitors in record numbers. Sure, the price is terrific. But these users are drawn by Nanao's reputation for quality plus a stunning new array of advanced technical features that are ideally suited for the graphics environment. Nanao even offers a choice of 17" models to satisfy your individual preference. Our FlexScan T2·17Ts has an

advanced Aperture Grill tube, while the F2.17EX features a flat-screen Invar Shadow Mask tube. Both monitors provide the power you really need to achieve true-to-life colors, crisp typography and a stable screen image. Ultra high 1280 x 1024 resolution at 82Hz refresh rate, Colorific™ color management software and on-screen image controls deliver a new level of graphics performance. For added safety against radiation emissions, TCO compliance is now available as a standard feature.

If you've been looking for a superior 17" monitor at an equally great price, your search is over. The T2·17TS and F2·17EX are available and affordable - from Nanao.

F2-17ex Dot Pitch

Scan Freq. Rec. Resol.

Max Resol. ScreenManager" and ScreenManager" Pro On Screen Control

Standards T2-17TS

Aperture Grill

0.25mm

MPR-II TCO

Scan Freq. Rec. Resol. Max Resol.

1600 s. 1200 @ up to 66Hz On Screen Control

Standards

ScreenManager" and ScreenManager" Pro

H:30-86kHz, V:55-160Hz

1280 x 1024 @ up to 82Hz

H:30-86kHz, V:55-1601 tz

1280 x 1024 @ up to 82Hz

1600 x 1200 @ up to 66Hz

MPR-II, TCO

3-year warranty**



CALL OUR FLEXFAX FAX BACK NUMBER 1-800-416-FLEX

*Savings based on MSRP and offer expres on 9/30/95, **1 year on P & L, and CRT. Superior In Every Detail is a regatered trademark of Nanso Corporation. All product names are trademarks of their respective companies. ©1995 Nanso USA Corporation.



Superior In Every Detail NANAO USA CORPORATION 23535 Telo Avenue, Torrance, CA 90505 (310) 325-5202 Fax: (310) 530-1679

1-800-800-5202

Red-Hot 100-MHz Portable Pentium

Screaming performance, finicky components

REX BALDAZO

t about the same time that 100-MHz Pentiums are reaching store shelves, Tadpole Technology is introducing a 100-MHz Pentium laptop. Tadpole's P1000 pushes the performance envelope with a factory-upgradable, no-compromise design. When you stretch the leading edge as far as the P1000 does, there are bound to be a few problems. But the result is still pretty sweet.

It's Really Hot

Fellow propeller heads will appreciate the rush we felt when we first powered up the P1000 and it reported 64 MB of RAM. It can hold as much as 128 MB, although the base model ships with a more pedestrian 8 MB. Even if you don't need huge amounts of memory, there's something alluring about a laptop that can handle more RAM than many desktop systems.

For additional expansion, the P1000's PCMCIA slot accepts two Type II or one Type III card. However, it lacks an internal 3½-inch floppy drive; instead, the drive is an external unit, as is the AC power supply.

Our lab tests revealed that the P1000 has prodigious computing power but abysmal battery life. When running the BYTE benchmarks, the P1000 was 110 percent to 120 percent faster than our baseline 90-MHz Pentium desktop system. In our Thumper II word processing test, battery life was a meager I hour II minutes.

Unlike most laptops, the P1000 has a case that's solidly constructed of magnesium alloy instead of plastic, and it functions as a large heat sink for the cooling system. Small air vents run the length of the case above the keyboard, and flip-down legs at the rear allow air circulation under

the unit and also improve the keyboard angle. There are no fans or other active cooling mechanisms. It works well; we ran the P1000 continuously for two days without problems.

However, we recommend that you don't rest the unit directly on your lap. We measured parts of the case at temperatures above 118°F in a room whose ambient temperature was 72°F.

Inside, the P1000's motherboard has a PCI (Peripheral Component Interconnect) bus and a

separate daughterboard for the CPU and main memory. Tadpole calls this arrangement the Advanced Notebook Architecture, which lets you upgrade the system by swapping daughterboards. You could switch to a faster x86 processor or even a different CPU architecture, such as a RISC chip. (Tadpole also makes SPARC-based laptops.)

Another sign that Tadpole has designed the P1000 for flexibility is that the pointing device has three buttons instead of two. Windows may need only two buttons, but some flavors of Unix can use all three.

Finicky Floppy

The external components are less flexible. The power supply is fairly small, but the cord that attaches to the computer is too short to reach the floor. It plugs in right next to the external floppy drive, which is also on a short leash.

To save desk space, it is naturally tempt-



ing to place the floppy drive atop the power brick—bad move. Electromagnetic fields from the power brick made the floppy drive unreliable for reads and writes. Disk reads were agonizingly slow, and formatting a blank floppy disk was impossible. The interference doesn't appear to cause any permanent damage, however. Separating the power supply and the floppy drive as much as their cords allow returned the floppy drive to normal operation.

Power Users Only

The P1000 is a muscle car among luxury laptops—no refinement, just tons of power. Everything about it says "industrial strength."

So what niche does the P1000 fit? Not a big one, that's for sure. Its short battery life makes it a poor choice for on-the-go work, although an external battery pack is available to extend its unplugged life. It has power to handle the most demanding

multimedia applications, but the lack of a built-in CD-ROM drive makes it less than ideal for that purpose.

Instead, the P1000 is aimed at power users. If you need raw Pentium performance that you can tuck under your arm, and price is no object, then the P1000 should be on your short list.

Rex Baldazo is a BYTE technical editor. You can reach him on the Internet or BIX at rbaldazo@bix.com.

Performance

.....

Integer index: 1.10
Floating-point index: 1.20

Battery life: word processing 1.18 hours

(1 = 90-MHz Dell Pontium)

Traded Information

Tadpole P1000 (8 MB of RAM)

340-MB hard drive\$7495 As tested (64 MB of RAM) 810-MB hard drive.....\$11,995 Tadpole Technology, Inc. Austin, TX (512) 219-2200 fax: (512) 219-2222

Circle 977 on Inquiry Card.

Best Feature

The Tadpole P1000 is blazingly fast: It ran the BYTE benchmarks 110 percent to 120 percent faster than our baseline 90-MHz Pentium desktop system. And with room for up to 128 MB of RAM, it can handle more memory than many desktop machines.

HANDLES AND STRAPS ARE PERFORMANCE TESTED FOR COMFORT AND RELIABILITY.







RIGOROUS CORNER DROP TESTING TO HELP PROTECT WHAT'S INSIDE.



SOLID CAST METAL. NOT PLASTIC. MEANS GREATER DURABILITY.






Тикск нідн DENSITY FOAM. WE DON'T SKIMP ON PROTECTIVE PADDING.

Nobody treats a portable computer rougher than Samsonite, because nobody builds a case that offers more protection than our new Guardian Series. But stringent testing is only part of the Samsonite quality story. Precision design, the finest materials and classic Samsonite craftsmanship provide increased protection for your laptop with these functional and durable cases. With over a dozen models available in full-grain leather, nylon or PVC, the Guardian Samsonite Series passes even the toughest test in the







SELF-ALIGNING ZIPPERS FOR SMOOTH AND RELIABLE OPERATION.

LAPTOP SYSTEM CASES

urban jungle. 1-800-955-4001.

LAPTOP COMPUTER CASES

PERFECT FOR THE MINIMALIST WHO LIKES

RIGHT FOR YOUR

TO TRAVEL LIGHT AND

LEAN, THESE BASIC CASES

ARE COMPACT AND JUST

DESIGNED ESPECIALLY WITH THE SERIOUS PORTABLE COMPUTING USER IN MIND, THESE CASES ACCOMMODATE YOUR LAPTOP, PRINTER AND A FULL RANGE OF ACCESSORIES.

LAPTOP OFFICE CASES

FORGET THE BRIFFCASE ----THESE ARE THE CASES YOU'LL USE EVERYDAY AS A PORTABLE OFFICE THAT TAKES YOUR BUSINESS ON THE ROAD-LAPTOP. ACCESSORIES, WORK MATERIALS AND ALL.

LAPTOP TRAVELLER CASES

WHO SAYS YOU CAN'T TAKE IT WITH YOU? OVERNIGHT STAYS ARE EASY WITH THESE ROOMY CASES THAT CARRY YOUR LAPTOP, PRINTER. PERSONAL ITEMS AND A CHANGE OF CLOTHES.



Survivor' Deluxe





EXTRA STUROY STITCHING FOR HANDLES AND STRAPS THAT ARE MADE TO LAST.



FULL-GRAIN LEATHER BODY MEANS NO VINYL ON SIDES OR PANELS.

RISC for the Road

The SparcBook 3XP is a powerful workstation in a small package

DOUG TAMASANIS

f you're looking for a lot of computer in a small box, look no further than Tadpole's SparcBook 3XP. This fullfeatured mobile workstation boasts an 85-MHz microSPARC II processor, dazzling graphics, built-in stereo sound, a generous array of I/O ports, a removable hard drive, and the popular Solaris operating system.

Cramming all these features into a portable computer doesn't come without a price, however. There's no internal floppy drive, the screen is too small for a multitasking system, battery life is short, and it costs more than most mid-size sport sedans. Despite these drawbacks, the 3XP is a powerful workstation squeezed into a very small package.

Under the Hood

The 7-pound 3XP includes a 340 MB, 520 MB, or 810 MB removable hard drive; up to 128 MB RAM; an internal 14.4-Kbps fax modem; slots for two type I or II or one type III PCMCIA cards; and a threebutton pointing stick-all in a magnesium alloy case.

Thanks to a Weitek Power 9100 graphics accelerator and 2 MB of video memory, the 3XP can display 256 colors in two different modes. In native mode, the 3XP supports accelerated graphics at a resolution of 640 by 480 pixels. In virtual mode, graphics are not accelerated, but the resolution is 1280 by 1024 pixels.

The quality of the Sharp active-matrix TFT (thin-film transistor) display is excellent, but a 9.4-inch screen simply isn't large enough for a Unix multitasking environment.

SparcBook 3XP......\$12,000 Tadpole Technology, Inc. Austin, TX (800) 232-6656 (512) 219-2200 fax: (512) 219-2222 Circle 1005 on Inquiry Card.

Best Feature

The 3XP is well equipped for L/O and includes a 26-pin Ethernet port; 50-pin Fast (10 MBps) SCSI-2; an ISDN port; line-level audio in/out; a stereo headphone jack; two 8-pin RS-232 serial ports; connectors for an external keyboard, mouse, and monitor; and a parallel printer port. Unfortunately, there are no software drivers for the ISDN port.

The Test Drive

Installing Solaris and starting up the system for the first time is easy, all you have to do is enter your IP address, time zone, root password and user account information. The entire process takes about half an hour, which is a notable feat by Unix standards. We were disappointed to find that the 3XP doesn't come with any man pages or a C compiler.

The keyboard is well laid out and is adequate for short-term use. The right and left Meta keys are not mapped by default, so you must assign them manually with the xmodmap command. We found the pointing stick well

designed, with the buttons located near the thumb's natural resting position. Pressing the right button is awkward, how-

An LED display just below the screen indi-

cates the battery's charging status, as well as the activity of network connections and the presence of PCMCIA cards. Under normal use, we averaged only 88 minutes of operating time with the internal battery.

In terms of performance, there is no noticeable difference between the 3XP and a comparable desktop workstation. With its 8-KB data cache and 16-KB

> SPECint92 rating of 64 and a SPECfp92 rating of 54.6. In spite of this, the 3XP runs surprisingly cool, never feeling more than warm to the touch even after 10 hours of continuous operation. The battery charger, however, grew quite hot

after a 90-minute recharge.

The system software includes a powerful set of system management tools known as the NCE (Nomadic Computing Environment).

By far the most useful feature of NCE is its save-and-resume capability. NCE saves the entire contents of main memory in a disk partition, then restores the system to its previous state when you power up again. The whole procedure required about 32 seconds on our 64-MB machine.


One caveat: You can't change the system configuration when the 3XP has been powered down in this manner. You must perform a regular system shutdown to make such changes. Also, we discovered that moving the 3XP during the save procedure can cause an unrecoverable loss of data. In fact, Tadpole advises against moving the 3XP at any time while it's operating; it must first be put into sleep mode. This is an unusual restriction for a portable computer.


instruction cache, the 85-MHz microSPARC II processor achieves a

The Tadpole 3XP RISC-based portable runs Solaris and

boasts numerous I/O ports, including SCSI-2 and Ethernet.







PC EXPO in New York. It's about power. Energy. Excitement. The kind you get when hundreds of the industry's leading manufacturers and thousands of Corporate America's most influential buyers come together at the most important event in the Industry. In the most important computer market in the world.

NDUSTR

HE

Z

ENT

EV

MPORTANT

HE MOST

NDUSTRY

HE

Z

Z

ш

W

V

K

0

2

S

0



They come to see and be seen. To buy and to sell. To listen and to learn. To be part of it all, all you have to do is be there. PC EXPO in New York. If it doesn't happen here, it just doesn't happen.

For more information, call 801-655-8024.

PC EXPO IN NEW YORK JUNE 20-22, 1995 Jacob K. Javits Convention Center 11th Avenue at 34th Street New York City



PC EXPO in New York is produced and managed by Bruno Blenheim, Inc. Fort Lee Executive Park One Executive Drive Fort Lee NJ 07024 800-829-3976 201-346-1400 Fax 201-346-1602

PC EXPO is a registered service mark of Bruno Blenheim, Inc.

Portable Multimedia

Toshiba's Satellite Pro T2150CDT offers almost everything

REX BALDAZO

sually you have to pay top dollar for premium performance and features. Multimedia laptops with a fast CPU, a good color screen, decent battery life, built-in speakers, and a CD-ROM drive usually cost a king's ransom. But sometimes a manufacturer comes up with a product that strikes a smart balance between power and price.

Toshiba has hit that target with the Satellite Pro T2150CDT. It's not as fast as the highest-end models, and it lacks some desirable features (e.g., video input/output) that are found on other multimedia portables. But it does offer most of the features you'd expect at a very competitive price.

Sights and Sounds

The 6.9-pound Satellite Pro is built on a solid foundation: a 75-MHz 486DX4 processor with 8 MB of RAM (expandable to 32 MB) and a 500-MB internal hard drive. There's also an internal double-speed CD-ROM drive that opens from the right side of the machine. The 3.5-inch floppy drive, however, is an external unit. When it's attached to the left side of the machine, the complete system is rather wide and not well suited to airline tray tables.

The CD-ROM tray can be opened even when the computer is turned off. We're not sure that's a good idea, because the tray might pop open while the machine is stowed for travel. Fortunately, the eject button is recessed to help protect against such accidents.

An internal PCMCIA bay accepts either one Type III or two Type II cards. If you can forgo the external floppy drive, the Satellite Pro becomes exceptionally portable because the AC power supply is built in-there's no heavy power brick to lug around. The only extra piece you need to carry is the power cord. And the whole package still weighs less than 7 pounds.

The 10.4-inch active-matrix screen can display more than 64,000 colors at 640- by 480-pixel resolution. We found the screen very readable, even outdoors on a bright New England winter day. Our only complaint is that it doesn't fold all the

way back, so you can't slide it under a monitor stand while working at your desk.

Stereo sound is built in, but stereo speakers are not-there's just one. For true stereo, you'll have to plug in a pair of external speakers or headphones (not included). A little knob controls the volume of both the headphones and the internal speaker, quite useful when you accidentally start Doom with the sound turned up.

In our Thumper 2 word processing test, we measured battery life at a respectable 5 hours and 12 minutes. For our CD-ROM test, we played Rebel Assault and exhausted the battery after 2 hours and 5 minutes. Unlike IBM's ThinkPad 755CD. the Satellite Pro doesn't have a joystick port, so we had to use the AccuPoint controller on the keyboard instead.

Performance on the BYTE benchmarks met expectations for a 75-MHz 486DX4



tested with the CDStone suite, was on target for a double-speed player.

Luxury Lite

formance.

IBM's ThinkPad 755CD costs around \$8000. Toshiba's Satellite Pro comes close to matching its features-and even outperforms the ThinkPad in terms of battery life and CD-ROM speed—for about \$3000 less. What's the catch?

Making the comparison to sports cars is inevitable: You might buy a Mitsubishi Eclipse because it's affordable and well built, but you can't help lusting after the unreachable Acura NSX. The ThinkPad is a high-end dream machine, a multimedia portable that's refined, well engineered, and loaded with options. If money

were no object, the choice would be

But the Satellite Pro T2150CDT offers almost as much for a lot less cash. Toshiba has done an intelligent job of integrating most of the features you'll need in a multimedia laptop without busting your budget.

Rex Baldazo is a BYTE technical editor. You can reach him on the Internet or BIX at rbuldazo@bix.com.

Performance

0.483349 Integer index: Floating-point index: 0.271478 **CDStone:**

Battery life:


(1 = 90-MHz Dell Pentium)

Word processing: 5.20 hours CD-ROM: 2.10 hours

Toshiba Satellite Pro T2150CDT (8 MB of RAM, 500-MB hard drive) \$4899-\$5199 (estimated) Toshiba America Irvine, CA 92718 (800) 334-3445 (714) 583-3000 Circle 1006 on the Inquiry Card.

For about \$3000 less, Toshiba's Satellite Pro comes close to matching the features of IBM's ThinkPad 755 CD, and its battery even outlasts the ThinkPad's.

can you improve



show up at the office?

The office is quiet. Desks are clean. You haven't seen an employee for weeks. And business has never been better. There's a perfectly good explanation for all this: RLN® (Remote LAN Node®). It provides your employees with transparent access to all the resources on your LAN, no matter where they're working. Even on glamorous road trips to places like Secaucus, New Jersey. Once connected, they can access the mainframe, use groupware applications, check E-mail and more, like any local user. And since you won't be keeping your eye on

every employee, every minute, we created superior management and security features. We also teamed up with

Citrix® Systems, Inc. and their award-winning software to develop our optional Application Server. It can boost remote access performance of LAN-based applications by as much as 300%. So call today about RLN. And start improving the work ethic in your office. And out of it.



For a copy of the "Understanding Remote Computing" White Paper and more information on RLN call 800-426-6283 x 322



Pentium Power Without Sticker Shock

The Eurocom 9600 is well equipped but has a short battery life

DAVE ANDREWS

uroPak International's Eurocom Model 9600 packages a 90-MHz Pentium with room for extralarge Type IV PCMCIA cards at a relatively affordable price. Multimedia luxuries (e.g., stereo speakers and a CD-ROM drive) are delegated to an optional docking station. The price of the basic notebook is \$4450 for a model with 8 MB of RAM and a 10.5-inch active-matrix color screen. You can lower that price by substituting a dual-scan color or monochrome screen.

The Eurocom 9600 offers numerous features that until recently were rare on notebooks. Standard equipment includes a removable 540-MB hard drive (an 810-MB drive is available for an extra \$350), an external video port for SVGA graphics (up to 1024 by 768-pixel resolution), an external keyboard port, a built-in microphone (which is located in front of the trackball), input jacks for an external microphone and line-level audio, an output jack for external speakers, a connector for the docking station, and a 16-bit FM sound synthesizer that's compatible with Creative Labs' Sound Blaster Pro 3.1 and the Windows Sound System.

All that's in addition to an ECP/EPP (Extended Capabilities Port/Enhanced Parallel Port), a pair of 16550 UART (universal asynchronous receiver/transmitter) serial ports for high-speed modems, and an extra-large cavity for PCMCIA peripherals. The PCMCIA bay accepts two Type 1/II cards or one Type II and one Type III card. It will even take a 15.5-mm Type IV PCMCIA card (e.g., a Global Position Satellite tracking device). Inside the computer, there's room for 40 MB of RAM.

The Eurocom 9600 forgoes the small LCD strip that many notebooks use to display the battery status and other system information. Nor does it have the separate brightness and contrast controls often found near the screen panel. Instead, it uses a Spartan combination of LED indicators and key combinations for these functions. And instead of a Windows applet, it has a ROMbased utility for tweaking the power management options. EuroPak says these features make it easier to install another OS (e.g., OS/2 or Windows NT) in lieu of Windows 3.1.

A 1-inch (25-mm) trackball positioned in front of the 86-key keyboard is the Eurocom 9600's mouse substitute. The trackball is easy to find and manipulate, but if you have big hands, the keyboard might feel a bit small. I'd definitely like to see a larger space bar.

Despite two NiMH (nickel-metal-hydride) battery packs, the Eurocom 9600 averaged only 1 hour and 28 minutes of battery life in BYTE's Thumper test. (We didn't run the CD-ROM test because there's no built-in CD-ROM drive.) EuroPak plans to introduce notebooks with longer-lasting lithium-ion batteries later this year, including a faster model based on a 100-MHz Pentium.

The Eurocom 9600 uses the 65540 VGA controller from Chips & Technolo-

Eurocom Model 9600 DUNN © 1995

gies, which includes 1 MB of on-board video memory. Unfortunately, EuroPak makes it hard for you to take advantage of the 65540's interesting video-overlay capabilities, because the Eurocom 9600 lacks a video-in port. A EuroPak official says the company hasn't seen a strong demand for integrated video-in-a-window functionality. You could buy a PCMCIA card that takes advantage of the 65540's

capabilities or install a video board into the optional docking station. When running BYTE's portable bench-

marks, the Eurocom 9600's performance was comparable to the baseline 90-MHz Pentium system. The Pentium gets a boost from a 256-KB secondary cache of 12nanosecond SRAM (static RAM). An internal fan keeps the CPU cool. Although

the machine becomes fairly warm after

running for several hours, you can rest it on your lap without any discomfort. And the system's 6.6-pound weight won't cut off the circulation to your legs.

The Eurocom 9600 continues EuroPak's strategy of providing highend portable power without requiring you to dig as deeply into your pockets as most of the competition.

Dave Andrews is a BYTE news editor. You can reach him on the Internet or BIX at dave.news@bix.com.

Performance

Integer Index: 0.933050 Floating-point index: 0.921311

Battery life: Word processing 1 hour, 28 minutes

(1 = 90-MHz Dell Peat

Product Information

Circle 1146 on Inquiry Card.

Eurocom Model 9600

with a 9.5-inch monochrome screen and a 540-MB hard drive,.....\$2850; with a 10.5-inch dual-scan color screen and a 540-MB hard drive,.....\$3450; with a 10.5-inch active-matrix color screen and a 540-MB hard drive ... \$4450 EuroPak International Nepean, Ontario, Canada (613) 224-6122 fax: (613) 722-2767

Best Feature

The Eurocom 9600 packages 90-MHz Pentium power in a sleek, affordable notebook. It weighs 6,6 pounds.

Explore the Internet

There's something for everyone on the Internet. And now you can get full access to this incredible resource without risk. With ten FREE* evening and weekend hours on Delphi Internet.

In 1992, Delphi Internet broke new ground by becoming the first major online service to offer full access to the Internet. Since then, Delphi Internet members have been at the forefront of the Internet revolution.

Delphi Internet connects you to 30 million people and 20,000 networks around the world.

Send e-mail. Search online databases. Download free software. "Chat" with people who share your interests.


Never been online? Don't worry. Hundreds of expert online assistants are here to help you get started. You'll also enjoy free, unlimited phone support — all part of the most responsive customer support in the industry.

Over 850 local access numbers are available nationwide. So start your ten free* hours today. Call 1-800-695-4005. Or to join directly by modem, follow the instructions at right.

FREE*! InterNav** for Windows.** Join now and we'll send you, absolutely free, InterNav for Windows — the point-and-click software Windows Magazine says will *steer you into the fast lane of the information highway.**

Coming Soon! Totally graphical user interface. To guarantee you easy access to the Internet's most exciting services, including the WWW, we'll soon introduce a new interface, featuring Netscape Navigator."





Ten-hour Free Trial!

For immediate access from any computer: Dial by modem i-800-365-4636. Press return until you get a prompt. At Username, enter IOINDELPHI. At Password, enter BYT695.

9,600 and 14,400 bps at no extra charge!

Free offer applies to new members only. Limit one per household. Offer is valid for a limited time. A valid credit card is required for immediate access. Free time may be used only during the remainder of the calendar month of becoming a member. Telcom surcharges apply during business hours (6 a.m. to 6 p.m. weekdays) via Tymnet or SprintNet and for access outside the mainland U.S. New members must agree to Terms and Conditions of membership when joining. Complete details and other restrictions are provided during the toll-free registration. Delphi Intermet and InterNav are trademarks of Delphi Intermet Services Corporation. Netscape and Netscape Navigator are trademarks of Netscape Communications Corporation. Windows is a trademark of Microsoft Corporation. You must indicate during the online signup that you use Windows in order to receive InterNav software.

O1995 Delphi Internet Services Corporat

Special Report Mobile Computing

Not Flashier, but Faster

AT&T's Globalyst 250P is good for running heavy-duty applications

DAVE ANDREWS

T&T's newest high-end notebook, the Globalyst 250P, lacks some of the multimedia amenities offered by IBM's ThinkPad 755CD. However, this notebook undercuts the ThinkPad's high price and delivers superior overall performance, thanks to a 75-MHz Pentium CPU that's matched to a 256-KB secondary cache of fast 12-nanosecond SRAM (static RAM). The 250P did exceptionally well in BYTE's FPU benchmark test while running noticeably cooler than faster notebooks based on 100-MHz Pentiums.

Like all portables, the Globalyst 250P makes some compromises. Its strengths include a 10.4-inch TFT (thin-film transistor) active-matrix color screen, resolutions that are as high as 800 by 600 pixels, better keyboard response than the 486based Globalysts, and sturdy construction. Weaknesses include a slightly larger girth than other notebooks and an inconveniently positioned trackball.

It has 8 MB of RAM, expandable to 40 MB; a 340-, 540-, or 810-MB hard drive; an internal floppy drive; parallel and serial ports; microphone and headphone jacks; an internal microphone and speaker; an external video port for SVGA graphics at resolutions of up to 1024 by 768 pixels; and PCMCIA slots for two Type I/II cards or one Type III card.

For multimedia presentations, you'll want to plug in external speakers and, if you plan to record a lot of voice-overs, a better microphone. The built-in microphone is highly directional; you've got to speak directly into it.

To maximize battery life, the Globalyst 250P offers a wealth of power management

options. You can configure individual subsystems (e.g., the serial port, hard drive, and LCD screen) to power down after a specified period of inactivity; a small LCD panel indicates the battery's remaining charge and the power management configuration. A suspend-mode button shuts down all the subsystems but retains data and system status for about half an hour.

Because of the small size of the suspend-mode button, we could not use the BYTE Lab's Thumper device to test the Globalyst 250P's battery life. However, we ran a variety of software on the machine, in-

cluding a word processor and audio/video playback applications, and found that the NiMH (nickelmetal-hydride) battery lasted for 2 hours and 45 minutes. If you need a longer battery life, you can replace the floppy drive with a second battery pack. You can also

swap the floppy drive for a \$230 expansion module that adds two more PCMCIA slots.

The Globalyst 250P is available with two optional LCD screens: 640 by 480 pixels with 65,536 colors, and 800 by 600 pixels with 256 colors. Both are 10.4-inch TFT active-matrix color LCDs. We tested the notebook with the 800- by 600-pixel screen. This higher resolution makes it easier to work in a GUI environment.

You can adjust the screen for lower resolutions, if you wish. However, if you switch from 800 by 600 pixels to 640 by

AT&T Globalyst 250P

480 pixels, the screen image shrinks by an inch on each side. That's because LCD screens, unlike CRT screens, have fixed-size pixels. Switching to a lower resolution results in a smaller screen image, not higher magnification.

The unused pixels are simply blacked out.

Input device preferences are personal, but reviewers found the Globalyst's pointing device awkward to use.

Weighing 6.9 pounds (plus 1.16 pounds for the battery) and with dimensions of 11.7 by 9.3 by 2.1 inches, the Globalyst 250P is large for a notebook. But the extra size does not necessarily mean a more luxurious working space. For instance, the trackball is positioned at the front of the machine and is perpendicular to the keyboard. You must drop your thumbs below the keyboard when you're mousing around. The Globalyst 250P's strong FPU performance and optional high-resolution

> screen make it good for heavy-duty number crunching and other FPU-intensive applications. (AT&T says the Pentiums used are free of the FPU bug.) Its multimedia features are adequate for most users, but if you want a lot of flash in your presentations, be prepared to pack extra equipment.

Best Feature

The Globalyst 250P's 800- by 600-pixel screen makes it easier to switch among several open applications. The unit also turned in strong FPU benchmark performance.

Performance

BYTE Benchi

0.836357 Integer index: Floating-point index: 0.958032

(1 = 90-MHz Dell Pentium)

Product Information

AT&T Globalyst 250P (SVGA version with 8 MB of RAM)

with a 540-MB hard drive....\$6074 with an 810-MB hard drive..\$6528 AT&T Global Information Solutions Dayton, OH (800) 447-1124

Circle 1150 on Inquiry Card.

Dave Andrews is a BYTE news editor. You can reach him on the Internet or BIX at dave.news@bix.com.

California Digital 17700 Figueroa Street Gardena, California 90248

Quanity Two Each \$699

Discount

Roland's LTX thermal plotters provide quick. cost-effective CAD out-



Also Available: LTX 2441 "B" thermal plotters offer true 400 DPI resolution. These are Roland's top-of-the-line thermal style HP-GL/2 compatible plotting machines, complete with vector to raster converter, 25mm/sec. speed, 2 line LCD, parallel/serial interface and autocut paper. 32 bit RISC CPU for speed, never need toner, ink cartridge, ribbons or other expendables.

9 Thermal Fujitsu Poqet Computer

one-pound palm-top package, engineered for on-the-go professionals. Conveniently stores in a briefcase or suit jacket. Ideal computer for word processing, spreadsheet applications, appointment organizer or any DOS based program where portability

ROM resident programs include: calendar with appointment scheduler, address-phone book with data search, calculator and modem communication software. Computer displays full 80 column by 25 lines on a brilliant LCD super twist screen. User selectable MDA or CGA gray-scale monochrome mode. Operates for weeks on two "AA" alkaline batteries. The Poqet has slots for two Type-I PCMCIA memory



cards. User can store up to two megabytes of data in each removable card. Static application programs can be stored in PCMCIA non-volatile "flash" memory. Internal-RAM, 512

kilobytes, stores active data and programs. Memory can be reassigned to resident RAM-drive.

Information remains resident while computer "sleeps". Upon reactivation the screen returns to where it was when the Poqet was deactivated. Auto-sleep Battery-saver features turns computer off after several minutes of inactivity. Power management even puts CPU into "sleep mode" between key strokes

Transfer spreadsheet business notes or home work notes directly to your desktop computer via optional Poqet data-transfer cable. Resident, Virtual Network program supports data transfer to and from your desk-top computer.

Keyboard 77-key QUERTY style layout has alternative numeric-cluster num-lock feature. includes: MS/DOS 3.3 and GW-Basic, Over all size (closed) 8.8" by 4.3" by 1.0".

Summagraphics Digitizer

The Summagraphic Summa-sketch III is a 12" by 12" digitizer with 1000 line per inch resolution. Used for CAD and computer graphics. Tablet includes stylus, four button cursor and Windows driver software. Also Available: 18" by 12" digitizer \$319.



Magnavox 5/

Magnavox 20CM64 MagnaScan-20 color display supports IBM VGA, Apple Mac, VESA, EVGA, 8514, XGA, SparkStation modes in resolutions up to 1280 x 1024 Non-Interlaced. Large 20", .31mm. CRT is ideal for CAD/CAM and desktop publishing applications. Easy access front controls, 30-64KHz. horizontal; 50-90Hz. vertical scan, ONE year warranty, and solid tilt-swivel base are only a few of the many features offered. Monitors are new but cases may show cosmetic blemishes.



Kensington 300VA Uninterruptable **Power Supply**



Professional Signs

Right From Your

PC or MAC.

and computer circuity damage from electrical brownouts, blackouts, surge, spike or power sags. True sine waveform, pre-synchronized inverter, instantuneous battery transfer time of 2 mS. or less. Quick-charge circuitry recharges maintenance-free sealed lead-acid batteries in 4 hours. 300 volt-Amps. 5.6" x 6.85" x 14.8".

2-Megabytes **PCMCIA Card**

Compatible with: HP95: Sharp PC3000; IBM Think Pad; ZEOS; Dell and most laptop computers

The Verbatim company, which is now owned by Mitsubishi, has elected to exit the S-RAM business. California Digital has purchased Verbatim's remaining inventory of 2-Megabyte memory cards.





from your computer. Make emergency trade-show signs, right at the convention center. Colored 3.25" wide, heat-sensitive

Doors, pipes, window, walls... any-

thing that needs a professional presentation can be labeled with the

Roland Stikamachine. Create mas-

terful and colorful vinyl signs-

or adhesive-backed vinyl materials give your displays a professional image. Built-in electronic scanner lets you copy, size and cut graphic images--without a computer. Connect the Stika to the serial port of your PC or Mac and output line drawings, corporate logos or any image stored

Now for only \$99, you have the power to make spur-of-the-moment professional signs and labels... anywhere!





Requests for complete catalog accepted by mail, FAX or E-Mail.

Order Toll Free (800) 421-5041

8 AM to 5 PM Pacific catalog@cadigital.com

Technical & Foreign (310) 217-0500

Facsimile (310) 217-1951

Purchase orders invited from educational and qualified organizations.

Specialists in international shipments
 Restocking charges may apply.

Friendly and courteous service since 1973
 Subject to available inventory.

Stock items shipped same day from California Digital's warehouse.

Circle 282 on Inquiry Card.

Get the Best Universal Diagnostics Toolkit works on any PC! On the market!

Featuring these two top-rated, award-winning diagnostic tools from MICRO 2000. Inc:

Version

ng & a steam of the standard o

Winners of these awards:



"You name it, this tests it. If you maintain PC's, you'll love it."

—Jerry Pournelle, BYTE Magazine, May 94





Govt. Serv. #: GS-00K-94AGS-5396

Call for upgrade pricing & complete new features list!

Micro-Scope 6.0 UNIVERSAL DIAGNOSTIC SOFTWARE

Fully O/S independent diagnostic software...

MICRO-SCOPE Universal Computer Diagnostics was developed to satisfy the expanding need for accurate system diagnosis in the rapidly growing desktop computer market. Patterned after super-mini and mainframe diagnostic routines, MICRO-SCOPE runs independently of any standard operating system, and is therefore at home on any machine in the Intel world. Speed, ease-of-use, and razor sharp accuracy are a few of the advantages that arise from this system independence, together with an impressive list of functions including the ability to perform low level formatting on every drive currently manufactured, including all IDE drives.

◆ LOW-LEVEL FORMAT—Performs Low-level format on all drive types including IDE drives. This function cannot hurt IDE drives. ◆ USE CONTROLLER BIOS—Program will access BIOS format built into any hard disk controller—even Controllers yet to be invented. ◆ O/S INDEPENDENT—Does not rely on O/S for diagnostics. Talks to PC on hardware level. All tests are full function regardless of O/S (i.e. Novell, UNIX, OS/2). ◆ TRUE HARDWARE DIAGNOS—TICS—Accurate testing of CPU, IRQ's, DMA's, memory, hard drives, floppy drives, video cards, etc. ◆ BATCH CONTROL—All tests, even destructive, may

be selected for testing. ◆ ERROR LOGGING—Automatically inputs errors during testing to an error log. ◆ AUTOMAPPING—Automatically bad sector maps errors found on hard disks. ◆ IRQ DISPLAY—Show bits enabled in IRQ chip for finding cards that are software driven. (Network, Tape Backup, etc.) ◆ IRQ CHECK—Talks directly to hardware and shows I/O address and IRQ of devices that respond. ◆ MEMORY EXAMINE—Displays any physical bit of memory under 1 Meg. Very useful for determining memory conflicts. Very useful for determining available memory space. ◆ SECTOR EDITOR—Allows the editing of any sector of floppy or hard disk media (even track 0). ◆ AND MUCH MORE... We don't have enough space here for everything this software can dol

DOST PROBE

The only Power-On Self-Test card you need to debug any "dead" PC...

This is the only card that will function in every system on the market. The documentation is extensive, and not only covers the expected POST Codes for different BIOS versions, but also includes a detailed reference to the bus signals monitored by the card."

—Scott Mueller from his globally recognized book, "Upgrading & Repairing PCs, Second Edition"

 Includes pads for voltmeter to attach for actual voltage testing under load. ◆ 4 LEDs monitor +5vdc -5vdc +12vdc -12vdc. Monitors Hi & Lo clock and OSC cycles to distinguish between clock chip or crystal failure. Monitors I/O Write and I/O Read to distinguish between write and read errors. • Monitors memory write/ read to distinguish between address line failures and memory chip failures. • Monitors ALE for proper CPU/DMA operation. ◆ Monitors Reset to determine if reset is occurring during POST, indicating short. Monitors progress of POST witbout POST codes. Reads POST codes from any IBM or compatible that emits POST codes. ISA/EISA/MCA. ◆ Compatible with Micro Channel computers. • Dip switch allows easy selection of I/O ports to read. ◆ Includes tri-state LOGIC PROBE to determine actual chip failures. • Manual includes chip layouts and detailed POST procedures for all major BIOS's. ◆ AND MUCH MORE

Also ask about our other Universally Compatible Products—

Micro-Scope CLIENT: The practical answer to remote diagnostics (no modern required).

The COMPUTER CONSULTANT: 100% accurate realtime

benchmarking tool.

Micro-Scope CERSUS: Inventory software to see and

record what's inside all of your PCs.

911-Recover: Foolproof data recovery for everyone.



Call Now for Special Pricing: 1-800-864-8008 or Fax (818) 547-0397

1100 East Broadway, Suite 301, Glendale, California * Phone 818/547-0125 • Fax 818/547-0397 International Orders please call: MICRO 2000 Australia: 61-42-574144 • MICRO 2000 Europe (UK): 44-462-483-483

Circle 265 on Inquiry Card

Growing Your Software Business Can Be Puzzling



Ask

about dongle

trade-in program.









Watch The Pieces Come Together.

Introducing The ON Button™ For Your Software


Now you can protect your software by controlling the right to use.

Buttons are microchips packaged in coin-shaped, stainless steel cans that contain critical

information to make your software run.



DS1420 ID Button": Basic security.





DS1425 Multi Button": 2K bits of RAM can protect multiple applications.



DS1427 Time Button: 4K bits of RAM, along with a tamper-proof real time clock.

write pages. Buttons tie together the pieces of your business puzzle.

> DALLAS SEMICONDUCTOR

4401 South Beltwood Parkway Dallas, Texas 75244-3292 •

Tel: 800-258-5061 •

Fax: 214-450-3869

NOTERO (BATT



NATION'S #1 BATTERY SOURCE

- OVER 1000 MACHINES CURRENTLY SUPPORTED
- FULL 12 MONTH WARRANTY
- NICKEL CADMIUM & NICKEL METAL HYDRIDE
- MEETS OR EXCEEDS OF BATTERY SPECIFICATIONS



AUTHORIZED STOCKING RESELLERS

- POWER EXPRESS 1-800-POWER-EX
- BULL EXPRESS 1-800-343-6665
- **BATTERY EXPRESS**
- # GLOBAL COMPUTERS 1-800-8-GLOBAL
- IN TECHNICAL 1-800-346-0601
- * QUILL CORP. 1-800-789-1331

PLUS. **RETAIL LOCATIONS**

- *AZ, TUCSON 1-602-747-8228
- # IL ALTAMONTE SEGS
- # GA, ATHENS 1-706-354-8444
- IL LOVES PARK
- IN, MISHAWAKA 1/219/271-2931
- MN, HERMANTOWN 1-218-723-1363
- = MN, ST. LOUIS PARK 1-612-929-6699
- OH, COLUMBUS 1-614-577-1998
- TX IRVING 1-214-256-2073
- WVI, MADISON 1-608-833-3630 • WI, SHEBOYGAN 1-414-459-9494

- CO, COLORADO SPGS. 1-719-599-9554
- FL, CLEARWATER
- # GA, ATLANTA 1-404-495-1644
- # IN, FORT WAYNE 1-219-171-2761
- LA, DAVENPORT 1 119-388-0808
- MN, ROCHESTER
 1-507-282-5767
- = MN, WEST ST, PAUL 1-612-450-7756
- = PA, CAMP HILL 1-717-730-7472
- " WI, APPLETON 1-414-749-9292
- WI, MENOMONEE FALLS 1-414-250-0222
- **wi, WAUKESHA** 1-414-548-9222

- = CO, DENYER 1-303-973-4000
- FL, FORT MYERS
- = GA, SAVANNAH
- * IN, INDIANAPOLIN 1-317-865-7710
- MN, 8LOOMINGTON
- *MN, ST, CLOUD 1-612-240-2332
- * NC, RALEIGH 1-919-790-1800
- #SD, SIOUX FALLS 1-605-362-1050
- WI, GREEN BAY 1-414-498-1100
- *WI, MILWAUKEE 1-414-282-5200 *WI, WAUSAU 1-715-842-8283

UNITED KINGDOM - MDS MARKETING (UK) LTD. - TEL: 44-(0)-181-884-4904

RESELLER & RETAILERS FAX INQUIRIES ON COMPANY LETTERHEAD TO (414) 922-6750.

THE ARTICLES THAT CHANGED THE WORLD MORE THAN A BIT—FROM BYTE

Only one magazine has been taking readers to the front lines of the microcomputing revolution since its inception almost two decades ago—BYTE!

Now you can relive the most glorious moments with this unrivaled chronicle of the evolution of this empowering technology. Here—and only here—you'll find the groundbreaking articles and features that *BYTE* alone had the vision to publish, including:

- Kernighan and Ritchie on C
- Stroustrop on C++
- Seminal pieces by Wozniak
- Articles covering the most important operating systems developments
- BYTE Awards from 1989-1992
- First-announcement product advertisements

The Best of By TE Two Decades on the Leading Edge
JAY RANADE / ALAN NASH Editors


\$24.95 (Paperback)

You won't want to miss this invaluable new "best of" collection. Of course, all the bits of microcomputing's most significant magazine count—but, from time to time, some bits of BYTE change the world. Get them all with *The Best of BYTE*.

Available at your local bookstore or call toll-free 1-800-822-8158



McGRAW-HILL, INC.



Now, Go From Paper To Electronic Forms Automatically.



Introducing TransForm.™ As incredible as it sounds, you can now scan your paper forms into fully editable, electronic forms in minutes.

Thanks to its artificial intelligence, TransForm senses boxes where data is entered and lets you type into them directly. Each form you create with TransForm can be filled or merged with variable data, E-mailed and faxed. What's more, all your forms can be filled and printed from nearly

any computer platform. ■ Another benefit: with TransForm, you can quickly make changes to forms at any time and print out new forms when you need them. No more throwing away stacks of obsolete forms! ■ And for convenient form storage, our mips FormShuttle™ holds up to 200 forms, and plugs right into the cartridge slot of your laser printer. Since forms stay printer-resident they'll print much faster. ■ Find out more today: 800-898-8560

Call the mlps authorized dealer near you.

DocuPrint, Sweden: 46-8-283390 mips Technologies GmbH, Germany: 49-6127-3845

Open Systems Solutions, Printline AG, Switzerland: Venezuela: 582-239-6113 411-814-1412

PC:\Forms>Inc., Wisconsin: 800-786-8827



(619) 679-4070 • Fax (619) 679-4073

FAST, FOCUSED ANSWERS TO YOUR IT QUESTIONS DELIVERED TO YOUR FAX MACHINE . . . 24 HOURS A DAY, 7 DAYS A WEEK

Instant access to Datapro's product and technology reports is just a phone call away. Whether you're working on a product plan or trying to stretch every dollar in a proposal to purchase, smart decisions depend on getting the right answers at the right time. *Datapro on Fax* is what you need.

Find out how *Datapro on Fax* can help you work faster and smarter. Call today for your free *Datapro on Fax* catalog.

Here are some of the topics covered of special interest to BYTE readers:

- > 486-based transportables
 - > CD-ROM drives
 - > Integrated desktop applications
 - Storage subsystems
 - > Client/Server technology and architecture





800-329-8398 (800-FAX-TEXT) or 609-764-2840





One Portable CD-ROM Drive — Two Simple Steps



With the backpack quad-speed CD-ROM drive, you're one cable connection away from a world of multimedia business advantages: Plug it into your PC parallel port to access a universe of CD-ROM titles. Take it with you for portable data retrieval. Or share it with other PCs.



No compatibility problems with virtually any IBM-compatible PC—Windows, DOS or OS/2. No

taking your PC apart to install this

quad-speed drive. Just plug it into your PC printer port—plug your printer into the backpack. A simple

solution from the backpack family

of tape, diskette and hard drives.

MicroSolutions

Call Toll Free - 800.295.1214

SEE US AT PC EXPO IN NEW YORK, BOOTH #2240

132 W. Lincoln Hwy, DeKalb, Illinois 60115 • Telephone 815.756.3411 • FAX 815.756.2928

The Micro International 7600 Notebook.

The fastest notebook in the world.

(Again).

But that's just the beginning of what you get for only

\$3300.

Built-in multimedia speaker for the built-in soundblaster compatible 16-bit soundcard!

Two type II PCMCIA card slots (equal to 1 type 3)

340mb removable local bus HD (up to 810mb available)

8mb RAM (up to 40mb using user-upgradeable modules) and 256K L2 cache!



Brilliant 10.3" Dual-scan Passive Matrix Color screen (Active Matrix also available).



Mic in / Speaker / Headphone out jacks

3.5" floppy drive

19mm trackball in just the right spot

Dependable NiMH Battery

A focus on service and support since 1984!

We give you free lifetime toll-free tech support. We preload the latest versions of DOS and Windows for Workgroups, including all video, sound, and PCMCIA card utilities. Our 1 Year Parts and Labor Warranty includes our outstanding 48 hour warranty service turnaround time, proving that we understand how you depend on our products. Our 30-day money back guarantee is pretty simple: you get a refund if you're not satisfied for any reason. Our RealHelp disk included with every notebook allows us to service your technical configuration files by remote access. Our 48-hour+ extensive burn-in and testing period on every single notebook, before it leaves our facility, ensures an absolute minimum of failures in your notebook. Anything less is just not mint!

* Shipping charges will be withheld from any refund, along with 2% of invoice total on any credit card orders.

Micro International, 10850 Seaboard Loop, Houston, Texas 77099. Top quality service and support *since 1984!*Full information (including specifications, all options & prices) available by fax or mail on request.
Fax (713) 495-7791 Hours: 8-6 Monday-Friday. Call today toll free:
*Pentium is a registered trademark of Intel Corporation.

1-800-967-5667



Remote Programming



Remote Programming of WIBU-BOXes via Phone, FAX or mail – New chances for more sales!

Order your evaluation package today!

- ✓ The most complete hardware palette
- ✓ WIBU®-BOX for LPT, COM, ADB, as card for (E)ISA slots and as PC-Card (PCMCIA)
- Protection for DOS, Windows and networks without requiring source code modification
- ✓ Win32s, Windows[™]NT, Mac[™]OS, QS/2[®], DOS

WIBU-KEY

High Quality in Copy Protection



WIBU-SYSTEMS GMBH, Germany
Rueppurrer Strasse 54, D-76137 Karlsruhe
Phone: +49-721-93172-0, FAX: +49-721-93172-22

Email: 100142,1674@compuserve.com

Southwind International Inc.
P. O. Box 308, Brookeville, MD 20833,
Phone: (301) 570-3497, FAX: (301) 570-4773



FOLDING A MAP HAS NEVER BEEN EASIER.

We are

looking for

Distributors

worldwide



Next time you're on the road, unfold your portable PC instead of a map and let Retki GPS Land Navigation System lead you to your destination. Through the use of the Global Positioning System satellites (GPS),

Retki can pinpoint your location and graphically represent your position on any of our wide selection of electronic maps, right on your portable PC, right in your vehicle.

Search for Map Locations by Address

Need to find a location of a client? Just type in the address,

and Retki will not only show you where that location lies on the map, but Retki can also show you the most direct route to get there. No more getting lost. No more missed meetings.



Personalize Your Maps

Create a relational database for each map, so as you use the maps, you can list the spots that are important to you and your business. You can create a list of delivery stops, client



locations, or even a list of your favorite lunch spots.

This feature rich package comes complete with a PCMCIA Type II GPS receiver and antenna, the Retki software to run on Windows, a comprehensive map of the United States, and a free local map to get you on your way.

Next time you're on the road, take along the Retki GPS Land Navigation System, and take the frustration out of road travel.

For More Information on the Retki GPS Land Navigation System, Call

1-800-99-RETKI

Liikkuva Systems International, Inc. Ask about our new V.1.5 on CD-ROM.

Come see us on the internet at http://www.liikkuva.com/

17" MONITOR FOR - \$2



The Tympani - More Bang For Your Monitor Buck!

The Orchestra Diva is singing again. This time, it's about our new 17" Tympani monitor. Now, for \$469, you can have a 17" screen, with two-thirds more Windows screen area than a 15" screen. Get a bigger, better and brighter image for larger text and

more vivid multi-media impact.

All that extra screen area, with a maxinon-interlaced resolution 1024x768, for an estimated street price of only \$469!

More Screen For Your Buck

Even with a \$469 price tag, the Tympani offers pincushioning control and Energy Star compliance, with DPMS power management.

For more features and performance, look to Orchestra's newest 15" and 17" displays. the French Horn II and the Tuba II.

You're In Control With Advanced On-Screen Display

The French Horn II and Tuba II support high refresh rates and have advanced On-Screen Display controls for adjust-

ing image geometry and color. Adjust the tilt/rotation, pincushion/barreling and trapeziod aspects, so your image is sharp, square and stable, just the way you like it.

Moreover, color balancing allows adjustment of Red, Green and Blue, so you can match your screen color to your printer output, or maybe just your mood.

Call us at (800) 237-9988 from 8:30am to 5:30pm, PST


and ask a product specialist about the full line of Orchestra 14", 15" and 17" displays as well as the Tempo Series of

PCI and Vesa Local Bus video adaptors.

For all your monitor needs, Orchestra has a model to fit your computing style.

For more information, or to find a

Tympani Toba II 0.42 Dot Pitch (mm) 0.28 0.28 Maximum Resolution (Non-interfaced) 1600x1280 1024×768 1280x1024 Transzoldal Control YES YES Tit/Rotation Control YES YES Pincushion Control YES YES Color Balance Control Color Temp. Control YES YES Microprocessor Controls IIIO YES YES On-screen Controls YES MO YES **Estimated Street Price**



(800) 237-9988

© 1995 Orchestra MultiSystems, Inc. All trade names are trademarks of their respective companies.



Outdoor Computing



With A BYTE


AND MANAGEMENT OF THE STATE OF

Ferocious Computing Devices

Harsh environments are no match for Badger Computers. Badger is the most extensive line of rugged mobile computers available anywhere in the world. Badger offers custom configurations with numerous wireless connectivity options. GPS and scanners can also be integrated. For tough computing needs call 1-800-3-BADGER and take a BYTE out of your workload today.

BADGER





KINGSTON. THE ONLY MEMORY THAT GUARANTEES WORRY-FREE TRAVEL.

In the course of your travels, you may deal with schedule changes, cancelled flights, and lost luggage. One thing you won't have to worry about is your Kingston Memory. Installing our memory ensures that you'll never have to worry about your system failing in the





middle of a big proposal or worse, not booting up. Kingston Memory is 100% tested and compatible with every popular notebook and portable system on the market, including your Compaq TM and Toshiba TM systems.

Kingston can't guarantee that you'll never lose your luggage or have your flight cancelled, but you'll never have to worry about your notebook memory again. It's the one thing in this fast-paced, hectic world you can truly count on. Call (800) 251-9058 for your free notebook configuration guide.



THE INSIDE NAME IN UPGRADES



IMPROVING YOUR MEMORY

We can't remember a time with so many different kinds of RAM to choose from. Here's your field guide to the new chips and what they do.



t used to be simple. You always wanted more memory in your computer, but you had to worry about only one kind—DRAM. The only important differences were in per-chip capacity. While the first IBM PCs in 1981 used 16-Kb chips, today's chips sport 16 Mb. Capacities up to 1 Gb have been announced, but those chips won't ship for a few years.

Memory technologies are so diverse that you can't tell the players without a scorecard. BYTE examines 17 new types of memory chips that embody not trivial distinctions but substantial differences: built-in caches, synchronization, specialized graphics processing, on-chip ALUs, and more. Add in new forms of packaging, and it's hard to keep tabs on what's what.

In "Fast, Smart RAM," Peter Wayner sorts out current and cutting-edge memory technologies. He looks at memory architectures, chips optimized for graphics and video applications, and supercomputer memory. Wayner considers which types of RAM will likely prevail in the marketplace and what will be in your next PC. Related text boxes consider why memory prices stopped falling a few years ago, the reasons flash RAM is here to stay, how the new RAMs affect future cache use and design, and why we're going to see several different types of RAM in a single computer.

"More Memory in Less Space" examines the trend to stacking memory wafers in layers, achieving densities as high as 2 GB per cubic inch. Rick Cook examines the evolution of commodity memory from DIPs to SIMMs and discusses why DIMMs (dual in-line memory modules) will be the norm for the next few years.

Finally, it's worth noting that the memory industry has produced remarkably little in the way of standard-setting activity. It's becoming evident that the marketplace, not an IEEE or ANSI

standards committee, will decide which memory chips become the mainstays of tomorrow's computers. This is a two-edged reality. On the one hand, it's fostering the current explosion of exciting new memory technologies; on the other hand, the marketplace is likely to remain fragmented for some time to come. But if we have to choose between encouraging new advances in technology and achieving a more stable commodity market, BYTE thinks it makes sense, especially over the long haul, to bet on ideas, imagination, and innovation.

-Russell Kay, Technical Editor

Fast, Smart RAM

RAM chips speed up and get more capable. BYTE helps you sort out the major players from the nonstarters _______187



More Memory in Less Space

Layering silicon wafers allows very high-density components......197



The Gateway to Japan's PC Market —

The Largest Piece of a Growing Asian Marketplace



September 27-29, 1995

Place: Nippon Convention Center (Makuhari Messe, Chiba, Japan) Organized by: Nikkei Business

Publications, Inc.

Support by: Ministry of International Trade and Industry (planned), U.S. Embassy's Foreign Commercial Service Collaboration: Database Promotion Center, Japan Cooperation by: Nihon Keizai Shimbun, Inc., Television Tokyo Channel 12 Ltd.

Reach over 50,000 members of Japan's PC community!

- 1. Japan's first comprehensive PC exposition Covering a wide range of the latest PC-related products and technology for all platforms.
- 2. "Partnership Solutions Program"

This program provides you with an opportunity to meet you future partner in Japan.

3. Technical Seminars

High-quality seminars held apart from the exposition wil attract high-level attendance.

4. Organizer's exhibit zone

Nikkei BP presents the state-of-the-art and future direction o PC multimedia.

5. Extensive Promotion

Expect high attendance thanks to promotion in Nikkei BP? PC publications and in other major media such as TV and daily newspapers.

Circle 78 on Inquiry Card.

Send Fax and Get Free Brochure Now! FAX. +81-3-5210-8285

You will soon receive a FREE INFORMATION PACKAGE from Nikkei BP WORLD PC EXPO Managing Office

(Please type or print)

Company	
Department in Charge	
Address	
Zip	Country
Tel.	Fax.
Contact Person	

Reserve Your Exhibit Space Today!

For more information, please contact:

Nikkei Business Publications America, In 575 Fifth Avenue (20th Fl.) New York, New York 10017 TEL. (212) 867-3414 FAX. (212) 867-3278

Organizer:


Nikkei Business Publications, Inc. WORLD PC EXPO Managing Office 2-7-6 Hirakawacho, Chiyoda-ku, Tokyo 102, Japan TEL. +81-3-5210-8393 FAX. +81-3-5210-8285

State of the Art

FAST, SMART RAM

Memory chips are getting faster and more capable but not less expensive. BYTE sorts out the new types of RAM—what each is good for, and which ones you're likely to see on your next PC.

PETER WAYNER



ntil recently, computer users could proudly wear T-shirts proclaiming, "Whoever dies with the most RAM wins." Complacent in their swivel chairs, they knew that they understood the place of memory in the computer world order.

Now, however, the realm of computer memory is becoming fragmented as RAM producers develop increasingly ingenious methods of squeezing ever more performance out of the chips. Some of their experiments involve on-board caches, specialized CPU-to-RAM interfaces, and even pure processing power directly on the memory chips themselves. Soon a desktop system will be judged on not only how much memory it has but also what architectural enhancements that memory offers to the system.

The force behind these changes has been increasingly apparent over the last decade: RAM-chip speeds have not kept up with the increasing speeds of CPUs. As chip manufacturers found ways to add more transistors to each chip, the CPU architects could easily increase speed by adding more arithmetic units to each chip. Twice as many arithmetic units could let a chip run almost twice as fast. On RAM chips, though, more transistors per chip simply meant that the chips could hold more data; they couldn't access it particularly faster. While faster chips (e.g., static RAM, or SRAM) were available, they were much more expensive and had lower capacity per chip because they required several more transistors to store each bit.

Working around the slow speed of RAM, CPU architects added a small amount of faster cache memory and created separate memory banks that would alternate serving data to the CPU. These techniques, though, are reaching maturity. Intel's P6 includes primary and secondary caches on the main chip die. Many systems augment this by placing a tertiary cache between the processor and the main memory; however,

SOB DAH

Flash Memory Looks Bright

eports of the demise of flash memory have been greatly exaggerated. If sheer storage capacity for laptops is your sole concern, then PCMCIA Type III PC Card hard drives of 260 MB for \$600 are attractive alternatives to 40-MB flash memory cards costing \$1200. Even flash memory supporters, like Bruno Beverina, vice president of SGS-Thomson's Memory Group, have long maintained that flash memory is "not likely to compete soon with hard disk technology in price and capacity." However, storage capacity Isn't everything.

Flash memory cards, with solid-state electronics and no moving parts, require far less power than hard drives, and this is especially significant in perpetually power-hungry laptops. Also, many older laptops simply lack the Type III PC Card slots required for such hard drives, but the more common Type I or II slots fit flash cards just fine. This can be an important consideration if you're outfitting or refitting a whole fleet of laptops. Access times for flash cards (as low as 30 nanoseconds) are from 100 to 1000 times faster than hard drive access times—a performance boost that could end naps between mouse-clicks.

Solid-state flash memory can withstand more serious shocks (some over 2000 Gs) than any hard drive (under 200 Gs), and this is important for ruggedized use in demanding environments. Because flash memory retains information even when the power is turned off, data can be stored without deterioration for time periods reck-

oned in decades and centuries. Finally, flash memory cards are reliable, with MTBF (mean time between failures) of millions of hours common. For all these reasons, flash memory cards will continue to be important for laptop use.

Flash memory cards are turning up in plenty of products besides laptops. On many printers and print servers, flash cards hold fonts, company logos, complete corporate stationery arrangements, and forms layouts, PDAs (personal digital assistants), including Apple's Newton and other handheld devices, use flash cards as a primary software-distribution medium. Kurt Wolf, divisional marketing manager for AMD's flash memory division, observes that, "In the PDA form factor, flash cards have greater system value than hard drives. You don't need 100 MB; you do need it to be rugged." Hubs and routers from vendors like Xyplex and Madge Networks use the cards to hold software (including compressed microcode) and indispensable unit parameters to support rebooting.

On the chip level, flash memory is even more widespread in computer-related applications. Flash BIOS, once found only in high-end laptops, is routinely replacing ROM BIOS in desktop machines, allowing the manufacturer or user to reprogram the BIOS electronically, without having to replace chips

The nonvolatile nature of flash memory is also important. Plug-and-Play features will require nonvolatile BIOS memory in which

configuration data can be updated. Hubs and routers also use flash chips to replace ROM, guaranteeing the option of simple up grading. Many modems use flash memory to hold configuration data and software: This lets you upgrade the modem simply and a no cost, by downloading information rathe than by swapping chips. Similarly, network adapter cards use flash chips to store the myriad configuration details. On SCSI hard drives, flash chips often hold the contro codes that can be customized to satisfy buyer's needs. The reliability of flash mem ory is not lost on the data security and RAID market: One ruggedized mini-RAID solution from Raymond Engineering eschews hard drives entirely and uses only multiple banks of flash memory.

In noncomputer products, flash memory chips (usually lower capacity) are appearing in cellular phones, pagers, answering machines (replacing DRAM), set-top boxes and digital cameras. It is simpler to design and manufacture generic cellular phones and configure their flash memory with the specific codes (e.g., GSM, Global System for Mobile communications) appropriate for their final destination, whether that's Germany, Singapore, or Cleveland.

Flash memory plays a similar role in TV set-top boxes, the darlings of the digital convergence cheerleaders: Generic boxes can be customized after manufacture and given special information as needed (and paid for). Even cars use flash memory as part of their engine control systems.

While the flash memory PC Card busi ness is expected to grow at less than 10 percent per year, some predict that the flash memory market as a whole—currently

the gain that each new level of cache produces is substantially smaller, as absolute gains in access speed are offset somewhat by the need to look in yet one more place (see the text box "Is Cache Losing Its Cachet?" on page 191).

This places more pressure on RAM designers to deliver information faster. The latest designs incorporate small quantities of extra logic that organizes the flow of data off the chip. These chips—known by names like FPM (fast page mode), EDO-RAM (extended data out RAM), or burstmode RAM—offer faster data flow when the data is requested in sequential order.

More exotic alternatives are emerging in the graphics arena, where innovation is more common because the standard unit is the video card, not the SIMM. This lets card manufacturers experiment with and adopt different technologies and still produce a board that works with all software. These card designers are exploring the use of FPM, EDORAM, and burst-mode RAM, and they're also investigating technologies like Mitsubishi Electronics' 3D RAM and Samsung's WRAM (Window RAM), both of which include more circuitry on the RAM chip designed to speed up common video operations. (For more on graphics RAM, see "Faster Graphics Cards on the Horizon," April BYTE.)

Systems designers are beginning to explore a greater range of nonvolatile memory. Flash memory is an electrically alterable memory that maintains its state until it is erased with a relatively large voltage. Originally developed by Intel, flash RAM has seen wide use in PCMCIA PC Card memory for laptop computers. (For an update, see the text box "Flash Memory Looks Bright.") FRAM (ferroelectric RAM), a newer competitor in the nonvolatile arena, uses iron in the fabrication process, an echo of the old ferrite-core memory used in early mainframes. FRAM also maintains its memory after the power stops. Both these memory products should find increasing use in highly portable products like PDAs (personal digital assistants).

In the farthest regions of the intellectual frontier, memory designers are experimenting with memory that can do many computations directly on the chip (see the about \$1 billion—will grow at 50 percent per year, reaching \$4 to \$10 billion by the year 2000. Several processes are fueling that growth. Ron Bohn, an analyst at Dataquest, sees flash memory as a "technology enabler." Certainly, consumer products using flash memory—like cellular phones—are growing in popularity fast. The price of flash memory is falling, and becoming competitive with DRAM. This causes a curious, if simple, upgrade behavior: People with 10-MB cards wait a year or two and buy a 20-MB card for the same price.

As inevitably happens with electronic technology, flash memory is also becoming a commodity with competing vendors, including powerhouses AMD, Fujitsu, IBM, Intel (the world's leading producer), Matsushita, Mitsubishi, National Semiconductor, Panasonic, SGS-Thomson, and Toshiba, in addition to smaller vendors, such as Centennial and M-Systems, Most flash memory is built to the same standards and is interchangeable: a customer demand that vendors satisfied.

Flash technology itself is moving forward. Single power-supply chips—at lower power—are supplanting dual power supply. Serial interfaces and smaller block sizes allow more flexibility. Wear-leveling algorithms place data evenly over the chip, increasing its durability and reliability. Chip size is shrinking, as the latest generation of 16-Mb (2-MB) chips attest. Look for a doubling of capacity per cell in the next year. Already 40-MB flash cards exceed the capacity of the lowest-end PC Card hard drives. Some people predict hard drive—size flash cards within five years.

-Edmund X. DeJesus

text box "Smart Memory" on page 190). They expect this will offer dramatic performance improvements on problems that can be solved in parallel. Placing the intelligence on the chip saves the time of moving the data on and off the chip.

The RAM Shift

The computer memory industry doesn't jump on these new innovations quickly, because it produces chips in such high volumes. No memory manufacturer can begin to build new formats or innovations until the demand is there, and the demand is not certain until system enhancements become essential.

By the time this article appears, the computer industry will be engaged in a large-

scale adoption of EDORAM for main memory. In fact, this year promises to be the one in which EDORAM begins to dominate the marketplace. Many system integrators and RAM manufacturers agree that the price differential that EDORAM commands will evaporate by early 1996.

The technology behind EDORAM is a simple extension of the trend that made FPM RAM the standard form of DRAM available. When you read an element in a DRAM array, you charge electrical lines to first select a row and then a column. The lines do not stabilize immediately, however, and the length of the delay is what prevents the RAM location from being read instantaneously.

FPM RAM returns data faster because it assumes that the next data requested will be in the next column of the same row. In many cases this happens, and there's no need to wait for the row delay. This process stops working reliably, however, if the CPU demands data too quickly. The lines do not stay stable long enough for the CPU to read off the answer. This usually begins to happen in CPUs running at speeds faster than 33 MHz.

To solve this problem, EDORAM adds a set of latches, or secondary memory cells, at the output. These sense the data being fed for output, store it, and keep it available long enough for the signals to reach the CPU reliably. These chips should be stable at system bus speeds up to 50 MHz.

You can add even more circuitry and let EDORAM offer information at still higher speeds. An approach known as burst EDORAM assumes that the CPU wants the next, say, four addresses and begins fetching them automatically. This technique can easily supply systems with a bus clock speed of up to 66 MHz reliably.

The Race Is On

CPUs are getting faster, however, and they demand ever faster memory. Many memory makers are investigating two solutions: synchronous RAM, in which the CPU and RAM are locked together by the same clock; and cache RAM, which gains speed by adding to the chip a small amount of fast SRAM that acts as a cache to the DRAM. Both are good choices for systems that run faster than 66 MHz.

The synchronous solution is a cleaner replacement for the old interfaces between chips. Normally, memory chips answer requests. SDRAM (synchronous DRAM) feeds off the same clock cycle as the CPU, anticipating the CPU's demands and stay-

ing in step. Some devices even have a pipelined architecture, in which a stage can fetch an address while other stages present the data for output. Many people predict that 1996 will be the year of SDRAM, because 66-MHz or higher CPUs will be common by then and will need SDRAM. Until then, however, SDRAM will command a 20 percent to 50 percent premium over commodity DRAM. Also, the price of these faster systems must cover the added cost of the different logic chips needed to drive the SDRAM.

Another way to speed memory access is by adding an on-chip cache. This approach, often called CDRAM (cached DRAM) or EDRAM (enhanced DRAM), succeeds because it places an SRAM cache on the same chip as the DRAM. CDRAM comes from Mitsubishi (Sunnyvale, CA) and is second-sourced from Samsung, and EDRAM comes from Ramtron International (Colorado Springs, CO). In both cases, this cache can respond more quickly to requests for the CPU if it has the right information already in the cache.

The chips also gain speed because the caches are able to fetch data from the slow DRAM in large blocks using the internal buses. Mitsubishi's CDRAM, for instance, features a 16-Kb cache with 128-bit lines on both its 4- and 16-Mb chips. When data is requested, the slow DRAM sends the entire 128-bit block to the fast SRAM. If the next address requested is in this block, as often happens, then the chip is ready. Picking the right sizes for the caches and buses is still an art, and practice varies widely. Ramtron, for instance, chooses to use a 2048-bit-

An Abbreviated Guide to the RAMs

CDRAM cached DRAM
CVRAM cached VRAM
DRAM dynamic RAM
EDRAM enhanced DRAM
EDORAM ... extended data out RAM
EDOSRAM ... extended data out SRAM
EDOVRAM ... extended data out VRAM
FPM ... fast page mode
FRAM ... ferroelectric RAM
RDRAM ... Rambus DRAM
SDRAM ... synchronous DRAM
SRAM ... static RAM
SVRAM ... synchronous VRAM
3D RAM ... Matsushita's chip for 3-D
video processing

VRAM video RAM

WRAM..... Window RAM

Smart Memory

he most sophisticated approach to squeezing more information out of memory chips is that being taken by Cray Computer (Colorado Springs, CO). Engineers are building a new version of the Cray 3 supercomputer using a special kind of memory that contains embedded processors. Each memory chip comes with 128 Kb of storage and 64 single-bit ALUs that can perform all the basic 1-bit operations. The 1-bit processors embedded on the Cray memory chips each contain three 1-bit registers. Data in any of the local bits of each processor can be loaded into and stored from these registers. Each of the three registers can have two different states, which means there are eight possible configurations for the set of registers. A programmer specifies an instruction for the 1-bit ALUs by presenting an ALU with 1 byte that contains the 1-bit answer to all eight possible configurations. The chips were designed by the Supercomputer Research Center (Bowie, MD) as part of a research program sponsored by the National Security Agency, or NSA. The technology was licensed by both Cray Computer and National Semiconductor, who will be fabricating the chip.

This chip was designed to act like normal memory most of the time. If, however, the main processor wants to use any of the 64 processors scattered throughout the memory, it raises one of the signal lines and effectively writes the instruction to the chip. The instruction is dispersed to the individual processors, each of which executes the instruction on 2048 bits of local data.

The processors have a 1-D shift register for communicating with one another. In many respects, this is the most significant difference between this approach and the classic single-instruction, multiple-processor arrays like the Connection Machine CM-

1. Those older machines used complicated 12-dimensional message-passing arrays to route data between processors. This limited the number of processors on each chip simply because there weren't enough pins in a standard package to handle a large 12-dimensional network.

The first computer system using this new memory will be known as the Cray 3/SSS, and the first customer is NSA, which will presumably use it for code breaking. Robert Cox, director of the Cray 3/SSS project, expects that the computer will find many uses in highly parallel problems (e.g., image processing and seismic computation).

Coherent Research (Syracuse, NY), a company that has manufactured and tested similar products, has shown how this specialized memory could be used in graphics accelerators. They produced a demonstration system that would identify which window was hit by a mouse, doing this by testing all the windows in parallel using the processor array embedded in the memory. Such highly parallel applications might be desirable, for instance, in future games that flash many different objects across the screen. With the ability to test for collisions and selection in parallel, game designers could add many objects to the screen without decreasing performance. This high-end memory could also have application in database searches, ray tracing, and other highly parallel problems.

In late March, the preceding was written before Cray Computer filed for Chapter 11 and laid off many employees. Obviously, the immediate future for this particular, and expensive, memory technology is uncertain, but the special demands of supercomputing may yet see it become a commercial reality.

wide bus to fill an 8-Kb SRAM cache on its 4-Mb DRAM.

Some systems designers are happy with cached memory chips. Ocean Information Systems (Covina, CA) manufactures 486 and Pentium motherboards that use Ramtron's EDRAM as the main system memory. The cache on the chips allows all the memory to operate at cache memory speeds. This makes an enormous difference when the CPU requests information that isn't in the L2 (Level 2) cache—something that happens more fre-

quently with multitasking OSes and bloated programs. Barnett Fischer, Ocean's director of R&D, says, "A 100-MHz Pentium runs at only 8 MHz if it misses the L2 cache." That is why a 33-MHz 486 system using EDRAM can switch among a number of tasks much faster than a 100-MHz Pentium with a standard DRAM. The Pentium will still be substantially faster on single-task benchmarks that don't leap outside the L2 cache, but it will crawl to an 8-MHz halt when the cache starts missing.

RAM Packaging

As EDORAM and faster products begin to permeate the market, they will be seen primarily as 72-pin SIMMs, currently the standard commodity configuration for the PC world, although that may not be the best long-term solution. All RAM manufacturers are investigating faster and denser packaging, including direct mounting, wafer laminating, and other ways of packing the wafers closer to each other (see "More Memory in Less Space" on page 197). Many manufacturers are continuing to examine packages that might offer a more stable and faster bus. For instance, SDRAM requires that the RAM and the CPU share clocking information, and more precise packaging may better serve this need.

One of the best-known alternative formats for RAM is RDRAM (Rambus DRAM) from Rambus (Mountain View, CA). This bundles better and smaller packaging with more-stable lines and faster signaling logic. The chips are close together, and the leads are designed to be short, precise, and manufactured to much tighter tolerances than are standard printed circuit boards. This minimizes the extra capacitance that can cause the signals to travel at unpredictable speeds.

The system is also strongly synchronized to a clock that regulates exactly when the information will be available on the bus. The transfer happens every 2 ns on both the odd and the even edge of the clock cycle. This synchronization is similar to the process proposed for SDRAM. All these factors combine to enable transfer speeds up to 500 MBps.

VRAM

The commodity market for main memory is forced to be conservative and slow-moving because all additional memory usually comes in a standard package. The designers of video boards, however, are free to use whatever types of memory circuits they like, and as a result, the market is filled with many different approaches. Some use commodity DRAMs, others use more specialized VRAMs, and still others experiment with more exotic combinations like WRAM and 3D RAM.

Whether to use DRAM or the more expensive VRAM to maintain an image on the screen is an old debate. DRAM serves one master—the controller, which is responsible for changing the image on the screen and for collecting the information and sending it off to the video monitor. In a video card using VRAM, the memory


chips serve two masters: One maintains and changes the image, while the other gathers the information for the video monitor. The VRAM is constantly serving both masters, each at a different port.

VRAM may have two ports, but that doesn't mean it's twice as fast or can provide twice as much information. The actual individual memory cells are the same in VRAM and DRAM. There's a limit to how much information can be moved in and out of an array of DRAM cells, because the addressing lines for the rows and columns must be charged and discharged. This total throughput volume is known as bandwidth. VRAM's dual ports don't double the total bandwidth; they merely reserve a slice for the circuitry that drives the screen-drawing function. This extra port increases the amount of information that can come and go from a chip, but it doesn't double it.

This segregation has two effects. The VRAM circuits always perform better at higher resolutions with more colors. The extra bandwidth helps in these high-end cases, where a 1280- by 960- by 24-bit screen image requires moving over 3 Mb onto the screen every time it is refreshed. But for lower resolutions, there's much less benefit to be gained from added bandwidth. In these lowend video configurations,

VRAM's second port is unused much of the time.

On the other hand, DRAM boards have no set restrictions on how the bandwidth is used, and this is precisely why lower-end



Mitsubishi's new 3D RAM memory chip, intended for specialized graphics applications, can determine whether a pixel is hidden, based on its z-value.

video-board manufacturers often choose it. Any memory that isn't used to refresh the screen is available for the video controller to use. If a low resolution is chosen for the screen, then the video controller can use the rest of the bandwidth to create complex images on the screen. The downside is that the amount of leftover RAM drops as screen resolution increases. These DRAM boards can dis-

play high-resolution images, but manipulating them becomes sluggish.

RAM manufacturers are exploring new RAM chips for video boards in many ways. Caches, synchronization, and latching can

Is Cache Losing Its Cachet?

BY DAVID F. BACON AND PETER WAYNER

dding cache memory is well recognized by computer buyers as a reasonable way to turbocharge a system's performance. Nowadays, however, the need for separate caches is disappearing as newer microprocessors add more cache directly onto the CPU die itself and as multitasking OSes fragment memory demands and lose much of the performance advantage that cache memory is supposed to provide.

Recent generations of CPU chips have had enough silicon real estate to include a small on-chip cache. These caches have generally been in the range of 8 to 32 KB, which is too small to help many applications. As a result, many computer systems have been built with a larger, off-chip L2 (Level 2) cache to supplement the on-chip L1 cache.

However, on-chip caches are getting larger. Intel's newly announced P6, for example, has 256 KB of on-board L2 cache, while Digital Equipment's Alpha 21164 has 96 KB of on-chip L2 cache memory. With large on-chip caches like these, the complexity and expense of adding an L2 cache to a PC or worksta-

tion makes less sense, so we can expect to see fewer of those types of machines in years to come.

Large software packages and multitasking OSes like OS/2 Warp can destroy the value of a cache if it isn't large enough to hold all the code being executed. When the CPU switches between jobs, it can't find the information it needs in the cache. and it must request it from the substantially slower main memory. Users of Microsoft Windows, for example, may notice this effect already when they ask their system to print in the background. Many machines can't keep both the printing code and the Windows code in the cache simultaneously, so the constant switching makes the system run at the slowest memory speeds.

Look for innovations in cache design driven by the growing presence of multiprocessors. Multiprocessors are just beginning to break into the mainstream server market, and with the demands of desktop
conferencing and high-end multimedia applications, multiprocessors are likely to
become the platform of choice for power
users before too long.

Cache design for multiprocessors is considerably more complicated. If processor A wishes to update a memory location cached by processor B, B's copy must be either invalidated or updated by A. Even worse, if B has already modified its copy, then before A can proceed, B's data must be either flushed back to main memory or transmitted directly to processor A. So far, we've seen two different approaches to solving this. Either all the processors monitor all the memory traffic, looking for potential conflicts with their locally cached data (a snoopy cache), or the main memory controller keeps track of which processors have cached which memory locations (a "directory-based" cache).

Each scheme has its advantages and disadvantages. Snoopy caches are generally easier to implement, but they require that all memory traffic goes over a shared bus. Directory-based caches require extra memory to keep track of the outstanding copies, but they can be used with more sophisticated processor-interconnection networks that provide higher bandwidth and scale to a larger number of processors.

Multiprocessor systems have been the subject of research for the past 30 years, but it's only in the last five or 10 years that they have managed to capture a significant portion of the high-end supercomputing market. Now, as multiprocessors make their way into the high-volume PC and workstation businesses, that research will come face-to-face with the real world.

One Machine, Many RAMs

BY RICK COOK

uring the next few years, our desktop computers may well use three or more different kinds of RAM, each chosen for a specific function. For example, a system might use fast, synchronous SRAMs for secondary or tertiary cache, an advanced asynchronous DRAM (e.g., enhanced DRAM, or EDRAM; or extended data out RAM, or EDORAM) for main memory, and RDRAM (Rambus DRAM) or WRAM (Window RAM) on the video card. And yes, you'll be able to plug a PC Card with flash RAM into it, too.

This will be a logical outgrowth of efforts to tune systems for maximum performance. In the old days, if you wanted a faster computer, you used a faster processor running at a higher clock speed. Today, however, designers need to carefully balance every subsystem to prevent bottlenecks. Since different types of RAM have different strengths, it makes engineering sense and, increasingly, economic sense to incorporate several types of memory into a single computer.

As the DRAM market fragments in a shower of new technologies, standards and standards-setting organizations are hardly involved at all. One of the earliest memory standards efforts, IEEE's 1596.4 (called RamLink), is stalled; no products have yet appeared and none are likely to appear for years, says Steven Przybylski, a consultant specializing in DRAM technology. And while synchronous DRAMs are covered by a JEDEC (Joint Electronic Device Engineering Council) standard, says Przybylski, it's incomplete, and synchronous parts from different manufacturers don't always work together. At the same time, however, the proprietary RDRAM technology has become one of the most standardized because its developer, Rambus (Mountain View, CA), has required compatibility from all its licensees.

Therefore, we're not likely to see a single DRAM standard again; instead, we'll have several de facto standards, each optimized for a particular kind of product or application in a classic commodity market. There's still a lot of shaking out going on among these exotic RAM technologies, with competing approaches for

nearly every niche.

We can see the effects of competition in the VRAM area. Until recently, dual-ported VRAMs were as much as twice the price of the equivalent DRAM. That led many analysts to predict that VRAM use would drop over the next several years as less expensive fast RAM technologies appeared. Instead, the price of VRAMs has dropped to the point that they're now competitive with the new DRAMs.

Another important factor driving memory in many directions is the considerable pressure to deliver more memory bandwidth. For the workstation market, RAM and computer designers are concerned about how they'll meet the needs of emerging 300-MHz. 300-SPECmark computer systems. A DRAM technology that's well suited for fast video might not be ideal for main memory, For example, Rambus does well in video applications because it's so good at handling burst data in memories of a few megabytes. Unfortunately, those same characteristics make it a less appropriate choice for the main RAM of a fast, general-purpose computer.

The result is a chicken-and-egg proposition. Everyone agrees we're going to need a lot more bandwidth in main memory quickly. But companies are reluctant to commit to a technology until a clear winner emerges, and that won't happen until one technology starts getting a lot of design wins. So in the end, rather than leaping directly to a new architecture for main memory, systems makers will probably proceed cautiously and incrementally.

In time, the DRAM market will probably come back to standardized, commodity parts available from many sources, and we'll once again buy primarily on price. However, that won't happen overnight. For the next several years, we're all going to have to be careful whenever we buy memory for our systems. Different computers may use very different RAM technologies, and it's inevitable that some systems will require specific parts from specific manufacturers. This isn't a pleasant prospect, but it's the price we'll have to pay for increased memory performance and capacity.

Rick Cook is a freelance writer living in Phoenix, Arizona. He can be reached on the Internet or BIX at recok@bix.com. all be used to increase the speed of the RAM on video boards. EDORAM, CDRAM, SDRAM, and other DRAM enhancements can be substituted on the board quickly and effectively. In addition, the same techniques can enhance dual-ported VRAM, which means we will see CVRAM (cached VRAM), SVRAM (synchronous VRAM), and EDOVRAM. Burst modes will also be increasingly common because video applications move large blocks of memory more often than many regular applications do.

Adding Intelligence to Video

Enhancing VRAM with caching and anticipatory bursting is just the beginning. There are many standard jobs for a video card that can be sped up by adding some extra intelligence to the RAM chip. WRAM technology is a good example of a dual-ported memory that also has added features for graphics. Matrox (Dorval, Quebec, Canada) is one company using WRAM memory in its video boards. (By the way, WRAM was named more for its ability to offer full-motion video than for any ability to speed up a Microsoft Windows operating environment.) The extra intelligence lets the chip do two-color pattern fills and aligned BitBlts at substantially improved speeds. Matrox engineer Dan Wood, responsible for analyzing the performance of memory chips, points out that these extra features let WRAM perform better than VRAM and at a lower cost.

The fast BitBlt is an effect that can be useful for double-buffering fast animation. WRAM can provide this effect only if the start and finish of the Blt are properly aligned. This is because the WRAM achieves the speedup by using its own internal bit bus. The information leaves a memory line and then is written to another line without leaving the chip. This helps accelerate animation, but it won't help with many of the random BitBlts that are needed to open a menu or drag a window across the screen.

Another intriguing solution is 3D RAM, created by Mitsubishi and Sun Microsystems (Mountain View, CA) to improve the performance of 3-D operations. The solution embeds much of the logic for z-buffering into the chip. Normally, a 3-D graphics card will draw a pixel in 3-D by looking up the pixel in the z-buffer, which stores the z coordinate of the last pixel drawn at this location. If the new z coordinate is smaller, then the pixel under consideration is closer to the eye and thus visible. The graphics card will then write this pixel

STATISTICA® (for Windows) A complete data analysis system with thousands of on-screen customizable, presentation-quality graphs fully integrated with all procedures . Comprehensive Windows™ support, OLE (client and server), DDE, customizable Auto Task toolbars, pop-up menus . Multiple data-, results-, and graph-windows with data-graph links . The largest selection of statistics and graphs in a single system; comprehensive implementations of: Exploratory techniques with advanced brushing; multi-way tables with hanners (presentation-quality reports); nonparametrics; distribution fitting; multiple regression; general nonlinear estimation; stepwise logit/probit; general ANCOVA/MANCOVA; stepwise discriminant analysis; log-linear analysis; confirmatory/ exploratory factor analysis; cluster analysis; multidimensional scaling; canonical correlation; item analysis/reliability; survival analysis; a large selection of time series modeling/forecasting techniques; structural equation modeling with Monte Carlo simulations; and much more . On-line Electronic Manual with comprehensive introductions to each procedure and examples - Hypertext-based Stats Advisor expert system - Workbooks with multiple AutoOpen documents (e.g., graphs, reports) Extensive data management facilities (fast spreadsheet of unlimited capacity with long formulas, Drag-and-Drop, AutoFill, Auto-Recalculate, split-screen/variable-speed scrolling, advanced Clipboard support, DDE links, hot links to graphs, relational merge, data verification/cleaning) - Powerful STATISTI-CA BASIC language with matrix operations, full graphics support, and interface to external programs (DLLs) = Batch command language and editable macros, flexible "turn-key" and automation options, customdesigned procedures can be added to floating Auto Task toolbars . All output displayed in Scrollsheets" (dynamic, customizable, presentationquality tables with instant 2D, 3D, and multiple graphs) or word processor-style report editor (of unlimited capacity) that combines text and graphs • Extremely large analysis designs (e.g., correlation matrices up to 32,000x32,000, unlimited ANOVA designs) • Megafile Manager with up to 32,000 variables (8 Mb) per record • Unlimited size of files; extended ("quadruple") precision; unmatched speed . Exchanges data and graphs with other applications via DDE, OLE, or an extensive selection of file import/export facilities (incl. ODBC access to virtually all data bases and mainframe files) . Hundreds of types of graphs, incl. categorized multiple 2D and 3D graphs, ternary 2D/3D graphs, matrix plots, icons, and unique multivariate (e.g., 4D) graphs Facilities to customdesign new graph types and add them permanently to menus or toolbars On-screen graph customization with advanced drawing tools (e.g., scrolling and editing of complex objects in 32x real zoom mode), compound (nested) OLE documents, Multiple-Graph AutoLayout Wizard, templates, special effects, icons, page layout control for slides and print-outs; unmatched speed of graph redraw • Interactive rotation, perspective and cross-sections of 3D displays • Large selection of tools for graphical exploration of data: extensive brushing tools with animation, fitting, smoothing, overlaying, spectral planes, projections, layered compressions, marked subsets Price \$995.

Quick STATISTICA (for Windows) A subset of STATISTICA; comprehensive selection of basic statistics and the full analytic and presentation-quality graphics capabilities of STATISTICA . Price \$495.

STATISTICA/QC - Industrial statistics add-on package (requires STA-TISTICA or Quick STATISTICA for Windows) - The largest selection of industrial statistics in a single package; quality control charts (compatible with real-time data acquisition systems), process capability analysis, R&R, sampling plans, and an extremely comprehensive selection of experimental design (DOE) methods . Flexible tools to customize and automate all analyses and reports (incl. "turn-key" system options, and tools to add custom procedures) • Price \$495.

STATISTICA/Mac (for Macintosh) - Price \$695 (Quick - \$395).


Domestic sh/h \$12 per product; 30-day money back guarantee.


tatSoft


2325 E. 13th St. • Tulsa, OK 74104 • (918) 583-4149 Fax: (918) 583-4376

Overseas Offices: StatSoft of Europe (Hamburg, FRG), ph: 040/ 420047, fax: 040/4811310; StatSoft UK (London), ph: 0462/482822, fax: 0462/482855; StatSoft Pacific (Melbourne, Australia), ph: (03) 663 6580, fax: (03) 663 6117; StatSoft France ph: (1) 45 66 97 00, fax: (1) 45 66 06 51; Available from other Authorized Representatives worldwide: Sweden: AkademiData Scientific ph: 018-210035, fax: 018-210039; Finland: Statcon Dy ph: 24-334678,


Text: 24-333867; Belgium: Texma NewTech phr. 10 61 16 28, fax 10 61 69 57; South Africa: Osins phr. 12-663-4500, fax 12-683-6114; Jepan (Macintosh): Three's Company, Inc., phr. 03-3770-7600, fax 03-3770-7784; Japan (Windows): Design Textnologies, Inc., phr. 03-3667-1110, fax: 03-3669-3110; Italy: Prompt SRL, phr. 49-893-3227, fax: 49-893-2897; Poland: Companion Optogramowanie phr. 12-399680, fax: 12-380791; Talwar: Intelligent integration Corp., phr. 2-759-1791, fax: 2-759-1790. StatSoft, the StatSoft logo, STATISTICA, and Scrollsheet are trademarks of StatSoft, Inc.








o I sam typing thi d, STATISTICA







State of the Art Fast, Smart RAM

back to memory for eventual display. If the z coordinate is greater than this new pixel, the previously drawn pixel would hide it; thus, it is forgotten.

The 3D RAM moves this whole operation onto the memory chip, where it's handled by an on-board ALU. Instead of the video card having to read, think, and write to draw a pixel in 3-D, it just has to write it to the 3D RAM, which decides whether it will be visible.

The ALU on the 3D RAM can also perform several operations, including

raster operations, alpha blending, and comparisons. Mitsubishi estimates that a video card with 3D RAM can render about 1.8 million 100-pixel polygons per second—an amount that they claim is nine times faster than a board equipped with VRAM.

The 3D RAM also makes significant use of cache technology. The basic 3D RAM is a 10-Mb chip with four 2.5-Mb arrays that feed one central ALU, which performs the raster operations on the incoming pixels. There is one L1 cache at

the ALU and four L2 caches at each of the four banks.

Nonvolatile Memory

In several ways, the market for portable computers is limited only by the availability of power for these machines. This distinction is not lost on RAM designers, who are exploring the use of nonvolatile flash RAM and ferroelectric RAM for the main memory of these machines.

Intel (Santa Clara, CA) is a big backer of flash memory, a technology that is similar to EEPROMs. The chips remember their data until they are hit by a larger voltage. Intel announced a 2-MB embedded flashmemory chip in late 1994. It hopes the chip will find acceptance among printer manufacturers who often need local storage for about 8 MB of flexible information on fonts and other display code.

Flash RAM chips have also found homes in portable, digital cameras and other products that need relatively small amounts of data. Some computer manufacturers are using the chips as a flexible BIOS store that you can upgrade if necessary. But greater acceptance is slowed by the relatively high cost of flash RAM.

Other companies are rapidly entering the race to develop ferroelectric RAM chips, which some people are calling the "ultimate memory." Hitachi and Ramtron are joined in one partnership, and Matsushita and Symetrix (Colorado Springs, CO) are working together in another. All are exploring building 256-Kb and 1- and 4-Mb devices for more-widespread use. Some industry observers expect that FRAM may prove to be a replacement for standard DRAM because it does not seem to degrade after a number of write operations. Flash memory wears out, which limits its usefulness to jobs that do not write data that often. If these companies succeed in developing chips that hold a significant density (16-Mb chips have just been announced), then FRAM may start replacing DRAM.

RAM Drives Forward

The RAM industry will continue to expand and flourish in the next decade—in part because it must. RAM is often the slowest part of today's computer systems, so designers will continue to concentrate on developing faster storage. The expanding market also leads to a greater variety of RAM products with different performance characteristics.

The most exotic memory won't just

Why RAM Prices Stay High

Three things used to be certain: death, taxes, and the announcement of a newer, faster, and cheaper computer two days after you buy one. Innovation continues to produce faster CPUs and less expensive hard drives, but the market for memory seems to have stalled. For several years now, 1-MB DRAM SIMMs have cost between \$30 and \$40. What happened to the steady drop in price per megabyte that we became so accustomed to?

The problem isn't in the labs. RAM manufacturers are making 16-, 64-, and 256-Mb chips. Both Hitachi and NEC recently announced success in developing a 1-Gb RAM chip. But those chips won't be available in quantities until the year 2002, and their rivals call these announcements a public relations move. Nevertheless, the research scientists continue to produce a new generation of RAM chips about every three years. But we're not seeing this research success translate into commensurate price drops.

The problem seems to lie with the CPU and software industries, where relentless competition has created an unexpectedly large and continuing demand for RAM. This demand continues to exceed supply, as people clamor for new machines running software that can't function without 8 MB of memory.

Multitasking OSes like OS/2, video games, and multimedia all need as much RAM as possible to function. Newer RISC chips such as the IBM/Apple/Motorola PowerPC add to the demand for more RAM, because the native object code for these RISC chips can be 30 percent to 40 percent larger than the corresponding code for the older 680x0 Macintoshes. One Intel

engineer took credit for the problem, saying that his company's relentless price-cutting and innovation made high-end CPUs with high-end memory requirements available to the masses. As long as the demand continues to soar beyond capacity, the RAM companies keep the price high and pocket the profits.

This high demand slows the adoption of new technology in two ways. First, RAM manufacturers have no need to push the newer 16-, 64-, and 256-Mb chips because they're making enough money on the smaller chips.

Second, systems designers often skimp on memory to bring the price of complete systems down to bargain rates. 64-Mb chips produce 16-MB SIMMs, and their use forces many systems manufacturers to produce computers with a minimum of 32 MB of memory. The lower demand for these large configurations slows demand for the bigger chips, and that, in turn, slows the evolution. At the moment, computer manufacturers are more likely to push 4-MB machines with a lower initial cost, even though people may be frustrated when they try to run new memory-hungry applications on them.

The only solution will be to equalize the supply. The high profits give the industry plenty of money to invest in new fabrication facilities, and there's plenty of evidence that new capacity will emerge. When this happens, increased competition will again drive manufacturers to greater innovation in their efforts to gain market share. Then, and probably only then, will we see prices start dropping again. Maybe we should try to talk Microsoft into investing in a RAM fabrication plant?



IT'S NEW. IT'S MORE THAN TAPE BACKUP.

Protecting critical files is important, but it's not the only reason for buying

The easiest, most reliable a tape system.

Move large files

way to protect and manage from home to office.

your PC's most valuable store important old records on tape. Use it to free

up disk space. Once you think about tape as a data management system, it's

easy to justify an *affordable** HP Colorado T1000.



With new high capacity Travan cartridges and Colorado Backup for Windows¹⁰

one-button automated software, the T1000 is the perfect match for your data. And, since it's from the world leader in tape backup, you know quality and reliability are built in. Call

1-800-451-0907 for more information.



*\$235 List Price. Dealer prices may vary.

© 1995 Colorado Memory Systems, a division of Hewiett-Packard, All rights reserved. Colorado and Jumbo are registered trademarks of Colorado Memory Systems, Windows is a trademark of Microsoft Corporation, TRAVAN is a trademark of 3M. TEBST/031695

State of the Art Fast, Smart RAM

AMD Advanced Micro Devices Suppovale, CA

Sunnyvale, CA (800) 538-8450 (408) 732-2400

Centennial Technologies Billerica, MA (800) 942-0018

(508) 670-0646 fax: (508) 670-9025 Fulitsu Microelectronics, Inc.

San Jose, CA (800) 626-4686 (408) 432-6333 fax: (408) 894-1706

Find

2

Where

Hitachi America, Ltd., Semiconductor & I.C. Division Brisbane, CA (800) 285-1601, ext. 10 (415) 589-8300

Intel Corp. Folsom, CA (800) 548-4725 fax: (916) 356-6110

Matrox Dorval, Quebec, Canada (514) 685-7230 fax: (514) 685-2853 Mitsubishi Electronic Device Group

Sunnyvale, CA (408) 730-5900 fax: (408) 732-9382

M-Systems Fremont, CA (408) 654-5820 fax: (408) 654-9084

Santa Clara, CA (800) 231-6072

(408) 721-5000 fax: (408) 721-7662 NEC Technologies, Inc.

Boxborough, MA (800) 632-4636 (508) 264-8000 fax: (508) 264-8673

Ocean Information Systems, Inc. Covina, CA

(818) 339-8888 fax: (818) 859-7668

Rambus Mountain View, CA (415) 903-3800 fax: (415) 965-1528

Ramtron International Corp. Colorado Springs, CO (800) 545-3726 (719) 481-7000 fax: (719) 488-9095 Raymond Engineering

Middletown, CT (203) 632-1000 fax: (203) 632-4329

Samsung Semiconductor, Inc. San Jose, CA (408) 954-7000 fax: (408) 954-7870

SGS-Thomson Microelectronics, Inc. Lincoln, MA

(617) 259-0300 fax: (617) 259-4420

Sun Microsystems, Inc. Mountain View, CA (800) 821-4643 (800) 821-4642 (CA) (415) 960-1300 fax: (415) 969-9131

Symetrix Corp. Colorado Springs, CO (719) 594-6145 fax: (719) 598-3437 symetrix@usa.net

Toshiba America Electronic Components Irvine, CA

(800) 879-4963

keep data around; it will compute with it as well. The most ambitious plans for memory will continue to emerge from the graphics arena, but it may not be long before high-end workstations begin to exploit smart memory for general purposes. You can now find on desktop machines, for example, many of the innovations that Cray Computer produced in the 1980s. The smart memory that Cray is using for its latest machines may prove to be another approach that wins over machines in the years ahead. Until that happens, the relatively gentle progression of faster and faster types of DRAM will provide systems designers with plenty of options when they integrate memory.

Peter Wayner is a BYTE consulting editor based in Baltimore, Maryland, and the author of Agents Unleashed (AP Professional, 1995). He can be reached on the Internet at pcw@access.digex.com or on BIX as "pwayner." His Web home page is http://access.digex.com:/~pcw/pcwpage.html.

URGENT—YOUR INPUT NEEDED

On: CPUS

Dear Reader:

To improve BYTE's coverage of technology in the State of the Art section, we'd like to get your feedback about what topics, areas, and products we should be considering, and in what ways. Later this year, we plan to look at CPUs—the latest developments in RISC processors, Pentium and P6 CPUs from Intel, and PowerPC chips from IBM/Apple/Motorola. We'll examine where CPU architectures are heading; what effects the move to smaller fabrication technologies will have on chip design, yield, and costs; what these trends will mean to you; and how the chips will work in your future systems.

But we'd like you to tell us what you want to see us report on and analyze. Are you interested in support chip sets, low-voltage processors, or increased on-chip caches, for example? We want to find out about concerns that we may not fully appreciate and just what aspect of CPUs you're interested in. Also, we'd appreciate your help in identifying the people we should be talking to—users, vendors, researchers—you tell us.

To let us know what you think, please use the following as a template to send us, via E-mail, an ASCII text file with your comments. Please be sure to include the <FIELDNAMES> with their angle brackets, followed by your information and comments. And thanks very much for your help.

Please E-mail the completed form to: surveys@bix.com

<TOPIC>

<LASTNAME>

<FIRSTNAME>
Jennifer

Technical Assistance Specialist

<TITLE>

<COMPANY>
United Systems

<PHONE> 800-555-1234

<EMAIL>
jsmithe@host.domain


<COMMENTS>

This is where your comments go. Be as brief or as long as you want. Tell us what you think, what you need, what you want to know more about. Tell us what you're doing. Tell us who we should be talking to.

MORE MEMORY IN LESS SPACE

Innovative packaging techniques squeeze more RAM into tighter spaces

RICK COOK



nless you're trying to upgrade a laptop, you don't generally think about how the memory for computers is physically packaged. But computer makers care a great deal about memory packaging. Computers, especially notebooks, are shrinking at the same time that memory requirements are rapidly escalating. Memory-hogging OSes like Windows NT and OS/2 are running memory-hungry graphics-oriented applications.

The market-research firm Dataquest (San Jose, CA) says the amount of DRAM found in the average business computer has grown from 4 MB in 1993 to 16 MB today. It will jump to 24 MB by 1997. Dataquest found that computer makers, trying to hold down prices in a fiercely competitive market, are shipping most systems with just enough memory for the basics—typically 8 MB. But customers know that isn't enough, and they're doubling the memory—often before leaving the store.

Dataquest memory analyst Ron Bohn says, "Companies try to ship with as little memory as they can without losing sales and while retaining quality." Herein lies the second part of the memory-packaging challenge: not just to cram more memory into smaller boxes but to do it in a way that allows users to add even more memory later on.

Skyscraper RAM

In early personal computers, RAM came in the form of DIP (dual in-line pin) chips—those little black centipedes with the silvery legs so beloved of experimenters and kit builders—that were soldered or socketed onto the motherboard. Later on, these chips were installed vertically onto small circuit boards that took up less space. While there's still plenty of life left in the SIMM format and its emerging successor, DIMM (dual in-line memory module), there's still real estate above those packages waiting to be grabbed. In an exciting

Service of the servic

State of the Art More Memory in Less Space

shift, several companies have announced memory-packaging technologies that take advantage of this third dimension by stacking memory chips closely on top of one another.

Among the companies that have announced 3-D memory modules are Cubic Memory, Staktek, and Dense-Pac Microsystems. A number of other companies, including Intel, Hitachi, and Texas Instruments, reportedly have development projects under way for 3-D modules. (Let's clarify one point of terminology: 3-D has two distinctly different meanings in relation to RAM chips. The various technologies for stacking or layering wafers are generally called 3-D, referring to a physical construction. Matsushita, however, uses the name 3D RAM for its specialized graphics-oriented memory chip, referring to what it's used for. The 3-D memory modules discussed in this article are 3-D in form, not function.)

Memory stacking has been tried before, albeit more crudely, by several companies that piggybacked several DIP chips into a single package. But all those early attempts, such as the 512-Kb modules on the first IBM ATs, used ICs that were already packaged. More recently, some companies have made special 3-D memory modules for such low-volume, high-cost applications as defense and aerospace. The newest generation of memory modules puts naked chips-bare silicon-into special packages. The thinness of the silicon wafers means you can cram more of them together, and maybe even at a competitive price.

The packaging potential of these new techniques is awesome. Staktek's Ribcage Stakpak DRAM module gets 16 MB into a volume of one-eighth of a cubic inch. Cubic Memory does even better, packing up to 2 GB of DRAM per cubic



inch in its 3-D modules. That kind of packaging density promises even smaller systems and even larger memory capacities in workstations and servers.

Ingenious as they are, 3-D memory modules pose some special problems for their creators. For example, to make the most of them, you need more address lines from the module to the motherboard than a standard SIMM or DIMM provides. That means a nonstandard motherboard layout, which in turn implies proprietary packaging. The small computer market has shown a considerable aversion to proprietary hardware, but the advantages of 3-D modules are so compelling that many computer makers have announced plans to use them.

While heat is a definite problem with logic chips (remember the first 5-V Pentiums that introduced us to the fan-on-achip?), it's a lot easier to handle in DRAM. Nonetheless, 3-D module makers take care to ensure adequate cooling via ventilation ribs and by using signal leads to conduct away heat.

Staktek has been building 3-D memory modules since 1992 and has patented several packaging techniques. Staktek's products use either standard memory dies or TSOPs (thin small outline packages) in thin plastic-leaded packages with an external metal mounting structure that provides both heat and signal transfer. To make clear that its technology is strictly a matter of packaging, the company's Stakpak products are available with flash RAM, up to 256 MB per module; DRAM, up to 128 MB; or SRAM (static RAM), up to 32 MB.

Cubic Memory is one of the most active companies making 3-D memory modules. Its process stacks DRAM chips that have gold wires running to the wafer edges. They are then interconnected by a conductive silver epoxy (see the figure "Wafer Stacking" on page 200). Cubic Memory is building 64-MB SIMMs for the 100-MHz Pentium-based laptop from Tadpole (Austin, TX), as well as other modules for Tadpole's SparcBook 3. For the Pentium model, Tadpole wanted to fit 128 MB of memory in just two SIMM slots. Panasonic is another Cubic Memory customer, offering a 32-MB DRAM PC Card for its notebook computers.

Clearly, 3-D modules will carry a price premium for some time to come. Cubic Memory claims that its devices cost only slightly more than conventional packagThis 128-MB 3-D module from Cubic Memory is surrounded by the 64 separate 16-Mb DRAM chips it replaces.

ing—\$44 to \$56 per megabyte, compared to \$35 to \$45 per megabyte for andard SIMMs, according to its presi-

standard SIMMs, according to its president Chet Brown—but the difference is real and will matter to most computer makers. That extra cost will probably limit the use of 3-D modules to situations where space is especially tight and memory requirements are particularly high. It's no accident that Tadpole is using the modules in high-performance notebooks.

However, not everyone thinks that 3-D modules need be costly. Staktek recently introduced a lower-cost package it calls the Uniframe Stakpak. According to James Cady, executive vice president for engineering, the Uniframe DRAM modules are available in OEM production volumes for under \$35 per megabyte now, and they should be under \$25 by the end of the year.

At the high end of the computing spectrum, Cray Research is shipping its T90 supercomputers with SRAM stacks. Forty 4-Mb SRAM chips are soldered between two printed circuit boards to provide a dense stack. Each memory module includes 16 stacks. Such dense packaging lowers the distance that signals must travel and stabilizes the capacitance of the signal lines. An expensive technology, it's well suited to supercomputer applications—computation-intensive operations that need massive amounts of memory. (For more on supercomputing, see "The Grand Challenges," February BYTE.)

The Old Reliables

When DIP chips lost out in the memory wars long ago, they were replaced first by the SIPP (single in-line pin package) and later by the SIMM, a module designed for DRAM in computers (and other applications) that is today's de facto standard for desktop computers. Essentially, a SIMM (and also a DIMM) is a small printed circuit board holding several DRAMs that plugs into a socket on the motherboard.

Perhaps the most obvious thing about SIMMs is that they stand sideways—perpendicular to the motherboard. This has two clear advantages: It saves motherboard real estate and permits better air circulation around the chips. Also, the modules are easier to handle than memory chips. Thus, nearly anyone can install them.

Hit the Road.

without ever leaving the information superhighway.

Win a luxurious 1996
Mitsubishi Galant LS
including power driver's
seat, an 8-speaker
Mitsubishi/Infinity
audio system, and the
exclusive Mitsubishi
HomeLink™ system.
Plus you get all the
other tools and toys
you need on the road:



Laptop Notebook Computer:

Take all your power apps and

mega graphics/multimedia files out on the road with this high-performance PC laptop.



Mobile Assistant:

Wireless communications and


route guidance system for the mobile office from Solid Computer Group.



Cellular Phone:

Compact, easyto-use, flip-style, state-of-the-art

cellular phone for the car, the sidewalk, the boardwalk, the boardroom, etc.





CompuServe Information Service:

One-year corporate subscription including up to

\$250 per month in user charges.

SWEEPSTAKES RULES

The contest is open only to U.S. residents who are licensed drivers, 18 years of age or older. No purchase necessary, Entrants should fill out their daytime tolophono number as indicated on the official entry form. You may obtain an entry form by sending a self-addressed envelope to BYTE Mobile Office of the '90s Sweepstakes, One Phoenix Mill Lane, Peterborough, NH 03458 by November 15, 1995 or fax to (603) 924-2535. Limit: one entry per person.

Entries must be received by mail or fax on or before November 15, 1995, or submitted in person at BYTE's Booth at Comdex/Fall, Las Vegas, from November 13 to November 15. The finalist will be determined in a random drawing to take place at BYTE's Comdex Booth #2654 at 3:00 PM on November 16, 1995. The winner will be contacted by telephone following the drawing and announced in the January 1996 issue of BYTE. Personal contact with the individual specified on the entry card must be made for the finalist to be declared the winner. If the winner cannot be contacted within 15 days of the drawing, then the unclaimed prize will be awarded to an atternate winner selected at random.

The winner shall be required to sign an affidavit of eligibility and a liability/publicity release which releases McGraw-Hill, Inc., from liability in connection with the winner's use the prize, and permitting McGraw-Hill to use the winner's name and likeness to promote the contest where permitted by law.

The odds of winning depend on the total number of entnes. McGraw-Hill, Inc., Mrtsubishi Motors, and their respective advertising egencies, subsidiaries, employees and employees 'families are not eligible to participate in this contest. McGraw-Hill, Inc. is not responsible for lost, late, or misdirected mail or ineligible entries. All Federal, State and/or local rules and regulations apply. Void where prohib-

One prize will be awarded: a 1996 Mitsubishi Galant LS (MSRP: \$22,979), plus various mobile computing tools described above; total prize value; \$33,924, Vehicle specifications, including color, will be determined by Mitsubishi Motors. Standard manufacturers' warranties will be provided. Vehicle will be delivered to Mitsubishi dealer closest to winner's locale. Winner is responsible for registering, licensing, and insuring the vehicle. The prize is not redeemable for cash, nor is substitution of the prize by the winner allowed. The winner is responsible for any and all taxes associated with the acceptance of the prize. BYTE reserves the right to substitute a comparable prize upon unavailability. For the name of the winner, send a self-addressed, stamped envelope after November 16, 1995 to Marketing Dept., Mobile Office of the '90's Winners, BYTE Magazine, One Phoenix Mill Lane, Peterborough, NH 03458.

PUT YOUR PEDAL TO THE METAL! (Enter today!)

Winner to be announced at the BYTE booth #2654 at COMDEX/Fall.

NAME:		
TITLE:		
COMPANY:		
ADDRESS:		
CITY:		
STATE:	ZIP CODE:	
PHONE:	FAX:	

Fax your entry to 603-924-2535 or mail to: BYTE, One Phoenix Mill Lane, Peterborough, NH 03458

State of the Art More Memory in Less Space

SIMMs come in two flavors: 30- and 72-pin. The 30-pin SIMMs use 8-bit DRAMs, and the 72-pin SIMMs use 16- or 32-bit parts. Generally, it takes four 8-bit SIMMs to give the same capacity as one 32-bit SIMM. There is also the matter of organization. SIMMs are usually set up to read

8, 9, 32, or 36 bits at a time. The 9- and 36-bit SIMMs include an extra bit per byte for parity checking. If your computer expects parity memory and you add nonparity SIMMs, the machine won't recognize the extra memory.

In practice, this is less of a problem than it appears. While there is a rampant proliferation of part numbers, there are relatively few kinds of SIMMs out there. According to David Sun, vice president of engineering at Kingston Technology (Fountain Valley, CA), the many part numbers actually simplify the situation for users, letting them order memory by computer make and model rather than having to know the specifications of the memory modules.

One result of the wide adoption of SIMMs is that add-on memory boards. once quite popular, are much less common today. Kingston, one of the biggest aftermarket memory suppliers, lists over 1000 memory modules but only 107 memory boards in its catalog, and just 13 memory-chip upgrades for computers.

Of course, the downside to memory modules is that you are limited to whatever kind of memory modules the manufacturer decided to support in whatever quantity the company decided to support them. An upgrader also must make sure he or she has the correct module for the system.

DIMMs Brighten

SIMMs are now giving way to DIMMs, which can pack twice as much memory into the same space. They achieve this by mounting DRAMs on both sides of the module

Wafer Stacking An eight-layer stack of DRAM wafers holds 64 MB and is 0.08 inch thick Vertical connections Circuit board 0.01-inch thick Here's how Cubic Memory layers DRAM wafers into a high-density silicon stack.

> and by using two sets of contacts, one on each side of the module board (SIMMs use only one set).

> According to In-Stat, a Scottsdale, Arizona, semiconductor consulting firm, SIMMs should account for 82 percent of the small computer memory market this year. By 1998, however, their market share will drop to 39 percent, and most of the rest will be DIMMs.

> DIMMs are more expensive than SIMMs of the same speed and capacity. but manufacturers and analysts expect this to change as DIMM volumes overtake SIMMs. In-Stat analyst Connie Batchelder says that in the long run costs will be the same.

Is 3-D Memory in Your Future?

For all its technological ingenuity, not everyone is convinced that 3-D packaging is the way to go, at least not in the short term. Kingston's Sun says that 3-D modules are basically a way of getting a half-generation advance on new memory

chips-say, from the current 16-Mb chips to the equivalent of 64-Mb chips. The problem that 3-D modules solve, Sun continues, is only temporary. When the higher-capacity part becomes more widely available, it automatically takes over from the inherently more expensive 3-D module.

Sun says that Kingston looked into developing its own 3-D module a few years ago, wanting to create a 16-MB SIMM equivalent out of 4-MB chips. In addition to the extra cost and limited life span, he says that a major deterrent was that Kingston

would have to buy memory wafers from one of the major DRAM fabri-

> cators. But once the higher-capacity chips be-

> > came widely available, the DRAM supplier would have no economic incen-

tive to cut into the sales of regular DRAM by selling the smaller wafer.

Still. Sun admits that 3-D modules have their place in systems where space is extremely tight and the manufacturer must pack in a lot of memory. He suggests that 3-D modules might make good sense in a PDA (personal digital assistant) or a graphics workstation doing high-end animation work.

But they may see even broader use in the future. The primary argument against 3-D modules is that the next generation of DRAMs will be along fairly soon, which will quadruple capacity per chip at the same or lower cost per megabit. This is based on historical trends, but this extrapolation is no longer a sure thing. And if the progression does break down, alternative solutions such as 3-D modules could become the new standard for memory modules. (For more on why the market hasn't yet seen higher-capacity DRAMs-and may not see them for a while-see the text box "Why RAM Prices Stay High" in the article "Fast, Smart RAM" on page 194.)

More in Less

Although we can't be sure what technology they will use, we can be absolutely certain that computer makers and users will pack more and more memory into computers at an increasing pace. What is ample at one point in time turns out to be unacceptable in a year or two.

Today's notebook computers can already use amounts of RAM that were unheard of in mainframes even 20 years ago, and they need every bit of the RAM they have to support modern applications and OSes. There's no reason to think that our memory requirements will diminish in the foreseeable future, so it looks like we're each going to need a lot more RAM in our computers just to see the century out.

Rick Cook is a freelance writer who lives in Phoenix, Arizona, He can be reached on the Internet or BIX at rcook@bix.com.

Cray Research

Eagan, MN (800) 284-2729 (612) 683-7100 fax: (612) 683-7199

Cubic Memory

Find

Where to

Scotts Valley, CA (408) 438-1887 fax: (408) 438-1890

Dense-Pac Microsystems, Inc. Garden Grove, CA

(714) 898-0007 fax: (714) 897-1772


Hitachi America, Ltd.

Semiconductor and IC Division Brisbane, CA (800) 285-1601 (415) 589-8300 fax: (415) 583-4207

Staktek Corp.

Austin, TX (512) 454-9531 fax: (512) 454-9409







A Universal Desktop for Unix

The Common Desktop Environment grew out of fear of Windows NT's encroachment into the workstation enterprise market.

page 200DM 3





Tickle Makes Developer Smile

Tcl provides a combination of extensibility, portability, easy embedding in C code, and simplified implementation of TCP/IP client/server communications that is hard for a developer to resist.

page 200DM 11

What's New

Machine 4.0 offers the power of Unix to the Mac; UnixWare 2.0 brings full-featured Unix to x86; Eye2eye provides access to Unix from Unix and Windows; the Sweep virus scanner brings security to Unix networks; and the hand-held DSP-100 provides accurate, fast testing of LAN cabling.

page 200DM 23



Intergraph's full line of Windows NT and UNIX integration products makes it easy to cross platforms. Streamline client/ server networks. And simplify every system manager's life.

PC-NFS for Windows NT.

Lets Windows NT users access files and resources on UNIX servers and workstations. And connect to corporate databases and mail systems. From the familiar Windows interface.

DiskShare for Windows

NT. Lets UNIX NFS users access files and directories on Windows NT servers and workstations. While taking advantage of UNIX

Call 1-800-291-9909 For Free Evaluation CD.

utilities to manage files on Windows NT seats. With Windows point-and-click interface.

eXalt for Windows NT.

Lets eXalt users move quickly between X-based applications and Windows NT. Without cumbersome text-file editing. Using a Microsoft Windows, Open Look, OSF/Motif or twm look-and-feel.

Batch Services for

Windows NT. Lets Windows NT users schedule, manage and reschedule non-interactive jobs. Locally or networkwide. With the Windows interface.

Total Support, 100% Satisfaction Guaranteed.

Like all Intergraph software, these integration applications come with the industry's top-ranked support. And a 30-day, 100% satisfaction guarantee. Call 1-800-291-9909 for your nearest reseller.



minimum of fuss."-

Open Systems Today 11/28/94



A Universal Desktop for Unix

DOUG TAMASANIS

he CDE (Common Desktop Environment) for Unix is here. The question is, who cares? Hewlett-Packard, Sun, IBM, and Novell care. They have invested two years and tens of millions of dollars in the development of CDE in the hope that the corporate world cares, too, and will buy into it. But is it too little too late?

The overall goal of CDE is to deliver a desktop interface to end users, software developers, and system administrators who want a common graphical user environment across multiple vendor platforms. According to John Sontag, chief architect of HP-UX for Hewlett-Packard, "CDE development was driven by user and developer demand." For end users, CDE presents an easy-to-use, intuitive environment offering the power of the Unix OS while hiding its complexities. For software developers, common services (such as the on-line help system) and a consistent set of industry-standard APIs across multiple hardware and software platforms make it easier to port to different flavors of Unix. For information systems professionals and administrators, CDE reduces the overhead of system administration in a heterogeneous environment.

CDE represents the first viable attempt by major Unix workstation manufacturers to provide a cross-platform windowing environment. The idea that CDE can gain Unix a significant foot-

hold in a desktop market dominated by Apple and Microsoft is unrealistic. What it can do is prevent Windows NT from eating into the enterprise market currently dominated by Unix.

Why CDE?

What motivated this group of companies to join forces on a project requiring such enormous expense and engineering time? Most



CDE represents the first viable attempt by major Unix workstation vendors to provide a cross-platform windowing environment

likely, they were driven together out of fear—fear of software giant Microsoft's future encroachment into the workstation enterprise market with the forever-promised, fully functional Windows NT.


The enterprise computing market (henceforth referred to as workstation) is one of the fastest growing portions of both the hardware and the software markets. Mainframe hardware and software sales are migrating to this market at an ever-accelerating rate. And there's more business here than you may think: Last year, IBM's main-

frame software sales alone were roughly twice the gross sales of Microsoft. With such lucrative market potential, it is well worth the effort of Microsoft to try to capture a portion of this market, and it has already established a beachhead with NT.

Microsoft has proven it can turn hardware into a commodity and pull profit margins into software sales. In the past, workstation hardware vendors protected high profit margins with

PAUL WATSON / THREE IN A BOX & 1995

Feature



Unix vendors currently control the high-end server market, and Novell is well positioned at the workgroup level. NT will enter the market at the departmental level, branching out toward the enterprise and divisional levels.

high-performance CPUs, proprietary Unix environments, and associated software. The threat of a PC workstation running a common enterprise OS like Windows NT could shatter the workstation market—a market already fragmented by a myriad of Unix flavors and hardware platforms.

According to a recent Summit Strategies report, Unix vendors have a threeyear window in which to establish a defensive position in the high-end server market. (See the figure "Encroachment of Windows NT into the High-End Server Market.") Some think that Unix OSes are better for application development because NT doesn't yet provide the full capabilities of Unix. As Britt Johnston, database development manager at Progress Software, sees it, "A year or two from now, people may have NT on their system as their principal operating system, but for now, it is still Unix."

Unix currently controls the mission-critical enterprise market. Unix is a true multitasking and multiuser OS, with over 25 years of history. Many organizations base mission-critical business processes on Unix applications. System administrators are wary of turning these processes over to software that has not yet matured. Says Oran Thomas, chief developer of CDE at TriTeal, "Today Unix is the only viable operating system choice for mission-critical applications in the client/server marketplace. Although Windows NT has potential and may indeed be the future, it still needs to prove itself."

The problem with Unix is that the tech-

nical world was the driving force behind its evolution, resulting in shortcomings in the delivery of a common, easy-to-use interface. So as Windows NT takes aim at the most vulnerable aspect of Unix, workstation vendors finally teamed up to deliver a common desktop that works on all their platforms.

In March 1993, HP, Sun, IBM, and Novell announced the signing of a JDA (joint development agreement) to create a sample implementation of a CDE. They united existing technologies from participating vendors into a homogeneous desktop. The result is an application layer that contains a consistent set of APIs. CDE incorporates the workspace manager and user interface of HP's VUE (Visual User Environment) with features from IBM's CUA (Common User Access) model, Sun's desktop productivity tools (mailer and calendar manager), and Novell's UnixWare Client components. The desktop bundles together the X11R5 server and windowing system, the OSF Motif widget set and window manager, and Sun's ToolTalk interapplication communication layer.

The JDA called for CDE to consist of 80 percent existing technology and 20 percent new development and integration. An example of existing technology incorporated into CDE is the user interface, the bulk of which came directly from HP-VUE, a product that has been shipping on workstations for over five years. An example of the development of new technology for CDE is the integration of the

various application components using the ToolTalk messaging system. Also, Sun's OpenLook MailTool and Calendar Manager required redevelopment under Motif. By using existing technology, the JDA members targeted delivery of CDE at one year from the JDA. Now, two years later, the release of CDE is a reality.

CDE: What It Is

Like its parent HP-VUE and most other Unix desktop environments, CDE is large, with over 2 million lines of code consuming 100 MB of disk space. It looks and feels much like HP-VUE, providing desktop management, session management, file management, application management, productivity tools, and application development tools. CDE also makes extensive provisions for integrating applications into the desktop.

CDE's extended Motif window manager includes a toolbar and virtual workspaces (see the screen shot). The toolbar, or front panel, holds icons for commonly accessed functions or applications, such as the mailer, file manager, printer, and trash can. The front panel has slide-up menus (the equivalent of pull-down menus but in an upward direction), allowing quick access to application launch icons. The front panel is completely configurable by the user or system administrator. The icons in the front panel fully support drag-and-drop operations.

A configurable number of virtual workspaces lets you organize work on separate screens. Configurable workspaces eliminate the need to search the desktop for open applications when you are working in a multiwindowed environment. At the click of a button, you can switch between workspaces and resume all applications with window sizes and locations in the same position as when you left the workspace.

From the CDE desktop, you can record the state of your session and resume that session at a later time. CDE stores information about each running application when you log out, including the applications contained in each workspace, their size and position on the screen, and whether they have been iconified. The system uses this information when you log in again, restoring the session to its previous state. CDE also supports a home session, letting you return to the same initial state each time you log in.

From the applications manager, you can group applications into toolboxes. These toolboxes form hierarchical groups of related applications much like program groups in Microsoft Windows. A system administrator can set up these groupings

Finally, a terminal server that's terminally easy.

If you've ever been frustrated by the shortcomings of terminal servers, you'll appreciate the superior ease and cost/performance_ratio of our PortServer."

Most of the credit
goes to PortServer's
exclusive RealPort*soft
ware. RealPort emulates
real TTY, so users don't have
to use Rlogin or telnet to login.

Install RealPort on a host, and it simplifies system administra-

tion by making serial ports on the

tion by making senal ports on the

PortServer appear to the user to be local.

RealPort also reduces host CPU overhead on any TCP/IP-based system by multiplexing several terminal or printer sessions onto a single TCP/IP

connection. This uses only a fraction of the host

Prom =UJIIII 15 KX

PortServer does a great job of emulating real TTY with our easy to install RealPort software. buffering resources and sends fewer packets across the Ethernet, reducing network traffic and host CPU utilization by as much as 30%.

PortServer itself seamlessly integrates terminals, PCs, modems and printers onto an Ethernet network. PortServer comes with either 8 or 16 ports;

RealPort software is available for

AIX, SCO UNIX, Solaris, UNIX SVR4, and

Novell' NetWare' Connect."


Digi offers a 30 day trial, a 5-year warranty and industry-leading technical support. For more information, plus a free "Pocket Guide to Terminal Servers," call today.



1-800-551-4794

U.S.A. (612) 943-9020 · European Office TEL +49 (0) 221 92052 0 · DigiBoard-Asia Pte Ltd TEL +65 732 1318 © Digi International. All rights reserved. All brand names and product names are trademarks or registered trademarks of their respective holders. GSA: GS00K93AGS6365 PS01

Feature



The CDE (Common Desktop Environment) looks and feels like HP-VUE, with its toolbar, pop-up menus, and virtual workspace manager. The Motif version of Sun's desktop productivity tools (mailer and calendar) is also shown.

for all users, but you can configure additional custom applications as well. CDE features several default toolboxes, including Desktop Tools for easy access to CDE clients, X Window System applications, and other Unix system functions. Third-party applications can create additional toolboxes upon installation.

The file manager uses colorful icons to help users distinguish between data files, source code files, executables, images, and documents. You can move frequently used files, such as third-party applications, from the file manager directly onto the desktop, where you can easily access them.

A powerful feature of the CDE lies in its comprehensive Data Typing and Action Database functions. Data Typing refers to the ability to identify a file as belonging to a class. The Action Database provides a means whereby specific actions apply to a known data type. The method of identifying a file can be as simple as using a file extension (e.g., .doc or .txt for a text file, or .c or .h for a source file), examining the first few lines of data in the file for a certain substring of characters, or running an OS command (such as the Unix file command). From the file manager, icon style identifies file association. Double-clicking on an envelope icon always launches the mail program with the specified file loaded regardless of the file type or exension. Data Typing and the Action Database are fully configurable, so you can customize your desktop for specific work

activities. CDE provides a number of predefined data types to simplify this process. You can select from preexisting icons, or you can create new icons with the provided icon editor.

Talking Tools

CDE bundles rich communications tools. The MailTool lets you compose, view, and manage E-mail through a GUI. It supports file attachments and communications with other clients through the optional ToolTalk messaging system. With the Calendar Manager, you can schedule and view appointments, create calendars, and send appointments to others via the MailTool using drag-and-drop.

ToolTalk provides a high-level communications mechanism by which the different CDE applications can pass complex messages. Upon initialization, each application that will participate in a session must register with ToolTalk. During registration, the application indicates what type of messages it needs to receive. When another application sends a message, perhaps about a file to be deleted, ToolTalk notifies all applications that have registered interest in file deletions.

Any client developer can make public a ToolTalk message that the client sends or receives. In this way, other clients may tightly interact with it. The clients defined by CDE (i.e., MailTool, calendar manager, and so forth) provide an initial set of public messages. Today, there is no de-

fined repository for public CDE ToolTalk messages from ISVs (independent software vendors).

Application Development and Integration

CDE includes the tools needed by application developers to create CDE-compliant applications. This bundle includes the X, Motif, Help, Printing, and ToolTalk APIs. With CDE's application builder, developers can construct their application's user interfaces interactively. The developer manipulates Motif and CDE widgets graphically to create the interface and then later fills in the application's functionality using the X toolkit's callback mechanism. This application builder is particularly useful for user interface prototyping but may be inadequate for full implementations of complex applications.

In addition, a windowing version of the Korn shell, dtksh, provides a mechanism for creating Unix shell scripts with GUIs. This lets you quickly write simple, easy-to-maintain shell scripts with sophisticated user interfaces. dtksh is simply the Korn shell with built-ins for all the X toolkit, Motif, and CDE functions.

The CDE is a collection of different applications that work together on a unified interface. For example, pushing a button on the front panel of the desktop may activate a text editor so you can produce a document that you later drag from the file manager onto the printer icon or perhaps mail to another user. Although this simple example uses four different applications and two types of data exchange, to you it is a simple and intuitive sequence of actions. CDE provides developers and administrators varying levels of application integration within the desktop, depending on the overall goal of the integration.

The first level of integration requires only that an application be installed under the Application Manager folder on the desktop. This allows launching of the application by double-clicking on the application's action or data file icons. For most applications, this level of CDE integration will not require code modifications—only slight modification of installation scripts and the creation of some new files.

The second level of integration encompasses the first-level integration but also requires that the application comply with the OSF/Motif 1.2 Style Guide and the CDE Certification Checklist, a document listing the requirements for CDE application-level certification. Second-level integration includes the option to support non-English environments with the use of an internationalization programming guide.

The highest level of integration includes

the first two levels and additionally requires integration with the CDE desktop services, such as printing, drag-and-drop, and on-line help. Fully integrated applications provide the transparent manipulation and access to applications expected in a desktop environment. Application in-

TriTeal Corp.

Carlsbad, CA

(800) 755-8325

fax: (619) 930-2081

tegration at this level is complex, requiring you to learn a new API for every service your application needs. Even the drag-and-drop function taken from OSF/Motif has a

new API. Typically, the simpler things get for users, the more complicated they get for developers.

Put Up or Shut Up

The marketplace will now get its chance to judge CDE on its promise to deliver the functionality and conformity of a universal Unix desktop. By the end of 1995, CDE will be available on SunOS 4.1.x, Sun Solaris 2.x, HP-UX 9.x and 10.x, IBM AIX 3.2.5 and 4.1.x, SGI IRIX 5.x, AT&T, SNI, and DEC OSF platforms, and Tektronix, Unisys, HP, and NCD X terminals. According to Hewlett-Packard's John Sontag, "Over the next 12 to 18 months, you

will see the emergence of CDE platforms, while in 1996 and 1997, you will see the release of native CDE applications. Developers will not produce versions specifically for CDE but will wait for their next development cycle."

As with any new product, deficiencies

exist in CDE 1.0. Some of these will be quickly evident, including limited support of standard formats in the help manager, meager functionality provided by the text ed-

itor, and lack of initial ISV integration and support. In addition, significant functionality remains undefined by CDE 1.0: fax, Internet access, device management, system administration, videoconferencing, PC interoperability, and desktop client security. Individual Unix workstation vendors will provide much of this functionality in a proprietary manner, while motivated ISVs will deliver a more homogeneous solution. At the very least, unless there is some horrific problem in the shipping version of CDE, it will achieve its purpose to unify the Unix desktop.

Now that CDE is a reality, the debate shifts to whether or not CDE delivers a

truly common desktop across Unix platforms and whether or not the desktop functionality and APIs provided by CDE are superior to those of Windows NT. The core technology provided by CDE will stay substantially generic across the various vendors' CDE implementations. Vendors will make minor modifications to support specific customer bases or proprietary software products.

After that, you can throw out the word common. All Unix workstation hardware vendors will be bundling and integrating differentiating technology into their desktops. A significant portion of this technology will be proprietary in nature. Vendors will do this to protect their percentage of the workstation enterprise market. CDE defines a relatively limited set of desktop applications, leaving significant areas in which vendors can add value and gain a competitive edge. Windows NT, on the other hand, will provide a significantly broader collection of desktop capabilities with a higher degree of integration.

By providing differentiating value added, the Unix workstation vendors may damage the validity of CDE as a unifying

E-Mail Made E-as



Now PC users on a Unix network can have a Windows-style, Windows-fast & easy interface to Internet and Unix email.

Just use EMBLA and you'll see email couldn't be easier. It's Windows "drag & drop" simple

- Remote users save on your phone bill! You can select and download only the mail you need.
- Supports MIME, IMAP & standard Windows socket API.

EMBLA is available now for just \$99. Call one of the resellers listed

below to order. For more information, contact ICL ProSystems at:

marcomms@pro.icl.se http://www.pro.icl.se





800-755-8649 sales@unldirect.com

800-617-SOFT http://www.software.net

software.net J.P. Brown(In Canada) 416-494-0472 davef%jpbrown@uunet.ca

Feature

desktop. Sound confusing? It is. The Unix workstation vendors spend millions of dollars developing a uniform desktop and Unix API specification, only to undermine the entire process by differentiating and providing proprietary capability.

In reality, it makes perfect business sense. If there were no differentiating capabilities within the workstation market. the hardware would become a commodity. and the profit margins would disappear. Since none of the Unix workstation vendors have demonstrated an ability to become a software company, they must protect the margins in their hardware.

It appears that the goals of COSE and CDE were twofold. The first consideration was to project an image of ultimate uniformity and harmony throughout the Unix workstation community so as to remove any leverage Microsoft might have in the enterprise marketplace by claiming Unix to be fragmented and isolated. The second and maybe more overriding consideration was to find the minimal level of uniformity required to achieve this while leaving room for the differentiation needed to protect profit margins.

What the Enterprise Really Needs

How will the true promise of CDE be realized by enterprise customers today? One avenue will be through software vendors whose main goal is to deliver a homogeneous CDE implementation across the heterogeneous Unix workstation marketplace. This implementation would stress commonality in function, configuration, and installation. Rather than OS and hardware release schedules and proprietary technology intended to protect hardware margins, enterprise customer needs would define its content.

One company working in this direction is TriTeal of Carlsbad, California. which claims that its TED (TriTeal Enterprise Desktop) will deliver a universal, generic version of CDE throughout the Unix enterprise. TED even comes with bundled technology that adds value to basic CDE. This includes clients such as fax, videoconferencing. Internet access, and PC interoperability-all of which will be common across platforms. With TED, TriTeal has tried to produce a true common desktop environment-networked, multiuser, multitasking, and interoperable-that still leaves room for the enterprise software.

It is unfortunate that the workstation vendors couldn't have agreed on CDE years ago when there was still a possibility that Unix could become a significant presence on the desktop. There is a possibility for limited success if enough application developers integrate their applications into CDE. There are rewards for developers who port to CDE, namely, fully integrated applications and uniform service applications on all supported platforms. The latter will let developers use fewer lines of code to extend applications. "CDE is a huge win for smaller workstation vendors who can look like the bigger companies without incurring the high cost of GUI development," says Britt Johnston of Progress Software.

The real winners could be the users, who would have a single desktop environment and consistent application interfaces across workstation platforms. The idea is valid; unfortunately, the product may be too late.

Doug Tamasanis is a BYTE senior technical editor with B.S. and M.S. degrees in radiation physics and an M.S. degree in systems engineering. You can reach him on the Internet at dtam@bix.com or on BIX as "dtam."



Add XRT widgets to your CDE/Motif development environment and start building better user interfaces faster and easier than ever before.

XRT/graph displays data in virtually any type of 2-D graph or chart. It has hundreds of features including time-axis, lightning-fast updates, and a graph-builder tool.


XRT/3d displays 3-D data in surface plots, bars and contour graphs.

XRT/table is ideal for displaying and editing tabular information including multi-font text and images, and even other widgets in cells.

All XRT widgets are highly-interactive, generate PostScript output, and use the standard Xt/Motif API, so they're easy to learn and integrate with

popular GUI builder tools. XRT widgets are available today for more than 15 UNIX/VMS architectures and are coming soon for Microsoft Windows®.

And there are never any runtime or royalty fees when you distribute your applications to end users.



FREE 30-DAY EVALUATION (800) 663-4723



(416) 594-1026 Fax (416) 594-1919 info@klg.com http://www.klg.com/

XRT/ is a registered trademark and XRT/graph, XRT/3d and XRT/table are trademarks of KL Group Inc. Windows is a registered trademark of Microsoft Corporation. All other trademarks are the properties of their holders

Circle 408 on Inquiry Card.



SILICON GRAPHICS TAKES YOUR IDEAS INTO THE FUTURE. DLT BRINGS THEM BACK EVERY TIME.

When you think of Silicon Graphics, terms like visual high-performance workstations, multiprocessing servers and multimedia solutions instantly come to mind. So having the most reliable, high-capacity backup or archival solution is extremely critical. Which is precisely why Silicon Graphics



offers Quantum's Digital Linear Tape (DLT™) for their Challenge, Onyx Reality Engine2, and Power Challenge server products.

Quantum's DLT 2000 tape drives let you store an exceptional 20 GB* of data at a blazing

2.5 MB/second transfer rate. And with a 10,000-hour head life, up to 500,000-pass/30-year media shelf life plus innovative self-diagnostic features, you'll have the highest confidence in data transfer and retrieval.

Because of its fast access rate, high reliability and industrial-strength durability, DLT is ideal for environments where users need to access large database files quickly. Applications such as CAD/CAM, scientific, and video are just a few prime examples.

Capacity*	Transfer Rate*	Head Life	Media Life
(GB)	(MB/S)	(Hrs.)	(Passes)
20	2.5	10.000	500,000

With its robust design, DLT easily meets the most stringent integration requirements making it a popular choice among major automated tape library manufacturers. Using one of the most sophisticated error detection and correction codes in the industry, DLT ensures that you can retrieve what you write.

Considering all this, you're probably not surprised DLT is fast becoming the industry's choice for mid-range computer environments. To learn more about using DLT for faster backup, safer archiving, and higher-performance storage, call Quantum today at **1-800-624-5545**.

No matter what high-performance equipment you're using, you won't want to venture too far out without a dependable way to get back.

Eco-Logical.



This symbol identifies energy-efficient computers that save you money and reduce air pollution by "powering down" when not in use.

Over 2000 computers, monitors and printers have earned the right to bear the Environmental Protection Agency's Energy StarsM logo. These computers are so smart, they go to sleep when not in use and wake up with a simple touch of the keyboard or mouse. Energy StarSM Computers don't cost

any extra, will save money on your energy bill, and prevent pollution from electricity generation. Be part of the solution and look for this logo when you make your next computer purchase. To receive a list of available products call the Energy StarSM Hotline at 202 775-6650.



Buy It And Save.

Tickle Makes Developers Smile

TERRY R. COLEY

s a scripting language, the Tool Command Language (Tcl, pronounced "tickle") has hit a sweet spot in the applications programming community. Tcl and its common extensions offer a combination of features—extensibility, easy embedding in C code, and simplified implementation of TCP/IP client/server communications—that developers find hard to resist. At the script level, Tcl's benefits extend to application users as well. Well-designed application-specific Tcl commands give users a flexible control language.

An excellent example of a Tcl extension is the popular Tk X Window System interface, which supplies a broad set of easy-to-manipulate scriptdriven graphical widgets. With Tk and Tcl's TCP/IP extensions, it's easy to write applications that take advantage of client/server architecture. Tcl-driven programs also provide the opportunity to create useful collections of scripts that implement common, higher levels of functionality not considered by the original programmer. Perhaps best of all, Tcl is free for downloading (see the text box "Availability of Tcl and Tk" on page 200DM 18), and you can distribute your Tcl-based applications royalty free.

With Tk and Tcl's TCP/IP extensions, it's easy to write applications that take advantage of client/server architecture

{\$a == "hello"} and {puts "a passed the test"}—are simply strings. It is up to the underlying code implementing the if command to make sense of the strings.

The everything-is-a-string characteristic lets you pass snippets of Tcl code around via variables. The variable command in "Loop" contains the entire for loop, making it possible to

manipulate it or pass it to another part of the Tcl script just like any other variable. In fact, you can use variables to build up sequences of executable Tcl commands.

"Loop" executes the stored for command immediately by passing it to the Tcl eval command. The eval command takes a single argument and passes it recursively to the Tcl interpreter.

So the Tcl syntax is simple. New lines or semicolons separate sequences of commands and their arguments. Also, new lines contained within braces represent a single string, allowing control commands to easily execute arbitrarily long blocks of Tcl code.

A Taste of Tcl

Tcl is a simple programming—or, more aptly, scripting—language. Like any true programming language, Tcl supports variables and control structures.

Everything is a string in a Tcl script. More precisely, the parser treats arguments to commands as strings, and it's up to individual commands to interpret these strings. For example, the set command takes two arguments: a variable name and a value. (See the listing "Loop.") The if command also takes two arguments—a conditional expression and a body—to optionally execute. To the Tcl parser, the two strings enclosed in braces—

PAUL WATSON @ 1995

Feature

Tcl Features

A scripting language is ideal for orchestrating a sequence of events. Unix shell scripts, and even DOS batch files, are examples of scripts that automate a sequence of events.

Scripting languages, including Tcl, are typically interpreted and not compiled. Tcl has two additional characteristics that are responsible in large part for its incredible success as a multipurpose scripting language: embedability and extensibility.

You can easily embed the power of the Tcl interpreter in your C/C++ applications because the interpreter is implemented as a C library. A single call to Tcl_CreateInterp() creates an instance of a Tcl interpreter object. To use the interpreter, your application passes strings into the Tcl_Eval() function. For example, the tclsh program in the Tcl distribution simply collects strings from the command line or input file and passes them to a Tcl interpreter.

After you've embedded the Tcl interpreter in your application, you will want to scripting language for the application has been done. Each time you write a new application using the Tcl interpreter, that application gets variables, program control commands, and file I/O commands; indeed, it gets the whole

Tcl language with no effort. Once you learn to write scripts for one Tcl-based application, you are well on your way to being effective with any other Tcl-based application.

The Tk Toolkit

Possibly the most widely used extension to Tcl is the Tk Toolkit, concurrently developed by Dr. John Ousterhout (Sun Microsystems) along with Tcl. The Tk Toolkit implements a broad set of graphical widgets that display on X servers. The key difference between Tk and other X widget sets is that you can create and manipulate each widget using

Tcl commands. A program called wish reads interactive input or lines from a script and passes them to an extended Tcl interpreter that implements the Tk Toolkit widget set. Using Tk, you can create X ap-

plications using simple, interpreted scripts. The scripts do not require compiling or linking, simply a text editor and the wish program.

To get a sense of the advantages of Tk scripting, compare a simple "hello world" application implemented in Motif with one implemented in Tcl/Tk. The application displays a window with a text message and waits for the user to click a button to terminate the application. The listing "Motif Hello World" contains the Motif script,

and the listing "Tcl/Tk Hello World" contains the Tcl/Tk script.

The first line in "TcI/Tk Hello World" initiates the interpreter (wish) that will run the TcI/Tk script. The second line creates a button widget, specifies its name (.hello), its text (Hello, world), and the callback command executed when you press the button (exit). The final line places the button widget (.hello) in the top-level window managed by the wish program.

TcI/Tk and the wish interpreter provide a tremendous simplification for building X applications, opening the world of creating X applications to a much broader audience. However, even if you are comfortable with Motif and C/C++ programming, you should consider some of the other advantages to coding with TcI/Tk. (See the table "TcI/Tk Features Summary" on page 200DM 14 for a summary of the pros and cons.)

The normal development loop consists of editing source code, compiling and linking, and testing and debugging. You repeat this process until the script functions correctly. The compile-link phase can become a significant time investment, especially with large X applications. Because of the interpreted nature of Tcl/Tk-based applications, you bypass the compile and link phases.

For larger Tcl/Tk applications, pieces of the application can reside in totally separate script files. In these cases, it is even possible to debug a new component while

Tcl/Tk Hello World

#!/usr/local/bin/wish -f
button .hello -text "Hello, world" -command exit
pack .hello

extend it to implement functions specific to your application. The Tcl_Create command function attaches a new Tcl command, which you specify to compiled code and binary data that you implement. From then on, any time the Tcl interpreter encounters your command, all the arguments will be parsed and sent as C character pointers to your C function.


Because the application-specific commands become part of the Tcl language, all the work to create a truly powerful

Motif Hello World

```
#include <stdio.h>
#include <X11/Intrinsic.h>
#include <Xm/Xm.h>
#include <Xm/Ym.shB.h>

void Quit(w, client_data, call_data)
Widget w;
XtPointer client_data, call_data;
{
   fprintf(stderr, "It was nice knowing you.\n");
   exit(0);
}
main(argc, argv)
int argc;
char **argv;
{ XtAppContext app_context;
   Widget topLevel, goodbye;
```

```
topLevel = XtVaAppInitialize(
    &app_context,
    "Xgoodbye",
NULL, 0,
    &argc, argv.
NULL,
NULL);
goodbye = XtVaCreateManagedWidget(
    "goodbye
    xmPushButtonWidgetClass.
    topLevel,
    NULL);
XtAddCallback(goodbye, XmNactivateCallback, Quit, 0);
XtRealizeWidget(topLevel);
XtAppMainLoop(app_context);
}
```



TriTeal's Enterprise Desktop. Welcome to CDE.

Now Available for HP, IBM, SGI, Sun & X-Terms. It's called the Common Desktop Environment (CDE), and for UNIX* systems everywhere, it's nothing short of revolutionary. By providing a single graphical interface across all UNIX platforms, CDE creates a common ground for users of every kind — and ushers in a whole new era of corporate computing freedom.

And now, with TriTeal Enterprise Desktop™ (TED), you can take the first steps into CDE. Starting with TriTeal's Visual User Environment™ (VUE 3.0), you'll enjoy the instant rewards of having one consistent, easy-to-use

desktop. With an installed base that's more than half a million strong, VUE is not only a proven technology — it's also a core component of CDE. Which makes it easy to migrate from VUE 3.0 to TED, a definitive CDE product.

From login to logout, TED provides an intuitive, graphical display that lets you access applications, data and network services without knowing a thing about UNIX systems. Best of all, it comes from TriTeal, widely recognized as the leader in CDE technology.

In the heterogeneous world of UNIX systems, one desktop is giving everyone cause for celebration. TriTeal's Enterprise Desktop. Call 1-800-TRITEAL for details about our 30-day evaluation program and the name of a reseller near you.



TriTeal Corporation
Phone: (619) 930-2077
e-mail: info@triteal.com
World Wide Web: http://www.triteal.com/

TriTeal Enterprise Deaktop and TED are trademarks of TriTeal Corp. UNIX is a registered trademark in the U.S. and other countries, licensed exclusively through X/Open Co. Ltd. Visual User Environment and VUE are trademarks of Hewlett Packard. All other trademarks are the property of their respective owners Buy TED
Get FAX Software
F R E E
1.800.874.8325

Feature

TCL/TK FEATURES SUMMARY

Advantages

- Reusable in multiple applications
- Simple syntax
- Storage of command sequences in variables
- Embedability
- Extensibility
- The Tk Toolkit
- . No compiling or linking
- Runs on any wishequipped machine
- Compilers available soon
- Easy client/server implementations

the main portion of the application is running. For

example, suppose you are changing or debugging a new dialog box. The main application invokes the Tcl procedure responsible for displaying the dialog box and returning a result to the main script. After testing the dialog box, you find that it returns an incorrect value or does not look the way you want it to. You edit the script containing the dialog box code. Now the main Tcl/Tk script must simply source the new script file and reinvoke the dialog box using the new code.

Tcl/Tk Windows applications run on

Disadvantages

- Slow execution speed
- Poor for data-intensive applications
- New compilers eliminate portability
- Lack of debugging tools
- Difficult to develop large applications



any machine with an executable version of the wish interpreter. Chances are you won't have to do any additional work to port your application across Unix platforms (and now even Microsoft Windows), because wish has been ported to almost every Unix platform. This is a distinct advantage to software developers looking to support a wide variety of platforms.

Some Disadvantages

Creating X applications using Tcl/Tk has a few disadvantages when compared with development in C/C++. Due to their interpretive nature, Tcl/Tk scripts are slower than compiled X applications. However, depending on the appli-

cation, the speed difference may not be discernible. In fact, unless you are doing large amounts of string manipulation, you will find that Tcl/Tk-based applications and user interfaces perform as well as compiled code.

Where performance has remained an issue, some developers have augmented the Tk widget set using new C/C++ code. The result is a new wish interpreter that understands the

command for an application-specific widget. This solves the performance issue at the price of losing the automatic platform portability.

Finally, excellent debuggers exist for working with C/C++ code. Such tools do not yet exist for Tcl-based code. For this reason, you should be cautious about developing overly large applications in Tcl/Tk.

Despite its disadvantages, Tcl/Tk is a powerful tool for rapid application and user interface development. Developers and users alike use Tcl/Tk to create functional Unix applications. One specific area in which Tcl/Tk scripts are particularly useful is in Unix system administration.


System Administration with Tcl

Unix system administration is a broad topic involving many areas, such as network administration, user account administration, security, policy enforcement, and process monitoring. The application described here is a Tcl-based toolkit called KIS (kernal information system), developed for monitoring process information

Finding Defunct Processes

Here, line 3 defines the KIS list of items to extract (PID is implicitly always the first item of the list). The search for defunct processes is done at the expense of a single kernel scan done in line 4. In line 6, the script performs a filtering operation of the kernel snapshot (stored in a KIS scan referred to by Tcl variable all Processes) to create a secondary KIS scan containing only the defunct processes. Every KIS scan of the kernel has an associated header with two pieces of information: a time stamp showing the collection time of the information and an ordered list of the attributes collected for each process. Lines 10–13 serve to ignore the time stamp information and output a simple header.

Line 15 begins a loop over each defunct process. The body of the loop first outputs information on the process. The loop in line 19 begins a traversal of the process's parentage, terminating at PID = 1. The initial condition for the loop (line 18) stores the parent of the defunct process in ppid. The script constructs a temporary filter for each iteration (line 20) that locates the process for which PID = \$ppid in the original, complete KIS scan. Parent information is output at line 28. The parent list will always contain one element (which is itself a list of PID PPID STATUS USER COMMAND for the parent) unless the parent died during the original kernel scan. The if statement in line 25 handles this contingency and will terminate the loop if a parent is not found (line 30).



Your Golden Gateway to Windows 95. **NEW BW-Connect NFS for DOS** and Windows.



Buy BW-Connect™ NFS v3.2 now and we'll upgrade you to the Windows 95[™] version absolutely free!* New version 3.2 includes the first commercial WWW server for Windows, slick new Internet access tools, and over 40 Windows applications in all.

- Full suite of Winsock client tools including FTP, telnet, a threaded news client, gopher and much more.
- High performance NFS client.
- Quick and easy installation.

- Largest suite of Inetd-based server tools including FTP, telnet, lpd, gopher, bootp and many others.
- E-mail with MIME attachments, MAPI interface, 100,000 word spell checker.
- Supports DHCP client and BOOTP client and server for easy, centralized TCP/IP administration.
- Personal Internet Publishing with WWW and gopher servers.
- Factory direct!
- \$349 per user! (Substantial quantity discounts available).

BW-Connect NFS for DOS and Windows is your migration path to Windows 95. So get on the road to open connectivity today. Like Carl says, "When using the Web to cruise the Internet, it's a wide world out there."

Order your FREE 30-day evaluation of BW-Connect today:

1-800-216-8450

Let's Connect!s



ato Hwy. With Cart & Fred" by B










*Provided user is under Beame & Whiteside Technical Support ("Support Servieve") contract at the time of the refease. ** Developer technic only. Novell make no warran respect to this product. All trademarks are the property of their respective owners. Beame & Whiteside Software, Inc., 70th Hillshowagh Su., Raleigh, NC 27603, Tel. (1918) 51-8906, Early (1918) 1-8909, Early (1918) 1-8906, Early (1918) 1-



REACH 90 MHz Now.



HIT 125 MHZ LATER—FREE!

Get faster, multi-processing performance now—and we'll give you even better performance later at no additional cost!

For a *limited* time, when you purchase ROSS' 90 MHz single-, dual- or quad-processor hyperSPARC™CPU upgrade modules, you'll get a coupon redeemable for ROSS' 110 MHz hyperSPARC upgrades when they become available, and later, 125MHz.

If you've postponed a CPU upgrade, act now! We're giving you a risk-free way to accelerate the performance of your SPARCstation™ 10 and 20 or SPARCserver™ 600MP Series units. You can boost your processing speed from 2 to 5 times (or more). And with ROSS upgrades priced at a small *fraction* of the purchase cost for a new workstation, this is horsepower you can use today!

Cruise into our World Wide Web site at http://www.ross.com for more complete details on the "Upgradable Upgrade."



5316 Hwy. 290 W., Austin Texas 78735 Phone: 800-774-ROSS in U.S., 512-919-5207 Global FAX: 512-919-5200 e-mail: info@ross.com

© Copyright 1995, ROSS Technology, Inc. All rights reserved.

All SPARC trademarks are trademarks or registered trademarks of SPARC International, Inc. hyperSPARC is licensed exclusively to ROSS Technology, Inc. SPARC and SPARCserver are licensed exclusively to Sun Microsystems, Inc. Products bearing SPARC trademarks are are based upon an architecture developed by Sun Microsystems, Inc.

Circle 404 on Inquiry Card (RESELLERS: 405).

Feature

on networks of Unix computers.

Suppose you are the system administrator for a multivendor network of computers used as compute servers. The servers are used to run extended simulations or to perform CPU-intensive database operations. A defined policy exists regarding how many CPU resources each individual user and each group collectively may use. Your job is to monitor and enforce that policy.

To accomplish this, you will need tools for managing Unix processes. You have several options to accomplish this job. You might try writing your own Unix shell scripts, writing your own C programs, or using commercial system management software. Each route has its own disadvantages: Process information may not be available from the Unix shell on various platforms; a C language approach is complicated and vendor specific; and many commercial systems are large and expensive and do more than you need. The combination of Tcl/Tk and KIS may provide the customizable solution you need.

Much like programming X applications, Unix kernel programming is a complex task further complicated by differences among the many Unix vendors. Taking advantage of the capabilities of Tcl/Tk, KIS solves this problem by making Unix kernel data on multiple Unix platforms available to Tcl scripts. Two listings of Tcl/Tk scripts demonstrate how easily you can develop kernel-level system monitoring with KIS. The first deals with finding defunct processes, and the second determines the number of processes per user.

Case 1: Finding Defunct Processes

Defunct processes are processes that have terminated but the parent process has not yet executed the Unix wait() or related system call for that child. This is usually an abnormal condition. Too many defunct processes can clutter the kernel, needlessly consuming process slots. It is useful to be able to identify defunct processes and look at their parentage quickly. When appropriate, issuing a kill on the parent will often free the process slots of the defunct process as well as the parent.

The KIS script "Finding Defunct Processes" displays the process ID, parent process ID, current state, ownership, and command string used to execute each defunct process. Additionally, the script displays the defunct process's parent tree up to PID == 1 (the init process). Using this information, system administrators can kill selected parent processes. This script can also function as the starting point for creating a script to automatically clean the system on a regular basis.

continued

2 WAYS TO PORT YOUR UNIX APPLICATIONS TO WINDOWS & NT:



HIRE MORE PROGRAMMERS

OR



TRY NuTCRACKER
RISK-FREE FOR 30 DAYS



NuTCRACKER® is the fast and affordable way to port all your UNIX® applications to Windows™95 and

Windows NT™ — without hiring an army of Windows programmers.

But don't take our word for it. We want you to use Nu/TCRACKER risk-free for 30 days. Try it and you'll see how easy it is to leverage your investment in UNIX into fully interoperable native Windows applications.

NuTCRACKER is a complete set of UNIX development tools that looks and feels like UNIX to all of your programmers. It's the solution that's already won enthusiastic converts at AT&T, Cabletron, Informix, and a host of U.S. government agencies.

With NuTCRACKER you can use your UNIX code and programming assets to develop new Windows products — right on Windows NT and Windows 95. It's also the best way to port UNIX applications across multi-CPU and multi-OS environments, without losing UNIX functionality.

NuTCRACKER also delivers a robust set of development tools. And if you have any questions, DataFocus offers everything from phone support to on-site Migration Services consulting. So before you hire your own army of Windows programmers, get all the details on our 30-day money-back guarantee offer. Call toll-free today.

800-637-8034



Cracking-Open Windows

Nz/TCRACKER from DataFocus Incorporated 12450 Fair Lakes Circle, Ste. 400, Fairfax, VA 22033 Phone (703) 631-6770, Fax (703) 818-1532 nutcracker@datafocus.com



Feature

Case 2: Processes Per User

"Finding Processes Per User" uses the Tcl/Tk/KIS tools to determine how many processes belong to each user or a particular user on a specific host. This 45-line script lets a system administrator specify a host and also a particular user, if desired. For ex-

ample, if you would like to know how many processes belong to user1 on host2, you could type nproc -u user1 -m host2.

In the script, lines 2–25 process the command-line arguments, while lines 27–45 perform all the work. Two important new ideas appear in this script: a KIS sort filter

and the tcp command for network communication. The tcp command establishes a connection to a KIS daemon that acts as a proxy to collect the desired information on the remote host. From your point of view, the only new wrinkle is that you must prefix all KIS commands

Availability of Tcl and Tk

Although Tcl grew up in a Unix environment, three different Microsoft Windows ports are available, one at ftp://ftp.ms.uky.edu/pub/tk-win and another from a group in Japan at ftp://ftp.sra.co.jp/pub/lang/tcl (look for files named tkwine*). The third port, for Windows NT, is available at ftp://mm-ftp.cs.berkeley.edu/pub/multimedia/winnt/tknt36r3.

Tcl/Tk on the Internet

You can download the TcI/Tk distribution from ftp://ftp.cs.berkeley.edu/ ucb/tcl

The Extended Tcl interpreter features many more Unix system-level access commands. It is available at ftp://ftp.aud.alcatel..com/tcl

FAQ (Frequently Asked Questions)

http://www.cis.ohiostate.edu/hypertext/faq/ usenet/tcl-faq/top.html

John Ousterhout's Home Page

http://playground.Sun.COM: 80/~ouster

Wade Holst URL

A particularly useful collection of TcI/Tk starting points is available at http://web.cs.ualberta.ca/

~wade/Auto/Tcl.html

On-line Manual Pages (Tcl language and C language API)

http://www.sco.com/IXI/of _interest/tcl/tcl_man .html http://www.sco.com/IXI/of

_interest/tcl/tk_man .html

http://www.sco.com/IXI/of _interest/tcl/tclAPI_man .html

http://www.sco.com/IXI/of _interest/tc1/tkAPI_man _html

Tcl and the Tk Toolkit Book

John Ousterhout's book, Tcl and the Tk Toolkit (Addison-Wesley, 1994, ISBN 0-201-63337-X), is available at many bookstores. You can also request a copy by sending E-mail to info@pgrams.com.

Unix System Management

The listings in this article are available on-line, at ftp://wag.caltech.edu/pub/kis



SPARCclassic • SPARC 2 • IPC • IPX • 670 MP • 690 MP • SPARC 10 • SPARC 1000

welcome to the great wide OPCI1

The future of computing is wide open.

If you're working in an open-computing environment—or are planning to make the change soon—the choices are more complicated than ever. You need the right mix of technical and business information to make the right decisions.

That's why you should be reading *Unix World's Open Computing*.

Written for professionals who integrate, manage, program and resell interoperable systems, *Open Computing* gives you the up-to-the-minute information that you need to:

- reduce information costs
- create strategic computing solutions
- select the right hardware and software
- improve productivity

Seize the opportunity—the open-computing era will reward both the individuals and the organizations that can put their knowledge to use and harness the potential of interoperable systems. Build your knowledge through the in-depth features, industry news, comprehensive product reviews, and programming tips in every issue of *Open Computing*.

To start receiving *Open Computing*, just call the toll-free number below. Receive twelve issues for just \$18.00 per year-half of the newsstand price. Your satisfaction is guaranteed.

subscribe now 1•800•257•9402



Feature

```
#1/usr/local/bin/ptclsh -f
1.
2.
    set oneUser O
3.
   set host localhost
    for (set 1 0) ($1 < $argc] (incr 1) |
5.
6.
        set arg [lindex $argv $i]
7.
        case $arg {
8.
        -m (
9.
        incr i
        set host [lindex $argv $i]
10.
11.
12.
        -4 [
        incr i
13.
        set userFilter "USER == \"[lindex $argv $i]\""
14.
15.
        set oneUser 1
16.
17.
        default |
18.
        puts "Usage: $argv0 -options"
        puts "Options:"
19.
        puts "-m (machine - specify host)"
20.
        puts "-u (user - specify one user)"
21.
22.
        exit 1
23.
24.
25. 1
26.
27. set c [tcp connect $host [kisPort]]
28. set 1 [$c send kis list -create USER]
29. set sort [$c send kis filter -create -sort $1 (USER)]
30. if $oneUser !
        set f [$c send kis filter -create $1 $userFilter]
31.
32.
        set s [$c send kis scan $1 $f $sort]
33. 1
34. else { set s [$c send kis scan $1 $sort] }
35.
        set o [$c send kis format $s]
36.
37. set formStr "%15s %4d"
38. set totPID 0
39. foreach userData $0 (
        set userNproc [llength $userData]
40.
41.
        incr totPID SuserNproc
42.
        set userName [lindex [lindex $userData 0] 1]
        puts [format $formStr $userName $userNproc]
43.
44. }
45. if | SoneUser [puts [format $formStr "Total:" $totPID]]
```

with \$c send to indicate that the command is to be sent to and executed in the KIS proxy process on the remote host.

Suppose you are interested in learning only about particular processes belonging to a user-for example, processes that are demanding more than a threshold of CPU resources? One way to modify "Finding Processes Per User" to collect only the important processes would be to create an additional KIS filter. A filter like "CPU > 60 && delta (CPU)/ delta (TIMESTAMP) > 10%)" will select only those processes with more than 60 CPU seconds and which occupied more than 10 percent of the CPU time between successive scans. The KIS delta() operator allows examination and filtering based on changes between successive KIS scan calls. To implement the above filter meaningfully requires an initial scan, followed by a pause, followed by another scan.

Tcl and Networking

The ability to communicate between Tclbased applications running on the same or

Finding Processes Per User

Lines 2-25 process the command line. The tcp on line 27 establishes a connection to a KIS daemon that acts as a proxy to collect the desired information on the remote host. All KIS commands are prefixed with \$c send, indicating to send the command to be executed in the KIS proxy process on the remote host.

Line 28 creates a KIS list, indicating that for each process you need only the USER (process ownership) attribute. Line 29 creates a KIS sort filter, resulting in the return of sorted information by USER. According to the command-line input, the script requests either all processes or only those processes belonging to a specified user.

Line 32 shows the simultaneous use of a KIS filter and a KIS sort filter to extract selected items and sort them. In this case, the sort by USER is trivial because the selection filter specifies one user. Each KIS sort filter adds an extra nesting level to the output of the kis format command (line 35). The script employs the sort even in the one-user case so that the same loop structure (lines 39-44) handles the output list (\$0). The extra nesting of the results groups processes with equal values of the sort filter. The foreach loop handles each unique value of USER and then simply counts the items in the subsidiary list.

different hosts is one of the most powerful extensions added to basic Tcl. The extension uses TCP/ IP connections to implement interapplication communication between Tcl-based clients and servers. Typical of Tcl-based codes, the top command boils down the

complexities of TCP/IP sockets programming to a few useful Tcl options. The networking Tcl commands tcp connect and \$c send give you all you need to develop useful client/server Tcl-based scripts.

The tcp connect command requires a host name and a port number to make a connection. (In the listing "Finding Processes Per User," the kisPort command supplies the locally configured port set up by the system administrator used for KIS proxy daemons.) When the script specifies the KIS port for a connection request, Unix (through inetd) takes care of starting up a KIS proxy daemon on the remote (or local) host. The proxy daemon becomes an information server, and the requesting application becomes the client.

After the code implementing the tcp connect command establishes a TCP/IP connection, it creates a new command in the Tcl interpreter of the client. The name of the new command is returned as the string result of the tcp connect command and is usually captured in a variable in the client application's interpreter.

The saved result of the tcp connect command is used by the client application for further reference to the newly created connection. Assuming you store the created connection command in the interpreter variable c, invoking this command with the send option (\$c send . . .) results in the remaining arguments on the command line being sent to the server as an executable command in the server's interpreter.

In "Finding Processes Per User," all the KIS commands were executed in the KIS proxy server via \$c send. In fact, the client code does not need the kis command built into its interpreter at all, but it does need the tcp command.

Future of Tcl

Every once in a while, an innovation comes along that changes the way a large number of people build software. Tel certainly falls into this category. The Tel/Tk combination provides an amazingly productive way to create X applications. Best of all, Tel/Tk and many extensions are distributed free with copyrights that allow unrestricted, royalty-free commercial use.

Just as Tk makes building X applications far more productive than using the X Windows C language interface, KIS lets system administrators build complicated, networked Unix process management applications with a fraction of the effort required to learn Unix kernel interface programming.

Terry R. Coley is the president of Parallelograms, where he focuses on managing software design. He holds a Ph.D. degree in computational chemistry. You can reach him on the Internet at pgrams@netcom.com. or on BIX c/o "editors."

A playground for experts. Training wheels for their friends.



Traveling the Information Highway

A new exhibit at

The Computer Museum

computer_info@tcm.org / 617. 423. 6758 / www.net.org 300 Congress Street, Boston, Massachusetts 02210

Principal Sponsor: Sprint

Major Sponsors: Apple Computer, Hewlett Packard, Novell, NYNEX, Stratus, S.W.I.F.T.



Official Media Sponsor

WE BUILD RAID ONE DRIVE AT A TIME




Start with a single Lypux desktop mass storage unit -- from 500MB to 4.2GB.



Add additional interlocking units to build a LymxStak.



Expand to desktop or deskside RAID when you are ready-- by adding a built-in Lynx Tower RAID subsystem.



Preserve 100% of your investment as your needs evolve to hundreds of gigabytes of rackmounted RAID mass storage in a LynxRack.

WITH 100% INVESTMENT PROTECTION.

Artecon's new LynxRAID™ enables you to upgrade from desktop mass storage to desk-side or rackmounted RAID with 100% investment protection. With LynxRAID, you can incrementally grow into RAID by utilizing your existing Lynx desktop units and expanding your system as your needs grow.

Every Lynx subsystem features options such as true hot-plug drive modules from 500MB to 4.2GB, individual front removable power supplies and LCD/keypads. Lynx units can be stacked for desktop RAID or racked into a highly modular RAID system for maximum reliability and redundancy on SPARC®, HP, SGI, RS6000, Mac or PC platforms.

At the heart of each LynxRAID configuration is a fault-tolerant, RISC-based RAID controller subsystem, which occupies a mere 5.25" of vertical rack space and can support either one or two independent or dual loadsharing RAID controllers. Each controller is available with up to 32MB built-in cache, supports RAID levels 0, 3 and 5 and fast-narrow, fast-wide and fast-wide differential host interfaces.

The LCD panel and keypad give access to RAID status display and configuration. A battery-backed alarm panel provides both audible and LED alarm indication of potential voltage, current, temperature or controller failure.

In addition, each controller is equipped with two front removable loadsharing power supplies and removable fans for maximum fault tolerance. LynxRAID Towers can support up to 29GB of RAID storage each. Single controller LynxRAID rack configurations offer up to 100GB in a 40" rack, while dual controller systems can expand to 200GB in the same footprint.

So when you think about RAID, think about protecting your investment with a solution that grows with you. Call Artecon today for information on LypurRAID configurations.

1-800-USA-ARTE

1-800-872-2783

Enterprising solutions for your enterprise.™



PO Box 9000, Carlsbad, CA 92018-9000 (619)931-5500 FAX (619) 931-5527 email: sales @ artecon.com

Artecon, Canada, (416) 487-7701 Artecon, Japan 81-3-3280-1210 Artecon, France 33-1-69-1818-50

What's New

UNIX FOR THE MAC

Machten 4.0 (\$695) brings Federal Information Processing Standard 151-2 Posix-compliant Unix to Macintosh and Power Macintosh platforms. The package provides preemptive multitasking and a full-featured high-performance TCP/IP protocol stack with Internet application protocols that support file transfer, virtual terminals, and E-mail. Also included are Internet tools (domain name service and Internet control message protocols), serial (compressed SLIP and PPP) and Unix (rsh and rexec) communication support, industrystandard client/server NFS file sharing, a full suite of Unix software development tools with C and C++, and a complete implementation of X11R5.

Contact: Tenon Intersystems, Santa Barbara, CA, (805) 963-6983.

Circle 1254 on Inquiry Card.

UNIXWARE 2.0

UnixWare 2.0 (\$99) is a full-featured Unix OS for Intel x86based platforms. Its highlights include SMP (symmetric multiprocessing) support that lets software take advantage of computers with multiple processors. Improved NetWare integration provides single log-on access to databases running on a Unix server through a NetWare LAN. Additional features include 32bit processing with a fully multithreaded kernel and preemptive multitasking, asynchronous I/O, user-level threaded APIs, and dynamically loadable modules. Contact: Novell, Summit, NJ, (408) 434-2300.

Circle 1255 on Inquiry Card.

UNIX-TO-PC CONNECTIVITY

This user environment for distributed computing systems provides transparent access to Unix facilities and applications from Unix and PC desktop systems. Eye2eye (\$595) provides Motif 1.2 run-time libraries with Motif/CDE or Microsoft Windows 3.1 style, appearance, and behavior; interoperability with the Windows control panel; and automatic conversion of Motif and Windows clipboard formats.

Contact: IXI Corp., Santa Cruz, CA, (408) 429-4500.

Circle 1257 on Inquiry Card.

INCLUSIVE INTERNET SERVER

The Netra Internet server comes with a complete suite of software, including configuration utilities, security software, an E-mail gateway, and file-transfer capabilities. Netra provides direct desktop Internet connections for PC, Mac, and Unix workstation users on LANs. The server supports Mosaic as well as other network browsing tools. A base configuration includes 16 MB of RAM and 535 MB of hard disk storage (\$6149), and an upper-level system provides 32 MB of RAM and a 1.05-GB hard drive (\$8499) and can be expanded to four processors.

Contact: Sun Microsystems, Mountain View, CA, (800) 821-4643 or (214) 386-8415.

Circle 1258 on Inquiry Card.

UNIX HSM

Metior HSM software provides distributed hierarchical storage management for Unix. Metior software can drive 12 tapes simultaneously in MediaLogic ADL's (Boulder, CO) SLA-8max (1.23-TB maximum storage) and SLA-4max (960-GB maximum storage) libraries or seven drives in the SLA-D (multiterabyte storage). The system is available on SunOS, Solaris, SGI, HP-IX, and SCO Unix platforms. There is also client support for NFS-mountable environments, including NetWare, OS/2, Macintosh,

The SPARCard 5 add-in board (from \$3495) provides a complete microSPARC environment designed to fit on a PC. Features include microSPARC II processor support, improved AT Bus throughput, expanded memory capability, and modular processor upgrade design. The three-board modular set fits into two ISA/EISA slots. Options include 70-, 85-, or 95-MHz processors; 500-MB or 1-GB hard drives; and up to 128 MB of RAM. All boards include standard Unix workstation I/O ports and the Solaris OS. Special software designed by Opus lets the PC monitor, mouse, keyboard, and floppy drive support both Unix and PC environments. A single keystroke or mouse-click switches between DOS and Unix environments and enables file transfers between environments. Contact: Opus Systems, Santa Clara, CA, (408) 562-9340.

and VMS. An 8mm base unit with three drives and 28 cartridges (\$17,595) provides storu

Circle 1256 on Inquiry Card.

pressed data.

SPARCARD 5

Contact: Automated Network Technologies, Englewood, CO, (203) 235-0035.

age of 392 GB of compressed

data and 196 GB of uncom-

Circle 1259 on Inquiry Card.

VOICE/DATA/FAX CONCENTRATOR

A concentrator from MultiTech Systems can simultaneously handle voice, data, and fax. The single-channel MMV101 (\$1299) bridges LAN, PBX, fax, and E-mail over a single telecommunications line. Communications lines can be analog, ISDN, Switched 56, fractions T1, or any DSU-based service operating at up to 128 Kbps. The MMV101 handles up to 128 Kbps synchronous or 115 Kbps asynchronous data transfer rates. The voice/fax interface can be to a PBX system, key system, or telephone using a standard FXO or FXS interface.

Contact: MultiTech Systems, Mounds View, CA, (908) 542-6121.

Circle 1261 on Inquiry Card.

SCHEDULING ON UNIX

Lucas has ported Artemis Scheduler Publisher 4.2 (\$1995) to the Unix platform, Available in eight languages, it provides enterprise-wide project management and cross-platform functionality and can merge, link, or exchange data across Unix, Windows, and Macintosh platforms. In addition, Artemis Scheduler Publisher can break down projects into smaller portions and then link them up to a master plan. It lets managers determine the length of a task based on required effort and available resources, and perform updated data transfer with off-the-shelf project management systems or databases.

Contact: Lucas, Fairfax, VA, (703) 734-1052.

Circle 1260 on Inquiry Card.

MULTIPLE LAN ROUTERS

NetBlazer LS ISDN (\$1399) and NI2B (\$1660) routers are capable of simultaneouly routing TCP/IP and AppleTalk communications, as well as Ethernet, to LocalTalk traffic. The routers also support ARA 2.0, frame relay, and interface balancing. Both include seven levels of

security, consisting of ID/password, callback, DES-based cryptographic handshake, filtering, Kerberos, SecurID, and PAP/CHAP. Both also support SNMP MIB II and enterprise MIB. Special ISDN (and syncronous communication) features include 4-to-1 compression using the STAC algorithm, 5ESS, and DMS 100 switch support as well as adherence to ISDN 1 and B channel protocol PPP.

Contact: Telebit Corp., Chelmsford, MA, (508) 441-2181.

Circle 1262 on Inquiry Card.

FILE-SHADOWING SOFTWARE

An on-line backup system takes periodic snapshots of a SPARC workstation's file system, letting users retrieve previous versions of a file with a single mouseclick. ZShadow (\$695 desktop. \$1195 server) stores the watchpoint of a Unix file system in a special save area on a system's hard drive. Typically, a 100-MB disk partition is sufficient for the average system. Shadowing occurs in the background without any user intervention. Because snapshots record only incremental effects, saving typically takes just a few seconds.

Contact: Zzyzx, San Diego, CA, (619) 292-7400.

Circle 1263 on Inquiry Card.

DISK DECLASSIFICATION SOFTWARE

UniShred Pro (\$829 per workstation) provides U.S. Government-approved declassification of confidential materials from Unix workstation disks. Uni-Shred overwrites all device-addressable sectors using direct SCSI commands. All Unix boot files, super blocks, swap space, file system partitions, and alternate cylinders are overwritten. The product is available for the Hewlett-Packard 9000 series with HP-UX 9.x, IBM RS/6000 with AIX 3.x, and Sun Microsystems' SPARC with SunOS or Solaris 2.x.

Contact: Los Altos Technologies, Los Altos, CA, (415) 988-4848.

Circle 1264 on Inquiry Card.

ENTERPRISE SNMP CSU/DSU FOR 64 KB AND 56 KB

The 6406-S CSU/DSU lets you see your entire network from a host site. Each unit features an embedded MIB II agent that monitors and maintains performance parameters and provides access to testing and loopbacks. The ATL 6406-S provides realtime SNMP alarm messages, allowing full access and control of an enterprise network in a lowcost 64-KB or 56-KB CSU/ DSU. The unit offers DDS speeds with either a 10Base-T or an AUI Ethernet interface (\$1395) or a serial interface (\$1195).

Contact: American Technology Labs, Ijamsville, MD, (301) 695-1547.

Circle 1265 on Inquiry Card.

UNIX VIRUS DETECTION

Now you can request virus scans for Windows- and DOS-based workstations on Unix networks. Sophos has ported its Sweep scanner (£495 for 25 users, £895 for unlimited users) to Unix, adding to the NetWare, Windows NT, OS/2, and Open VMS platforms now supported. Users run the Intercheck client that sends virus checking requests to Sweep on the main server. Sweep runs in a "SoftPC" PC emulation mode, feeding requests back to the workstation. This lets Sweep run on Banyan Vines and Artisoft LANtastic networks.

Contact: Sophos, Oxfordshire, England, +44-1235-559933. Circle 1266 on Inquiry Card.

SPARC 20 CLONES

Integrix offers two SparcStation 20-compatible workstations. Both have 100-MHz quad HyperSparc processors from Ross Technology and a newly designed chassis that supports up to two internal hard drives, one floppy drive, and an internal CD-ROM drive. A complete SWS20 system based on the 100-MHz HyperSparc CPU, 32 MB of memory, a 1-GB hard disk, and a 17-inch color monitor lists at \$10,495. The SWS20 features an integrated 24-bit SX graphics card with 8-bit overlay; the addition 4 MB or more of video memory activates the 32-bit SX graphics. The SWS-20E features an ISDN interface for high-speed data transfer and lists at \$9995.

Contact: Integrix, Newbury Park, CA, (800) 300-8288 or (805) 375-1055.

Circle 1268 on Inquiry Card.

X11R6 PC X SERVER FOR NT

Exceed 4 for Windows NT (\$545) provides X11R6-compliant PC X Window System-server capabilities, letting Windows NT users on Intel, Alpha, and MIPS platforms access Unix, VMS, and other X-based computers and applications. Exceed 4 includes a scripting language (Exceed Basic) and dial-up capability for remote access to Unix- and X-based applications over standard telephone lines. Also included is password protection of X-server configuration settings and remote configuration administration, enabling automatic configuration and installation of Exceed on multiple PC desktops. Using the Tektronix Serial Xpress Protocol (SXP), Exceed provides remote file transfer and printing of Unix files on home-based PCs and printers.

Contact: Hummingbird Communications, Markham, Ontario, Canada, (905) 470-1203.

Circle 1269 on Inquiry Card.

WIDGETS FOR ONX

The KL Group has ported its XRT/3d (\$2495), XRT/graph (\$1995), and XRT/table (\$1495) widgets to the QNX real-time operating system. XRT/graph is a powerful 2-D graphing widget that aids in creating bar charts; x,y plots; pie charts; area graphs; financial graphs; and logarithmic scientific charts. XRT/3d is a sophisticated 3-D surface, bar, and contour graphing widget for X Window System applications developers. XRT/table lets developers and end users display and manipulate tabular data in OSF/Motif applications.

Contact: The KL Group, Toronto, Canada, (416) 594-1026.

Circle 1270 on Inquiry Card.

HAND-HELD DIGITAL CABLE METER

A hand-held tool designed to test installed Category 5, ISO,

and IEC LAN cabling to 100 MHz is available. The DSP-100

(\$3795) uses DSP (digital signal processor) technology to provide extremely high accuracy (±2dB), faster test speed than analog devices, and fault identification with location of cross-talk faults. The DSP-100 performs a one-button pass/fail autotest in less than 5 seconds for NEXT (near-end cross talk) and other parameters in installed Category 5 cabling. The DSP-100 can detect the location of faults, including **NEXT** problems caused by defective components or poor workmanship. **Using TDX (Time Domain Crosstalk** Technology), the DSP-100 can pinpoint these or other NEXT faults with a graphical representation showing the amount of, and distance to, a cross-

500 autotest results for downloading to a PC or printer with the provided DSP-Link software. The unit comes with a rechargeable nickel-cadmium battery.

Contact: Fluke, Everett, WA, (206) 356-5500.

talk fault. The DSP-100 stores over

Circle 1267 on Inquiry Card.



think 2X. And 4X. PowerDrive² reads both existing and emerging titles. If you're thinking compatibility options, PowerDrive² gives you **two** of those as well. Its internal or external drive easily connects to any PC or Mac. owerDrive² from Panasonic. It will change the way you look at multimedia storage, forever. For more information on the new anasonic PowerDrive², call 1-800-742-8086, and ask for ext. PD.

other brand and company/product names are trademarks or registered trademarks of their respective companies.

Communications & Systems Company



Local Air Networks

WaveLAN wireless LANs offer robust range, throughput, and roaming

REX BALDAZO

Ithough slower than wire-based networks, wireless LANs solve several knotty problems: cabling restrictions, frequent reorganizations, and most recently, networking of highly mobile employees. Current wireless LANs solve this last problem with PCMCIA PC Card adapters and roaming-enabled access points—two technologies that take good advantage of the growing corporate use of portable computers.

Equipped with PC Card wireless LAN adapters, notebook-toting workers, for example, can set up ad hoc peer-to-peer networks at meetings or off-site locations and work collaboratively over the air waves. Through radio-equipped access points with roaming capability, the same group (or groups) can also stay tied into the office LAN for file and print services and move seamlessly from access point to access point without concern of losing that all-important network connection (see the text box "On the Roam" on page 206).

We tested two wireless LAN systems with roaming-enabled Ethernet access points, from AT&T and Digital Equipment. Both are based on AT&T Wave-LAN technology, provide similar performance, and are interoperable. They are not easy to set up, and bandwidth is still limited (2-Mbps, raw data rate), but for many applications, you won't notice the lower throughput. You may not even mind the higher price (about \$900 per station, depending on size and configuration), if you can take advantage of the benefits of wireless networking as it was meant to be.

Old Champ

WaveLAN is the oldest wireless LAN technology that works in an unlicensed radio band yet still provides more range and throughput than its more recent competitors. WaveLAN technology uses a direct-sequence spread spectrum radio operating at 915 MHz in the 902- to 928-MHz ISM (Industrial, Scientific, and Medical) bandwidth. A number of vendors have licensed WaveLAN technology to use in their own wireless LANs, in-

Based on AT&T
WaveLAN technology,
access points from
AT&T (left) and Digital
Equipment (right) work
together flawlessly
despite design
differences. The PC
Card wireless adapters
[inset] are virtually the
same equipment with
different case colors.

cluding Digital, Solectek, and Persoft.

WaveLAN, however, is not the wave of the future, mainly because the 902- to 928-MHz bandwidth isn't available outside of Canada, the U.S., and Mexico, The 2.4-GHz ISM bandwidth (2400 to 2483.5 MHz) is available internationally, and several companies' wireless LANs operate in that bandwidth already. Other companies including AT&T plan to have their products in that bandwidth as well. Further. the IEEE 802.11 committee is slowly developing an interoperability standard for 2.4-GHz wireless LAN products (see "Universal Wireless LANs," May 1994 BYTE). Broadcasting at a higher frequency, 2.4-GHz products don't have the range that the 915-MHz WaveLAN does. International signal power restrictions can further limit the range.

While the 802.11 specification firms up (maybe in 1996), you can achieve interoperability of a sort with products based on AT&T's WaveLAN technology. It's not going away anytime soon. According to Becky Diercks, program director of Wireless Research at Business Research Group, the worldwide wireless LAN market last year was about \$100 million, with AT&T and its licensees controlling some 40 percent of that.

Family Affair

AT&T produces Type II PC Card radio transceivers that are part of both its own WaveLAN product and Digital's Roam-About line. Both also offer ISA-bus-based transceiver cards for desktop systems. Solectek, another WaveLAN licensee, sells a WaveLAN-based parallel-port adapter for older portables. Except for color, the WaveLAN and RoamAbout PC Card radios are essentially identical, including their \$695 price. We could even use the Digital enabler software to get the AT&T radios operational.

An external antenna the size of a deck of playing cards connects to the PC Card adapter via a short cable. The antenna sits in a clip holder that attaches to the clamshell lid of your notebook computer with two small adhesive pads. Thanks to the clip arrangement, you don't have a bulky antenna permanently attached to your computer. A PC Card with an integral antenna

Reviews Local Air Networks

would be nice, but it isn't feasible for the 915-MHz radio bandwidth, because the antenna must be relatively large. (Xircom's 2.4-GHz PC Card transceiver is the first to use an integral antenna.)

It's in their access points that the two products differ. They have different cases,



a notebook.

Adhesive patches

permanently attach

the clip, but you can

remove the antenna.

Open air range is

800 feet.

microprocessor controllers, management software, and radios. But AT&T and Digital, along with Solectek, have cooperated to keep their access points interoperable.

AT&T's 286-based WavePoint is clearly the older of the two. To link up with a wired LAN, the bulky white box includes connections for thick, thin, and twistedpair Ethernet, with DIP switches determining which connection is active. The radio for communicating to the wireless stations is built into the WavePoint, with a long external cable connecting to a separate wall-mountable antenna. In fact, the WavePoint itself can be wall-mounted.

Digital's RoamAbout Access Point is also wall-mountable but in a smaller and more stylish box. The box can also fit into a DEChub90 or DEChub900, two modular Ethernet hubs from Digital. The Roam-About box has only thin and twisted-pair Ethernet connections but doesn't require setting DIP switches to identify the active connection. According to Digital, a Motorola 68360 processor gives the Roam-About unit a performance edge over the AT&T access point when the wired LAN undergoes heavy traffic.

Instead of a built-in radio transceiver, the RoamAbout Access Point has a single

PC Card slot that takes the same radio unit as the client stations. This modular design provides for upgrades to future radio technology (i.e., 2.4 GHz) or to other existing wireless LAN products. In fact, this month, Digital provides a software upgrade that allows the RoamAbout Access Point to use WaveLAN or RangeLAN2 cards and automatically configures to whichever type of transceiver card is in the slot. Proxim's RangeLAN2 technology uses frequency hopping in the 2.4-GHz bandwidth.

New access points will ship with this capability, and older units can be upgraded through a BootP process. A downside to this design is that the PC Card radios have a short cable, making antenna placement less flexible than with the WavePoint.

Configuring IDs

To allow overlapping of coverage cells and roaming between cells, wireless stations and access points use a combination of ID numbers. Each access point must have a unique *network ID* so that stations communicating with that access point can unambiguously identify their packets. This allows access point coverage areas to overlap while keeping packets intended for each access point separate. Network ID doesn't matter for client stations except for ad hoc networks without an access point—then all stations must have the same network ID.

To identify that they are all part of the same greater network, all access points and client stations share a common domain ID. The domain ID is transmitted publicly, so for security, the access points and stations must also have a common beacon key, which is encrypted in transmissions. The domain ID and beacon key signify membership in the same extended infrastructure network, and client stations can move freely between access points without losing their network connections.

Setting these IDs is a big part of the Wave-LAN configuration process. While AT&T's and Digital's access points have blinking LEDs to indicate status. neither has any sort of control panel for setup. Instead, you use a separate workstation to configure them, and here is one place where the two companies differentiate their offerings.

With Digital's RoamAbout Access Point, you connect a serial cable from a computer and using a terminal program, access a series of text menus to set IDs and roaming parameters. We had no problem using the Windows Terminal program to do this. With AT&T's WavePoint, you perform setup through a LAN connection, either wired or wireless, using a program called the Configurator. The wired LAN approach is easier to set up than Digital's approach because you don't have to find and attach a serial cable.

If you choose to set up the access point from a wireless station, however, you're in for trouble. To get the station up and running, AT&T offers a batch file that creates a boot disk with the necessary wireless LAN driver and configuration parameters. Once you have booted the station with the disk, you run the Configurator to define a configuration file and upload it to the access point. Unfortunately, the boot disk sets your workstation to one network ID and the WavePoint comes set to another, so the WavePoint ignores the transmission.

You must edit a file on the boot disk to correct the network ID and then reboot and upload the new configuration. Of course, if the new configuration includes a different network ID, you must modify the boot disk again to the new ID so that the next time you use the Configurator, it will use the new network ID. Most of this should be handled automatically, perhaps by the Configurator itself. Until this problem is fixed, you should upload the access point configuration file over the wired network.

It Gets Worse


Documentation for both products is abysmal, and in at least one instance, it's plain wrong. The Digital RoamAbout Access

FILE TRANSFER PERFORMANCE AND ROAMING

Moving large files is a weak point for wireless LANs. Compared to transmission on a 10Base-T LAN, transfer of a large file (4,027,556 bytes) to a wireless WaveLAN station took more than eight times longer. Wired/wireless performance differences with other types of operation won't be as dramatic. Moving the file between stations in different access point cells added a 6 percent delay to the transfer. The case with roaming adds the further delay it took for a station to hand off from one access point to another. Results for AT&T and Digital LANs were essentially identical with low traffic on the wired part of the LAN (the test conditions).

	TIME (S)	THROUGHPUT (BYTES/S)
Wired to wired	16	251,722
Wired to wireless	132	30,512
Wireless to wireless	139	28,975
Wireless to wired to wireless	148	27,213
Wireless to wired to wireless (roaming)	153	26,324

Reviews Local Air Networks



constant load created

and measured by NSTL's

low-level packet blaster

larger (512-KB) packet

throughput saturated

was identical for AT&T

conditions (all stations

and Digital wireless

LANs under our test

in a single cell).

program. With the

size, aggregate

with four active stations. Performance

Point manual states that you use hexadecimal values to set certain roaming thresholds, but the setup program actually requires decimal values.

Digital's PCMCIA radios have no installation program. You have to manually copy the programs over, add a line to your CON-FIG.SYS file to run the enabler program, and make sure your extended memory manager excludes

the memory window that the adapter uses. If you run Windows, you have to add an EMMExclude line to the 386Enh section in your SYSTEM.INI file to exclude the same memory window. A simple install program should handle all this.

AT&T provided a batch file that copied files over and another batch file to create the Configurator boot disk. But after that, you had to walk through the exact same steps as with the RoamAbout.

Installation under NetWare can be problematic for both products because of inadequate documentation. Both manuals describe how to add domain ID and

beacon key statements to your NET.CFG file, but they don't mention that you should place the statements directly after the Link Driver statement or that you should indent them from the left margin. Less experienced Net-Ware users would certainly appreciate a couple of explanatory sentences added to either company's manual.

Home on the Range

Once configured, we tested roaming with the AT&T and Digital for Workgroups 3.11 and Net-Ware 3.1. Supplied with NDIS and ODI drivers, both products work with any DOS- or Windows-based NOS (network operating system). Under WFW, because there were no installation programs, we had to manually set the domain ID and beacon key in the PROTOCOL.INI file. After that, we were able to move between access point cover-

age areas without dropping the connection and without significant performance degradation.

To test the WaveLAN and RoamAbout products, we acquired eight PC Card adapters and two access points from each manufacturer. For client stations, we used a variety of notebook PCs: one 486DX4 and one Pentium each from DTK and

Micro International, two Toshiba T1910s (486SX), a Toshiba T4900CT (Pentium), and a Toshiba T2150CDT (486DX4), Unfortunately, the WaveLAN and Roam-About systems require complete Intel PCMCIA chip-set compatibility, which kept us, for example, from using two Business Audio notebooks from Austin Direct (Databook PCMCIA chip set).

For planning layout of access points,

both WaveLAN and RoamAbout products come with software that lets you use a wireless

station as a monitor to test signal quality. You can monitor both access points and other wireless stations. We used it to verify that we had overlapping coverage between access points and to confirm that open-air range met the manufacturers' claim of 800 feet. It did (over 900 feet, actually). We also found a hand-held network tester worthwhile to determine if initial setup problems came from an access point itself or its connection to the wired LAN. Microtest's Compas tester saved many hours of hair pulling.

The BYTE editorial offices occupy a 45-year-old building with a mixture of fairly solid interior walls and large open areas divided into cubicles with 5-foot-high partitions. Two WaveLAN stations placed 150 feet apart at either end of the building were just out of range so that our roaming test setup with two access points was appropriate.

Using two access points allowed testing of

wireless roaming capabilities. By generating

network traffic with as many as eight client

stations within a cell, we could also begin to


We tested with two active access points in three different configurations: two AT&T WavePoints, two Digital RoamAbout Access Points, and with one of each. We measured no significant throughput differences between file transfer tests with the AT&T and Digital products, so the file transfer performance numbers involving two access points represent the case where we had one of each type of access point. Wave-LAN and RoamAbout radios also performed identically, so we could mix and match adapters during testing.

To provide an idea of how WaveLAN compares to standard wired Ethernet, we

transferred a fairly large file between a variety of combinations of wired and wireless stations. Throughput between two wireless stations was 28,975 bytes per

second, well below the 251,722 Bps we got when moving the same file between two stations on our unswitched 10Base-T network. Data transfer speed between a wireless station and a wired station was somewhat faster at 30,512 Bps.

We then moved the same file from a wireless station, to the access point, across our wired network, and out the other access point to another



FAST, FLEXIBLE STATISTICS & GRAPHICS FOR SERIOUS SCIENTISTS

Biologists • Environmental Researchers • Medical Researchers • Psychologists • Statisticans

Discover hidden patterns in your data easily.

With SYSTAT, it's easy to overlay, combine charts and to simply rotate even the most complex 3-D plots with the press of a button.


Display geographic clearly and quickly.

package which lets you easily combine axes, contours, surfaces, scatterplots and icons on any map.

b 3 Z

Display your raw medical data in a simple, easy-tounderstand format.

SYSTAT is the first statistical package to offer automatic dot plots.



STRUCK STRUCKS SET AT MEDI PET STILES PET STREET

SYSTAT is the only statistical

70

ffUl

Temperatures

Rinter 20

10



SYSTAT is the only package which can combine kernel density, contours and other graphical objects inside scatterplot matrices.

YOU CAN RELY ON SYSTAT FROM DATA TO DISCOVERY

"...nearly every kind of statistical analysis imaginable, and its graphics capability is far and away the best of any PC statistical package." - InfoWorld

"...the most flexible program for graphical representation of numeric data...and it has the most comprehensive procedures for data exploration." - MacUser

"...the best software for analysis of designed experiments...superb graphics, high quality statistical algorithms..." - PC Magazine

Comprehensive statistics for all types of scientific data

- A full range of powerful statistics
- Work with an unlimited number of variables
- Robust algorithms give precise, accurate results even when your data are extreme
- Most powerful GLM procedure
- Design of experiment procedures include Taguchi, Plackette-Borman, Box-Behnken, Latin Squares and mixture models
- Extensive matrix procedures for finding inverse, Cholesky decomposition and many others

The most graphics

- More graph types than any other statistical package - even more than Sigma Plot, Delta Graph and Harvard Graphics combined
- Extensive, high-precision world maps

- Flexible, easy-to-control object-oriented graphics
- Interactive graphical transformations tools to explore data
- Fast problem-solving capabilities, including Quick Buttons, Quick Graphs and a powerful internal calculator
- Object-oriented graphics to easily edit all aspects of your graphs and charts
- Extensive graphical tools for exploring your data in real-time, including 3-D rotation of graphs, color and grayscale fill defaults and rescaling

Extensive programmability and flexibility

- Choose command line or easy-to-use menus
- Handles all steps in analysis data analysis, screening, intermediate, graphic presentation













SYSTAT is available for DOS, Windows and the Macintosh. For more information. contact SPSS Inc. at

> 1 (800) 543-5835 (312) 329-2400 fax 1 (800) 841-0064



Reviews Local Air Networks

wireless station. Overall throughput in that case was 6 percent less than the wirelessto-wireless case. We also tried this test while moving one of the workstations between the access points. Performance was slightly reduced, but we were impressed by how well the products handled roaming, especially when we tested with an AT&T WavePoint at one end and a Digital RoamAbout Access Point at the other (see the table "File Transfer Performance on page 202").

To estimate how quickly wireless stations could saturate the available bandwidth within a wireless cell we gauged throughput with different numbers of active stations. To measure throughput, we ran a low-level IPX test developed by NSTL that blasts IPX packets between pairs of stations. We tested with one pair of communicating stations and then two, three, and finally four pairs all simultaneously blasting IPX packets. We also varied the size of the IPX packets, first using 64-byte and then 512-byte packets.

Aggregate throughput hit the wall with just two pairs (four stations). Adding stations beyond that reduced

the individual throughput between pairs of stations without increasing aggregate throughput. Using bigger packets increases throughput. With 512-byte packets, mea-

Product

RoamAbout PC Card Information Adapter

RoamAbout

RoamAbout Access Point...\$1795 Digital Equipment Corp. (800) 457-8211 (508) 692-2562 fax: (508) 392-0603 Circle 979 on Inquiry Card.

WaveAround

WaveLAN PC Card Adapter..\$695 WavePoint Access Point....\$1995 **AT&T Wireless Communications** & Networking Division (800) 288-9283 fax: (513) 445 5552 Netherlands: +31 3402 97554 fax: +31 3402 97555 Circle 980 on Inquiry Card.

sured throughput was twice what it was with 64-byte packets.

Power consumption is an important consideration with wireless adapters, especially for more mobile stations. We ran the BYTE battery test with our Thumper II test system on a Toshiba T4900CT (a 75-MHz Pentium notebook), both with and without a WaveLAN adapter plugged in. Without the adapter, the Toshiba ran for 4 hours and 15 minutes. With the LAN card plugged in and not actively broadcasting, the Toshiba's batteries lasted just 3 hours and 5 minutes, a substantial drop. Be-

cause WaveLAN acts in peer-to-peer fashion even when using access points, implementing power management is difficult, and neither company does it.

On the Roam

DAVE ROWELL

ntil recently, access points limited the mobility of wireless stations. To stay connected to a wired LAN through an access point, a station had to remain within range of that particular access point. Even if you had a number of access points set up into a sort of cellular network covering your entire facility, you couldn't actually roam and remain connected because there was no capability to automatically hand off from one access point to the next.

To allow roaming, WaveLAN-based access points use a combination of advertising to client stations and coordinating among themselves. The advertising is in the form of message frames called beacons, which the access points broadcast every 200 milliseconds or so. Beacons contain the domain ID, the beacon key, and the access point's network ID, the last two encrypted together.

Clients decide which access point to attach to based on signal strength. When a client registers with a new access point. its sign-on request message includes the network address of its old access point. The new access point can then notify the old of the change so that packets addressed to the client will arrive at the right destination.

To prevent periods of reduced throughput from lost frames, WaveLAN-based clients switch access points before transmission drops off. The switching process uses a set of rules with three configurable signal strength thresholds so that switching occurs in time, but not unnecessarily. When the signal-to-noise ratio of transmissions from the current access point drops below 24 percent, a station goes into a promiscuous mode.

It's still getting 100 percent of access point transmissions, but the station starts decoding other access point beacons and will register with another access point if the signal-to-noise ratio is 30 percent or higher. This higher threshold ensures that a station doesn't bounce back and forth between two access points with similar signal-to-noise ratios, thereby degrading performance.

If the signal-to-noise ratio drops 18 percent, a point close to where frames start dropping, a station goes into a fast search mode. Now it will accept any access point providing a signal-to-noise ratio greater than 24 percent, Again, the higher threshold provides a hysteresis effect that prevents bouncing.

Dave Rowell is a BYTE technical editor, You can reach him on the Internet or BIX at drowell@bix.com.

Limited Performance

It isn't a surprise that wireless LAN performance wasn't up to par with a wired LAN. However, we were surprised by how quickly we reached the limits of the wireless LAN. With only four stations actively sending packets back and forth, we had effectively reached saturation. Adding stations brought no additional bandwidth, it just reduced each station's available bandwidth while keeping the aggregate throughput the same. Under more normal usage patterns, it would take more stations to saturate WaveLAN.

What's great about AT&T WaveLAN and Digital RoamAbout is that they work well together. We expected the PC Card radios to interoperate because they are identical; however, we were pleasantly surprised at how well the access points worked together, letting us roam back and forth between the two implementations.

In comparing the two, the edge goes marginally to Digital's RoamAbout. Both vendors have lousy software setup and painfully incomplete documentation. We liked the fact that the RoamAbout Access Point used the same PC Card radio as the rest of the wireless stations and can take other types of radios. Digital's access point setup was easier than AT&T's somewhat byzantine WavePoint setup process. But because they interoperate so smoothly, you can just pick and choose the pieces of each that you like.

Rex Baldazo is a BYTE technical editor. You can contact him on the Internet or RIX at rbaldazo@bix.com.



Oracle Hits the Road

Oracle Mobile Agents take over network transactions so that wireless clients can get to corporate data in seconds

PETER WAYNER

any people who tend to work "in motion" know the siren call of wireless networking, but until recently, there have been few products that simplify the technology. Creating a wireless network is not as simple as taking a traditional network and replacing the wires with radio transceivers. Old network protocols don't work well in the radio environment, which is susceptible to weather, noise, crosstalk, and other demons of the ether.

Now that the technical hurdles of wireless data transmission are becoming well understood, software makers are helping programmers tap the power of wireless networks. One of the first to do so is Oracle (Redwood Shores, CA), whose Oracle Mobile Agents toolkit essentially solves the problem of shuffling information between distant, wireless clients and corporate database servers. The toolkit can handle communication with any program, not just Oracle's database products.

Agents in Motion

Oracle Mobile Agents is structured around a client-agent-server model that interposes a software agent between client and server (see the figure "The Client-Agent-Server Paradigm"). The agent runs on the server machine and is responsible for handling requests from off-site clients. It then takes the requests and gets answers from the server. Ideally, the agent programmer can incorporate enough intelligence in the agent to significantly reduce the amount of network traffic between the server and the client.

Many protocols that run over wired networks often exchange several messages to establish a connection before processing any information. This is fine when the speed of the network is blindingly fast, but it fails quickly on wireless networks, which often require 2 to 4 seconds to transmit a single packet. The Oracle Mobile Agents' job is to roll all this interaction into one packet. (For a more detailed breakdown of the different transmission media's response times, see the figure "Speed in Response Time" on page 208.)

Oracle's definition of an agent is different from General Magic's (Mountain View, CA), the creator of the heavily anticipated agent language Telescript, which at the time of this writing was still unavailable to the general public. Telescript is virtually a full-fledged OS, with agents roaming around in it that are themselves full-fledged programs capable of interacting with each other. Oracle takes a simpler, more evolutionary approach. Its agents are simply plug-in software modules that programmers can use to add functionality to Oracle Mobile Agents. These agents can't roam from machine to machine: They are closer to Adobe Photoshop plug-ins or applets than they are to full applications.

This lack of functionality is not much of a handicap. Some people might even call it a feature. The Telescript approach is clean and thorough, but it can be overkill for simple applications. Oracle Mobile Agents lets you choose the right amount of power for your purposes.

On one end of the scale might be a simple "Hello, world" agent that will respond to any message with the string "Hello, world," all done in 200 lines of C code. The result would have none of the generality or complex authentication features bound up in Telescript, but it would do the job. On the other end of the complexity scale might be an agent with a built-in

parser and interpreter that will accept arbitrarily complex programs as messages.

After you write the agent, Oracle Mobile Agents takes over the handling of the data between the wireless network and the server. It aggregates the incoming packets until the complete message is available. If transmission glitches garble the data, the software handles getting new copies of the missing or scrambled packets. When the message is complete, Oracle Mobile Agents fires up the correct agent and hands it the message. This makes life easy for programmers because they need to write only agent code that accepts a full-formed message.

Using the Toolkit

Oracle Mobile Agents comes with two major development components. One lets you create agents for Unix systems, and the other lets you build both agents and clients running on Windows machines. The Unix agents, which run as processes, access a central message gateway that interfaces with the radio network. Time-sharing between multiple agents running on the same server is handled by whatever Unix variant is serving as your OS. Users with bigger databases or more-complicated installations will probably choose to run Unix on their server.

You can use the Windows development component to create clients and agents.

The Client-Agent-Server Paradigm

| Application | Client | Client | Customer-written | Cu

Reviews Oracle Hits the Road

The core is a message manager that runs as a separate application. When client-based applications want to access distant agents, they communicate with the message manager by either calling functions in a Windows DLL or passing an OLE 2.0 object. The message manager handles the chores of communicating with the distant agents. The manager is flexible because it can communicate using a wireless network, phone lines running PPP, or a standard LAN. This gives better service to people who have a wired connection handy at a certain moment.


Modifying your application to send messages to an agent is fairly easy. The application must create a connection by asking for the distant agent by name. (When the agent is started on the distant server, its name, IP address, and port number are published.) If the local message manager can find the agent through the wireless network, then the connection is established.

You must also arrange for information to flow from the message manager to the application by either initializing a DDE link or identifying an OLE 2.0 notification link. The server-based message manager will send any incoming traffic intended for an application through this path.

Once a connection is established, the application can pass messages back and forth to the agent with a simple procedure call or object transfer. Oracle Mobile Agents packs the data correctly and negotiates with the radio network to ensure that the data arrives.

For example, a program written in Microsoft Visual Basic can communicate with a distant agent with four straightforward commands. First, the program establishes a connection using the command Set ConObject=GetObject("Agent Name", OLE_MM_CONNECT). Next, it creates a new outgoing message using the command Set OutMessage-Binding _VBMxLib.GetNewOutGoingMessage.The program packs the contents of the message using the command OutMessage .PutVar. The Visual Basic routines are smart enough to pack the messages correctly based on data types. Finally, the command OutMessage. Send sends the message on its way.

The rest of the application must contain code for interpreting arriving messages. This can be as simple or as complicated as your application demands. The struc-



ture of the basic code, though, is a simple case statement. The libraries for C are just as easy to use.

Oracle Mobile Agents comes with instructions for building these Windows applications using Visual Basic, various vendors' C/C++ compilers, Powersoft's PowerBuilder 3.0, or Microsoft's Excel 5.0. The manual also comes with a sample application that you can use as a skeleton for building the system. The Unix software comes with several sample applications that also make good skeletons.

Testing While in Motion

To test Oracle Mobile Agents, we used preexisting applications and wrote our

own. First, Oracle allowed us to access a suite of simple programs written for internal corporate use, including an E-mail package, a stock quote server, and sever-

al other database applications. We then wrote the client packages in Visual Basic and loaded them on an IBM ThinkPad 360C notebook computer equipped with a Motorola InfoTac radio modem. We used Oracle's E-mail and stock link for several weeks in a variety of locations throughout Washington, D.C., Baltimore, and New York City. This approach also gave us experience using the RAM Mobile Data network, which shuttled requests between the ThinkPad client and the agent/server combination at Oracle's headquarters in Redwood Shores, California.

RAM Mobile Data coverage is significantly broader and more reliable than it was when we tested it several years ago. The InfoTac modem was able to establish a link in most cases. But it would not work in the basement of a house in a hilly region of Baltimore or in the inner rooms of

a New York City apartment. In both cases, the service worked fine when we moved the radio modern closer to a window.

During this period of intense use, the Oracle Mobile Agents software didn't trash messages, deliver bogus stock quotes, or mangle E-mail. Problems crept in only when we couldn't get a strong signal, a condition that was clearly indicated by a light on the modem.

We also created several simple agents, along with applications to call them. We wrote the agents in C by using the RAM Mobile Data network to talk to a Unix box at Oracle headquarters. For applications, we used Microsoft's Visual Basic on the IBM ThinkPad 360C. The process went

without serious glitches. Anyone with some experience programming in either C or Visual Basic should find the software easy to use. The Oracle Mobile Agents team has

obviously anticipated development problems and included a fair number of debugging features.

Wireless Made Easy

Oracle Mobile Agents

1.0.....\$747 and up

Redwood Shores, CA

Circle 976 on Inquiry Card.

(415) 506-7000

Oracle Corp.

If you maintain a network server containing data that might be valuable to people who spend most of their workday away from phone lines, then Oracle Mobile Agents offers a reliable, fairly easy way to build a link between your network server and a wireless modem. You don't have to think deeply about roaming agents or complex network strategies. Oracle Mobile Agents' designers did the hard work for you.

Peter Wayner is a BYTE consulting editor and the author of Agents Unleashed (AP Professional, 1995). He can be reached on the Internet at pcw@access.digex.com or on BIX at pwayner@bix.com.



Hands-Off Backup

Bundled with Palindrome backup software for NetWare, HP's SureStore Tape 12000e DAT Autoloader can provide weeks of unattended network backup

BILL LAWRENCE

ff-site administration of small LANs is becoming more and more common. With the networking of small businesses and corporate field offices, nonresident administrators and off-site consultants cleverly use remote control software, dial-up routers, or low-speed WAN links to manage the LANs in their care. These remote tools permit off-site administrators to manage LANs from afar in just about every way but one: Someone still has to be physically present to handle the mundane but vital task of changing backup tapes.

To help in this area, Hewlett-Packard has developed a loose product specifica-

tion called LABS (Low Admin Backup for Servers), which combines an autoloading tape drive with highly automated backup software (see the textbox "HP Pushes Automated NetWare," March BYTE, page 148).

HP SureStore Tape 12000e LABS for Novell is the first product to implement LABS. It couples HP's SureStore Tape 12000e autoloading DAT (digital audiotape) drive with a custom version of Palindrome's

NetWare-compatible Backup Director software, called Backup Director for the Workgroup. The 12000e is a DDS-2 DAT drive with a six-cartridge magazine. Presuming you use the magazine as it comes with five 120-meter, 4-GB tapes and one cleaning cartridge, you've got 20 GB of available storage, or around 40 GB with the 12000e's built-in data compression.

Backup Director takes advantage of the 12000e's automation features by handling tasks like tape drive cleaning and monitoring for problems. For example, the software automatically schedules restore and compare operations for periodic verification.

If problems occur, Backup Director can send alerts via NetWare's SEND command or MHS-compatible E-mail. The drive includes standardized alerts for common maintenance conditions, such as when a tape cartridge should be retired because it's reached the end of its duty cycle or

The combination of HP's
12000e DAT autoloader
and automated backup
software from
Palindrome will reduce
on-site visits by
nonresident
administrators. The
SCSI drive holds a
magazine (inset) of five
4-GB DDS-2 cartridges
and one cleaning
cartridge.

(and a driver that's ASPI [advanced SCSI

because it's failed. The 12000e's high capacity coupled with Backup Director's completely automated management of backup sessions means you can run daily backups that need no attention for amazingly long periods.

High Capacity, Low Price

The 12000e is an external SCSI drive that comes housed in a 5.25-inch full-height case. Its easy-to-read LED front panel displays the drive's current status, including which magazine cartridge is loaded. The 12000e is among the first drives to support the DDS-2 DAT specification, which calls for a cartridge capacity of 4 GB and a maximum sustained transfer rate of 510 KBps. The drive's built-in data compression typically doubles both those figures.

When used with Backup Director, the 12000e is directly connected to a NetWare 3.x or 4.x server with a SCSI controller

(and a driver that's ASPI [advanced SCSI programming interface] compatible). In our tests, the primary server was a 486DX/33 PC with an ISA bus and two 400-MB IDE drives. Connected to an Adaptec 1543 ISA controller, the 12000e backed up at speeds averaging 25 MB per minute. Large restores went more slowly because Backup Director makes a special pass through the tape to restore directories first and then makes a second pass to restore files.

DDS-2 compares favorably with the popular 8-mm tape drives (precompression capacity of 5 GB to 7 GB and transfer rate of 500 KBps) from Exabyte, particularly when you consider cost per megabyte. Exabyte single drive units without autochangers typically sell in the mid-\$3000 range, approximately the same price that you pay for the 12000e with its capacity leveraging autochanger.

Strategy Included

If you've got better things to do than master the intricacies of a full-featured backup program, you'll love Backup Director. Simply install the software on the same NetWare 3.x or 4.x server to which you've connected the 12000e autochanger, insert the tape magazine, and forget about it. D JUDICE @ 1995

Reviews Hands-Off Backup

The Palindrome software automatically performs a full weekly backup of your server with daily incrementals in between. Backups start automatically at midnight, and after each week of backups, the Backup Director software repeats the cycle on a new tape. Thanks to the 12000e's fivetape magazine capacity (six with cleaning cartridge), you can store five iterations of backups without any intervention on your part.

While five weeks of unattended backups is enticing. leaving all your tapes and your

server in the same room means your backup efforts will come to naught if fire or natural disaster strikes that room. Fortunately, Backup Director makes it easy for you to implement a weekly off-site tape rotation regimen. All you do is specify the day of the week when you want to switch your tapes, and when that day comes, Backup Director will prompt you to insett a new magazine.

Self-Service Restores


Since HP designed the 12000e LABS for Novell combo to liberate network administrators from having to physically attend to backup issues, it's only logical that the package should also free LAN managers from that most unscheduled interruption of them all—the file restore. As any experienced network administrator knows, the most frequent reason that files need

restoration is not disk failure, it's pilot error-a user accidentally overwrites or deletes an important file and then needs to have it back.

Making good use of the HP autoloader, Palindrome's software empowers network users to pertheir own

restores through a Windows client program. The client automatically installs in the PUBLIC directory of the server, making it easy to launch. Using the program's File Manager-like interface (see the screen shot), users can browse for the files they need to restore, cruising through a database of backup sessions that Backup Director maintains on the server.

The Windows client includes a "recov-



ery expert" that coaches you through the steps required to prepare and launch a file restore. You can also create sophisticated file-finding and filtering configurations that make it easy to pinpoint a file buried in a haystack of backup database information.

Backup Director could be easier to install, particularly on a NetWare 4.x server. With NetWare 3.x, the software installs easily enough. It automatically creates a user named BACKUP with supervisory access to the server, loads the appropriate NetWare target service agent module for your NetWare version, and it's ready for action. With NetWare 4.x, you have to create the BACKUP user yourself. And with NetWare 4.1, the installation process fails to load the correct target service agent, which means initial backup attempts fail until you manually

HP SureStore Tape 12000e LABS for

HP SureStore Tape 12000e

additional preloaded DDS-2

cartridge magazine...\$160

Hewlett-Packard Co.

Santa Clara, CA

(800) 826-4111

(415) 857-1501

(no software).....\$3650

Circle 1000 on the Inquiry Card

(includes Palindrome BackupDirector

for the Workgroupsoftware)....\$4650

Novell

Product Information

load this module. With neither Net-Ware version does the install program offer to modify your server's AUTO-EXEC.NCF file so that the right modules automatically loaded every time you start the server.

Backup Director's ease of use comes at the sacrifice of some advanced features. Network managers, for example, can't use the backup software to move large groups of files from one volume or server to another. The program restores files only to the server and volume from which they were backed up. The HP Sure-Store/Backup Director combination is also a one-server-only solution. Though the Palindrome software complies with Novell's SMS (Storage Management System) specification,

> which provides for backing up any device running a target service agent module, you can backup only the server attached to the 12000e drive. That also means you can't back up drives on

client workstations.

If these limitations bother you, there are or will be other backup packages available that support the 12000e. Palindrome offers its more fully featured Network Archivist, and Legato

Systems has Staccato, a LABS product for the 12000e. Cheyenne Software is adapting ARCserve for use with the 12000e, as is Arcada Software with its Backup Exec for Windows NT.

That Just Released Feeling

BYTE received a 12000e LABS package about two months after Hewlett-Packard first started shipping this hardware/software combination. We quickly discovered a bug that seemed to prevent recovery under some circumstances from the most severe of hardware emergenciesthe complete failure of a server disk volume. Though you would normally call your HP dealer to solve a problem, we called HP tech support directly. A support technician responded promptly to our call but had no immediate answer to our problem, even though full-volume restores are generally urgent matters.

Hewlett-Packard and Palindrome later determined that we were running version 3.5 of Backup Director, which they stated was included only with the earliest shipments of the product. They supplied us with version 3.5a, which completely solved the problem. If you happen to buy the drive with Backup Director version 3.5, insist on getting an upgrade.

Despite a few maiden-voyage anomalies, the 12000e LABS for Novell package with its Backup Director software bring unprecedented ease of use to a network task that is long overdue for simplification.

Bill Lawrence is part of a team that manages a 2800-node network for a major Western utility. He is the author of Using Net-Ware 4.1 (Que, 1995) and Using NetWare 3.12 (Que, 1994). You can reach him on the Internet or BIX at blawrence@bix.com.



Better Business Processes

A customized linked spreadsheet gives Process Charter for Windows the smarts that plain flowcharters lack

DAVID ESSEX

lowcharting, like outlining, is one of those things you should have taken more seriously in college. When faced with the chaos of work in the Age of Downsizing, you come to realize that, far from being a pointless exercise, flowcharting can be the best way to conceptualize a process that needs fixing.

Scitor Corp. has hit on an absurdly simple idea. Instead of merely making a robust set of graphical flowcharting tools and offering links to spreadsheets, Scitor has coupled an actual, process-optimized spreadsheet to the drawing tool. The result is Process Charter, an easy-to-use program that lets you simulate processes depicted in the flowchart.

We used Process Charter to design a half-dozen flowcharts depicting various editorial processes, both existing and wished-for. We ended up throwing most of them out, learning much about the proper uses and key limitations of Process Charter along the way. (The moral: make sure you've clearly designated the entities that flow through the system; or, a system framework does not a simulation make.) We ended up converting an existing paper flowchart of a BYTE article's flow through the magazine's editorial, design, and production departments. A work in progress, this imposing chart is potentially an important tool for editorial management.

Discrete Events and Queuing

Process Charter is a discrete event simulator. It calculates the state of the system elements at discrete points in time. At a higher level, systems are either deterministic or stochastic: perfectively predictable if all conditions are met, or relatively more random if some conditions are varied. Of the stochastic type, simulations may be either continuous or discrete, which are to each other what analog is to digital. In discrete models like those created by Process Charter, systems are profiled by taking "snapshots" of the system state at fixed intervals.

Hand-in-hand with discrete event simulation is the concept, often seen in computer science, of queuing. In the context of simulation, queuing is widely relevant

because it models the basic input-processoutput functions of all systems. But queuing in the same context also means lining up and (sometimes) waiting for service. Simulation textbooks often cite a classic queuing problem: customers lining up at a bank to wait for the next available teller. Not surprisingly, Process Charter comes with a sample bank-teller simulation, which is explained in the figure, "The Bank-Teller Queuing Problem" on page 212.


It's not hard to see why queuing is a key

concept in Process Charter. A case in point: in our article-flow simulation, queues can result if articles enter the system faster than any one component can process them. A queue then becomes a bottleneck to be avoided by redeploying resources. Process Charter gives you specialized Flow Model and Key Values spreadsheets (again, refer to the figure) for identifying bottlenecks by examining time values in cells.

Charting the Process

The first step in modeling a process with Process Charter is to create the flowchart. Here, the program works like a standard flowcharting tool. Toolbar icons and menu items let you access the three main views: diagram, spreadsheet, and graph. In the diagram view, the main control panel is a square on the left toolbar containing four small icons, each representing an entry mode: Select (for selecting a chart item for some additional operation); Figure, Line, and Text. We found ourselves relying on the mode buttons almost exclusively, even though most icon functions are duplicated in the drop-down menus, and a few functions (like line creation) are available via mouse control in other modes.

A palette of standard shapes (e.g., a diamond for a branching decision point,



Scitor helped Boeing use Process Charter for Windows to determine that daily maintenance procedures would take 27 hours to complete unless some jobs were done in parallel. The flowchart and simulation were later used for training maintenance personnel.

a parallelogram for input/output, etc.) sits handy along the left side. To use a shape, you click once on the palette icon, then point at the main window and click again to place the object. Connections between objects are most easily established by clicking in the middle of the originating object and dragging to the location of the destination object. An arrow will appear between the two figures. Alternatively, you can drag-and-draw lines in Line mode, but we sometimes found Process Charter too smart for its own good as it tried to figure out the best path between objects. Lines seemed to wrap unexpectedly around the far sides of objects, and one time, we ended up with a tangle of lines that looked too confusing. We could have used a menu command to delete all the lines, but we scrapped the entire chart instead.

Once you've got a dozen objects and lines on the screen, the ability to modify the configuration becomes critical. Here, Process Charter provides adequate tools, chief among them the ability to draw a box around an area and drag it. You can also reshape lines and make objects "snap to grid" so they line up with each other after your reference points have scrolled off screen. We did, however, find ourselves wishing for more intelligence in

Rackmount

- **ENCLOSURES**
- **KEYBOARDS**
- **MONITORS**
- **DRIVE ENCLOSURES**

141111111111111111111111111111111111

Integrand's unique enclosure design uses modular construction. We have 3 basic models for ISA/EISA bus computers. Over 100 interchangable modules allow you to customize them to nearly any requirement. Integrand offers high quality, advanced design hardware and strong support. Why settle for less?



Monitor: 10" Super VGA Color from \$650 PC Enclosures from \$300

Keyboards: Drawer, Shelf & Panel from \$85

Made in U.S.A.

Rack & Desk Models

Accepts Most Motherboards and Passive Backplanes

Up to 20 Slots

Rugged, Modular Construction

Excellent Air Flow & Cooling

200 & 300 Watt Supplies, UL, CSA, TUV

Call or write for descriptive brochures, prices or applications assistance:

8620 Roosevelt Ave. . Visalia, CA 93291


209/651-1203

FAX 209/651-1353

We accept VISA and MasterCard Circle 72 on Inquiry Card.

EMIXTIAT TM IBM - 286/386/486 TM INTEL. Drawn and come

Reviews Better Business Processes



the way Process Charter handles inserts. Rather than having to carefully draw a circle around a wide swath of objects to clear space for a new one, it would be nice to insert a figure and its associated lines and have the program move everything else down for you. It's the flowchart equivalent of the word processor's insert key, and it would save users the hassle of untangling lines and uncovering figures.

This is only a taste of Process Charter's flowcharting powers. There is a whole range of tools for changing colors, shading, typestyles, figure sizes, and so on.

The Smart Parts


The next step is to put some numbers behind the flowchart objects. For this, Process Charter offers a fairly clean input mechanism that does, however, come with a moderately steep learning curve. In a nutshell, you have to define resources (typically people and their pay rates) in the Resources spreadsheet, and then access the Activities dialog box to associate the resources to each action. When Process Charter

runs through a simulation, it uses these definitions to quantify run times and costs. You also use the Activities box to establish the times (fixed or random within a range) that it takes to finish one task before going to the next one. Other variables in this box control such things as the size of the queue, routing choices, and timing flows through the system.

Click on the running-person icon, and up pop dialog boxes for setting up the simulation. Here, you choose the start and end times, as well as the seed value, which Process Charter assumes to be limited only by time unless you name a number. You can then either run the simulation at the predetermined speed or step through it; Process Charter highlights each activity as it is being activated. Speed seems to bog down, as you might expect, as the

Win a Notebook Computer!

BYTE's research department would like to know what your computer notebook requirements are. Please take a few minutes to fill in this form by July 31 and you will automatically be entered in the sweepstakes. The prize is this WinBook XP, a DX4-100MHz notebook.



6 (If you require a color screen) What



Portable: a notebook or subnotebook computer weighing 8.5 lbs. or less.
1 Do you plan to purchase a portable computer within the next 12 months? (Choose one.)
Definitely yes
Maybe (continue survey as if you plan to buy)
No (continue survey as if you plan to buy)
1A (If yes or maybe) Will this unit be paid for
by yourself or by your employer?
Self (please go on to Question 2)
Employer (please go to Question 1B)
1B (If paid by employer) Approximately how
many are employed by your company:
(Choose one.)
1000 or more employees
500-999 employees
100-499 employees
50-99 employees
Fewer than 50 employees
Uncertain6
2 Will you require CD-ROM with your next
portable computer? (Choose one.)
Yes, internal CD-ROM, built into notebook1.
Yes, external CD-ROM, connected to port or
docking station
No
Uncertain4.
3 For the unit selected above in question 2,
what weight would you be willing to accept?
(Ghoose one.)
4.5 lbs
5.0 lbs
5.5 lbs
6.0 lbs
6.5 lbs
7.0 lbs6
8 lbs. or more
3/6 H

4 What type of processor will you requ	uire?
(Choose one.)	
Intel 486 SX/33 MHz	
Intel 486 DX2/50 MHz	1
Cyrix DX2/50 MHz	3
Cyrix DX2/66 MHz	4
Cyrix DX2//80 MHz	5
Intel 486 DX4/75MHz	6.
Intel 486 DX4/100 MHz	
486, unsure which version	
Intel Pentium 60 MHz	
Intel Pentium 75 MHz	.10.
Intel Pentium 90 MHz	
Intel Pentium 100 MHz	
Intel Pentium 120 MHz	
Intel Pentium 150 MHz	
Intel Pentium, unsure which version	
AMD K5	
Cyrix M1	
Other	
Don't know	
4A What type of bus will you require?	
PCI only	
ISA only	
Both PCI and ISA	
No preference	
5 Which screen will you require for yo	ur
portable computer?	
Screen type (Choose one.)	
Monochrome	1.
Dual-scan color	
Active-matrix color	
Screen size (Choose one.)	
8.4 diagonal	4.
9.4 inch diagonal	
10.4 inch diagonal	
11.4 inch diagonal	
12.4 inch diagonal	
Larger than 12.4 inch diagonal	

resolution will you require? (Choose one.)
640 x 480 x 256 colors
800 x 600 x 256 colors
1024 x 768 x 256 colors
1280 x 1024 x 256 colors
1024 x 768 true color
Uncertain6
7 Will you require the following in your
portable, docking station or both?
Docking Portable Station Both Neither
Speakers11234
Available CD-ROM 5 6 7 8.
Available floppy drive9101112.
Parallel port
Serial port17181920.
Ethernet port
Infrared port25262728.
SCSI port
Tape back-up
8 (If paid by employer in 1A) Would your orga-
nization agree to purchase terms of net 45
days with 3% late fee stipulated? (Choose one.)
Yes
No2
Uncertain
9 What is the most important feature you
look for in a notebook computer?

Contest Rules

Contress trations

The contest is open to all U.S. residents 18 years of age or older. No purchase necessary. An individual may enter regardless of whether or not he or she chooses to participate in the survey. Entrants should fill out their daytime telephone number where indicated. Limit one entry per person.

Entries must be received by July 31, 1995 to be eligible for the drawing. The finalist will be determined in a random drawing to take place at BYTE. The winner will be contacted by telephone on August 1, 1995. Personal contact with the individual specified on the entry card must be made for the finalist to be declared the winner. If the winner cannot be contacted within 15 days of the drawing, then the unclaimed obze will be awarded to an elemante drawing, then the unclaimed prize will be awarded to an alternate whose selected at random. The winner shall be required to sign an affidavit releasing McGraw-Hill, Inc., from liability in connection with use of the prize.

The odds of winning depend on the total number of entries re-ceived by the cutoff date of July 31. Employees of McGraw-Hill, Inc., Winbook, their agencies, subsidiaries, employees and armilies are not etigible to participate in the contest. McGraw-Hill, Inc., is not responsible for lost, late, or misdirected mail or in-eligible entries. All fodoral, state, and/or local rules and regu-lations apply. Vold where prohibited by law. One prize will be awarded. Total value of prize is \$3900. The prize is not re-dependable for each, nor is substitition of the notre by the winner deemable for cash, nor is substitution of the prize by the winner allowed. The winner is responsible for any and all taxes asso-ciated with the acceptance of the prize. BYTE reserves the right to substitute a prize upon unavailability. For the name of the s to substitute a price upon in availability. For the halfe of the win-her, send a self-addressed, stamped envelope after August 1 to Winbook Sweepstakes, Marketing Department, BYTE Magazine, One Phoenix Mill Lane, Peterborough, NH 03458.

Title:		
City:	State:	7/pc
Phone:	Fac	




The PKWARE Data Compression Library products allow you to include state-of-the-art, patented data compression technology within your software applications. Data produced by the PKWARE Data Compression Library products is compatible across platforms!

The PKWARE Data Compression Library products offer an all purpose data compression algorithm which compresses ASCII or binary data quickly. An adjustable dictionary size allows software to be fine tuned for maximum speed or compression efficiency. The use of application defined callback functions allow maximum flexibility. No runtime royalties. The format used by the compression routine is completely generic and not related to the PKZIP® file format.

Versions available for DOS, OS/2, Windows, and soon for Win32.



Compatible with IBM Cset/2 & Borland C++ for OS/2.



 Requires 36k of memory to compress & 12.5k of memory to OS/2 Version \$350



Compatible with Microsoft Windows 3.x applications.

- Fully reentrant.
- The DLL requires 36k of memory to compress & 12.5k of memory to extract. Windows Version \$350



Supports both Intel & Alpha object modules.

- Compatible with Microsoft Visual C 32-bit & Borland C++.
- Requires 36k of memory to compress & 12.5k of memory to extract. Win32 Version \$375



- Compatible with popular 16-bit language compilers.
- Can be used in any memory model.
- Requires 35k of memory to compress & 12.5k of memory to extract.

DOS Version \$275



9025 N. Deerwood Drive Brown Deer, WI 53223-2437 Phone: (414)354-8699 Fax: (414)354-8559 Please add \$5.00 Shipping & Handling per package in the U.S. & Canada; \$11.25 overseas. Wisconsin residents please add 5% state sales tax & applicable county sales tax. No COD.







Copyright 1994, PKWARE, Inc. PKWARE, the PKWARE togo, PKZIP, and the PKWARE Data: Compression Library are registared trademarks PKWARE, Inc. Microsoft is a registared trademark and Windows, Win32, and the Windows logo are bademarks of Microsoft Corporation. OS/2 a the OS/2 togo are registared trademarks of International Business Machines Corporation. Trademarks of other companies mentioned here apper for identification purposes only and are the property of their respective companies.

BY695

number of activities per process rises. We were alarmed by a drastic slowdown on one test machine (a Tandy [AST] 486SX/ 33 with 4 MB of RAM-Scitor's minimum memory requirement) until we realized that our unlimited seed value was shoving articles through the process in gridlock-inducing volumes. You can also get into some trouble by monkeying with a variable that controls the real-time speed of each activity.

The light show pales in value to the copious reports that Process Charter creates post-simulation. As shown in the diagram on this page, the Flow Model and Key Values spreadsheets are usually your best analysis tools. Flow Model tabulates the raw numbers of objects that flowed through the system and the average time spent on each activity. Key Values summarizes the important Flow Model data. Here's where you nail bottlenecks and spot inefficient uses of high-priced personnel.

There's Nothing Like It

Besides the few quibbles already cited, a few more bear mention. The manual, though nicely laid out, methodical, and comprehensive, is missing index entries for such key terms as "seed," and several toolbar items are ignored, though you can find the references by flipping through text. The on-line help is similarly spotty, and the manual-based tutorial is too short. On the other hand, Scitor throws in three simple-yet-informative sample processes as well as some on-line case studies.

Deeper study of simulation is probably necessary to get the full value of the program. Furthermore, accurately depicting business processes in the flowchart takes much thought, while assigning honest numbers to the spreadsheets is a potential pitfall. Still, process modeling and simulation is an undeniably powerful tool, and Process Charter for Windows will likely do more than any previous program to make these disciplines accessible to non-specialists.

David Essex is a technical editor for BYTE reviews. He can be reached on the Internet or BIX at dessex@bix.com.

Product Information

Process Charter

Scitor Corp.

Menlo Park CA (800) 549-9876 (415) 462-4200 fax: (415) 462-4201 E-mail: info@scitor.com Circle 1004 on Inquiry Card.

Wanted: A Good OS/2 Spreadsheet

In the duel between OS/2 spreadsheets, Lotus and Athena Design left some empty chambers in their six shooters

DANIEL GASTEIGER

espite the recent popularity of IBM's OS/2 and its hipper, leaner offspring, Warp, none of the major spreadsheet developers have taken the technically impressive OS very seriously. Lotus has remained the key provider of OS/2 spreadsheet technology, but its product plays like a DOS version of 1-2-3 barely adapted to OS/2's GUI. And it lags way behind Lotus's other GUI spreadsheet, 1-2-3 for Windows release 5.

Meanwhile, a lesser known company, Athena Design (Boston, MA) has been running its own spreadsheet software, called Mesa, on Next machines. Late last year, the company began shipping Mesa 2.0.1, a totally new spreadsheet for OS/2 based loosely on the Next version. Mesa offers many advanced features, and its object-oriented approach makes it an excellent fit in the GUI environment.

Unfortunately, it seems as if Mesa's designers skipped history class on the day electronic spreadsheets were covered. Users raised on other platforms (1-2-3 or Novell's Quattro Pro for DOS; 1-2-3, Quattro Pro, or Microsoft Excel for Windows; or 1-2-3 or Excel for the Macintosh) will likely feel frustrated working in Mesa. With so many outstanding examples of the spreadsheet around, it's surprising anyone would ship such a powerful spreadsheet that falls short in so many areas.

GU! Enough for You?

1-2-3 release 2.1 for OS/2 is a full-featured DOS spreadsheet with many graphical goodies sprinkled in. Unfortunately, sprinkling does not a GUI spreadsheet make; 1-2-3 still feels as though it belongs in DOS. Lotus plans to change all this with the expected debut of Windows 95 in August. Lotus says the OS/2 Warp version of 1-2-3 will have some of the advanced GUI features of Windows 95. such as new right-mouse-button controls and a simplified user interface that employs a tabbed book metaphor. Modeless InfoBox widgets will let you change spreadsheet attributes and see the results without first closing dialog boxes. Tighter integration of suite applications is also


planned. The goal is to standardize features sets of the Windows and OS/2 versions of 1-2-3.

At the other extreme. Mesa is a GUI spreadsheet from the ground up, but it falls short of being full-featured. At least both products deliver on one feature that has become a spreadsheet standard: three-dimensionality. A 1-2-3 file contains 256 spreadsheet layers, and a Mesa workbook begins with one layer that you can add to as needed. If you're a graphical 3-D spreadsheet product, you really must have index tabs on your sheet layers. Mesa has such tabs, but 1-2-3 does not. Hand in hand with sheet tabs, Mesa gives you the ability to name sheet layers and to use the names in formula references. Nameable tabs simplify navigating in three dimensions and entering formulas that span several sheet layers.

In a poorly conceived departure from a GUI spreadsheet standard, Mesa places its sheet tabs on the right edges of its layers,

perhaps to conform to the OS/2 standard of running tabs down the sides of hypertext help pages. The Big Three Windows spreadsheets (1-2-3, Excel, and Quattro Pro) arrange tabs at the top or bottom edges, with the obvious advantage of sacrificing only one of 20 rows on the display rather than one of nine spreadsheet columns. Experienced spreadsheet users may find Mesa's seven-column display constricted.

GUI spreadsheets should also be able to show graphs and drawings alongside numeric data. 1-2-3 lets you paste graphs in the spreadsheet and add graphics from the clipboard or from graphics files. However, to draw on the spreadsheet, you must



Mesa 2.0.1 (top) and 1-2-3 release 2.1 both let you draw on spreadsheets as well as superimpose graphs and imported files. However, the drawing tools, especially 1-2-3's, are somewhat awkward and limited.

create an image in some other program and paste it into the sheet—moving and resizing the image until you get the desired result. Mesa's draw layer is slightly more sophisticated. With it you place lines, arrows, circles, and rectangles on the sheet as you might with a simple paint program. These tools could use refinement, though; for example, adding a geometric shape to the worksheet requires interacting with a cryptic dialog box (see the screens above for a comparison of 1-2-3's and Mesa's graphing abilities).

Perhaps the most obvious GUI feature of both 1-2-3 and Mesa is their respective toolbar facilities. In both products, a collection of buttons appears across the top

Reviews Wanted: A Good OS/2 Spreadsheet

border of the spreadsheet as one-click shortcuts to common tasks. In 1-2-3, the default icon palette holds 21 SmartIcons, and there is a dialog box you can use to change to other palettes, and even to design your own palettes. You can select from more than 60 icons as you customize the SmartIcons facility. Mesa calls its collection of icons the toolbar. It offers only 15 icons, and there is no utility for customizing the collection.

Mesa gathers a huge number of spreadsheet formatting and editing tools into a package of dialog boxes called the Selection Manager. Using the dialog boxes, you can add sheet layers, assign page names, add rows and columns, change widths of columns and heights of rows, and so on. These options and more are available through Mesa's pull-down menus, so the Selection Manager is a sort of shortcut to oft-needed commands.

Both Mesa and 1-2-3 offer variations on a number of useful GUI features. For example, 1-2-3 lets you view up to five successive spreadsheet layers simultaneously in a "perspective" view, and Mesa lets you open multiple windows onto a single workbook. Both spreadsheets provide copious graphing options-bar, line, pie, area, and x,y (scatter plot) graphs, to name a few. While Mesa displays a graph in the spreadsheet, it offers only textual dialog boxes and pull-down menus to help you choose graph types. Once you activate 1-2-3's graph window, you can access a graph gallery in which pictures represent the available graph types. Such a gallery is decidedly GUI-like, and sorely missing in Mesa.

The Rest of the Story

Product Information

An important feature set for any spreadsheet is a robust collection of navigation aides. Users of DOS spreadsheets have always had powerful cursor-movement options. Mesa's concession to keyboard

users is to allow one-page hops via the PageUp and PageDown keys and a jump to cell Al via the Home key. To make serious jumps around the sheet, you have to use the mouse.

The paucity of keyboard navigation options in Mesa shows up in its cell-editing facility as well. For example, as you create a formula entry, you must either type cell and range addresses, or click

and drag over cells and ranges to include in the formula. Moving your hands from keyboard to mouse and back as you build complex @ functions becomes tiresome, particularly if you're used to pressing arrow keys to point at cells and ranges. Gosh, you can't even highlight a range by holding down Shift and pressing arrow keys.

What GUI spreadsheet doesn't offer database management tools? Mesa. 1-2-3, though, contains a sophisticated tool set, including the powerful and underrated (albeit sometimes tricky) DataLens facility for linking to external database tables. With it you can query databases across networks, join tables, and perform virtually any database operation. Even without DataLens, 1-2-3's ability to query databases built in the spreadsheet is quite powerful and gives 1-2-3 a significant edge over Mesa.

Power User's Powerhouse

Power users are often willing to trade a slick user interface for high-speed, low-resource performance. Depending on your exact needs, Mesa will likely be the better choice. For one thing, there's the size of the two programs. Mesa comes on two floppy disks, and 1-2-3 comes on five (six, according to the documentation, but we found only five). Considering how many more features 1-2-3 offers, it's not surprising that Mesa is so much smaller.

Once you've installed the software, you'll discover further performance differences. For example, launching Mesa from the desktop took nearly 40 seconds if it was our first task after booting up OS/2; launching 1-2-3 took only 19 seconds. On another measure, a Mesa file containing a small (6 columns by 6 rows) spreadsheet model and a single bar chart used less than 7 KB of disk space. A similar 1-2-3 file along with its satellite graph file used over

1	SPREADSHEET FEATURES: WHI	CH PROGRAM	IS BETTER?
E	FEATURE 1-2-3 MESA GUI Poor Good 3-D worksheet files Good Nameable sheet tabs None Good Recalculation speed Fair Use of cursor keys Charts/graphical objects In-sheet database management Access to external databases Good None	MESA	
	GUI	Poor	Good
1	3-D worksheet files	Good	Good
	Nameable sheet tabs	None	Good
	Recalculation speed	Fair	Excellent
	Use of cursor keys	Excellent	Poor
	Charts/graphical objects	Fair	Good
	In-sheet database management	Good	None
	Access to external databases	Good	None
	Shortcut icons on toolbar	Excellent	Fair

Red indicates winner for that category.

OVERALL

16 KB. Finally, when we loaded the spreadsheet with formulas that keyed off the @RAND function (a random number generator), a recalculation cycle in 1-2-3 took almost twice as long as it did in Mesa.

Good

Fair

People who build automated spreadsheet applications might appreciate Mesa's use of REXX for a macro language. REXX is OS/2's built-in programming language, so it's a natural choice to automate any OS/2 application and to link processes across applications. Mesa also includes some spreadsheet-specific procedures you can call from REXX scripts.

On the other hand, 1-2-3 uses a proprietary programming language to augment simple keystroke macros. This approach makes spreadsheet automation easy to learn, especially given adequate documentation in 1-2-3's manual and on-line help system.

Why 1-2-3 Is Superior

Dozens of other features distinguish the two products, and most of them weigh in favor of 1-2-3. For example, 1-2-3 is keystroke- and macro-compatible with the DOS versions of 1-2-3, so it affords the only reasonable upgrade path for people with spreadsheets already running in DOS. For the time being, the current OS/2 release offers most of what you could want in a spreadsheet; it's just not packaged appropriately for a GUI OS. What's more, it's a better spreadsheet overall than Athena Design's much more graphical Mesa.

Daniel Gasteiger is an independent spreadsheet consultant living in Lewisburg, PA. He recently contributed to the Que book, Using Lotus SmartSuite, and in 12 years has published more than 300 articles about spreadsheet software. You can reach him on the Internet or BIX at editors@bix.com.

Boston, MA (617) 426-6372

fax: (617) 426-7665

E-mail: info@athena.com

Circle 1002 on Inquiry Card.

Simple SQL

Four Windows tools enable easy data access for business managers

CHARLES VOGT

QL is a foreign language to most business managers, yet their information demands require on-line access to enterprise databases. These days, you can't rely on scheduled summary reports; to compete, organizations must deliver real-time data to business managers so that they can make informed, time-critical decisions. SQL front-end tools empower nontechnical managers by giving them direct access to client/server databases.

Because the principal task of the products examined in this report is to give non-technical users easy access to corporate data, they all must support an *administrative layer*. This insulates the manager from the complexities of the database structure and from having to learn SQL.


This report includes evaluations of Andyne GQL from Andyne Computing; BusinessObjects from BusinessObjects, Inc.; Esperant from Software AG; and IQ for Windows from IQ Software. Impromptu from Cognos is not included in this group because a stable prerelease copy of version 3.0 was not available in time (see the text box "Impromptu: The Report-Based Alternative" on page 223 for an early impression).

Version 2.1.1 of Esperant is evaluated in this report, but version 3.0 is scheduled for release by the time you read this. Software AG says the new version will incorporate many new features on top of its

core technology. But the focus of this review is not on query/reporting tools that provide some features of the administrative layer (e.g., predefining the joins in the database). Such programs are oriented more toward programmers and technical users and do not fit NSTL's criteria for this report.

Querying Paradigms

BusinessObjects and Esperant take similar




approaches to organizing data and offer flexible structures for building the query model. Both organize data into categories (referred to as *classes* in BusinessObjects) and items.

Essentially, each category consists of a customized table or view. The names of the categories are defined by the SQL administrator. Items (referred to as *objects* in BusinessObjects) correspond directly to the columns in a database, although the administrator has the ability to create calculated columns.

Both packages permit columns from more than one table to be represented as a single category in the query model. Because the products also support multiple models. generating ad hoc queries and defining selection and sorting criteria. Once a query is finished, you can easily create reports and charts for presenting the data. Of the four programs reviewed, BusinessObjects delivers the most polished solution.

the administrator can tailor the data to match the perspective of a specific department or manager.

IQ for Windows organizes a database into so-called IQ Views for querying. The administrator determines which tables to include. All the columns in the IQ View are then presented to the end user as a list;



Reviews Software Roundup

this does away with the entire concept of tables and categories. The administrator can create many IQ Views that show different subsets of columns, depending on the context being served (but only one IQ View can be used at a time). IQ is the only product here that does not permit permanent definition of calculated columns.

Andyne GQL takes a much different approach. It graphically represents tables in a window on the screen. The tables appear as icons that resemble folders. Once the tables are organized on the screen, the administrator defines the joins by making physical connections between the table icons. Tables that define the intersection of two tables appear as a link between two tables (which is referred to as an *embedded relationship*).

Even though it depends on physical links to define a model, Andyne GQL permits tables to be merged and represented as one view. This is limited to instances where there is a one-to-many relationship between the table being merged and the destination view.

In addition, Andyne GQL adds flexibility by letting you define multiple windows within the same administrative layer. This lets you represent the database, or different parts of it, on separate screens. You can also define procedures to automate certain tasks and to add buttons to the windows that automatically run predefined queries.

SQL Joins

All four SQL tools support direct joins between tables. With all the programs except for Esperant, the administrator defines joins from a dialog box that constructs the join statements (e.g., orders.ordernum = entry.ordernum) and creates a new table of defined joins. Rather than defining the join clauses, the Esperant administrator defines the primary and, if applicable, foreign key(s) for each table and then indicates whether the relationship is one-to-one, one-to-many optional, or one-to-many required.

The definition of joins gets more complicated if an administrator defines multiple join paths in the model. If the SQL tool being used does not provide a facility for resolving the ambiguity, a query will generate a Cartesian product, listing each record with all possible join combinations. Depending on the number of rows involved, this process could tie up the server for a long time.

BusinessObjects and Esperant resolve ambiguous joins by permitting the admin-

Highlight	S	
	Strengths	Limitations
Andyne GQL	Can display database structures graphically	Graphical model limits flexibility, adds to maintenance
	Automated query buttons	Limited to one query at a time
	Easy importing of database structures	Overly technical user's manual
BusinessObjects	Fastest program overall	Administrator must maintain macro objects
	Easlest interface for creating queries	Report editor is difficult to use
	Best facilities for distributing administrator layer	Query names limited to eight characters
Esperant	Query Expert helps avoid semantic mistakes	Administrative layer is difficult to create and maintain
	Easiest report generation and editing	Limited to one query at a time
	Most flexible security	Slower querying of large databases
IQ for Windows	Cross-tab queries are easy to generate	Report writer is difficult to learn
	Charts are easy to generate	Slower queries with aggregates
	Flexible report writer	Carnot permanently define calculated columns

istrator to define what they call *contexts* and *join paths*, respectively. In cases where there are multiple paths between the columns selected for the query, these two tools prompt the user to select one of the defined paths between the tables.

In Andyne GQL, the user graphically identifies the path to be taken between the tables during the definition of the query. However, GQL does not provide any facility for preventing the user from selecting both paths between the tables. If both paths are chosen, GQL generates a Cartesian product of the tables included in the query.

IQ for Windows is the only tool that does not provide a facility for resolving ambiguous join paths. If an IQ View is created that refers to tables with multiple join paths, an IQ query will generate a Cartesian product. The only available solution in IQ is to create separate IQ Views, each defining only one of the paths between the tables.

Query Capabilities

All four products let you build calculated fields (e.g., revenue) along with aggregate fields (e.g., total revenue from all sales or total number of sales). In addition, all four can generate aggregates for groups (e.g., total sales or total volume of sales by product category).

IQ for Windows, however, performs all the calculations itself instead of using the aggregate functions in SQL. IQ achieves most of the same functionality as the other products by retrieving all the detail records that match the query criteria and then performing the calculations on the system that's running IQ. (The effect of this is evident in some of the performance results.) IQ lacks one important capability in this area: It can't apply the SQL COUNT statement to a joined table (e.g., the orders table in a query retrieving orders by salesperson).

Esperant offers different query capabilities by extending the kinds of information that can be generated in an ad hoc manner. These extensions include complex subqueries that you can apply as criteria in record selection, queries that return the percentage of items matching the specified criteria, queries that compare two sets of records, and queries that calculate the result as a percentage of the aggregate (e.g., total, average, maximum, and minimum).

Esperant's Query Expert is a rules-based interface designed for nontechnical and technical users alike. It uniquely incorporates rules to ensure that you produce only valid and semantically correct queries. It's the only interface that prevents you from generating invalid queries that include aggregates by graying-out invalid selections based on the choices made.

As a result, Query Expert prevents you from improperly using aggregates at multiple levels of detail. You can easily make this kind of mistake in BusinessObjects and Andyne GQL; the result of such a mistake is a syntactically correct SQL SE-

Testing by the Book

STL tested the speed of the four SQL query tools using a book-order-entry database. Tests were done on Microsoft SQL Server for NT 4.2 running on top of Windows NT Server 3.5, which acted as a back-end server. The SQL query tools ran on a separate workstation under Windows for Workgroups 3.11.

The test database consists of eight tables: books, categories, publishers, authors, links, orders, entries, and salespeople. The amount of data in the database is purposely kept to a minimum so that the tests measure the speed of the query tool, not of the database server.

The database consists of 2048 books, 20 categories of books, 30 publishers, and 256 authors. Each book has two authors, as is indicated in the 4096 link records. The database was created with 4096 order records, a total of 20,480 entry records (five books are sold per order), and 15 salespeople.

The simple select test measures the time required to run a simple query that retrieves the first and last names sorted by last name, then first name, from the author table (which has 256 rows). The database server takes little time to process this query and return the data.

the author's last name and then by first name. This query requires data from three tables (authors, links, and books) and returns 584 rows from the database. The database server takes somewhat longer to process this query than the first because it must join the three tables and retrieve data from both authors and titles.

Query with grouping and subtotal measures the speed of processing a more complex query that groups the resulting records and calculates a subtotal. Each program creates a query that retrieves the total revenue generated by each salesperson by state.

The results of this test show a surprising spread in performance. The database server takes significantly longer to process this query than it does for the first two tests. Correspondingly, Esperant's performance is better on this test, because the time for the server to process the query represents a greater portion of the total time.

Andyne GQL, BusinessObjects, and Esperant all generate essentially identical queries by making use of the SQL SUM and GROUP BY clauses. As a result, the database server does all the calculations and returns 15 rows (one for each state),

totals by state on the local computer.

Complex query with report to screen measures how long it takes to process a complex query (with results grouped by two criteria) and to generate a screen report with two levels of subtotals and a grand total. This test measures the speed at which the query tools can process aggregates on grouped result records, as well as the speed at which the results of a query can be presented as a report. (The result shown in the table for BusinessObjects includes the time the program took to execute the query as well as the time it needed to generate the report as a separate step in the process.)

This test measured the speed of Esperant's Reporter rather than that of its Query System. The Reporter automatically runs the query and generates the report without the intermediate step of displaying the results in a columnar matrix. Also, because this test includes an aggregate (i.e., total sales revenue for each category by state), IQ for Windows again retrieves all the detail and order records (1801 and 1522, respectively) and calculates the aggregate locally.

In the *print report* test, technicians print the 15-page report generated dur-

ing the previous test to a Texas Instruments microLaser with the Windows Print Manager enabled. Testers format the reports in each program as identically as possible (with regard to such details as fonts, borders, headings, and titles) for this and the previous test.

For this test, NSTL records two times for each program: the time elapsed until control is returned to the user, and the time for the completion of the printing (determined

by the drop of the last page from the printer). Because this test measures the time needed to print a report already generated to screen, the times for return of control to the user are short.

The exception to this, however, is IQ for Windows, which takes more than 20 times as long as Esperant to return control. IQ does not permit a report generated to screen to be printed. Instead, the user must close the report and select Output to Printer to print the report. IQ then, again, processes the query before generating the printed output.

FRONT-END PERFORMANCE

All times are in seconds.

	ANDYNE GQL	BUSINESSOBJECTS	ESPERANT	IQ FOR WINDOWS
Simple select	1.6	1.5	8.8	3.7
Query with three-table join	5.6	4.7	27.8	7.1
Query with grouping and subtotal	8.4	7.9	28.4	308.2
Complex query with report to screen	22.2	21.9	31.6	42.3
Print report: Return of control	24.7	10.6	9.7	219.9
Print report: Page drop	162.1	139.6	140.0	355.1

Although all four products generate equivalent queries that take the same amount of time for the server to process, IQ for Windows and Esperant take substantially longer to process the query. NSTL attributes the slow performance of both to inefficiency in storing the data in their local data structures (in RAM).

Query with three-table join measures the time required to run a more complex query that retrieves the names of authors and book titles by authors with last names that start with H or S. The query specification includes sorting the records first by

grouped by salesperson.

In contrast to the other programs, IQ for Windows takes a much different approach to this query—and all queries that include aggregates. Instead of using the GROUP BY and aggregate functions to have the server perform such calculations, IQ retrieves all the detail records that correspond to the selection criteria. In this case, it retrieves 20,480 entry records and 4096 order records, along with the first and last names of the 30 salespeople. After retrieving the detail records, IQ sorts the records and calculates the sub-

Reviews Software Roundup

	ANDYNE GQL	BUSINESSOBJECTS	ESPERANT	IQ FOR WINDOWS
Administrative				
Automatic dictionary/model generation	•	•	•	•
Régistine columnytable namins	100	1104	(6)	
Add descriptions for column/table names	0	0	•	0
Show columns from multiple ables in a single entity	0			-
Define calculated columns in model	•	•	•	0
Redefine display format for column		. 0	0	•
Define valid joins	•	•	•	•
Define multiple joins between tables				
Define theta joins using complex criteria	•	•	•	•
Define complex join paths		•		(4)
(ambiguous joins)				4
Limit tables displayed/accessible Limit columns displayed/accessible	-			
Limit number of rows returned	0	•	•	
Distribute models via database			0	0
Automate queries as graphical buttons	•	0	0	1
Define dialog boxes for user-query entry.		•	0.00	0
Set up user accounts for queries only	0	•	•	•
Define groups of users	0	3		
End-User Facilities				
Multiple active query/result windows	•	•	0	0
Start multiple instances of program			0	(1)
Save query for personal/global use	•	•	•	•
Guards against semantically incorrect queries	0	0	•	
Permits direct entry of SQL		0	•	0
User can limit number of rows retrieved	0		0	•
User can cancel queries	•	•	•	
Query Criteria	112			
Insert criteria from static lists	•	•	0	0
Apply criteria to calculated values	0	•		0
Supports union operator Can store lists of selection criteria	0	0	0	0
Supports outer joins (with database server)		0		
Automatica y generates subqueries	0	3	•	.0
based on criteria				
Replace retrieved values with	•	0	0	0
defined text/values				
Save SQL code generated by query				-0
Query Calculations				
Count records matching criteria	•	•	•	•
Count records in joined table	•			0
Show percentage that matches criteria	0	0	•	0
Compare two sets of results Add calculated column using	0	0		0
arithmetic functions				•
Add calculated column using trigonometric, other functions	100	•	•	0
Query Results	-			2
Filter/sort results without resubmitting query		0	0	0
Dynamically adjust column widths		0	0	0
Change order of columns	•	0	0	0
Add calculated fields without resubmitting query	0	a a	- 0	0
= yes	s loons in Pr	ogram Manager		

LECT statement that produces results of indeterminate meaning (for more details, see the review "Make Bulletproof SQL Queries," February BYTE).

GQL is the only tool that has a drill-down feature in its query interface. After retrieving the results of a query, you can use GQL's drill-down mode to highlight a result in the retrieved data. Once a result is highlighted, it's automatically added as a selection criterion for retrieving more detailed information. This feature lets you move quickly from a summary to detailed information.

Performance Considerations

NSTL's tests reveal some significant performance differences among the four products, even on simple queries (see the text box "Testing by the Book" on page 219). BusinessObjects and Andyne GQL perform up to expectations. But Esperant is surprisingly slow when storing information retrieved (in RAM) from the database server.

It takes Esperant significantly longer than BusinessObjects and GQL to retrieve even simple queries. Esperant's poor performance is less noticeable on queries that take longer to process on the server, because Esperant adds time only after it starts receiving the enterprise data.

Unlike Esperant, IQ for Windows' slow performance is directly attributable to the way it uses SQL. IQ does not use the aggregate functions in SQL to generate summary information. Instead, it retrieves all the corresponding detail records and then performs the calculation locally. This has two effects: More of the network bandwidth is used between the database server and the client generating the query, and the queries using aggregates tend to take substantially longer to run than they would if processed on the server.

Model Distribution

The facilities that are provided for distribution and security vary significantly among these products. BusinessObjects provides the cleanest approach by using a database, or databases, to store and distribute *universes*. Prior to installation, BusinessObjects creates a repository database on a server that's accessible to all users. (Multiple repositories on various servers can be created later if all users cannot access a single database server.)

Thus, when the administrator completes the definition or maintenance of a universe, the universe is exported to the repository; a user's copy of the universe is then

FRESH IDEAS




HOT TOPICS

Ingredients For Success From Computing McGraw-Hill



VIDEO DIALTONE TECHNOLOGY

0-07-042724-0/\$60.00




LINKING LANS, 2ND ED.


0-07-057063-9/\$45.00



BUILDING MULTIMEDIA PERFORMANCE SUPPORT SYSTEMS

0-07-911684-1 / \$45.00 (book/disk)





AN INTRODUCTION TO ATM NETWORKING

0-07-024043-4/\$55.00



THE McGRAW-HILL
INTERNETWORKING
HANDBOOK

0-07-063263-4/\$79.50

On CompuServe: GO MH
On Internet: 70007.1531@compuserve.com
Internet Catalog at URL:gopher://mcgraw.infor.com:5000



Reviews Software Roundup

Build report from multiple queries Create report with multiple rows per result record Cata-group result Collapse/expand level of detail displayed Collapse/expand level of detail displayed Collapse/expand results Generate partial report Create report templates Generate partial report Create report templates Collapse, footers for breaks Supports subtotals, grand totals Formatting and Editing (Overall Report) Select type/ace/size Select type/ace/s		ANDYNE GQL	BUSINESSOBJECTS	ESPERANT	IQ FOR WINDOWS
Multiple reports can be open for editing Dull'd report from multiple queries Create report with multiple rows per result record Create report and results Conleage/expand level of detail displayed Beport on stored results Connecte report remplates Deline headers, looters for breaks Deline headers, looters for breaks Deline headers, looters for breaks Supports subfotals, grand totals Formattling and Editing (foverall Report) Select typeface/size User-delined field heights User-delined field heights Vertically align contents Vertically align contents Words warp, withis fields Add title page Editing toolbars and ruler Snap to grid (helps align contents) Prage Formattling Borders, rules User-delined headers, footers Set defined page breaks Include report databriline Include report databriline Include query databriline Include query databriline Concluder sport databriline Includer sport databriline Includer sport databriline Includer sport databriline Control of the sport of th	General Reporting Facilities				
Build report from multiple queries Create report with multiple rows per result record Canagroup results Collapse/expand level of detail displayed Coreate report templates Coreate report templates Coreate report templates Collapse/expand level of detail displayed Coreate report templates Coreate report templates Collapse/expand level of detail displayed Coreate report templates Collapse/expand level Coreate report templates Collapse/expand level Collapse/expa	Automatically generate report from query results	•	•	•	•
Create cross-tab report Create report with multiple rows per result record Calangroup result Collapse/expand level of detail displayed Collapse/expand level of detail displayed Collapse fexpand level of detail displayed Coreate report templates Collapse fexpand level of detail displayed Create report templates Collapse fexpand level of detail displayed Coreate report templates Collapse fexpand level of detail displayed Coreate report templates Collapse fexpand level of detail displayed Collapse fexpand level of details Collapse fexpand level of details Collapse fexpand level of details Collapse fexpand level of de	Multiple reports can be open for editing		3		0
Create report with multiple rows per result record Can group results Can group results Collapse/expand level of detail displayed Can group results Collapse/expand level of detail displayed Can group results Construct group Constru	Build report from multiple queries	•	0	•	0
Canagroup results Collapse/expand level of detail displayed Collapse/expand level of detail displayed Collapse/expand level of detail displayed Coreate report results Coneate report templates Coneate report templates Collapse report subtotats, grand totals Collapse report subtotats, grand totals Collapse report subtotats, grand totals Collapse report details Collapse report details Collapse report details Collapse report details Collapse report data/time C	Create cross-tab report	0			•
Collapse/expand level of detail displayed Generate partiel report Greate report templates Deline headers, footers for breaks Supports subtotals, grand totals Formatting and Editing (Overall Report) Select typeface/size User-defined field heights Verically align contents Verically align contents Collapse and totals From the support of the	Create report with multiple rows per result recor	d •	•	•	•
Generate partial report			N. D. C.	5.5	
Generate partial report			•		
Create report templates Define headors, footers for breaks Supports subtotals, grand totals Formatting and Editing (Overall Report) Select typerface/size User-defined field heights Vertically align contents Vertically align conten					
Deline headers, footers for breaks Supports subtotals, grand totals Formatting and Editing (Overall Report) Select typeface/size User-defined field heights User-defined headers Shap to grid (helps align contents) Print preview Definition toolbars and ruler Shap to grid (helps align contents) User-defined headers, footers Set defined page breaks Include report date/time Include query date/time Set space between rows User-defined headers, footers Set defined page breaks Include query date/time Definedude query da	The state of the s		-		
Supports subtotals, grand totals Formatting and Editing (Overall Report) Select typeface/size Jaser-defined field widths Joser-defined field heights Horzonstuly atops contents Vertically align contents V					
Select type face /size		0	The second second		0.000000
Select typeface/size Jean-defined field widths User-defined field heights O Vertically align contents O Wort-wrap within fields Add title page Gaining footbars and ruler Shap to grid (helps align contents) Print preview Page Formatting Borders, rules User-defined headers, footars Set defined page breaks Include report data/time Include query data/time Include query data/time Set space between rows Include linked external objects via DDE Charting Bar (columns) Pie Charting Bar (columns) O Charting Chartin	Supports subtotats, grand totals				-22
User-defined field heights User-defined field heights Hortzontuly at or contents Vortically align c	Formatting and Editing (Overall Report)				
User-defined field heights	Select typeface/size	•	•	•	•
Horizontally align contents Vertically align contents Vertically align contents Word-wrap within fields Add title page Citing follobars and ruler Snap to grid (helps align contents) Print preview Page Formatting Borders, rules User-defined headers, footers Set defined page breaks Include report date/time Include query date/time Include query date/time Include guery date/time Include linked external objects via DDE Charting Bar (columns) Pie Line Combination (e.g., line, histogram) Include leged Data Experting Can act as Windows DDE server dBase Paradox Excel 1-2-3 for DOS or Unix Quattro Pro ASCII delimited text Microsoft Word for Windows Microsoft Word for Windows Microsoft Word for DOS WordPerfect WordPerfect O O O O O O O O O O O O O O O O O O O				10	
Vertically align contents Word-wrap within fields Add title page Gibring loolbers and ruler Shap to grid (helps align contents) Print preview Page Formatting Borders, rules User-defined headers, footers Set defined page breaks Include report date/time Include query date/time Set space between rows Hide sections Include linked external objects via DDE Charting Bar (columns) Pie Charting	User-defined field heights	0	•	•	
Word-erap within fields Add title page Citing folipars and ruler Shap to grid (helps align contents) Print, preview Page Formatting Borders, rules User-defined headers, footers Set defined page breaks Include report date/time Include query date/time Set space between rows Hide sections Include linked external objects via DDE Charting Bar (columns) Pie Charting Bar (columns) O Charting Chartin	Horizontally as go contents	0			
Add title page		0	•	0	
Editing toolbars and ruler Snap to grid (helps align contents) Print, preview Page Formatting Borders, rules User-defined headers, footers Set defined page breaks Include report date/time Include query date/time Include query date/time Include sections Set space between rows Include linked external objects via DDE Charting Bar (columns) Pie Charting Bar (columns) Include linked external objects via DDE Charting Chart					101
Snap to grid (helps align contents)				•	
Prof. preview Page Formatting Borders, rules User-defined headers, footers Set defined page breaks Include report date/time Include query date/time Include query date/time Set space between rows Include linked external objects via DDE Charting Bar (columns) Pie Charting Bar (columns) Pie Charting C				700	
Page Formatting Borders, rules User-defined headers, footers Set defined page breaks Include report date/time Include query date/time Set space between rows Include linked external objects via DDE Include linked external objects via DDE Ctarting Bar (columns) Include linked external objects via DDE Include linked externa			0		
Borders, rules User-delined headers, footers Set defined page breaks Include report date/time Include query date/time Include query date/time Include query date/time Include sections Include linked external objects via DDE Include linked external objects via DDE Charting Bar (columns) Include linked external objects via DDE Include legend Inc	Print preview	3	7.07		õ
User-defined headers, footers	Page Formatting				
Set defined page breaks			•	•	•
Include report date/time				-	
Include query date/time		-		-	
Set space between rows Hide sections Include linked external objects via DDE Charting Bar (columns) Bar (columns) Cline Cline Cline Combination (e.g., line, histogram) Include legend Combination (e.g., line, histogram) Can act as Windows DDE server Clan act as Windows DDE		2	NAME OF TAXABLE PARTY.	0	
Hide sections					
Charting				-	
Charting		-			0
Bar (columns) Pie Cline Cline Cline Cline Cline Combination (e.g., line, histogram) Include legend Combination (e.g., line, histogram) Include legend Can act as Windows DDE server Cline					
Pie 0			•	0	•
Line					
Scatter		_	The state of the s	Company of the Company	
Area	VIVORE CONTRACTOR OF THE PARTY				1000
Combination (e.g., line, histogram)	7 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		•		•
Data Exporting Can act as Windows DDE server	Combination (e.g., line, histogram)		0		0
Can act as Windows DDE server dBase Paradox Paradox 1-2-3 for Windows 1-2-3 for DOS or Unix Quattro Pro ASCII delimited text Microsoft Word for Windows Microsoft Word for DOS WordPerfect O O O O O O O O O O O O O O O O O O O			•	A STATE OF THE PARTY OF THE PAR	-
Can act as Windows DDE server dBase Paradox Paradox 1-2-3 for Windows 1-2-3 for DOS or Unix Quattro Pro ASCII delimited text Microsoft Word for Windows Microsoft Word for DOS WordPerfect O O O O O O O O O O O O O O O O O O O	Data Exporting				
Description			•	0	0
Paradox O O O Excel Included in the processing of the processing	To the same of the				
Excel	Paradox				0
1-2-3 for Windows 1-2-3 for DOS or Unix Ouattro Pro ASCII delimited text Microsoft Word for Windows Microsoft Word for DOS WordPerfect O O O O O O O O O O O O O	Excel				
Quattro Pro O O O O O O O O O O O O O O O O O O O	1-2-3 for Windows	•	0	0	0
ASCII delimited text Microsoft Word for Windows Microsoft Word for DOS WordPerfect	1-2-3 for DOS or Unix	0	•	•	•
Microsoft Word for Windows Microsoft Word for DOS WordPerfect O O O O O O O O O O O O O	Quattro Pro	0	0	•	0
Microsoft Word for DOS O O O WordPerfect O O O	ASCII delimited text		•		
WordPerfect O • O					•
		0	•	0	0
API for external access to query function O O O					•
	API for external access to query function	0	0	•	0

automatically updated the next time he or she uses it. The same mechanism is used to distribute queries defined by the administrator (or by anyone else). With this mechanism, a user automatically has a personal copy of the universe definition with his or her defined queries, which allows the administrator to easily update the base definition of the universe.

Andyne GQL models are distributed by making the model file(s) freely accessible. They can be either copied locally or shared. If the files are copied locally, updates can then be distributed automatically by the database. GQL can update the administrative layer separately from the user layer, so changes can be made to the database structure without affecting any customizations.

The administrator distributes Esperant's so-called DataViews by either copying the files onto the local disk or granting read access to a shared directory. Any updates are made globally by updating the shared directory or, for nonnetworked distribution, by copying the DataView files into each local directory.

The definitions of IQ for Windows' data dictionaries are stored in a single file that the administrator can create and name (with a .DAT extension). Multiple data dictionaries can also be created. The administrator grants access by making the dictionary file available on the network.

SQL Security

All four programs provide some level of security. All except Andyne GQL permit definition of user accounts to control access to the query models.

GQL lets the administrator define a single password per model to restrict user access. In addition to any password required, GQL requires each user to enter the database user ID and password to access the database. A variety of security options are defined when a GQL model is created. The administrator can specify, among other options, whether a user can update the data model, edit the SQL statements generated, and save passwords with defined queries.

Esperant offers a wide range of grouplevel security. In addition to requiring a user name and password, Esperant requires each user to enter the database user name and password before opening a DataView. (Esperant can also be configured to save queries with the database user ID and password embedded.)

An Esperant administrator can control whether groups of users can open queries,

Impromptu: The Report-Based Alternative

mpromptu 3.0 delivers a different perspective on ad hoc access to databases than the four products tested for this report. Impromptu 3.0, which NSTL evaluated in the early beta stage, takes a report-based approach to ad hoc database access rather than a query-based one. Even with this different perspective, Impromptu has much of the same core functionality as the other products.

With Impromptu, an administrator sets up a catalog that creates a layer between the user interface and the underlying database structure. Although the program is report-based, Impromptu's query-definition tool can generate many of the same queries as the other programs. The Impromptu catalog organizes the database's columns into a set of hierarchical folders (much like the categories in Esper-

ant and the classes in BusinessObjects).

Catalog definition in Impromptu starts out with one folder per table in the database, which is based on data retrieved from the data dictionary. Impromptu then lets you move columns from one table to another or move the folder representing a table and insert it one level below another table. An administrator can also define aliases for column and table names and define joins in the database.

You generate Impromptu reports with the query-definition tool, selecting columns and applying selection criteria. Like the four evaluated programs, Impromptu lets you calculate columns, sort data, eliminate repeated data items in grouped queries, and perform aggregate calculations on grouped data. Impromptu even lets you select criteria based on aggre-

gates—a feature provided by Esperant, but not the other three programs.

Many of Impromptu's reporting capabilities are centered around the templates provided with the program. The Impromptu beta version included templates for a catalog list, a customer form, an invoice form, name tags, and mailing labels. The more complex ReportWise templates step you through defining a custom report. Impromptu frames hold the retrieved data, but they can also contain OLE objects, pictures, and text.

Overall, Impromptu offers an alternative perspective on ad hoc data retrieval. NSTL's beta evaluation of Impromptu leads us to believe that Impromptu is worth a close look, especially for organizations interested in generating highly formatted reports from a database.

databases, reports, and saved tables. The administrator can also specify whether a particular user can save query results, save queries, save the generated SQL, and print from the program, among other options.

Each BusinessObjects account can be assigned either novice or expert status, which determines only whether a user can edit the SQL statements generated by the software (experts are permitted to; novices are not). By default, the software automatically connects to the database by using the user ID and password that were stored when the universe was defined.

If an organization requires an individual password, the user ID and password must be added as arguments to the command line that launches BusinessObjects. There is no way to configure BusinessObjects to require each user to enter the database user ID and password in a dialog box.

IQ for Windows provides a broad set of security features based on user accounts and groups of users. However, it implements the security through the DOS character-mode program, and the security is based on assigning numeric levels to users, groups, and various database resources. This makes overseeing the security quite burdensome for the administrator.

Nontechnical SQL

Of the four SQL tools, BusinessObjects delivers the most polished solution. Its paradigm of classes and objects lets the administrator easily establish customized views into critical business data. Distribution of the model through a repository on a database server makes it easy to keep large numbers of users up to date. Once the administrator builds the model and defined macro objects (e.g., calculated fields),

BusinessObjects presents an easy-to-use interface for generating ad hoc queries and defining selection and sorting criteria. Once a query finishes, it's easy to create reports and charts for presentation of the

Esperant 2.1.1 is a first-generation product that will soon be replaced by version 3.0. While the administrative module of Esperant 2.1.1 is rough around the edges, it does enable an administrator to organize the contents of a database to match specific needs. The key features of Esperant are its query language and Query Expert, which directs you through sophisticated queries with assurance that you're getting all the information you need. Esperant-generated queries take the best advantage of SQL to expand the variety of queries available to business managers for ad hoc information.

Where to Find

Andyne Computing, Ltd. Kingston, Ontario, Canada (800) 267-0665

Circle 1138 on Inquiry Card.

(613) 548-4355

BusinessObjects, Inc.

Cupertino, CA (800) 703-1515 (408) 973-9300 Circle 1139 on inquiry Card. IQ Software Corp.

Norcross, GA (800) 458-0386 (404) 446-8880 Circle 1140 on Inquiry Card.

Software AG of North America, Inc.

Reston, VA (800) 423-2227 (703) 860-5050 Circle 1141 on Inquiry Card. This report contains the partial results of a recent issue of Software Digest, a monthly publication of NSTL, Inc. To purchase a complete copy of the report, contact NSTL at 625 Ridge Pike, Conshocken, PA 19428, (610) 941-9600; fax (610) 941-9950; on the Internet, editors@nstl.com. For a subscription, call (800) 257-9402, BYTE magazine and NSTL are both operating units of McGraw-Hill, Inc.

What do you want from a modem? Speed? Interoperability? Reliability? Read on—all the information on 28.8-Kbps external and PC Card modems is right here.

JIM KANE AND HELEN HOLZBAUR

o you believe that time is money? This old adage is especially true in the world of telecommunications. Every time you access a remote computer, you're incurring costs: the easy-to-spot direct costs, like phone bills and connect charges, as well as the hidden costs of computer time and operator inactivity. It's no wonder we welcome devices that promise to reduce file transfer time. These V.34 modems answer that call.

We tested 25 external and seven PCMCIA PC Card modems, all capable of pushing data at rates of up to 28.8 Kbps. How do these modems transfer data so quickly? To begin with, they use state changes (0 as a low-frequency signal on the wire, 1 as a high signal) to represent data. For modems from the computer Stone Age (i.e., below 1200 baud), the baud rate represented the bit, or transfer, rate. Engineers then discovered that they could encode more than 1 data bit in each state by using DPSK (Differential Phase Shift Keying). Thus, by increasing the number of phase shifts for each bit, a 2400-baud modem could achieve transfer rates of 2400 or 4800 bps.

The next major development, QAM (Quadrature Amplitude Modulation), added a new dimension called amplitude modulation. QAM generates 4 bits for each phase shift, using both phase and amplitude as

How to use this guide

Unless otherwise indicated, performance scores are reported in bytes per second. We weight unidirectional throughput more heavily than the other performance tests, because this test line represents typical line conditions found in most of the U.S. If you have special requirements, such as full-duplex operation or network management, look more closely at the reported "Two-way Communications" result.

The average throughput for each modem during one-way (half-duplex) communication. This represents the typical rate at which the modern transmits data over a normal phone line.

The Overall Score is heavily weighted on performance, but it also takes into account the features, such as spoofing capability, leased-line support (for dedicated highspeed connection to a remote site), and various supported protocols. We also factored usability into the overall score, although lightly, because most people install their modem only once, program the modem software to handle the AT commands, and expect the device to function consistently thereafter.

BEST OVERALL Practical Peripherals ProClass 288LCD ns ratt, easy to use, has an informative LCD screen, and a built in clock. This modern took top honors is almost easy sepect of our benchmarks, including to-view throughput, the TM (Telecomensia) casons industry Association (Table 0 tests, and inspared time performance across industry Association (Table 0 tests, and inspared time performance across in the second of the second o

features, such as their ability to

spoof, the protocols they support,

and the availability of on-line help.

Kines Colleg 205 Y.FC & Pag AAAA AAA 4930 6573 9093 Des 200 1.34 & Fee We evaluated the modems on their

Impaired lines simulate difficult phone conditions, including noise and satellite delay.


The average performance of a modem over the lines represented by Table 6 of the TIA/EIA Telecommunications System Bulletin TSB37.

The percentage of calls to and from other modems in which a modem made a V.34 connection.

The average throughput for each modem during two-way communication. This score is more important than oneway throughput only for applications that require fullduplex capability, such as LAN bridging.

Inside Communications





EXTERNALS

BEST OVERALL Practical Peripherals ProClass 288LCD

This modern is fast, easy to use, has an informative LCD screen, and a builtin clock, it took top honors in almost every aspect of our benchmarks.

Practical Peripherals ProClass 288LCD

Impressive performance numbers make the ProClass a winner in the data transfer category. However, it lacks support for flash-ROM upgrades. **PAGE 227**

LOW COST

Maxtech/GVC XM288E

The \$199 Maxtech modern turned in solid performance numbers and excels in usability. PAGE 227

PC CARD

BEST OVERALL Practical Peripherals PCMCIA ProClass 288 with EZ-Port

This PC Card modern finished with slightly lower performance numbers than those of the Hayes Optima but posted higher usability numbers. It also tied for top honors on our PCMCIA interoperability testing. PAGE 231

REST DATA Haves Optima 288 V.34 & Fax

The Optima is the big winner based solely on data throughput. It has the best one-way throughput results of all the PC Card modems we tested. The Haves also handled the TIA (Telecommunications industry Association) testing better than the others. **PAGE 231**

dimensions. Add in data compression with error correction and modems could accurately transfer large amounts of data (a modem that uses data compression must have an error-correction protocol for it to work).

Microcom developed MNP-5, one of the first datacompression methods. MNP-5 worked with the MNP-4 error-correction protocol to achieve a 2-to-1 yield; a compressible file could be transmitted in half the normal time.

To further things along, the ITU (International Telecommunications Union) came up with the V.42bis compression method. This protocol works with V.42 error correction to provide up to 4-to-1 compression.

The newest class of modems is based on the ITU V.34 standard and pushes the U.S. telephone infrastructure to its limit. V.34 modems differ from their predecessors because they negotiate more than just the basic baud rate, encoding scheme, error-correction, and compression protocols. They also "probe" the line and assess its capabilities and quality to optimize the data transfer rate, and they make necessary adjustments as line conditions change during a transfer. The V.34 standard offers 60 combinations of modulation schemes and baud rates to make line adjustments on the fly.

V.34 sounds great, but you won't see it in action all the time unless you communicate solely within a pristine fiber-optic telephone network system. Even though large cities have installed fiber-optic cable to the telephone trunks, most connections extend through the copper wire strung between poles along the U.S.'s roadways. These links are subject to data disasters caused by electrical interference, rotting insulation, a variety of wildlife, and aging copper wire. Luckily, your V.34 modem falls back to a lower data transfer rate as line conditions worsen. If the line conditions improve, the modems will fall forward again.

THE FASTEST, THE SLICKEST, AND THE FRIENDLIEST

EXTERNAL V.34 MODEMS

ith the advent of the ITU's V.34 specification, the standard Windows 3.1 serial-port communications driver becomes hopelessly outmoded. The Windows driver supports a maximum DTE (data terminal equipment)—your PC—rate of 57,600 bps, and even that is unreliable if you are using your modem in a back-

ground application. To overcome this limitation, we tested the modems with Bio-Engineering Research Lab's (Ashland, OR) TurboComm, which is an enhanced serial-port driver for Windows. As a result, we achieved 115,200-bps communication between the modems and the computers, enabling us to test the modems' capabilities rather than Windows' inabilities.

External modems come in all shapes and sizes: We tested the standard rectangles, Sony Watchman look-alikes, and modems that look like baby monitors and even shark fins. The winner of this BYTE/NSTL Lab



The Logicode Quicktel exemplifies the new shapes of external modems.

Report is Practical Peripherals' ProClass 288LCD (it looks like a Sony Watchman).

The 288LCD outperformed all the other modems in our

impaired tests, in the TIA (Telecommunications Industry Association) lines test, and in the two-way throughput tests. Its features score was high due in large part to the LCD. With a glance at the panel, you can monitor each call's progress, including line conditions, connect speed, and compression type. Attaching cables to it is a little difficult, so if you move your modem around much, the 288LCD may not be your best choice.

The performance of Hayes' Optima V.FC & Fax was almost identical to that of the ProClass 288LCD in the throughput tests. The Optima is a solid performer in all aspects of testing; it has everything we have come to expect from Hayes, including a long features list and the standard Hayes front panel. Surprisingly, its performance result was only average in our Interoperability test, although to many people, a Hayes modem still represents the industry standard.

What really differentiated the top two modems was their ability to transfer files

over less-than-ideal line conditions. Here, the edge went to the Practical Peripherals' ProClass 288LCD.

Number three and four were fairly expensive entries: Black Box's Modem 3400 and Motorola ISG's V.3400. These two are steady performers in both ideal and poor line conditions (the Black Box failed only one TIA line, and the Motorola

VOICE AND DATA:CAN THEY SHARE THE SAME LINE?

Wouldn't it be nice to discuss a fax as it is being transmitted or to talk about the contents of a shared whiteboard as it is being altered—all without needing a second telephone line?

Several single-line SVD (Simultaneous Voice and Data) technologies are contending to become the SVD standard (see "Doing It All on One Line," January BYTE). Technologies such as VoiceView from Radish Communications Systems, quickly switch between voice and data to simulate SVD, and Multi Tech Systems' MSP (Multi Tech Supervisory Protocol) and AT&T Paradyne's VoiceSpan provide simultaneous voice-over-data sessions. Intel and a group of modem makers are backing a technology called Digital SVD that lets users put voice and low-rate video on top of data. These schemes are all stopgap SVD solutions until ISDN digital telephony takes over.

To test this emerging technology, we set up an SVD session with two preproduction MT2834PCS-ISI modems from Multi Tech. Multi Tech's proprietary MSP technology uses a packet-transfer scheme to send voice and data simultaneously. The Multi Tech modem's Talk AnyTime hardware feature lets users talk after a data link is established between the two modems.

During testing, when the remote user picked up the handset, we held a conversation using a Digital Simultaneous Data Link (DSP circuitry converts voice into digital format) while still passing data through the modems. We did not notice any significant drop in data transmission performance during our tests when we activated the voice/data feature.



The Multi Tech MT2834PCS-ISI SVD modem.

Of the differing technologies for SVD, Radish's VoiceView is the most widely installed and uses an alternating or switched voice/data integration standard. When it recognizes incoming data, in effect it mutes the handset and begins data reception. As soon as the line is again free of data, the VoiceView-enabled modem reactivates the handset and resumes the role of passive listener. Voice-View does not support videoconferencing and other applications that depend on continuous data flow, but it is an alternative to expensive ISDN solutions. Microsoft is building VoiceView support into Windows 95, and Radish has licensed VoiceView to Rockwell to build into future-generation modem chips.

As with Multi Tech's MSP, AT&T Paradyne's VoiceSpan achieves SVD by allowing voice and data to share bandwidth. Conversation happens at a normal rate, but when you talk and exchange data, speech quality degrades. Intel-supported Digital SVD splits the modern line into two virtual channels: one transmits voice while the other transmits data or graphics.

passed all the lines). Except for the color of their cases, the two look identical. However, nothing about these two modems impressed us enough to justify their \$895 price tags: neither supports spoofing (see "What Does It Really Mean" on page 232) for communicating with older software, and both have extremely short warranty periods.

The Maxtech/GVC modem.

Weighting for Best Overall and Low Cost (<\$400) DATA AND FAX PERFORMANCE 75% USABILITY 15% FEATURES 10%

the XM288E. is our recommendation for those on a tight budget. Both it and the Motorola ISG V.3400 have similar scores for throughput and impairedline (including the all-encompassing TIA

lines) performance, but the XM288E sends faxes faster. As with its more expensive counterparts, the XM288E doesn't support spoofing or flash-ROM upgrades, but it lists for only \$199, so you are, in fact, getting what you pay for. All the prices we quote, unless noted, are list prices; you should be able to find lower street prices.

The Hayes Accura v.34 and the U.S. Robotics Sportster V.34

Weighting for **Best Data** PERFORMANCE USABILITY 15%

FEATURES 10%

288 are also eligible for the low-cost category. The Accura is a scaleddown version of the more feature-laden Optima, but its performance is just as fast. Surprisingly, U.S. Robotics' Sportster

outperformed its higher-end Courier cousin.

Only one modem consistently failed a performance suite: The Archtek SmartLink 2834A simply could not connect to any of the fax machines in our test bed. Even with a firmware upgrade, the modem still could not speak "fax."

KEY

Ratings from 1 to 5: ▲ is the lowest; AAAA is the highest.

BYTE BEST

V.34 EXTERNAL MODEMS

Practical Peripherals wins hands down

BEST OVERALL

Practical Peripherals ProClass 288LCD



It's fast and easy to use. It has an informative LCD screen and a built-in clock. This modem took top honors in almost every aspect of our benchmarks, including two-way throughput, the TIA (Telecommunications Industry Association) Table 6 tests, and impaired-line performance testing. Its unusual look and small footprint delighted our testers. The

Hayes Optima 288 V.FC & Fax also provides solld performance, good usability, and excellent features, including a five-year warranty. The Hayes Optima V.34 & Fax placed lust after the Optima 288 V.FC & Fax. This modem has the best one-way throughput scores of all the modems we tested.



			OVERALL			THROU	ICHPUT 1			
	MANUFACTURER/MODEL	PRICE	SCORES	FEATURES	USABILITY	ONE-WAY	TWO-WAY	IMPAIRED 1	TIA 1	ENTEROP 2
BEST	Practical Peripherals ProClass 288	LCD\$459				5839	4934	6973	9307	76/80
MOUTH	Hayes Optima 288 V.FC & Fax	\$579			44	5847	4930	6573	9093	60/76
SMO-P	Hayes Optima 288 V.34 & Fax	\$579		444	44	5848	4445	6151	9013	72/72
EMER-19	Motorola ISG V.3400	\$895	***		***	5551	4699	5752	7532	84/80

Data throughput, plain and simple

BEST DATA

Practical Peripherals ProClass 288LCD



The criterion for best data modern is speed, speed, and more speed. No fax scores. The 288LCD's impressive performance numbers make it a winner. The LCD serves as a way of programming the modem. This eliminates much of the need to learn complex setup strings, and it lets you configure the modem without being attached to a PC. Unfortunately, the 288LCD lacks support for flash-ROM upgrades. The Hayes Optima V.FC & Fax followed the 288LCD, outperforming it only on one-way throughput.

			OVERALL			THROU	IGHPUT 1			
	MAHUFACTURER/MODEL	PRICE	SCORES	FEATURES	USABILITY	ONE-WAY	TWO-WAY	(MPAIRED 1	TIA 1	INTEROP 2
KEST	Practical Peripherals ProClass 288LCD	\$459			***	5839	4934	6973	9307	76/80
HARET-IP	Hayes Optima 288 V.FC & Fax	\$579	***	AA	AA	5847	4930	6573	9093	60/76
INC.	Black Box Modern 3400	\$895	***	444	444	5553	4699	5810	7458	80/80
DINES-IP	Hayes Optima 288 V.34 & Fax	\$579	***	44	AA	5848	4445	6151	9013	72/72

Evading the ever-elusive street price

COST (LESS THAN \$400)

Maxtech/GVC XM288E



The \$199 Maxtech/GVC XM288E and the \$299 Hayes Accura v.34 turned in virtually identical performance results. The Hayes excels in features, the Maxtech In usability. The Maxtech does what you want without the flashy LCDs, dasigner case, and high price tag. It also includes a five-year warranty. The Hayes modern delivers excellent performance and good features, but it doesn't support the high DTE (data terminal equipment) rate that the Optimas deliver or synchronous

mode transfers. The Logicode Quicktel has the best features list of this group, and the Taiwanese Lectron Pragmatic is next. It doesn't offer a U.S. support number, but we didn't need any. And the Zoom v.34x was our big winner in interoperability, completing the highest percentage of possible connections.

			OVERALL			THROU	GHPUT 1			
	MANUFACTURER/MODEL	PRICE	SCORES	FEATURES	USABILITY	ONE-WAY	TWO-WAY	IMPAIRED 1	TIA 1	INTEROP 2
1231	Maxtech/GVC XM288E	\$199	***	A	***	5584	4733	5908	7597	76/96
DME1-IP	Hayes Accura v.34	\$299	***	AA	AA	5846	4261	5729	8814	68/72
MINER-P	U.S. Robotics Sportster V.34 288	\$339		AA		5493	4240	5917	7725	68/92
PLINOETH-UP	Logicode Quicktel	\$279		***		5508	3458	5593	6744	72/68
EQUER-UP	Lectron Pragmatic DL1428RF	\$200	***	AA	***	5464	3507	5418	7571	88/88

¹ Bytes per second; higher numbers are faster.

² Percent V.34 calls/percent V.34 answers.

How We Tested

e received identical pairs of modems from each vendor and subjected them to seven different telephone line conditions and five kinds of data transfer tasks. We used Microsoft Windows 3.1 to drive the data through the modems, using serial communications enhancement software to take advantage of the 16550 UART (universal asynchronous receiver/transmitter) buffer chips and to overcome the limitations of the standard Windows communications driver. The test lines represent the findings from comprehensive TIA (Telecommunications Industry Association) surveys of lines in the U.S. Our performance tests also include varying amounts of line impairments.

THROUGHPUT TESTS

During throughput tests, modems transfer three types of files ranging in size from 131 to 333 KB. We measure each pair of modems for one-way and twoway transmissions over "central-office impairment conditions," a minimally impaired telephone line that represents most of the calls made in the U.S.

IMPAIRMENT TESTS

We selected six lines with specific local loop conditions. The most difficult lines are based on the V.56bis standard on the Intercontinental Network Model, Each line introduces a different combination of impairments: long satellite delays, phase roll, and noise. We connect like pairs of modems to a TAS series II modem tester that simulates the trunk line and local loops at both ends of the connection. The modems perform a one-way transfer over a given line at least 10 times.

Most of the modems negotiated the first four impaired lines without much difficulty. However, they were not as successful with the V.56bis lines. None of the external modems was able to negotiate the 16A.6.6 line at all. Only one PC Card, the Megahertz, was able to connect, and it could only do it once (a minimum of four connects is required for a successful test).

TIA LINE TESTS

For these tests, we adhered strictly to the guidelines specified by Table 6 in

the TIA bulletin TSB37-A. Following the procedures outlined in TSB-38, each modem negotiated each line once to transfer the TAS compressed file.

FAX TESTS

We used Microsoft Windows for Workgroups 3.11 to



send a single-page fax to a Brother Intellifax 620, a Hewlett-Packard Office-Jet, an Okidata DOC-IT 3000, a Sharp FO-510, and a Toshiba TF50. Only one modem failed this test. The scores are closely clumped because the fax machines transmit and receive data at a slower rate and thus limit the modems' performance.

INTEROPERABILITY

We gave each external modem three opportunities to call every other modem and transmit a single file. The scores represent a percentage of the successes (V.34 calls/V.34 answers). PC Card modems performed a similar test with six different external modems.

FEATURES AND EASE OF USE

We evaluated the modems on their features, such as their ability to spoof, the protocols they support, and the availability of on-line help. For PC Card modems, we looked at their connectors. slot type, and software. Ease of use includes the thoroughness of the documentation as well as the ease of installation and availability of customer support.

tester, from the front and

from its business end.

MODEM TEST EQUIPMENT

We connected identical pairs of modems to a TAS series II modem tester manufactured by Telecom Analysis Systems (Eatontown, NJ). The TAS is able to simulate most line conditions found throughout the world, including the central-office impairment conditions as specified in TIA line 17C: "There is mild white noise (22.0 dBm), second-order nonlinear distortion (55.0 dB compressed), third-order nonlinear distortion (56.0 dB), near echo (40.0 dB), far echo (20.0 dB), and a short satellite delay (27.1 ms). The loop emulator generated an EIA1 at both ends of the connection. This condition represents a direct connection spanning 2000 feet and is the shortest local loop." We connected the modems via the TAS to a Compag Deskpro 486DX2/66M equipped with a Hayes ESP board to ensure that communications between the TAS and the modems used the 16550

UARTs (universal asynchronous receiver/transmitters). Each modem supports V.42 error correction and V.42bis data compression, which we initialized on all the modems (even if the modem's default settings specified other protocols), so our throughput test results include the affect of these features as well. We configured the moderns to receive data at their fastest supported rate (up to 115.2 Kbps) and to use hardware RTS (request to send) flow control rather than XON/XOFF.



Jim Kane, Project Manager/NSTL, has been testing network and PC hardware at NSTL for the past five years.

Helen E. Holzbaur, R&D/NSTL, was a systems administrator and network manager at Temple University for 10 years before joining NSTL.

Fred Crown, Testing Consultant/NSTL, has 15 years of experience in the computer industry.

John McDonough, Technical Writer/NSTL.

The Lab Report is an ongoing collaborative project between BYTE magazine and National Software Testing Laboratories (NSTL), BYTE magazine and NSTL are both operating units of McGraw-Hill, Inc. Contact the NSTL staff on the Internet at editors@nstl.com; at NSTL_Inc., or at (610) 941-9600. Contact BYTE on the Internet or BIX at editors@blx.com or at (603) 924-2643.

WHAT'S DRIVING MAXTECH?

Driven by the Power of...

EXPERIENCE • MaxTech, along with it's affiliate GVC Corporation, is the world's largest manufacturer of PC modems, networking products and computer peripherals. No wonder five of the top 10 PC manufacturers put their name on our products.

PERFORMANCE • MaxTech custom designs each product
using the latest technology for maximum performance and reliability. That's why our products
are consistently rated as having the best

price/performance value.

PRICE • Each year, MaxTech produces over 5 million communication products in it's five ISO-9002 certified plants. This buying clout and production efficiency enables us to deliver high quality products with "value-added" features at the lowest possible price.

Modems • All MaxTech and GVC modems are engineered for throughputs up to 50% faster than other brands. And, each modem is packed with extras, such as call-back security, voice features, free fax/data software and a complete on-line service package.


Network Products • From 16-bit ISA NIC's to 32-bit EISA and PCI NIC's, HUBs, pocket adapters, PC cards and transceivers, MaxTech offers a complete line of network products for effortless network management.

Introducing the Yesbook — We took the "No" out of Notebook • Yesbook computers features a modular design which enables you to change and upgrade any key component at any time. You can custom select the CPU, the display, disk drive and more.

Monitors • Our line of 9" to 21" GVC brand color monitors provide the quality and performance you need. They come loaded with convenience and power features, all at prices tailored for the tightest budgets.

Now You Know.....

Since 1978, MaxTech has been driven by a commitment to the performance you need, at a better price than you thought, and the experience to make it all stick. For more information about MaxTech products, please call 1-800-9FOR-MAX.



SOLUTIONS FOR MOBILE PROFESSIONALS

PICK A PC CARD

or the first time, our modem testing has expanded into the world of PCMCIA. We tested seven modems from different vendors, and we found little to differentiate them. These modems, designed to fit into credit-card-size slots, are perfect for mobile computing. As with any modem, the concern is for short connect times, high throughput, and, hopefully, ease of use. It may seem a bit steep to pay \$499 for such a little modem, but keep in mind that you are not purchasing a box. Instead, you are purchasing the convenience of communicating on the road without taking along a "luggable" modem as well as investing in an emerging technology.

But like all good things, there is a downside to this micro-technology. Even though the peripherals provide more power and speed in smaller packages, they must still communicate with big, older technology. A good example of this awkward interface is the telephone connection. PC Card modem vendors have developed an ingenious way of implementing RJ-11 in their 5-mm-thick cards. EZjack, EZ-Port, and XJack are examples: The retractable RJ-11 jack pops out from the visible edge of the PC Card for when you need to connect to a phone line, and it tucks neatly back in when you are done. But the connectors are fragile. Rough handling can easily result in a broken jack and an unusable modem. Also, depending on how the jack is implemented, it could interfere with other PC Card devices in a loaded mobile system. Fortunately, all the jacks of this kind in this issue were offset enough to the side so that you could use other PC Card devices, such as an Ethernet or SCSI adapter, simultaneously.

This new breed of modems is probably the most standardized PC Card device available. All the major Card and Socket Services software programs offer at least minimal support for modems. Each of the modems that we tested came with its own software, and all operated with a point enabler. The advantage of using a point enabler to

Make Analog Connections on Digital Phone Lines Sans Destruction

There is nothing more frustrating than trying to make modem connections behind digital PBXes while in a hotel or at client sites. If there isn't a dedicated analog line for your modem, how do you send off your E-mail over a PBX line (the most common office phone system)? On top of that, there's a chance you can accidentally fry your PC Card modern by transmitting over digital PBX lines that carry higher voltage than analog lines.

Most modems are designed to work exclusively on analog phone lines. Directly connecting modems to certain PBXes, multiphone line jacks, and digital line jacks can subject the modems to excessive electrical current, resulting in a blown fuse, disabling DAA (data access arrangement) to a data line. This failure occurs because the digital line jacks don't use the same pins for tip and ring. These concerns have started a market for computer/telephone interface products that make connections on digital, PBX, hotel, and international telephones. Several devices let you connect your analog modern into a telephone handset so that you can use any digital line.

Unlimited Systems' ((619) 622-1400) Konexx Konnector Model 111, a \$159 portable device, protects modems from being destroyed by high voltage (see "Tales from the Trip" on page 159). It creates an RJ-11 jack at any telephone. The Model 111 is compatible with V.FC/V.34 specifications. You just unplug the coiled

handset cord from the telephone base unit, plug in the Model 111, and plug the handset cord into the Model 111. A telephone level switch matches the modem signal to the telephone's signal.

A similar analog/digital bridge is Radish's ((800) 474-5001) InsideLine (\$119.95), It connects standard modems into the telephone systems of most multiline business systems. Inside-Line feeds modern signals into the telephone base via its handset jack and matches signal levels to the requirements dictated by the base. The phone handset itself reconnects to InsideLine. This arrangement maintains the proprietary connection between the phone and host PBX or key system. Products' Modern Saver. Also among this genre of connectors is Tele-

Above: Unlimited Systems' Konexx Konnector Model 111. Right: IBM PC

Company Peripheral Adapt's ((408) 370-0515) TeleSwitch, a \$149.99 device that eliminates the

For basic PBX protection while on the road, IBM PC Company Peripheral Products' ((704) 595-7716) Modem Saver is a \$29 pen-size device that clips on a shirt pocket and detects when it's OK to connect an analog device to an unfamiliar phone line. You just insert it into the telephone jack and indicators let you know if the line is safe and warns you if the modern can be damaged by currents above 90 milliamperes. However, this is just a warning device and does not offer real protection against modem failure.

frustration of trying to find an analog line when you're not on home turf.

Several modem makers are integrating safeguards that prevent you from blowing a fuse. Representatives of Haves Microcomputer Products say that they have not yet encountered a PBX-fried modern but have started installing a high-current resistor in PC Card modems to provide "a comfort factor" for users. Modems from Megahertz with the C40 chip set include a Digital Line Guard that disconnects the modern when the current exceeds 125 mA.

-John McDonough

power up the modem and set the necessary parameters (e.g., speed, parity, and data/stop bits) is that the enabler is not memory-resident. Once you configure the mode and terminate the enabler, you free the memory for other applications. This

Weighting for **Best Overall and** Low Cost (<\$400) DATA AND FAX PERFORMANCE 75%

USABILITY 159

FEATURES 10%

greatly reduces the overhead that complex communications software produces.

The installations for the DOS point enabler can be tricky if you're unaccustomed to selecting interrupts and

port addresses. Most modems have unique enabler software. Don't be fooled by the enabler's name (e.g., ENAB-LER.EXE). More than likely, if you switch modems, you need a new executable and a new initialization string. Documentation was often cryptic as to where to find the appropriate command line for the enabler. Freeing memory is less of an issue in desktop systems that tend to be highly expandable than it is in mobile systems, where there is little space for installing extra SIMMs and where power conservation is a major consideration.

Now for the good news. The performance of PC Card modems on a fairly clean telephone line approaches that of the high-end externals and far exceeds that of the only-aver-



age V.34s. In fact, if we had based our rankings solely on throughput, interoperability. and fax scores. the top two PC Card modems would place third and fourth overall. Unfortunately for the

PC Card devices, we also consider performance under lessthan-ideal conditions. In the TIA tests, we subject these modems to 36 different line/ loop conditions while transfer-

BEST \mathbf{BYTE}

V.34 PC CARD MODEMS

Looking for high speed and interoperability?

BEST OVERALL

Practical Peripherals ProClass PCMCIA 288 with EZ-Port



The Practical Peripherals ProClass PCMCIA 288 modem finished with slightly lower performance numbers than the Hayes Optima but had noticeably higher usability numbers. It also tied for top honors on our PC Card interoperability testing. It comes with a retractable

phone jack (EZ-Port), and during testing, one of the two wires inside snapped off, rendering the modern useless. Once replaced, the modem ran extremely well, finishing first in our PC Card fax testing.



It also lists for \$40 less than the cost of the Optima 288 V.34 card. On the other hand, the Optima has several interesting features, including integrated overload protection, which prevents the unwary user from inadvertently "frying" the modem on a hotel PBX line.

			OVERALL			THROU	IGHPUT 1			
	MANUFACTURER/MODEL	PRICE	SCORES	FEATURES	USABILITY	ONE-WAY	TWO-WAY	IMPAIRED 1	TIA 1	INTEROP 2
1231	Practical Peripherals PCMCIA 288	\$459			444	5751	4819	4759	7179	83/100
ROWGER-UP	Hayes Optima 288 V.34 & Fax	\$499			•	5752	4732	5477	7884	67/83
EMEL-IP	Megahertz V.34 PCMCIA	\$449				5491	4353	4052	6744	33/83
NUMBER-UP	U.S. Robotics Sportster 28.8	\$499	***			5471	4256	5109	7424	83/100
DUNNEED-UP	TDK Systems DF2814	\$469	***		A	5485	5857	5938	7047	100/50
19061-09	Microcom Travel Card 28.8P	\$349	***		**	5612	3588	5152	7522	50/50
MARTINES - NO	Multi Tech MT2834LT	\$399			***	5037	2286	4369	6604	83/17

Fast data mover

BEST DATA

Hayes Optima 288 V.34 & Fax



The Hayes Optima 288 V.34 & Fax is the big winner based solely on data throughput. It has the best one-way throughput results of all the PC Card modems we tested. The Hayes also handled the TIA testing better than the others did. The Optima is the only PC Card modern we tested that supports synchronous communication (with optional Hayes software). Practical Peripherals ProClass is the first runner-up, thanks to its five-year warranty and excellent one-way throughput scores. Its support for flash-ROM upgrades renders it less likely to become obsolete as quickly as those that don't support this option.

			OVERALL			THROU	DCHPUT '			
	MANUFACTURER/MODEL	PRICE	SCORES	FEATURES	USABILITY	ONE-WAY	TWO-WAY	IMPAIRED 1	TIA 1	DITEROP 2
TEST	Hayes Optima 288 V.34 & Fax	\$499	***	***	A	5752	4732	5477	7884	67/83
NUMBER-UP	Practical Peripherals PCMCIA 288	\$459				5751	4819	4759	7179	83/100
EUROER-0P	Megahertz V.34 PCMCIA	\$449		AA	***	5491	4353	4052	6744	33/83
RUNDIER-UP	U.S. Robotics Sportster 28.8	\$499		A		5471	4256	5109	7424	83/100
RUNNER-UP	Microcom Travel Card 28.8P	\$349				5612	3588	5152	7522	50/50
MILE-P	TDK Systems DF2814	\$469		44	A	5485	5857	5938	7047	100/50
MINER-IP	Multi Tech MT2834LT	\$399		44	***	5037	2286	4369	6604	83/17

¹ Bytes per second; higher numbers are faster.

ring a small file. Because the TIA tests are executed only once (unless the modem fails. and then we retest it), the scores represent a general "feel" for how well a modem can perform under adverse conditions. The PC Card modems averaged about 300 bytes

per second less than their external counterparts. The difference in the impaired line testing, where we make modems repeatedly transfer a much longer file, is even more dramatic. Here, the difference is a staggering 2500 bytes per second. The moral: If you are

KEY

Ratings from 1 to 5: ▲ is the lowest; ▲▲▲▲ is the highest.

going abroad and expect to use your modem reliably, you may want to consider dragging an external one along just in case.

² Percent V.34 calls/percent V.34 answers.

HONORABLE MENTIONS



The Practical Peripherals Pro-Class 288LCD, our winner in the

Overall and Data categories, sports the largest LCD panel. No longer content to just beep, scream, and flash at us, modems are beginning to express themselves better. The 288LCD updates you on connect status, connect time, line conditions, compression status, and it

lets you configure the modem at the modem, eliminating much of the need to learn and input Hayes AT commands.

The Telebit FastBlazer 8840 may be more suited to high-end network use, with its numeric keypad on the front

and LCD screen that are well suited for network administration. The FastBlazer is just as informative as the Practical Peripherals ProClass



288LCD, with the exception that at test time, it could not communicate line conditions. By now, Telebit should have released a firmware upgrade that will support this function.

PC Card EZjacks, EZ-Ports, and XJacks are attached RJ-11 phone jacks. Now you don't have to use little dongles or extra cables; phone lines fit right into the modems'

simultaneously use the phone, forcing you to detach the phone cord from the jack. We found out the hard way that frequent attaching and detaching stresses the tiny wires

retractable jacks. On the downside, these jacks do not let you that form the connection, and they

The U.S. Robotics Sportster comes with a different kind of PC Card phone jack. Even though it isn't a retractable jack (you could lose it), it clips into the modem giving you the

security of knowing the cable will not slip. Also, the jack has two inputs, letting you use the telephone simultaneously without having to plug and unplug the jack from the modem.

are apt to break.



WHAT DOES IT REALLY MEAN?

If you have delayed purchasing a modem until V.34 arrived, you may find the information on the modem box akin to reading the side of a cereal box (you know there's a lot in the product, but you aren't quite sure what it all means). Here's a list of some of the more common features and what they really mean.

The modem is software upgradable, often as simple as typing DOWNLOAD modem.

V.42bis and MNP 5 for 4-to-1 compression

The modern can compress files, but 4-to-1 compression can be achieved only with V.42bis and a compressible file. Files created with utilities like ZIP or ARC are already compressed and would not benefit from these protocols. When the transmitting modern detects redundant units of data, it recodes them into shorter units of fewer bits. The receiving modem then decompresses the redundant data units before passing them to the computer.

V.42 or MNP error correction

Any modern that supports compression must also support its companion error-correction protocol. V.42 uses LAPM (Link Access Procedure for Moderns). LAPM is an error-control protocol incorporated in ITU-T Recommendation V.42. As with the MNP, LAPM uses CRC (cyclic redundancy check) and retransmission of corrupted data (ARQ) to ensure data reliability.

Data throughput of up to 115,200 bps

Transfer rates this high for an external modern require a serial port with at least a 16550 UART (unlversal asynchronous receiver/transmitter). The UART is a chip that transmits and receives data on the serial port.

Compliant with V.34 and V.FC

Modems are designed to "speak" the official V.34

protocol and the earlier V.FC Rockwell modulation scheme, as well as v.FAST.

Data rates or data transmission of up to 28.8 Kbps

The data or DCE (data communication equipment) rate is the maximum modem-to-modem speed that a modern can attain. Moderns negotiate the DCE rate during the handshaking process. Note that the modems can go only as fast as the slowest modem in the link will allow. This speed is dependent on the protocol that is used (e.g., V.34).

Fall back/Fall forward

Fall back is the ability of a modern to change Its transmission speed downward automatically when it encounters an overly noisy line (e.g., a 28.8-Kbps modern might fall back to 14.4 Kbps.) When the Iline condition improves, modems that support fall forward will renegotiate a higher transmission rate.

Satellite delay

When you communicate with telephone networks that use satellites to transmit signals, the process of beaming a signal to a satellite and routing it to the receiving land station results in a delay. This delay can be disastrous to some modems.

Spoofing allows older software, using older protocols, to run efficiently at higher speeds. Modems that spoof accelerate XModem and other stop-and-go protocols by returning a false acknowledgment as soon as a packet is sent from the DTE to the modern.

SOME OF THE V.PROTOCOLS

The newest ITU-T (International Telecommunication Union-Telecommunication) standard allows data rates up to 28.8 Kbps and line-probing capability.

The interim standard that preceded the ITU-T V.34 standard and is similar to it.

V.FC (V.FAST CLASS)


When the ITU-T delayed in approving the V.34 standard, Rockwell developed a proprietary modulation scheme for data communications speeds of up to

An ITU-T standard that extends the V.32 connection range: 4800, 7200, and 9600 bps, as well as 12 and 14.4 Kbps. V.32bis modems fall back to the next lower speed when line quality is impaired, and fall back further as necessary. They fail forward to the next higher speed when line quality improves.

An ITU-T standard for modern communications that defines a two-stage process of detection for LAPM error control.

V.42bb

An extension of ITU-T V.42 that defines a specific data communications compression scheme for use with V.42 error control.



Buying computer products is a major commitment. A commitment of time and money. So before you jump in with both feet, make sure the relationship is going to work. Look for the NSTL Seal.

National Software Testing Laboratories puts hardware and software through the most rigorous testing in the industry. Our exclusive compatibility tests, using real world equipment like yours, ensure that components will talk to each other, work together, get along great — or they can't carry the Seal. And that's true for everything from drivers and servers, to applications, adapters and printers.

For more information about the NSTL Seal or a list of manufacturers who have earned it, call 800-220-NSTL or 610-941-9600. Before you walk down the aisle.



ROLL CALL OF V.34 MODEMS

Microcom, Inc. Desk Porte Fast \$519 5605 3601 5120 7722 Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603		PERFORMANCE						
Best Data Products 2834FX \$299 5474 3511 5065 7524 Black Box Corp. Modem 3400 \$895 5553 4699 5810 7458 Boca Research, Inc. V.34 28,800 bps Boca Modem \$232 4 5478 3865 5890 6873 Cardinal Technologies, Inc. Cardinal 28.8 Fax/Modem \$179 4 5474 3510 5294 7455 CXR Telcom 2845-FD1 \$795 5479 4405 5516 7001 Hayes Microcomputer Products Accura v.34 \$299 5846 4261 5729 8814 Hayes Microcomputer Products Optima 288 V.34 & Fax \$579 5847 4930 6573 9093 IBM Corp. Options Data/Fax 7852 Model 10 \$287 5473 3737 5365 7581 IBM Corp. Options Data/Fax 7852 Model 13 \$429 5443 4403 5406 6044 Lectron Pragmatic DL1428RF \$200 5484 3507 5418 7571 Logicode Technology, Inc. Quicktel \$279 5508 3458 5593 6744 Maxtech/GVC XM288E \$199 5584 4733 5908 7597 Microcom, Inc. Desk Porte Fast \$519 5605 3601 5120 7722 Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT28342DX-ISI \$349 5226 3977 5586 6603 Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	INTEROPERABILITY 2	TIA LINES ¹	IMPAIRED LINES			LIST PRICE	MODEL	MANUFACTURER
Black Box Corp. Modem 3400 \$895 5553 4699 5810 7458 Boca Research, Inc. V.34 28,800 bps Boca Modem \$232 ' 5478 3865 5690 6873 Cardinal Technologies, Inc. Cardinal 28.8 Fax/Modem \$179 ' 5474 3510 5294 7455 CXR Telcom 2845-FD1 \$795 5479 4405 5516 7001 Hayes Microcomputer Products Accura v.34 \$299 5846 4261 5729 8814 Hayes Microcomputer Products Optima 288 V.FC & Fax \$579 5847 4930 6573 9093 IBM Corp. Options Data/Fax 7852 Model 10 \$287 5473 3737 5365 7581 IBM Corp. Options Data/Fax 7852 Model 13 \$429 5443 4403 5406 6044 Lectron Pragmatic DL1428RF \$200 5484 3507 5418 7571 Logicode Technology, Inc. Quicktel \$279 5508 3458 5593 6744 Maxtech	72/72	6244	2612	3963	4909	\$289	SmartLink 2834A	Archtek America Corp.
Boca Research, Inc. V.34 28,800 bps Boca Modem \$232 \ 5478	88/88	7524	5065	3511	5474	\$299	2834FX	Best Data Products
Cardinal Technologies, Inc. Cardinal 28.8 Fax/Modem \$179	80/80	7458	5810	4699	5553	\$895	Modem 3400	Black Box Corp.
CXR Telcom 2845-FD1 \$795 5479 4405 5516 7001 Hayes Microcomputer Products Accura v.34 \$299 5846 4261 5729 8814 Hayes Microcomputer Products Optima 288 V.34 & Fax \$579 5848 4445 6151 9013 Hayes Microcomputer Products Optima 288 V.FC & Fax \$579 5847 4930 6573 9093 IBM Corp. Options Data/Fax 7852 Model 10 \$287 5473 3737 5385 7581 IBM Corp. Options Data/Fax 7852 Model 13 \$429 5443 4403 5406 6044 Lectron Pragmatic DL1428RF \$200 5464 3507 5418 7571 Logicode Technology, Inc. Quicktel \$279 5508 3458 5593 6744 Maxtech/GVC XM288E \$199 5584 4733 5908 7597 Microcom, Inc. Desk Porte Fast \$519 5605 3601 5120 7722 Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603 Practical Peripherats ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	68/68	6873	5690	3865	5478	\$2324	V.34 28,800 bps Boca Modem	Boca Research, Inc.
Hayes Microcomputer Products	76/72	7455	5294	3510	5474	\$1794	Cardinal 28.8 Fax/Modern	Cardinal Technologies, Inc.
Hayes Microcomputer Products Optima 288 V.34 & Fax \$579 5848 4445 6151 9013 Hayes Microcomputer Products Optima 288 V.FC & Fax \$579 5847 4930 6573 9093 IBM Corp. Options Data/Fax 7852 Model 10 \$287 5473 3737 5365 7581 IBM Corp. Options Data/Fax 7852 Model 13 \$429 5443 4403 5406 6044 Lectron Pragmatic DL1428RF \$200 5464 3507 5418 7571 Logicode Technology, Inc. Quicktel \$279 5508 3458 5593 6744 Maxtech/GVC XM28BE \$199 5584 4733 5908 7597 Microcom, Inc. Desk Porte Fast \$519 5605 3601 5120 7722 Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603 Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	80/72	7001	5516	4405	5479	\$795	2845-FD1	CXR Telcom
Hayes Microcomputer Products Optima 288 V.FC & Fax \$579 5847 4930 6573 9093 IBM Corp. Options Data/Fax 7852 Model 10 \$287 5473 3737 5365 7581 IBM Corp. Options Data/Fax 7852 Model 13 \$429 5443 4403 5406 6044 Lectron Pragmatic DL1428RF \$200 5464 3507 5418 7571 Logicode Technology, Inc. Quicktel \$279 5508 3458 5593 6744 Maxtech/GVC XM288E \$199 5584 4733 5908 7597 Microcom, Inc. Desk Porte Fast \$519 5605 3601 5120 7722 Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603 Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	68/72	8814	5729	4261	5846	\$299	Accura v.34	Hayes Microcomputer Products
IBM Corp. Options Data/Fax 7852 Model 10 \$287 5473 3737 5365 7581 IBM Corp. Options Data/Fax 7852 Model 13 \$429 5443 4403 5406 6044 Lectron Pragmatic DL1428RF \$200 5464 3507 5418 7571 Logicode Technology, Inc. Quicktel \$279 5508 3458 5593 6744 Maxtech/GVC XM288E \$199 5584 4733 5908 7597 Microcom, Inc. Desk Porte Fast \$519 5605 3601 5120 7722 Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603 Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportser V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	72/72	9013	6151	4445	5848	\$579	Optima 288 V.34 & Fax	Hayes Microcomputer Products
IBM Corp. Options Data/Fax 7852 Model 13 \$429 5443 4403 5406 6044 Lectron Pragmatic DL1428RF \$200 5464 3507 5418 7571 Logicode Technology, Inc. Quicktel \$279 5508 3458 5593 6744 Maxtech/GVC XM288E \$199 5584 4733 5908 7597 Microcom, Inc. Desk Porte Fast \$519 5605 3601 5120 7722 Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603 Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339	60/76	9093	6573	4930	5847	\$579	Optima 288 V.FC & Fax	Hayes Microcomputer Products
Lectron Pragmatic DL1428RF \$200 5484 3507 5418 7571 Logicode Technology, Inc. Quicktel \$279 5508 3458 5593 6744 Maxtech/GVC XM288E \$199 5584 4733 5908 7597 Microcom, Inc. Desk Porte Fast \$519 5605 3601 5120 7722 Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603 Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modern 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 ◆	80/96	7581	5365	3737	5473	\$287	Options Data/Fax 7852 Model 10	IBM Corp.
Logicode Technology, Inc. Quicktel \$279 5508 3458 5593 6744 Maxtech/GVC XM288E \$199 5584 4733 5908 7597 Microcom, Inc. Desk Porte Fast \$519 5605 3601 5120 7722 Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603 Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	60/60	6044	5406	4403	5443	\$429	Options Data/Fax 7852 Model 13	IBM Corp.
Maxtech/GVC XM288E \$199 5584 4733 5908 7597 Microcom, Inc. Desk Porte Fast \$519 5605 3601 5120 7722 Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603 Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 *	88/88	7571	5418	3507	5464	\$200	DL1428RF	Lectron Pragmatic
Microcom, Inc. Desk Porte Fast \$519 5605 3601 5120 7722 Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603 Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	72/68	6744	5593	3458	5508	\$279	Quicktel	Logicode Technology, Inc.
Motorola ISG V.3400 \$895 5551 4699 5752 7532 Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603 Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	76/96	7597	5908	4733	5584	\$199	XM288E	Maxtech/GVC
Multi Tech Systems, Inc. MT2834ZDX-ISI \$349 5226 3977 5586 6603 Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	76/36	7722	5120	3601	5605	\$519	Desk Porte Fast	Microcom, Inc.
Practical Peripherals ProClass 288LCD \$459 5839 4934 6973 9307 Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	84/80	7532	5752	4699	5551	\$895	V.3400	Motorola ISG
Supra Corp. Supra Modem 288 \$250 5460 3413 5425 6938 Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	88/80	6603	5586	3977	5226	\$349	MT2834ZDX-ISI	Multi Tech Systems, Inc.
Telebit Corp. FastBlazer 8840 \$1199 5283 4746 4911 6467 U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	76/80	9307	6973	4934	5839	\$459	ProClass 288LCD	Practical Peripherals
U.S. Robotics, Inc. Sportster V.34 288 \$339 5493 4240 5917 7725 U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	80/72	6938	5425	3413	5460	\$250	Supra Modern 288	Supra Corp.
U.S. Robotics, Inc. Courier V.Everything \$595 5466 3502 5831 7599 •	84/100	6467	4911	4746	5283	\$1199	FastBlazer 8840	Telebit Corp.
7.20	68/92	7725	5917	4240	5493	\$339	Sportster V.34 288	U.S. Robotics, Inc.
Zoltrix, Inc. V.34 ZX-288 \$166 5586 3610 5766 7465	68/100	7599 •	5831	3502	5466	\$595	Courier V.Everything	U.S. Robotics, Inc.
	76/80	7465	5766	3610	5586	\$166	V.34 ZX-288	Zottrix, Inc.
Zolltrix, Inc. V.fast ZX-288 \$136 5501 3611 5426 7113	64/80	7113	5426	3611	5501	\$136	V.fast ZX-288	Zoltrix, Inc.
Zoom Telephonics, Inc. Zoom V.34x \$299 5474 3501 5214 7537	84/92	7537	5214	3501	5474	\$299	Zoom V.34x	Zoom Telephonics, Inc.

-					PERFO	RMANCE			MAX. S	PEEDS (Kbps)
		LIST	THROU	GHPUT 1					D	CE
MANUFACTURER	MODEL	PRICE	ONE-WAY	TWO-WAY	IMPAIRED LINES	TIA LINES 1	INTEROPERABILITY 2	FAX 3	DATA	FAX
Hayes Microcomputer Products	Optima 288 V.34 & Fax for PCMCIA with EZjack	\$499	5752	4732	5477	7884	67/83	60	28.8	14.4
Megahertz Corp.	V.34 PCMCIA	\$449	5491	4353	4052	6744	33/83	65	115.2	14.4
Microcom, Inc.	Travel Card 28.8P	\$349	5612	3588	5152	7522	50/50	61	28.8	14.4
Multi Tech Systems, Inc.	MT2834LT	\$399	5037	2286	4369	6604	83/17	68	28.8	14.4
Practical Peripherals	ProClass PCMCIA 288 with EZ-Port	\$459	5751	4819	4759	7179	83/100	60	28.8	14.4
TDK Systems	DF2814	\$469	5485	5857	5938	7047	100/50	61	28.8	14.4
U.S. Robotics, Inc.	Sportster 28.8	\$499	5471	4256	5109	7424	83/100	60	28.8	14.4
BYTE Best.	1 Bytes per second: higher n	umber are	a factor 2	Percent V 34	calls/nercent V 34 a	newere	3 Seconds	4 6	Street nrice	

TESTED

FEATURES CONTINUE ON NEXT PAGE

	MAX DCE	. SPEEDS	(Kbps)			CHIP	SETS			ERROR CO	NTROL/CO	MPRESSION	
FAX 3	DATA	FAX	DTE	DATA PUN	IP	VIII	CONTROLLE	R	MNI		LAPB	LAPM	V.428IS
	28.8	14.4	115.2	AT&T C88	82-29Q-5		AT&T 1633	F08 AB	•	0	•	•	•
60	28.8	14.4	115.2	Rockwell	RC288DP	Pi, R6682-269	Rockwell L	3903-55P, L39	9/U •	0	0	•	•
61	28.8	14.4	115.2	SGS-Tho	mson 754	4	Motorola 68	3302	•	0	0	0	•
60	28.8	14.4	115.2	Rockwell	RC288DP	Pi	Rockwell L	39	•	0	0	0	•
60	28.8	14.4	115.2	Rockwell	R6682-21		Rockwell L	3902-57	•	•	0	0	•
60	28.8	9.6	115.2	AT&T 163	33		Proprietary		•	0	0	0	•
61	28.8	14.4	115.2	Rockwell	R6682		Motorola 68302		•	0	•	•	•
61	28.8	14.4	230.4	Rockwell	R6682		Motorola 6	3302	•	0	•	•	•
61	28.8	14.4	280.4	Rockwell	R6670		Motorola 6	3302	•	0	0	0	•
60	28.8	14.4	115.2	Rockwell	RC288DF	Pi .	Rockwell L	39		•	0	0	•
60	28.8	14.4	115.2	AT&T DS	P1633		AT&T Z801	82-29	•	0	0	0	•
60	28.8	14.4	115.2	Rockwell	RC288DF	Pi	Rockwell L	39/U	•	•	0	•	•
60	28.8	14.4	115.2	Rockwell	RC6682-2	21	Rockwell L	39U2-57	•	•	0	0	•
60	28.8	14.4	115.2	Rockwe	II 288DP	ı	Proprieta	ry GVC 291	0.	0	0	0	•
61	28.8	14.4	115.2	Rockwell	RC288DF	Pi	Zilog Z808	2	•	•	0	•	•
62	28.8	14.4	115.2	56002			Motorola 6	3302	•	0	0	0	•
68	28.8	14.4	115.2	AT&T DS	P33		Zilog 182		•	0	0	•	•
60	28.8	14.4	230.4	Rockwe	II RC288	IDPI	Highspee	d 80C52	•	0	0	•	•
60	28.8	14.4	115.2	Rockwell	RC288DF	Pi	Rockwell 3	900 Series	•	•	0	0	•
	28.8	N/A	115.2	Proprieta	ry		Proprietary	1	•	0	0	•	
60	28.8	14.4	115.2	Texas Ins	struments	C51	Intel 186 w	ith USR code	•	0	0	•	•
60	28.8	14.4	115.2	Texas Ins	struments	C51	Intel 186 w	ith USR code	•	0	0	•	•
60	28.8	14.4	115.2	Rockwell	RC288DF	Pi	Rockwell I	.39/U	•	0	0	0	•
60	28.8	14.4	115.2	Rockwell	RC288DF	PIVFC	Rockwell I	.39/U	•	0	0	0	•
60	28.8	14.4	115.2	Rockwell	RC288DF	Pi	Rockwell L	3900-55 or L3	902-57	•	0	•	•
	0.00	CHIP SE		-		NTROL/COMF		SLOT	XJACK	CARD & SOCKET		UNICATIONS	-
DTE 230.4	DATA PUMP		ONTROLLER Dallas DS80C320	MNP S	MNP 10	O LAPB LA		Type II	CONNECTOR	SERVICES		VARE PROVID	
230.4	HOCKWEII HG	063-17 D	Danas DSOUC320	•	9	0	•	турап		•		Program	88 FOMOIA
115.2	AT&T DSP16	3x Z	Zilog Z80182	•	0	0	•	Type II	•	•	Point	Enabler; Sys	tem software
115.2	Rockwell RC	288DPi Z	Zilog Z8082	•	•	0	•	Type II	0	•	Point	Enabler	
115.2	AT&T DSP33	3 Z	Cilog 182	•	0	0	1-10	Type II	0	•		Enabler, Pho ager Plus 3.0	enixCard
230.4	Rockwell RC	288DPL D	Dallas Highspeed 80C5	2 •	0	0	•	Type II	•	0	Point	Enabler	

Type II

Type II

0

0

N/A = not applicable. • = yes; O = no.

115.2 Texas Instruments C51 Intel 186

Proprietary

0

0

300.0 Rockwell

Point Enabler

Point Enabler


ROLL CALL OF V.34 MODEMS

			FAX SUP	PORT			COMM	AND SETS	
MANUFACTURER	MODEL	CLASS 1	CLASS 2	V.17	V.29	HAYES ESCAPE	TIES ESCAPE	BREAK ESCAPE	PROPRIETARY
Archtek America Corp.	SmartLink 2834A	•	•	•	•	•	0	0	0
Best Data Products	2834FX	•	•		0	•	0	0	0
Black Box Corp.	Modern 3400	•	•	•	•	•	0	0	0
Boca Research, Inc.	V.34 28,800 bps Boca Modem	•	•	•	0	•	0	0	0
Cardinal Technologies, Inc.	Cardinal 28.8 Fax/Modem	•	•	•	•	•	0	0	0
CXR Telcom	2845-FDF1	•	•	0		•	0	•	0
Hayes Microcomputer Products	Accura v.34	•	0	•	•	•	0	0	0
Hayes Microcomputer Products	Optima 288 V.34 & Fax	•	0	•	•	•	0	0	0
Hayes Microcomputer Products	Optima 288 V.FC & Fax	•	0	•	0	•	0	0	0
IBM Corp.	Options Data/Fax 7852 Model 10	•	•	•	•	•	0	0	0
IBM Corp.	Options Data/Fax 7852 Model 13	•	•	•	•	•	0	0	0
Lectron Pragmatic	DL1428RF	•	•	•	•	•	0	0	
Logicode Technology, Inc.	Quicktel	•	•	•	•	•	0	•	0
Maxtech/GVC	XM288E	•	•	•	•	0	•	0	0
Microcom, Inc.	Desk Porte Fast	•	0	•	0	•	0	•	0
Motorola ISG	V.3400	•	0	•	•	•	0	0	0
Multi Tech Systems, Inc.	MT2834ZDX-ISI	0	•	•	•	0	•	•	0
Practical Peripherals	ProClass 288LCD	•	•	•	•		0	0	0
Supra Corp.	Supra Modem 288	•	•	•	0	•	0	0	0
Telebit Corp.	FastBlazer 8840	0	0	0	0	•	0	0	
U.S. Robotics, Inc.	Sportster V.34 288	•	•	•	•	•	0	0	0
U.S. Robotics, Inc.	Courier V.Everything	•	•	•	•	•	0	0	0
Zoltrix, Inc.	V.34 ZX-288	•	•	•	•	•	0	0	0
Zottrix, Inc.	V.fast ZX-288	•	•	•	•	•	0	0	0
Zoorn Telephonics, Inc.	Zoom V.34x	•	•	•	•	•	0	•	0

								CO	MMAND S	ETS		OTHER	
				FAX SUPP	ORT		HAYES	TIES	BREAK	PROPRIETARY	FLASH	LEASED-LINE	
1	MANUFACTURER	MODEL	CLASS 1	CLASS 2	V.17	V.29	ESCAPE	ESCAPE	ESCAPE	è	ROM	SUPPORT	DOS
ST.	Hayes Microcomputer Products	Optima 288 V.34 & Fax	•	0	•	0	•	0	0	0	0	•	Smartcom Exec
	Megahertz Corp.	V.34 PCMCIA	•	•	•	•		0	0	0	0	0	N/A
	Microcom, Inc.	Travel Card 28.8P	•	0	•	0	•	0	•	0	0		N/A
	Multi Tech Systems, Inc.	MT2834LT	0	•	•	•	0	•	•	0	0	0	N/A
NIII.	Practical Peripherals	ProClass PCMCIA 288 with EZ-Port	•	•	•	•	•	0	0	0	•	0	QuickLink II
	TDK Systems	DF2814	•	0	•	•	•	0	0	0	0	0	QuickLink II
	U.S. Robotics, Inc.	Sportster 28.8	•	•	•	•	•	0	0	0	•	0	QuickLink II
	= BYTE Best.	N/A = not applicable.	● = yes	; O = no.									

TESTED

	THER									
FLASH ROM	LEASED-LINE SUPPORT	DOS		SOFTWAI	RE	MAC	WARRANTY (YEARS)	PHONE	TOLL-FREE PHONE	INQUIRY
•	•	DOSFax Lite, Comit	Lite	WinFax Lite, Co	mit Lite	QuickLink II Fax	5	(818) 912-9800	N/A	1105
0	0	Deirina 4 in 1		Delrina 4 in 1		MacCommCenter	2	(818) 773-9600	(800) 632-2378	1106
0	•	FaxTalk		FaxTalk		N/A	1	(412) 746-5500	N/A	1107
0	0	NA		FaxWorks		MacCommCenter	5	(407) 997-6227	N/A	1108
•	0	N/A		FaxWorks, Com	nit	N/A Lin	nited lifetime	(717) 293-3000	(800) 775-0899	1109
•	0	N/A		N/A		N/A	5	(408) 435-8520	(800) 433-1425	1110
0	0	Smartcom Exec		Smartcom		Smartcom II	5	(404) 441-1617	N/A	1111
0	0	Smartcom Exec		Smartcom		Smartcom II	5	(404) 441-1617	N/A	1112
0	•	Smartcom Exec		Smartcom		Smartcom II	5	(404) 441-1617	N/A	1113
0	0	QuickLink II Plus		QuickLink II Plu	S	QuickLink II Plus	1	(602) 629-3200	(800) 426-2968	1114
•	•	N/A		N/A		N/A	1	(602) 629-3200	(800) 426-2968	1115
0		BitFax, BitCom		BitFax, BitCom		MacCommCenter	2	+886 2 5682399		1116
•		Delrina 4 in 1		Delrina 4 in 1		FaxLite, QuickLink II	Lifetime	(805) 388-9000	(800) 735-6442	1117
0		Deirina 4 in 1		Deirina 4 in 1		FaxPro with Micropho		(201) 579-363	Carried to the Second	
		N/A		FaxWorks		N/A	5	(617) 551-1000	(800) 822-8224	1119
0		FaxTalk Plus		FaxTalk Plus		N/A	2	(508) 261-4000	(800) 487-1456	1120
0	0	MultiExpress, MultiE	vnrace		S, MultiExpress	MacCommCenter	10	(612) 785-3500	(800) 328-9717	1122
0	0	Fax	живаа		ess, MultiExpress	Macconinoenter	10	(012) 783-3300	(000) 320-3717	1122
0		QuickLink II		WinFax Lite,	QuickLink II	MacCommCenter	Lifetime	(805) 497-477	4 N/A	1123
•	0	Comit		Comit, FaxTalk		MicrophoneLT, Faxcilitate	5	(360) 604-1410	(800) 727-8772	1124
•	•	N/A		N/A		N/A	2	(408) 734-4333	(800) 835-3248	1125
0	0	QuickLink II		QuickLink II		MacCommCenter	5	(708) 676-7010	(800) 342-5877	1126
•	•	QuickLink II		QuickLink II		NA	2	(708) 982-5010	(800) 342-5877	1127
0	•	N/A		BitWare Lite		N/A	5	(510) 657-1188	N/A	1128
0	•	N/A		BitWare Lite		N/A	5	(510) 657-1188	N/A	1129
0	0	Comit, DOSFax Lite		Comit, WinFax	Lite	Microphone LT, MaxFax	7	(617) 423-1072	(800) 666-6191	1130
WINDOWS	SOFTWARE	MAC	SLOT TYPE	XJACK CONNECTOR	CARD & SOCKE SERVICES	T COMMUNICATIONS SOFTWARE PROVIDED	WARRANTY (YEARS)	PHONE	TOLL-FREE PHONE	INQUIRY NUMBER
Smartcom	_	NA	Type II	•	•	Point Enabler; Hayes	5	(404) 441-1617	NA	1346
***************************************			.,,,			PCMCIA Instali Program		. ,		
FaxWorks I	Data	N/A	Type II	•	•	Point Enabler, System s	oft 5	(801) 320-7000	(800) 527-8677	1347
FaxWorks		N/A	Type II	0	•	Point Enabler	5	(617) 551-1000	(800) 822-8224	1348
MultiExpres Express Fa		N/A	Type II	0	• 11/4	Point Enabler, Phoenix Manager Plus 3.0	CARD 5	(612) 785-3500	(800) 328-9717	1349
WinFax Lite	e, QuickLink II	MacCommCenter	Type II	•	0	Point Enabler	5	(805) 497-4774	N/A	1350
QuickLink I	ľ	STF Startfaxing, Microphone LT	Type II	0	0	Point Enabler	5	(916) 478-8421	(800) 999-4835	1351
QuickLink I	II	N/A	Type I	0	•	Point Enabler	5	(708) 676-7010	(800) 342-5877	1352



"We recommend the Action AXP 2", as an excellent all-around NT workstation."

BYTE Magazine, March 1995

"WHOOSH!"

Windows Magazine, March 1995

"AXP275 streaks from the gate, shatters records, the stopwatch"

Government Computer News, February 6, 1995

"Alpha cleans Pentium's clock"
Windows Sources, February 1995

"As good as it gets if you need speed"

PC World, February 1995

"Action AXP275 runs NT at full throttle"

PC WEEK, November 7, 1994

The AXP275 offers the fastest Win32 performance we've seen..."

Windows Sources, February 1995

"Every component of this computer is representative of the best technology available."

PC World, February 1995

The World's First Personal SuperComputer (PSC)

Nothing compares to the computing power of the ACTion AXP275 RISC PC—the first Personal SuperComputer. The PCI—based ACTion System from BTG uses Digital Semiconductor's Alpha 21064A 64—bit microprocessor, with a cycle time of 275 MHz—the fastest processor available today!

Capable of peak execution rates of 555 MIPS, its performance is equivalent to a supercomputer. Imagine what you can do with this much computing power!

With Microsoft® Windows NT™ installed, the ACTion Alpha AXP275 provides the

same familiar user interface as the MS Windows operating system, and runs MS DOS and all 16-bit and 32-bit Windows applications.

Powered by Digital and Microsoft Graphics by Nokia and Number Nine Storage by Hewlett-Packard and Toshiba Networking by Cogent.

To learn more about the ACTion AXP275 or any other of our ACTion System computers, including Pentium, call:

(800) 449-4228 FAX (703) 876-1920





















Designing Alpha-Based Systems

Digital's trio of processors

offers different design

possibilities

BRUCE FAUST

n a world where speed is king, not all RISC PCs are created equal. Currently, there is a marketing battle over which of the industry titans' RISC PCs are the fastest. However, there's one unmistakable truth concerning RISC PCs: If you have ever used one and run a "native" Windows NT

application (an application compiled for the RISC processor, not something running in an x86 emulator), you'll never want to go back to an x86-based system.

Consider, for example, Digital Equipment's Alpha AXP family of microprocessors. Digital's Semiconductor Operation (Hudson, MA) has developed CPUs for many years, and the Alpha comes from the microVAX family of CPUs. However, the Alpha is rather unique when compared to other RISC processors. It was designed from the beginning as 64-bit processor, which differs from other 64-bit RISC processors that have evolved from 32-bit implementations. It has 64-bit address and data lines, pipelined both in and out of the processor. Furthermore, not only is the Alpha superpipelined but superscalar as well. In a superscalar design, the CPU is issuing more than one instruction per clock tick. Digital's newest Alpha design, the 21164, issues four instructions per clock tick. This super-superscalar approach, coupled with a 300-MHz clock speed, yields a mind-bending 1.2 billion instructions per second.

There are essentially three types of Alpha CPUs. The table on page 240 shows a comparison of the Alpha family of processors. These are the 21066, 21064 (with two varieties), and 21164. As the table shows, the taxonomy of each processor is quite similar. However, there are variations in the internal cache sizes, clock speeds, and external glue logic required. With that in mind, let's start with the first member of the Alpha family.

The 21066 (PCA, PC Alpha)

The 21066's strength lies in its ready ease of integration into a PC system, hence the moniker, PC Alpha. That's because the 21066 provides all on-board cache, DRAM, and PCI (Peripheral Component Interconnect) logic signals. The PCI bus interface is 32 bits wide, which offers

transfer rates of up to 132 MBps. Put another way, the designer doesn't have to design the external glue logic for the cache, main memory, or a PCI interface. A computer architect can lay out the motherboard and then attach the multiplexed address and data lines for the write-back cache and main memory. Digital added an on-board PLL (phase-locked loop) that further sim-

plifies the implementation of the PCI interface. You supply the 21006 with an external 33-MHz clock signal, and the PLL multiplies it internally to give the processor a clock speed to either 166 MHz or 233 MHz. Meanwhile, the external hardware, such as the PCI bus, cache, and memory continue to operate at 33 MHz, simplifying design and component costs.

In some tests, the 21066 can outperform the faster 21064 family of CPUs in PCI I/O, simply because the former processor's PCI interface is efficient. The cache and DRAM bus are 64 bits wide, giving the processor bandwidth up to 264 MBps. However, because the cache and DRAM interface are time-multiplexed, the 21066 takes a performance hit relative to the 21064 and 21164 processors on memory accesses.

While the 21066's integer performance is bested by Intel's Pentium (94 SPECin92 at 233 MHz versus 112 SPECint92 for a 100-MHz Pentium), the Alpha's floating-point performance is quite impressive (110 SPECfp92 versus the Pentium's 82 SPECfp92). Floating-point computations are extremely important for such applications as rendering, animation, CAD, and other scientific applications. The strengths of the 21066 are evident in low-cost 64-bit RISC applications. If you want good floating-point performance as well as good I/O performance in a low-cost workstation, the 21066-based workstation is for you. Users of 21066-based systems enjoy about 25 percent better floating-point performance than Pentium 100 users. Base prices for 21066-based machines are under \$4000.

The 21064

The 21064 was the first Alpha processor to arrive on the market, originally running at 150 MHz. Now the chip ticks along at 275 MHz. However, the 21064 requires external glue logic to interface the cache, DRAM, and PCI. The 21064 uses separate (nonmultiplexed) address and data lines; therefore, memory accesses are more efficient than in the 21066. This bus arrangement also allows such enhancements as doubling the data paths from 64 bit to 128 bits, which offers a more effective method for

Core Technologies CPUs

minimizing wait states and maximizing cache efficiency. However, designing the cache technology to minimize the wait states from the CPU to cache memory is somewhat difficult, because a 21064 running at 275 MHz has a 4-ns (nanosecond) access cycle time. As result, even using the currently available 15-ns, 1-Mb static RAMs yields four wait states per memory access at best.

Using such cache techniques as two-set associativity and synchronous static RAMs greatly improves cache performance. For sequential data applications, it is sometimes better to operate a smaller yet faster cache, such as one 512-KB cache using 10-ns parts. In

applications where the data might be accessed randomly, having a larger yet slower cache offered better performance.

Newer 21064-based designs that offer cache SIMM modules are on the way. These cache SIMM modules are densely populated and can use fast 10-ns, 256-KB or 1-MB parts. These modules can be expanded from 2 MB up to 8 MB, allowing the 21064-based system to gain the best of both worlds: fast 10-ns access time for sequential applications and a deep cache for random-access applications. However, this makes the 21064 design more complex than developing a 21066-based machine.

Although the 21064 might be more of a design challenge for engineers, users who like the more-power approach to computing love this class of machine. Running native Window NT applications, a 275-MHz 21064 machine is about twice the speed of the Pentium 100 system, and floating-point performance is roughly four times faster than that of the Pentium. Emulated 16-bit x86 applications on the Alpha run at about the speed of a 50-MHz 486DX2. So, if you run many 16-bit applications, you might want a Pentium system instead.

The 21164

The 21164 is the newest in a series of Alpha CPUs from Digital. And this one really screams, especially when it can operate at 300 MHz. At this speed, it posts 330 SPECint92 and 500 SPECfp92. The key to this blazing performance is that the processor has a level 2 cache on-chip and issues four instructions per clock cycle. Because the level 2 cache is latched to the speed of the microprocessor, it offers zero wait states. The only exception, of course, is if the next set of data is not cached in either the level 1 or level 2 cache and must be fetched from an off-chip cache or from main memory. With cycle times now less than 4 ns, and using cache module SIMMs with 10-ns speeds, the 21164 will probably have at least four wait states. However, silicon that glues this chip to a third level cache, DRAM, and PCI interface is not yet available. Such chip sets are expected to be released later this summer. Also, the planned

	21066	21066A	21064	21064A	21164
Total on-chip cache size	16 KB	32 KB	16 KB	32 KB	112 KB
On-chip secondary cache size	n/a	in/a,	n/a	n/a	96 KB (unified data and instruction
Die technology (micron size)	.68	.50	.75	.50	.50 to .40
Clock speed (MHz)	166	233	150, 166, 200	233, 275	266, 300, 300+
Transistor count (millions)	2.2	2.4	1.6	1.8	9.6
External data bus	64 bit	64 bit	128 bit	128 bit	256 bit
External cache (level 2)	256 KB to 1 MB	256 KB to 1 MB	128 KB to 16 MB	128 KB to 16 MB	n/a
External cache (level 3)	n/a	n/a	n/a	n/a	2 MB to 64 ME
Build in DRAM interface	• 6		0	0	0
Build in cache RAM interface		•	0	9	0
Build in PCI interface (32 bit)			0	O	ō
External chip set required?	0	0	•	•	•
External chip set PCI interface	32 bit	32 bit	32 bit	32 bit	64 bit
Pin grid array count	287 pln	287 pin	2431 pin	431 pin	499 pin
Power dissipation	22.5 W	27 W	27 W	32 W	43.5 W

PCI interface is expected to be expanded to 64 bits, adding to the complexity of the ASIC design of the glue interface. Early versions of systems based on this chip will be expensive. Such systems will have complex designs and will require costly high-speed parts to keep the 21164 running at full speed. Also, the 21164 alone has a price tag of \$3000—higher than the price of some PC systems.

Market Outlook

Despite the Alpha's lead in the clock and performance race, Digital clearly has a number of obstacles it must overcome to make the processor pervasive. First and foremost, more software vendors need to embrace the Alpha. Currently, a number of vendors have ported applications to the processor. To date, over 1500 vendors with applications such as Word and Excel have already been ported. However, it's the ports of such software as Microstation, Pro Engineer, and NewTek's Lightwave 3D that has fueled a boom in the Alpha-based workstation market. These applications are heavily floating-point intensive, and the native versions of these applications run circles around Pentium and even other competing RISC architectures.

Another obstacle is support silicon. Glue logic chip sets are crucial for system designers to develop hardware capable of harnessing the Alpha technology. Without this, I doubt many designers would be interested in developing programmable array logic—based motherboards. However, DeskStation (Lenexa, KS) has recently developed a chip set for the 21064 and one for the 21164. These should be available early this summer. Other vendors should follow suit.

Finally, pricing for the Alpha chip technology must entice users to make the switch from Intel or its clones over to Alpha. Time will tell if Digital has made the right gamble.

Bruce Faust holds a graduate degree and is founder of Carrera Computers and NekoTech. Both NekoTech and Carrera manufacture RISC PCs based on Alpha technology.

Windows 95 Graphics Architecture

New device-driver interfaces in Windows 95 help vendors of graphics boards showcase their

hardware-acceleration features

STANFORD DIEHL

rmed with figures forecasting huge growth in the entertainment market and showing skyrocketing sales of multimedia-capable systems to the home, Microsoft is touting Windows 95 as a multimedia OS from the ground up. With multimedia in mind, Microsoft has revamped the graphics architecture of Windows.

Most of the improved graphics architecture of Windows 95 has already shipped incrementally as APIs for Windows 3.1. These components will be integrated under Windows 95 and will sit on top of a new set of DDIs (device-driver interfaces). They are the DCI (Display Control Interface) DDI, 3-D DDI, and GDI (Graphical Device Interface) DDI (see the figure "Windows DDI Architecture").

They will make it easier for vendors to write drivers that take advantage of specific hardware-acceleration features. The DDIs will act somewhat like DLLs for driver writers. Developers can call specific components of the DDI that their hardware can take advantage of and throw out the parts they don't need. The grand vision is a uni-

versal driver architecture for Windows 95 and, eventually, for Windows NT

dows NT as well.

The DDI Model

DCI, which was developed by Microsoft and Intel, grants video codecs direct access to hardware video accelerators. A video codec can determine if the graphics hardware supports special video functions (e.g., scaling and RGB-to-YUV conversion). If so, the codec can send unscaled YUV (the color format used by motion video) data directly to the video accelerator, freeing the CPU of scaling and conversion tasks. The device driver exposes a surface of video memory. The application can then write directly into the

video surface, either on-screen or off-screen. But DCI is currently only a specification; it's up to the graphics-card vendor to implement specific hardware features in a custom DCI driver. The DCI DDI will let vendors implement DCI functionality with little custom code.

DCI has been a boon for motion video on the Windows platform. It has driven Microsoft to follow the same model for enabling hardware acceleration of other graphics functions. Microsoft announced a set of four APIs that will encapsulate what is now the DCI DDI (see the text box "DCI: The Next Generation"), extending the model beyond digital video and standardizing interfaces for sound, multiuser games, and digital joysticks.

3-D Windows

Windows 95 won't ship with an integrated 3-D engine. Microsoft says it doesn't want to impose an engine on developers who are already tied to existing 3-D APIs. Thus, 3-D engines from Render Morphics (since bought by Microsoft), Criterion, and other vendors will sit atop the 3-D DDI. As DCI does with video accelerators, the 3-D DDI will take advantage of 3-D hardware when it's available. It will allow the hardware to handle supported functions and "fill in" the gaps by emulating other 3-D functions in software. A game might display flat-shaded polygons if played on unaccelerated hardware, but on 3-D hardware, you would get smooth texture mapping while maintaining performance.


The onus is on device-driver developers to enable hardware 3-D acceleration. When 3-D DDI ships ("post-Windows 95 launch," according to Microsoft), a driver devel-

oper will enable the set of 3-D functions offered through the DDI that his or her card can handle. Developers won't have to worry about which 3-D engine is being used. The application sends the 3-D function to the DDI, and it handles the rest, sending supported functions to the hardware and passing unsupported functions back to the CPU. Therefore, 3-D applications will

no longer have to support different 3-D chips.

continued

Windows 95 will provide a series of graphics APIs—for video, games, and 3-D rendering—using a new set of DDIs (device-driver interfaces) that enables vendors of graphics boards to showcase their hardware-acceleration capabilities.



Core Technologies Operating Systems

Games, Games, Games

For games development (a huge focus of Windows 95), WinG functionality will be integrated into the DIBEngine. Developers who create their own graphic worlds can bypass the GDI by blasting DIBs (deviceindependent bit maps) directly to the screen. This will allow games to run as fast (or faster) under Windows as under DOS. Games developed previously with the WinG API will run as is under Windows 95.

DOS sessions should be much more robust under Windows 95. Each session can carry its own configuration environment, featuring unloadable device drivers. Dynamic drivers that uninstall after use will also free up more conventional memory under DOS. And in the single-application mode, you can dedicate all resources to a single DOS session. You cannot multitask in the single-application mode, but you can ensure an optimal configuration for a resource-hungry game.

WinToon will also be integrated into the DIBEngine. Full-screen animations will be easier to deploy on the Windows platform, and features such as chroma-keying will let developers lay animations across various backgrounds, including video.

This is where an integrated engine improves performance. In Windows 3.1, DCI works through Video for Windows. Under Windows 95, however, developers can tap into DCI when it makes sense. Animators

can use the best performance scheme available: GD1, DCI, WinG, or a 3-D engine. All these components are now interlinked and talk to each other (see the figure). For instance, the DIBEngine could call a DCI video-memory surface (if a motion-video accelerator chip is present) and render a 3-D object on the video surface using specialized 3-D hardware. All these separate pieces come together in Windows 95.

Better Video

A new Windows technology called Surround Video can create a full 360-degree graphics environment. You first create background images with existing production techniques (e.g., 360-degree photography). Surround Video blends the image together to form an endless loop, correcting image distortion through remapping algorithms. Blue-screen keying superimposes overlay images or motion video on top of the background. The view from within the interface extends right or left in a full circle. Surround Video also incorporates authoring tools and scripts for designating a sequence of scenes, including other panoramas. Hot spots link to DIBs, AVI (Audio Video Interleave) movies, audio files, or other launchable components.

A new file type, called a striped DIB, stores scan lines as vertical strips (4 pixels wide). When you scroll to a new scene (a different view of the panorama), the engine loads enough vertical strips to fill the viewable area. In this way, the entire file is never read into memory (only the initial 640- by 480-pixel image is; a full 360degree image is typically 4000 by 480 pixels). To improve display

DCI: The Next Generation

In Windows 95, DCI (Display Control Interface) will be enriched with four new APIs. They will provide direct interfaces for fast video, sound, multiuser games, and digital joysticks.



Essentially, the new version of DCL DirectDraw will let applications access hardware video and display surfaces directly.



The direct interface to sound cards. A consistent API for mixing and developing digital (WAV) sounds. Windows 95 will also support general MIDL



A set of interfaces for developing multiuser games.



Device-level interface for digital joysticks. Developers can write to one digital joystick standard to support multiple joystick vendors.

performance, two sets of stripes—those making up the view directly to the right and the left of the current view-are loaded into memory. When you pan left or right, the corresponding stripes are blasted to the screen. (For more information on Surround Video and Apple's QuickTime VR, see "See You Around," May BYTE.)

In addition to 32-bit versions of Cinepak and Indeo, Microsoft is banking on MPEG support to enhance video playback under Windows 95. Windows won't include an MPEG codec in the box, but the MCI (media control interface) command set will incorporate MPEG control. You can load installable MPEG codecs from other vendors (e.g., Mediamatics or Xing Technologies) through MCI and manipulate the video just as you would an AVI file. Of course, DCI will directly access hardware MPEG decoders, when available, or otherwise launch MPEG decompression in software.

MPEG lets developers "scale-up" video playback. Under Video for Windows, video frames are simply dropped to keep audio and video in sync. To avoid dropped frames, developers often choose a frame rate according to the "lowest common denominator" hardware of the targeted audience. The problem? A video title captured at, say, 12 frames per second plays the same on a 486/33 computer as it does on your high-performance PCI-based (Peripheral Component Interconnect) Pentium machine.

MPEG, on the other hand, can dynami-

cally adjust playback to meet the performance capabilities of your hardware. MPEG inserts key frames at configurable intervals. Intermediate frames look ahead and back to these key frames (i.e., bidirectional interframe compression), pointing to blocks of similar data to reference during compression and decompression. MPEG can adjust the media stream dynamically, perhaps running only key frames on a slower machine or sampling audio at only 11 kHz. On a hardware-assisted system, the same MPEG stream could run at a full 30 fps with 44-kHz audio.

Multimedia 95

Clearly, Microsoft has done a lot of work to make Windows 95 a true multimedia OS. The success of this initiative will depend on the stability

Microsoft Corp. Redmond, WA (800) 426-9400 (206) 882-8080 fax: (206) 635-6100

and robustness of the platform as well as on third-party vendors adhering to the Microsoft call to arms: quality 32-bit applications, ease-of-use features, and light footprints.

Consumers of multimedia may have a distorted view of what Windows 95 can deliver. It looks like a solid multimedia OS, but it is not designed to run optimally on low-end systems. For true multimedia applications, you'll need some fairly beefy hardware to take advantage of the architecture's scalable design. If you want to play, ante up a PCI Pentium.

Stanford Diehl is director of BYTE reviews. You can reach him on the Internet or BIX at sdiehl@bix.com.

Adding Apple Events to Your Mac Application: Part 2

This final installment illustrates how

to write the event handlers and the

dispatch table

TOM THOMPSON

ast month's column, Part 1 of this series, described how Apple Events function as a high-level means of IAC (Interapplication Communication). This month's installment will finish up the series, completing the task of adding Apple Event capabilities to your Mac application.

Part 1 left off at step two of the process, in which you build the application's dispatch table. The listing "Build-

ing the Dispatch Table" shows the data structure and for loop used to accomplish this. The loop calls another Apple Event Manager function, AEInstallEventHandler, with the elements of an event's class number, its ID number, and a pointer to the handler function.

It's crucial to use NewAE-EventHandlerProc() on the pointers you supply. This sets up universal procedure pointers to these functions. This way, the Power Mac's OS can safely context-switch to the handler code's instruction set (which could be either PowerPC or 680x0). This takes care of step two.

Step three is to write the handlers themselves. The code to these is shown in the listing "The Four Event Handlers." Notice that we punt on handling an Open Application and Print Document event: That's because application designs vary so widely that there's no good generic code example possible.

However, these code stubs

show what your application must do to respond to required Apple Events in a given situation. For our Open Application event, we merely do nothing and return a "no error" code (noErr), indicating that things are OK.

If your application doesn't happen to support printing, you return a code of errAEEventNotHandled to inform the calling application that no service is possible for that request. For a Quit Application event, all you have to do is knock down the flag that keeps the main event loop active. Upon leaving the main event loop, your application performs any housekeeping chores and exits.

The Open Document handler code shows how your application receives filenames through a high-level event. It uses a boatload of Apple Event Manager calls to pick apart the event for the information you need.

First, you call AEGetParamDesc() to extract the para-

Building the Dispatch Table

```
// Structure for installing handlers into AE event dispatch table
struct AEinstalls
     AEEventClass theClass;
     AEEventID theEvent:
     AEEventHandlerProcPtr theProc;
typedef struct AEinstalls AEinstalls;
   Build high-level event dispatch table and add our handlers to it.
// Must use static declaration so the dispatch table has file scope.
Boolean Init_AE_Events(void)
OSErr
          err;
short
static AEinstalls HandlersToInstall[] = // The four required Apple Events
      {kCoreEventClass, kAEOpenApplication, Core_AE_Open_Handler},
{kCoreEventClass, kAEOpenDocuments, Core_AE_OpenDoc_Handler},
{kCoreEventClass, kAEQuitApplication, Core_AE_Quit_Handler},
{kCoreEventClass, kAEPrintDocuments, Core_AE_Print_Handler},
    NewAEEventHandlerProc(HandlersToInstall[i].theProc), O, FALSE); if (err) // If there was a problem, bail out
          Report_Err_Message (PROBLEM_WITH_AE_HANDLER);
return FALSE;
     ) // end if
} // end for
  return TRUE:
} // end Init_AE_Events()
```

Core Technologies Programming

```
The Four Event Handlers
// High-level open application event.
pascal OSErr Core_AE_Open_Handler(AppleEvent *messagein, AppleEvent *reply, long refIn)
) // end Core_AE_Open_Handler()
// High-level open document event
pascal OSErr Core_AE_OpenDoc_Handler(AppleEvent *messagein, AppleEvent *reply, long refIn)
short
                    fileDesc:
AEDesc
                    highLevelErr;
OSErr
AEKeyword
                    ignoredKeyWord;
                    ignoredType;
ignoredSize;
DescType
Size
                    numberOFiles;
 long
FSSpec
                    inFSS:
  if (!(highLevelErr = AEGetParamDesc(messagein, keyDirectObject, typeAEList, &fileDesc)))
      if ((highLevelErr = AECountItems(&fileDesc, &numberOFiles)) == noErr) // Count files
          for (i = 1; ((i <= numberOFiles) && (!highLevelErr)); ++i)
              if (!(highLevelErr = AEGetNthPtr(&fileDesc, i, typeFSS, &ignoredKeyWord, &ignoredType, (char *)&inFSS, sizeof(inFSS), &ignoredSize))) // Get each name
                 Do_Your_Stuff(&inFSS)
         ) // end if !highlevelErr
) // end for
) // end if == noErr
highLevelErr = AEDisposeDesc(&fileDesc); // Dispose of the copy made by AEGetParamDesc()
      ) // end if !highLevelErr
  return highLevelErr;
 // end Core_AE_OpenDoc_Handler()
 // High-level print event
 pascal OSErr Core_AE_Print_Handler(AppleEvent *messagein, AppleEvent *reply, long refIn)
     return errAEEventNotHandled;
                                             // No printing done here
 // end Core_AE_Print_Handler()
 // High-level quit event
 pascal OSErr Core_AE_Quit_Handler(AppleEvent *messagein, AppleEvent *reply, long refIn)
     guserDone - TRUE:
                                      // Tell main event loop we want to stop
     return noErr;
 } // Core_AE_Quit_Handler()
```

meters from the event's data structure. This function coerces the parameters into an array known as a descriptor list and drops it into the buffer pointed to by fileDesc.

Next, AECountItems() determines the number of objects in the list, which is the number of files to open. The value returned by this function sets up the for loop used to collect the filenames.

Finally, AEGetNthPtr() gets the filenames from the descriptor list. The filenames are coerced into file-system specification records (typeFSS), a format used by most System 7 File Manager functions. When the filenames are in a form that's usable by the Mac OS, your application can perform the requested processing on their contents. Note that this same code can be used to get the filenames for a Print Documents Apple Event.

Finally, you need to let the Mac OS know that your application

can process Apple Events. To do this, you must set the isHighLevelEvent-Aware bit in the application's SIZE resource. If you fail to set this bit, the Mac OS never sends high-level events to your application. Most development



environments provide a menu that lets you easily set this bit.

These snippets of code should help give you a jump-start on adding Apple Event capabilities to your Mac application. To obtain the Apple Event Registry: Standard Suites document mentioned in Part 1, which lists the structure and content of certain types of Apple Events, contact the APDA (Apple Programmer's and Developer's Association) at (716) 871-6555 or by fax at (716) 871-6511. Ask for part number R0130LLA. It costs \$85.

Another excellent source of information, where all those dense technical IAC concepts are translated into something a typical programmer can comprehend, is Dave Mark's *Ultimate Mac Programming Secrets* (IDG Books, 1994). It also has a lot of code samples on CD-ROM, the best training material of all. ■

Tom Thompson is a BYTE senior technical editor at large with a B.S.E.E. degree from the University of Memphis. He is an Associate Apple Developer and author of Power Macintosh Programming Starter Kit (Hayden Books, 1994). You can contact him on AppleLink as "T.THOMPSON" or on the Internet or BIX at tom_thompson@bix.com.

Simplifying Remote Management

Standards-based remote

monitoring takes hold

SALVATORE SALAMONE

wo trends—decentralization of organizations and the growing use of LANs-have created a challenge for network administrators. They find themselves responsible for keeping LANs in many remote locations up and running.

A big part of the problem is that many smaller sites cannot afford to have full-time technical staffers to handle problems. Even simple problems can be a pain. After all, you can't expect a person who has little experience with computers to attach a protocol analyzer, such as the fullfunction Network General Notebook Sniffer Analyzer, to the network and diagnose the problem on their own. (And that's not to disparage protocol-analyzer manufacturers, who have been making their products easier for networking professionals to use.)

Recognizing that managers need to somehow see what's going on at distant locations, the IETF (Internet Engineering Task Force) has developed specifications for an RMon (remote monitoring) system that keeps tabs on the

is an extension of the IETF's SNMP, which is commonly used to manage large networks. The idea behind RMon is to distribute, throughout a network, probes that collection information about the traffic on that network.

The difference between SNMP and RMon is that SNMP monitors and manages network devices like hubs and bridges, while RMon monitors LAN traffic. With RMon, some of the management intelligence is moved out onto the network, where


RMon probes alert a centralized console whenever a threshold, such as number of packets, is exceeded.

In a typical use of RMon technology, one probe would be located on each LAN segment. The probe would monitor data transmission on that segment and organize the information it collects into a format that makes traffic patterns and diagnose problems at remote sites.

Because of these helpful features, RMon is taking off. Virtually all router and intelligent-hub vendors are offering RMon capabilities in their products or say they soon will. Other companies, such as Armon Networking, offer stand-alone RMon probes that connect directly to Ethernet or Token Ring LANs. Armon's product is called On-Site. And many protocol-analyzer vendors, such as Network General, are offering RMon probes.

While RMon has great potential to help network administrators better manage remote-site LANs, there is some confusion about what role an RMon probe plays in traditional network analysis and troubleshooting. The major point of confusion is a belief that RMon probes will obviate the need for traditional protocol analyzers.

That's simply not the case. In fact, most networks would do well to employ both RMon technology and protocol analyzers. The two perform complementary, not competing, functions. An analogy might help explain the difference between an RMon probe and a protocol analyzer. In general, it's the difference between knowing that the editor of BYTE got 50 letters and knowing what opinions were expressed by readers in those letters. Analogously, when deployed throughout a network, RMon can give a network manager good statistical and trend information about the number of packets passing over the network. continued



RMon probes distributed throughout a network collect traffic information that is called up on a central management station. Protocol analyzers are then attached to a LAN it easy for a manager at a central site to analyze segment when more detailed packet analysis is needed.

Core Technologies Networks

A protocol analyzer is able to take a captured packet and decode all seven of its protocol layers.

Naturally, there's some overlap in the functions of an RMon probe and a protocol analyzer. For example, many protocol analyzers can perform trend analysis on the data they collect.

The way the two technologies can work to complement one another is to use RMon to baseline networks, study usage trends, and identify potential problems before they cause trouble for users. This will help reduce the number of trips to remote sites that technicians must make to solve problems (see the figure).

And when a problem requires higher-level diagnostics to be performed, use a protocol analyzer. For example, a person could go to a troubled site with a laptop running Comtest's protocol analyzer, NM Elite. This Ethernet network analysis and testing tool includes an alarm and event log, as well as an expert system that helps diagnose common network problems. (NM Elite was the winner of BYTE's Best of CeBIT award in the connectivity software category.)

It's in the Details

The type of information an RMon probe might collect is how many packets and what size packets are transmitted on the LAN segment. It will also look at the number of packets broadcast and collisions. This information could be used to spot a defective adapter card, which is bombarding the LAN with bad packets causing poor performance.

RMon probes can also collect a trace of the traffic on the LAN segment over a period of time and pass this trace to a central site for analysis. This feature of an RMon probe can be used to study traffic patterns and perform trend analysis of the bandwidth demands of the users on that segment. One of the most important features of an RMon probe is that it can be used to send alerts and alarms to network management systems if a preset threshold of some network parameter has been exceeded (e.g., if collisions exceed a level that is considered the norm for a particular LAN segment).

The benefit of an RMon system is that it automatically collects information about the traffic on a LAN segment that is in a remote location. For a manager responsible for many LAN segments that are not all in the same location, that can be a great cost-saving benefit.

For example, without RMon, any problem called into a network troubleshooting center that cannot be solved over the phone requires a trip by a technician to the site. The cost implications of such an approach to network troubleshooting are high. First, there's the technician's time. Even if it takes him or her only 15 minutes to solve the problem, there's the round-trip travel time to consider. And that's a best-case scenario.

Whom should you send to the remote site when a network fails? It's hard to know whether a router or CSU/DSU (channel service unit/data service unit) has failed, or if there's trouble with the leased line.

Without being able to diagnose the problem remotely, a company may first send the wrong person to the site. This wastes that person's time and leaves the problem to be resolved. Adding to the cost of problems at remote sites is the fact that even if the right

Find	NM Elta	0
Where to Find	Notebook Sniffer Analyzer\$9995 Network General Menlo Park, CA (800) 764-3329 (415) 473-2000 fax: (415) 321-0855 Circle 1148 on Inquiry Card.	
3	OnSite	

Circle 1149 on Inquiry Card.

Packet Capture

A Part of the Control		
Group	Purpose	
Statistics	Collects and tracks information about collisions, data rate, and other network parameters.	
History	Samples from gathered statistics to build a running history of network performance.	
Alarm	Compares network parameters from Statistics Group to preset thresholds to help identify potential problems.	
Event	Generates an alarm when a threshold is crossed	
Host	Keeps table of statistics for every MAC (media access control) address.	
HostTopN	Prepares tables of hosts, sorted by the value of any statistical parameter gathered over a set period of time (e.g., the hub port through which the most number of packets have passed).	
Matrix	Stores statistics.	
Filter	Checks packets against manager-defined filters.	

person goes to the site and solves the problem instantly, the people working there are stymied until the technician arrives. If it takes a technician 2 hours to get to a site, the people there must sit idly by for a quarter of the business day.

Allows capture of only packets that meet filtering

Using RMon can also help reduce the number of "emergency" trips to remote sites. By virtue of letting a manager preset performance threshold levels, he or she might be able to spot a problem in the making. This would let a manager take corrective action before the users on the network even notice that anything has happened.

For example, information gathered by an RMon probe might let a manager see that traffic on a LAN segment is increasing at a steady pace and is getting close to the maximum percentage bandwidth utilization that is acceptable before performance noticeably

> drops. Noting this trend, a manager can segment the LAN so that traffic on each new segment is well below the level where performance suffers.

> In this way, the users never see any performance degradation. And a network manager does not receive a call in a few months (when traffic has greatly increased) from screaming users saying it's taking forever for their applications to run.

That's just an example of how RMon will make it easier to automatically collect information about the state of remote networks. This will let managers become more proactive when it comes to keeping their remote sites out of trouble. And with networks becoming increasingly decentralized, network managers will need all the help they can get.

Salvatore Salamone is a BYTE news editor based in New York, You can reach him on the Internet or BIX at ssalamone@bix.com.

Smart Connectivity does more than simply get you from here to there.

It connects you simply, easily, and securely.



you



endless solutions. Smart Connectivity gives

you the power to quickly go



where you need to go.

It gives you



the freedom to navigate the



information age. Smart Connectivity works seamlessly and



keeps pace with your changing needs.



Smart Connectivity offers solutions for success.

SMARTERM® is Smart Connectivity.

SmarTerm offers smart emulation and TCP/IP connectivity choices for Windows, 32-bit Windows, and DOS. SmarTerm is the most precise terminal emulation for UNIX, VAX/VMS, MV, and AViiON hosts and includes TCP/IP (a Windows Sockets DLL) and LAT protocol stacks. It works in every network environment—both Ethernet or Token Ring. SmarTerm is easy to use and support with its powerful automation tools and top-notch Technical Support Team.

Evaluate SmarTerm's Smart Connectivity. Call Persoft today at 1-800-368-5283.



"PC Week Labs recommends SmarTerm..."
-Michael Blakely, PC Week

Persoft, Inc., 465 Science Dr., P.O. Box 44953, Madison, Wisconsin 53744-4953 U.S.A. Phone (608)273-6000, FAX (608)273-8227

Persoft Inc, European Headquarters, Lower Woodend Barns, Fawley, Henley-on-Thames, Oxfordshire, RG9 6JF, United Kingdom Phone +44 (0)1491 638090, Fax +44 (0)1491 638010

Copyright 1995 Persoft, Inc. All Rights Reserved. SmarTerm and Persoft are registered trademarks of Persoft, Inc. All other trademarks are property of their respective owners.

Circle 80 on Inquiry Card.



From the Editors of BYTE Magazine

Five Years of BYTE At Your Fingertips!

Cover Stories Product Reviews BYTE Lab/NSTL Reports Benchmarks Features Core Technologies Columns Product and Technology News And More!

Search

for product. technology, company, author

Export

selected articles to your word processor

INTRODUCTORY OFFER: Save \$5.00 of the Regular Subscription

Price!

Find

search results in context, by issue, or by article title

Select

copy and print what you need!

Scan the comprehensive index in as much detail as you need

Locate

the information you need quickly and easily from your BYTE issues library

> Now you can search through five years' worth of BYTE magazine—over 60 issues—to quickly find any article in minutes! As the only global magazine for computer technology experts, BYTE is your #1 information resource for new products and technologies. BYTE on CD-ROM is a fullyindexed full-text database that is the perfect complement to your collection of back issues.

Because the Experts decide.

Order Now &

Save! Subscribe to BYTE on CD-ROM for only \$54.95 and receive the full text of BYTE from 1990-1994 PLUS quarterly updates on CD-ROM that include full text and graphics from every issue in 1995! Or order just the full text of BYTE on CD-ROM (text only) from 1990-1994 for only \$39.95.

Place Your Order Today!

- ☐ Send me BYTE on CD-ROM PLUS 1995 quarterly updates with full text and graphics for just \$54.95.
- ☐ Send me BYTE on CD-ROM with the full text of BYTE from 1990-1994 for just \$39.95.
 - ☐ Check enclosed (make checks payable to BYTE Magazine, US funds only) Charge my: MasterCord VISA AMEX

CARD #

Call 1-800-924-6621 (outside of U.S. 603-924-2625) or FAX your order to 603-924-2683

NAME ADDRESS

CITY COUNTRY 255001 Mail to: BYTE on CD-ROM

One Phoenix Mill Lane, Peterborough, NH 03458

JERRY POURNELLE

Privacy and Liberty

here's a galaxy called M-87 about 30 million light-years away in the general direction of Cygnus. Observers using the Hubble space telescope are now pretty sure that in that galaxy there is an object weighing something like a billion solar masses compressed into a blob about the size of the end of your thumb. If you have an Internet connection, you can see M-87 and a bunch of other stuff that comes from the repaired Hubble on your computer screen (send E-mail to Holland Ford at Ford@STSCI.edu to find out where you can get more information through the Internet).

I've just been to the annual meeting of the AAAS (American Association for the Advancement of Science). There was a lot of talk about nifty stuff you can find on the Internet, as well as things the Internet lets you do. "Shared minds" and "accidental collaborations" are a couple of them. More on that in a moment.

One of the most heated discussions at AAAS concerned Internet policy and privacy. The principal exchanges were between Dr. Michael Nelson of the White House Office of Science and Technology Policy and Marc Rotenberg of the Electronic Privacy Information Center. The White House policy is that law-enforcement officers must be able to listen in on telephone calls, read fax messages, and record data transmissions. All this would be subject to search warrants, of course; but before they can get a warrant, they have to be able to get at the transmissions.

Rotenberg noted that if this is the era of electronic democracy, it's odd that just after his group delivered a petition from 47,000 people against the Clipper chip, the White House endorsed Clipper. Nelson's answer was, "We pay attention to everyone, not just users."

Clipper, for those of you who may have tuned in late, is a scheme in which a hardware-encryption system would be built into computers. Thus, when you communicate through a computer—E-mail, fax, data transmissions, essentially any communications—there would be automatic encryption at your end and decryption at the other end. Anyone intercepting your mes-


sages would be unable to read them.

Anyone but the government, that is, Clipper would have built into it a backdoor key that could be used by the government to decrypt any message intercepted. Of course, the government could intercept and decode messages only after obtaining a warrant, and government agencies would keep the backdoor key secure, and everyone can be confident of that, and I am Marie of Romania.

Clipper was supposedly killed last year, but there are periodic attempts to revive it or something like it. There is also pending legislation to provide quite a bit of federal money—up to \$500 million—to alter telephone-switching equipment to facilitate government access to telephone, fax, and Internet communications. As Rotenberg put it, they want half a billion bucks to make it easy to wiretap phones.

About then, I began wondering what the argument was about. It seems to me that the cat's out of the bag no matter what they do. Anyone who wants can get PGP (Pretty Good Privacy)—I hope this is the last acronym for the month, but it probably isn't.

PGP is a shareware public-key-encryption



Galaxies on the
Internet,
technological
threats to privacy,
CD-ROM art
exhibitions—the
esteemed Dr.
Pournelle serves
up another
technological stew

JUNE 1995 BYTE 249

Pournelle

system worked out by Phil Zimmerman. His system incorporates encryption algorithms developed by RSA Data Security, a Redwood City, California, company, Zim-

merman and RSA were in a pretty hefty dispute at one time, but they have settled their differences. RSA sells BSAFE and TIPEM Developer's Toolkits, which can help programmers build systems like PGP.

Public-key systems have two keys: your private key,

which you keep, and a public key, which you broadcast to all and sundry. Anyone out there can use your public key to encrypt a message that can be decrypted only by your private key. So long as you keep that key secure, anyone can send you messages that only you can read, just as you can use other people's public keys to send them private messages. Moreover, if you use your private key to encrypt a message, anyone with the public key can decrypt it—and thereby be sure that you sent it. Applications that use the RSA public-key cryptosystem, like PGP, solve the dual problems of privacy and authentication.

PGP isn't easy to use, but Jim Bidzos, president of RSA, says, "Two million Lotus Notes users send 5 million RSA publickey-encrypted messages every day, and

> most of them don't even know they're using RSA technology. That's how well it's integrated." The Netscape Navigator Internet browser is another tool in widespread use that incorporates RSA's technology as its security engine, and, again, most users don't know they're using it.

The cat is truly out of the bag; but the government won't let go.

Zimmerman very carefully did not put his PGP system on any BBSes. He did give copies to several friends. One of his friends carefully uploaded it onto local BBSes that were not connected to the Internet. Of course, someone then predictably uploaded it to the Internet, and now PGP is available to anyone, anywhere.

This means that no matter what back doors the government puts into the "official" or "authorized" encryption schemes, if you put your message through PGP first, the government isn't going to read it-at least not without considerable effort by the organization generally known as NSA. (That's assuming that Zimmerman hasn't built a back door into PGP, but there are pretty good reasons for assuming that.)

When I pointed this out, Nelson replied that most criminals are pretty stupid, and they won't go to the trouble of using PGP. However, if law-enforcement officers don't have access to the bit stream, there's no possibility of using message interceptions as a tool of law enforcement. There are bad guys out there, and the government has to keep up with them.

Last night, I used the Internet to put that proposition to Jim Warren, who's been around this business as long as I have. His reply was that while some crooks may be stupid, there are a lot of smart ones, and unless we get some standard encryption regularly in use, there's going to be a lot more computer crime—highway robbery on the information superhighway. It's happening already.

This business of the rights of privacy versus the right to have a government strong enough to protect us from criminals and

> MKS Germany: 49-711-16714-0 Circle 76 on Inquiry Card.



management tool with their development tools (and they've all built in hooks), maybe you should check it out. Datamation. August 1994.

terrorists isn't easily settled. I expect most BYTE readers start with the same prejudice I have against making it easy for the government to spy on me; but I did want to point out that the government's case isn't trivial, and Nelson makes a pretty strong argument for it. I'll leave it there for the moment, because what I really want to talk about is Zimmerman.

Although Zimmerman didn't put PGP on any BBS, it did get to the Internet, which means that people overseas could call in to the U.S. and download it; and many did. For good or ill, there are laws in the U.S. against exporting cryptographic programs and information. The Justice Department has threatened to charge Zimmerman with violation of those laws. If they manage to convict him, the penalty would be a mandatory 80-month prison sentence. That's nearly seven years, which is about the time actually served by murderers, at least in California.

Zimmerman hasn't been charged; but for a couple of years now, they have threatened to do it, and having an 80-month sentence hanging over your head is a pretty severe punishment all by itself. Because Zimmerman never actually exported the program, my guess is they'll never get a conviction, but that's just a guess—and it's not six-plus years of my life that's at stake.

I asked Nelson why they don't just drop the silly charges. He said that the White House and the president can't get involved. It would be political interference with the Justice Department, and that would be improper. I find that fatuous: it basically says we have rule by a bureaucracy that has no responsibility to the elected officials and through them to the people. However, that appears to be the position of the White House.

I would myself have thought that the Constitution requires the government to bring you to a speedy and public trial, there to be confronted by the witnesses against you; that years of "investigation" is a form of punishment unknown to the law. After all, what's to investigate? There aren't any facts in dispute here.

Nelson was also concerned about precedents.

My suggestion was that this has gone on long enough. If the president thinks he doesn't have the Constitutional authority to tell the Justice Department to either charge Zimmerman or let him alone, I won't argue with him; because the President undoubtedly has the authority to pardon him. It could be a narrow pardon, issued to Zimmerman alone for any alleged violations of

Save Disk Space

PKZIP version 2.0

PC WORLD



PKWARE introduces the next generation of its award winning compression utility. PKZIP 2.0 yields greater performance levels than achieved with previous releases of the software. PKZIP compresses and archives files. This saves disk space and reduces file transfer time.

WORLD CLASS AWARD Software developers! You can significantly reduce product duplication costs by decreasing the number of disks required to distribute your applications. Call for Distribution License information.

Put Your Executables on a Diet

Software developers! Save disk space and media costs with smaller executables. You can distribute your software in a compressed form with PKLITE Professional.* PKLITE Professional gives you the ability to compress files so that they cannot be expanded by PKLITE. This discourages reverse engineering of your programs.



PKLITE increases your valuable disk space by compressing DOS executable (.EXE and .COM) files by an average of 45%. The operation of PKLITE is transparent, all you will notice is more available disk space!

Compression for YOUR Application



The PKWARE Data Compression Library allows you to incorporate data compression technology into your software applications. The application program controls all the input and output of data, allowing data to be compressed or extracted to or from any device or area of memory.

All Purpose Data Compression Algorithm compresses ASCII or binary data quickly. The routines can be used with many popular DOS languages. A Windows DLL and an OS/2 32-bit version is also available!

PKWAREING

The Data Compression Experts

9025 N. Deerwood Drive Brown Deer, WI 53223-2437 (414) 354-8699 Fax (414) 354-8559

PRIVARE Data Compression Library for BOS \$275 PRWARE Data Compression Library for OS/2 \$350 PROFESSION PRINTERS \$45.00 PRINTE \$46.00 PRINTE Brofessional \$146.00

Please and \$5,00 56th per package in the US & Canada \$11.25 overseas. Wisconsin residents and appropriate state sales tax & county sales tax. Wish and plasteream accepted no COD orders.

Pournelle

the Export Control laws. That would set no precedents. The Justice Department could charge anyone else with violating those laws; but it would end the persecution of Zimmerman, which has gone on long enough.

If you agree, write the White House. It wouldn't take the White House staff 5 minutes to draft a two-sentence pardon, and the President could sign it in 20 seconds.

Incidentally, I've long pointed out that there are dangers to the free exchange of information. As an example, what happens when you can sequence anthrax at home from a floppy disk? And should we freely exchange the DNA sequence of the smallpox virus once that's available?

Groupware is creating accidental collaborations in the sciences. Dr. James Ostell, chief of the Information Engineering Branch of the National Center for Biotechnology Information of the National Library of Medicine (ostell@ncbi,nim.nih.gov) is charged with taking information generated through government grants and projects and getting it out the door.

The result has been a lot of development tools they distribute for free. While most of these are keyed to biotechnology data, and particularly to searching DNAsequencing databases, many of the organizing principles used are perfectly general and can be adapted for use by anyone

interested in looking through multiple databases. If you're designing that kind of software, you should be aware of what the NCBI is doing.

A recent visitor to the NCBI was looking at inherited resistance to certain parasites in animals and a particular DNA gene sequence

that seemed to enhance that resistance. Ostell was showing her how to use his information-search system. They fed in the DNA sequence of interest. Up came hits in the expected animal literature, but then there were two more—in yeasts. Yeasts don't have the kinds of parasites animals do, and animal-parasite researchers generally don't read journals about yeast research. A look at the journal reporting the yeast work showed that the proteins had something to do with cell membranes. It's a lot easier to grow yeast than mice.

Another hit showed the genetic loca-


tion of the gene in yeasts and an experiment that suggested that the gene controls mechanisms that stop transport across cell boundaries. When his visitor left, she had found the equivalent of a year's work she


wouldn't have to do, as well as some strong ideas on what to do next. This whole drama took only about 15 minutes in an office with a computer screen.

Genetic research can be highly competitive. This search software is in the public domain. Query: If you

make a discovery through searches of public databases, is that a real discovery for purposes of patent law? I don't think anyone knows how to answer that question. Its twin is: How do you get research people to put their results into these databases? Suppose you make a discovery that seems worthless, but someone else, who has done no biochemical work at all, is able to couple it with two other "worthless" results to make a commercial product?

Of course, groupware can be used in fields far removed from biochemistry and genetic engineering. We haven't got even





Morris I. Bolsky & David G. Korn 0-13-182700-6 / \$38.00

The inventors of Kornshell bring you the most authoritative and user-friendly tutorials and specifications.

UNIX SYSTEM ADMINISTRATION HANDBOOK, 2/E

Evi Nemeth, Garth Snyder & Scott Seebass 0-13-151051-7 / \$48.00

A full revision of the best-selling, most comprehensive guide for UNIX system administrators. Includes all six popular versions.

PANIC!

System Crash Dump Analysis Chris Drake & K.A.D. Brown 0-13-149386-8 / \$36.00

The first book to give detailed guidance on UNIX system panics, crashes, and hangs why they happen and what to do.

THE SCO PERFORMANCE TUNING HANDBOOK Gina Miscovitch & David Simons 0-13-102690-9 / \$42.00

A systems-oriented approach to performance tuning using SCO UNIX, SCO MPX, SCO Open Desktop, and SCO Open Server Systems.

ESSENTIAL SCO SYSTEM ADMINISTRATION **Keith Vann**

0-13-290859-X / \$28.00

This multifaceted tool for managing SCO UNIX and SCO Open Desktop/ Open Server systems helps both pro and novice administators perform key tasks.

THE McGraw-Hill Bookstore—information for Today's professionals

Mail to: The McGraw-Hill Bookstore, 1221 Avenue of the Americas, New York, NY 10020. Order by phone in NY at 212-512-4100; outside NY call toll free (800) 352-3566; or fax this coupon to us at 212-512-4105. Fax or phone orders delivered within 10 days!

THE NEW KORNSHELL COMMAND AND PROGRAMMING LANGUAGE, 2/E

UNIX SYSTEM ADMINISTRATION HANDBOOK, 2/E

PANIC! THE SCO PERFORMANCE TUNING HANDBOOK

ESSENTIAL SCO SYSTEM ADMINISTRATION Check, money order, or credit card only:

■ Visa ■ MasterCard ■ AMEX ■ Discover

Account No. Exp. Date,

Address City

Please add applicable sales tax, plus \$3.50 for U.S. postage and handling

BYTE 695

a small start on the legal problems these accidental collaborations are going to pose.

I went from Atlanta to Washington before getting back home. I'm due to go back there shortly. They want me to testify to the House Science and Astronautics Committee about the future of space flight and, in particular, low-cost access to space. I know from my mail that a lot of you are interested in this, and I'll have more information when things settle in.

I used the trip to give Gateway 2000's Liberty notebook a thorough test. As I usually do, I carried two machines, Liberty and Zenith's Z-Noteflex, because I must have a working system, and Zenith laptops are highly reliable.

So, I find, is Liberty. It weighs only 4.2 pounds and is easy to use on an airplane. The 78-key keyboard is usable, although I would not have thought so from my first inspection. The keys are all jammed up close together near the hinge of the computer, leaving empty space down below where there would be a trackball, except there is no trackball. I'll get to the pointing device in a bit. The Returm key looks too small, the Backspace key is in the wrong place, the Control key is down at the bottom and can't be switched with the stupid Caps Lock, the Tab is little bitty—all features I hate in a keyboard. On the gripping hand, Liberty is a light machine, and I really and truly wanted something I could carry around with me.

The upshot was that I wrote several thousand words with Liberty on an airplane seat tray and was able to meet a deadline. All that empty space at the bottom of the keyboard is just great as a wrist rest. I hate writing on airplanes, but I had no choice, and using Liberty I was able to pound out the words. That, however, was first-draft work using Q&A Write, a DOS program running under Windows.

The acid test was final-editing a complex book, requiring footnotes, endnotes, and comments, as well as rewrites of many paragraphs and insertion of new material. This required Microsoft Word 6.0c, which is a hairy program inclined to be slow on older laptops—it brought one of our Hewlett-Packard laptops to its knees—so I was prepared for the worst. Instead, Liberty worked splendidly. My saves were speedy, and I always do a full save with backup, not the Fastsave option. The Liberty I have uses a 100-MHz 486DX4, and it's plenty fast.

Liberty uses an odd pointing device: a gizmo like a pencil eraser head up where the Backspace key ought to be, with the "mouse buttons" down just below and to the right of the space bar. Right-handers will use the EZ Point integrated pointer with a finger and whack the buttons with the thumb. That takes getting used to, and you sure want to adjust the mouse speed and acceleration in the Windows control panel. After an hour, I was able to use it, and in another hour, I found I actually preferred EZ Point to a thumbball. Of course, I'm right-handed; I don't know how a left-handed mouse user would even get started.

I know there are those who don't like the Liberty's "mouse"—one friend calls it dorky-but I find I can use it just fine.

I do wish they had put a second blue Fn key on the right side of the keyboard; although there are non-Fn PageUp and PageDown keys, End and Home require Fnarrow, and that requires two hands. That, however, is about the only thing I would do to that keyboard. Because I am very picky about keyboards, that astonished me, so I did a bit of self-analysis.

My conclusion is that I still prefer big keyboards with lots of keys laid out just the way I want them; but I use notebooks



American Made Steel Chassis

Computer or RAID Applications



- Rugged all-steel construction
- Designed for FCC certification
- Easy assembly and service
- Full line of models and sizes
- Competitive prices
- American made redundant power supplies, removable disk drive modules, RAID controllers, Passive Back Planes in stock!

Call **NOW** for information and **FREE** color catalog

1-800-394-4122

VISA & MasterCard accepted Same day shipment!

Designed, Manufactured, Guaranteed by: CALIFORNIA PC PRODUCTS

408-638-9460 205 Apollo Way - Hollister, CA 95023

Circle 105 on Inquiry Card.

Pournelle

in such cramped and generally uncomfortable places that I don't expect things to be just right, so I put up with more. Whatever the reason, I like the Liberty keyboard just fine.

Liberty also has a big (10.4-inch) color screen. In fact, it's larger than the Z-Note-flex's screen and about as big as any laptop screen I know. It's bright and clear and very easy for me to see at laptop distances in nearly any light. Nothing is going to make writing and editing on airplanes much of a pleasure, but Liberty took a lot of the sting out of it.

There's no floppy drive on Liberty; if you want a floppy disk backup copy of your work, you attach a rather small external floppy drive to the parallel port. It can be done at any time, and it will work on battery power, provided you don't wait until the battery is really low.

Liberty's battery life is about 3½ hours with hard usage. By hard, I mean that I saved to the hard disk after every footnote and every major paragraph, and I hardly gave the machine any rest at all; and I got 3½ hours of work done on each leg of the trip. Here at home, I can get longer than 4 hours, but that's not with hard use. I think 3½ hours is an honest estimate of what you'll get on the road.

Liberty's batteries are fairly small, and you can easily carry an extra one in your briefcase. I've experimented with changing on the fly. Liberty doesn't exactly turn off; if you hit the off switch, it goes into a deep sleep that it recovers from only when you hit that switch again. When it does, it's right back where you were when you turned it off. This is as opposed to the light sleep that happens when you don't hit a key for a while; the screen goes dark, but striking any key wakes it up again. Anyway, if you turn Liberty off and quickly change batteries while it's in deep sleep, nothing gets lost. I've tried that a few times and I believe it, although I'll still save before I do it.

Liberty has two PCMCIA Type II slots (or one double-thickness slot, if you choose to use it that way). I've got a Megahertz 14,400 PCMCIA Data/Fax Modem with XJack in one of them, and it works just fine with Procomm 2 in a DOS window (I know I'm old-fashioned, but that's the program I use) and WinFax. The Megahertz card has a gizmo that lets you connect to an ordinary phone line; no special cable is needed. The connection is more secure than the cable connection to the Data Race RediCard RC-1496 Data/Fax Modem in my Z-Noteflex. I haven't noticed much difference in communications capabilities between the Megahertz and Data Race

products. Both appear to be good enough.

All told, then, Liberty is a real joy, the first lightweight portable I'd contemplate carrying as my only machine on the road. Provided that you get used to the pointing device, I think you'll like it. I sure do. Recommended.

Everyone's trying to enter the mouse business, either to make a better mouse or to replace mice. Logitech not only has trackballs but cordless mice, which work quite well, as do their normal mice. And Microsoft has gone beyond the "Dove soap bar" (Home Mouse) to its "Big Teardrop" (Mouse 2.0), another good standard mouse. But the big tendency is to use something else.

Lexmark—a spin-off company that used to be the IBM Information Products Division—has a Classic Touch line of keyboards. They're the genuine IBM loud clickers that use Lexmark's bucklingspring technology. You can also get Lexmark keyboards with quieter keys using rubber-dome technology (e.g., Quiet Touch, Easy Touch, Streamlined, and Thinlined keyboards). Me, I have always liked the sound and feel of those IBM loud clickers.

Lexmark keyboards mostly have the 101-key layout, with the function keys across the top of the board; an island, with the arrow keys in an inverted T pattern; the six special keys (e.g., Insert, Home, and PageUp) in a block above the arrow keys; and a numeric keypad off on the right.

Some of these keyboards incorporate pointing devices. There's one with a trackball in the upper right corner, called the Classic Touch with 25-mm Trackball. Another, the Classic Touch with Integrated Pointing Stick, has an eraser-head "mouse" just above the B key; the button keys are down below the space bar. This is similar to the device on IBM ThinkPad laptops, and it operates much the same as Liberty's eraser head.

There's also a weird one, the Select-Ease. It's split down the middle and pivots at the top, so that you can have your hands at what they think is a natural angle. (The Select-Ease comes standard with an extended numeric keypad.) This is similar to the Microsoft Natural Keyboard, except that with the Microsoft keyboard you have no choices, except height adjustment. The Select-Ease can be turned back into a normal keyboard or spread at a really odd angle if you'd prefer that.

Most of these keyboards (including the Select-Ease) come with what Lexmark calls the Erase-Eaze option. What that

means is that the space bar is split in half, and you can program half of it—normally the part struck by the left thumb—as the Backspace key. This neatly solves the problem created by putting the real Backspace key in the wrong place, up on the row with the numbers instead of next to the P key, where it belongs (and where it was on IBM Selectric typewriters).

The thing about Erase-Eaze is that if you've been typing for very long, you'll really hate it. Niven somehow acquired an Erase-Eaze keyboard, and not realizing that you could program it so that it didn't have that feature, he donated it to a school to get it out of his house. Incidentally, he's quite happy with the Microsoft weird-hump keyboard, and that's the one I have on his machine when we work together at Chaos Manor.

Of these Lexmark keyboards, the one that intrigues me most is the Classic Touch with Integrated Pointing Stick without the Erase-Eaze option. It doesn't take all that long to learn how to use the pointing stick, and once you do, it's sure a lot easier than reaching over to grab a mouse. Having said that, I'll confess that I am still using my Northgate Computer Systems' OmniKey Plus keyboard and a Microsoft New Mouse, but that's in part because I like function keys along the side rather than on top, and my keyboard has the Backspace key next to the P.

One of these days, though, my Omni-Key Plus will finally wear out, and when it does, I may well go over to the Lexmark Classic Touch with Integrated Pointing Stick. I've used it several times now, and I like it a lot.

Keyboards are very personal things. Because I spend a lot of time pounding on one, I tend to be pretty fussy about the one I use. If you do a lot of writing, check out the Lexmark keyboards. You may love one of them.

Yet another pointing device is the GlidePoint from Cirque; it's a fingerpad. It sat here unopened for about a month because five years ago I tried mushpad pointing devices and hated them; but Roberta's Power Machas one, so I thought what the heck.

Connecting up the GlidePoint required unplugging the Microsoft mouse, plugging in the GlidePoint, and resetting the machine. It worked first thing. I've since tried it on other machines with similar results. The machine believes it has a Microsoft mouse.

The GlidePoint is 2½ inches tall by 3½ inches wide; a bezel reduces the actual mushpad surface to 2½ by 1½ inches. To use it, just put your finger on it and move

it around. The cursor follows quite nicely. There are two buttons at the bottom of the GlidePoint, and they work as expected. It's pretty easy to activate them with your thumb.

Most interesting, though, is that you can tap the surface of the mushpad to get the same result as a single click of the left mouse button, and a double-tap acts like a

double-click. This works quite naturally and takes no getting used to.

What does take getting used to is click and drag, where you click and hold with your thumb and then drag with your finger. It's not all that hard to do, but it's not as natural as clicking and

dragging with a mouse, and I haven't yet become comfortable with it. I sure am with everything else though, and I'm strongly tempted to change over just to see if it improves productivity. Alex used it to play Master of Orion last night and found it quite satisfactory for that. I haven't tried it with Doom yet.

Fair warning, some people, including a couple of BYTE editors, really hate this thing. Others like it. Like all personal equipment, you have to take a view about this. In any event, the GlidePoint is a serious contender as a pointing device, and, if you're sick of rodents, you might want to look into it. It works.

About half the time I don't spend pounding on a keyboard seems to be spent on the telephone. Often I need to do both, particularly when I'm trying to get technical support and I'm on hold waiting for "the next available" person. While there's no remedy for being put on hold, there is a way to keep on working while it happens: use a Plantronics Super Headset with M10 Adapter. Not only does that leave both hands free, but I can listen to my classical music station while I continue to type away. There's a volume control in the adapter, and if I turn that all the way up, I'm sure to hear when someone comes on the line.

Once you do reach someone in technical support, it's very useful to have both hands free while discussing the problem, particularly if the difficulty is hardware. The Super Headset comes on a long cord—it doesn't start to pull uncomfortably until I'm about 10 feet from the instrument—and attaches to the side of my phone with Velcro, so that I can move the phone across the room and then get 10 feet from that. The result is that I can get to almost any machine in the office. I also do radio in-

terviews by phone when I'm trying to get publicity for a book, or for the space program, and it's pretty convenient to have a headset for that.

The adapter has settings to let it work with just about every kind of phone. We have a TIE six-line system, and that gives it no problems. Installation is simple: the adapter plugs in where the handset went

and then the handset and headset plug into the adapter. Plantronics sells a little hook-like gizmo that you can hang the headset from. Without that, it's somewhat awkward finding a place to keep the headset when it's not in use. Other than that, I've had no problems.

I've found that sometimes I use a gadget for a while and then get tired of it. I've had this Super Headset for several months now, and I use it more now than when I first got it. If you spend much time on the phone, you may well want one. Recommended.

PhoneDisc '95 PowerFinder is actually five CD-ROMs that contain just about all the private and business phone numbers, as well as addresses with ZIP codes, in the country. It doesn't list addresses for unlisted telephone numbers, but it sure lists a lot of names and addresses. I found people I haven't thought about for years.

It's remarkably easy to use. Insert the CD-ROM and run phone disk (from File Manager, DOS, or Norton Commander) directly from the CD-ROM. You can also install it on a Mac. Then search by name, business type, or city and street address. The business types are by occupation code numbers, but that doesn't turn out to be a problem. Just browse. The response in Windows is nearly instantaneous on my Cheetah 66-MHz 486DX. Because it's a DOS program, you can do Alt-Enter to mark and paste.

If you can use a computer at all, you can use this. Just spend 10 minutes fooling around with it, and you'll learn it. Highly recommended.

If you get the Discovery Channel, you know it does a great job on documentaries. Now there's a series of multimedia CD-ROMs based on those documentaries. There's one on space (Beyond Planet Earth), another on whales (In the Company of Whales), and another on sharks (Sharks). They're all pretty good, but I'd rather watch the Discovery Channel.

The CD-ROMs have some material that's probably not in the TV shows, and,

For More Information

A series of multimedia CD-ROMs based on Discovery Channel documentaries, Beyond Planet Earth, in the Company of Whales, and Sharks (\$49.95 each) are all pretty good. Contact Discovery Communications, Inc., Bethesda, MD, (800) 762-2189 or (301) 986-1999. Circle 1151 on Inquiry Card.

The BSAFE Developer's Toolkit and TIPEM Developer's Toolkit (\$290 each) can help programmers build systems like PGP. Contact RSA Data Security, Inc., Redwood City, CA, (800) 782-5453 or (415) 595-8782; E-mail: Info@rsa.com. Circle 1152.

If you do a lot of writing, check out the Lexmark Classic Touch Keyboard (\$99; with Erase-Eaze option, \$104), Classic Touch with 25-mm Trackball (\$129; with Erase-Eaze option, \$134), Classic Touch with Integrated Pointing Stick (\$129), or Select-Ease (\$179). Contact Lexmark International, Inc., Greenwich, CT, (800) 438-2468 or (606) 232-2000. Circle 1153.

GlidePoint (\$89) is a serious contender as a pointing device, and if you're sick of rodents, you might want to look into it. It works. Contact Cirque Corp., Salt Lake City, UT, (800) 454-3375 or (801) 467-1100; E-mail: cirque @xmission.com. Circle 1154.

Liberty (\$2799 to \$4499) is the first lightweight portable I'd contemplate carrying as my only machine on the road. Contact Gateway 2000, Inc., North Sioux City, SD, (800) 846-5257 or (605) 232-2000. Circle 1155.

A Passion For Art: Renoir, Cezanne, Matisse, and Dr. Barnes (\$49.95) is the first CD-ROM I've seen from this company, and it's really neat. Contact Corbis Publishing, Bellevue, WA, (206) 562-6000. Circle 1156.

I've got a Megahertz 14,400 PCMCIA
Data/Fax Modem with XJack (\$249) in one of
Liberty's PCMCIA Type II slots, and it works
just fine with Procomm 2. Contact Megahertz
Corp., Salt Lake City, UT, (800) 527-8677 or
(801) 320-7000. Circle 1157.

PhoneDisc '95 PowerFinder (with one free update, \$249) is actually five CD-ROMs that contain just about all the private and business phone numbers, as well as addresses with ZIP codes, in the country. Contact Digital Directory Assistance, Inc., Marblehead, MA, (800) 284-8353 or (617) 639-2900. Circle 1158.

I've had a Super Headset with M10 Adapter (\$186) for several months now, and I use it more now than when I first got it. Contact Plantronics, Santa Cruz, CA, (800) 544-4660 or (408) 426-5858; E-mail: 74357.234 @compuserve.com. Circle 1159.

of course, you can go over it more than once—in fact, you will, because some of the multimedia presentations are given several times. There are also four experts, talking heads who each answer the same questions. In the space CD-ROM, the experts include Buzz Aldrin, second man on the moon. Buzz is always interesting, but I'd as soon watch him on the Discovery Channel rather than as a 2-inch-square talking head on my computer screen. For that matter, I'd as soon read what he has to say in *Discovery* magazine, where I'd also get a lot more pictures.

On the other hand, there are some good motion pictures, and In the Company of Whales has recordings of whale songs; if you've never heard whales sing, nothing in print is going to describe it for you. On the gripping hand, you can read the magazines and watch the TV shows—rent the tapes if you don't get the Discovery Channel—and get all that's on the CD-ROM and more.

I suppose I'm getting jaded. A few years ago, I'd have been thrilled to have CD-ROMs on science at junior high level, especially multimedia as well done as these. As it is, I can recommend them for science clubs or school libraries, but I doubt anyone will spend more than a couple of hours with any one of these.

In contrast to the Discovery CD-ROMs, A Passion for Art: Renoir, Cezanne, Matisse, and Dr. Barnes doesn't give you talking heads. Instead, there's a rapid-fire series of stills with a voice-over by a breathless announcer right out of the old newsreels to tell the story of the Barnes Foundation. I had never heard of it before, and it's fas-

There's a walk through the gallery, and you can zoom in to paintings and sculptures from Dr. Albert C. Barnes' private collection of impressionist and Postimpressionist paintings. There are lots of comments and details concerning what modern art is about and why it inspired such devotion; and all this is done very smoothly.

This CD-ROM didn't start as a magazine or a videotape, and that shows. It does things only a CD-ROM can do. Moreover, when you do get tired of the CD-ROM presentation, there's software to let you build your own slide show.

Corbis Publishing buys up nonexclusive rights to artistic and educational artworks—images, sounds, and anything else they think they can use—and makes interactive multimedia presentations from them. This is the first I've seen from the company, and it's really neat. I'm going to keep this one.

My mention of The Bell Curve: The Reshaping of American Life by Differences in Intelligence by Charles Murray and Richard J. Herrnstein (see my February column) brought a lot of mail. Some of it was astonishingly intemperate, considering how little I said; my guess is that several of the professors who wrote in such hot tones had read only one chapter of the book. Much of the controversy over The Bell Curve is concentrated on a chapter that I didn't mention and isn't central to the book's thesis.

We may all wish that we lived in Lake Wobegon, but we don't. The Bell Curve forces you to consider that half the people in this nation are below average in intelligence; and while that might not have been so important in the past, it has implications for a merit society in the information age. Some of those implications involve public policy. You needn't accept the recommendations that are made by Murray and Herrnstein (although I'd be astonished if some of those who wrote me had any inkling at all of what those recommendations are), but you won't escape the implications by not thinking about them.

One possible policy is to assign people to jobs strictly on the basis of merit. The problem is that if you're to have full employment, you need to have jobs for everyone. And it's no more certain that assigning "the best person to each job" is the most overall efficient way than that the best solution to the classic traveling-salesman problem is for him to go to the closest town at each decision point. In fact, personnel managers have for a long time known that the "assignment problem" in which you must place everyone who applies is mathematically analogous to the traveling-salesman problem; and that generally is considered to be in the domain of computer science.

Enough on that. By next week, I'll have all my space program papers finished, and I promise not to mention policy wonking for at least two months.

Jerry Pournelle holds a doctorate in psychology and is a science fiction writer who also earns a comfortable living writing about computers present and future. Jerry welcomes readers' comments and opinions. Send a self-addressed, stamped envelope to Jerry Pournelle, c/o BYTE, One Phoenix Mill Lane, Peterborough, NH 03458. Please put your address on the letter as well as on the envelope. Due to the high volume of letters, Jerry cannot guarantee a personal reply. You can also contact him on the Internet or BIX at jerryp@bix.com.



Classic point & click.



Classic pans & picks.

BYTE's 20th Anniversary Special Edition September 1995.

- 20 Best Programming Languages
- 20 Best Hardware Products
- 20 Best Software Products
- 20 Best Network Products
- 20 Most Important Technologies
- 20 Most Important Individuals in Industry And More!

- 20 Most Significant Computer Contributions to Society
- 20 Most Important Companies
- 20 Most Spectacular Company Failures
- 20 Worst Bugs
- Predictions for the Year 2000

Don't miss this classic

Attention Advertisers!

Reserve your space now and reach 100,000 extra readers. Space closes July 12.

Because the Experts decide.

What's New Hardware



WIRELESS INFRARED PRINTING

The LaserJet 5P and 5MP printers include an infrared port for wireless printing from portable PCs and PDAs. The devices offer 6-ppm print speeds, flexible paper-handling capabilities, 600- by 600dpi output, expandability, and font management software. The LaserJet 5P and 5MP printers also

come with SIMM slots that you can use for additional memory, other printer languages, and customizing options. The LaserJet 5P (\$1109) is expandable to 50 MB, and the LaserJet 5MP (\$1299) is expandable to 35 MB.

Contact: Hewlett-Packard, Santa Clara, CA, (800) 752-0900 or (208) 323-2551;

E-mail: http:\\www.hp.com.
Circle 1322 on Inquiry Card.

SCALABLE MULTIPROTOCOL WAN SERVER

For data-communications service providers expanding their networks, the Multi-Protocol WAN-Server 3000 (base unit, which includes a rack-mountable 16port Interface Distribution Module and SBus Host Interface Card, \$3500; additional 16 ports. \$2800) provides up to 64 highspeed WAN access ports for integration into SPARC systembased data switches, network servers, and multiline data- and voice-delivery systems. Every port is independently configurable and has the ability to support data transfer rates of up to 256 Kbps full-duplex per line: software-selectable electrical interfaces, including RS-232, RS-422, RS-449, RS-485, RS-530, and V.35; and synchronous and asynchronous transmission.

Contact: Aurora Technologies, Waltham, MA, (617) 290-4800; E-mail: info@auratek.com.

Circle 1343 on Inquiry Card.

MODEM/FAX/LAN COMBO PC CARD

WinMax contains a 19.2-Kbps "soft" data modem, a fax card, and an Ethernet LAN interface adapter for 10Base-T LANs, all in one PCMCIA package (modem/LAN combo, \$249; modem/fax only [V.32 terbo], \$129; LAN interface only, \$99). The

software-driven modem maximizes data throughput by using the power of the PC to perform data compression and error protection and to issue the commands to instruct the AT&T data-pump chips to perform modem functions. Large buffers in the modem let you transfer hundreds of characters during a single interrupt, drastically reducing the computer's processing load.

Contact: Data Race, San Antonio, TX, (800) 329-7223 or (210) 558-1900; E-mail: bdavis@datarace.com.

Circle 1325 on Inquiry Card.



SPARC-5-COMPATIBLE A WORKSTATION

Powered by an 85-MHz Micro-Sparc II chip, the entry-level configuration of the microCompstation 5/85 RISC system (less than \$4000) comes with an SVGA/ CG3 frame buffer, a 14-inch color monitor, 16 MB of memory, a 520-MB hard drive, two serial ports, one parallel port, and three SBus expansion slots. The system also includes built-in 16-bit audio capabilities and such components as internal speakers and

audio ports. Options include 15-, 17-, and 20-inch color monitors; up to 256 MB of memory; up to a 4-GB hard drive; and a Turbo GX or Turbo GX+ graphics accelerator.

Contact: Tatung Science & Technology, Milpitas, CA, (800) 659-5902 or (408) 383-0988; E-mail: annie@tsti.com. Circle 1333 on Inquiry Card.

COMPUTER TELEPHONY APPLIANCE

The components of the Quadra-Fax fax and voice processing system (two-port systems, from \$2995; four-port systems, from \$3995) are the system unit and the administration software. The system unit sends and receives faxes, records and plays back voice prompts and messages, detects and interprets DTMF signals, and performs adaptive call progress. The administration software creates voice files for prompts and responses from desktop sound systems, and it configures the system with dialing instructions and other telephone functions.

Contact: Brooktrout Technology, Needham, MA, (800) 333-5274 or (617) 449-4100; E-mail: info@brooktrout.com.

Circle 1340 on Inquiry Card.

MULTIMEDIA KIT

The Diamond Multimedia Kit 6000 (\$399) combines an IDE quad-speed CD-ROM drive, a 16-bit stereo-quality sound card, speakers, automatic installation software, and six finance and office-productivity applications. The CD-ROM drive provides a 600-KBps transfer rate, an access time of 230 ms, and a buffer size of 128 KB.

Contact: Diamond Multimedia Systems, San Jose, CA, (800) 468-5846 or (408) 325-7000.

Circle 1327 on Inquiry Card.



UPGRADE YOUR DDS ▲ TAPE DRIVES

The MiniChanger 400 Series of auto-loaders includes two different models. The MC400S (\$2995) combines TapeWorks' robotic tape-cartridge-loader mechanism with a DDS-2 tape drive, which provides a 64-GB tape backup storage system, and a six-tape Flat-Pak magazine with DDS-2 media and a SCSI-2 connector cable. The MC400U upgrade product (\$1595) includes TapeWorks' robotic mechanism without a tape drive, a sixtape Flat-Pak magazine without media, and a SCSI-2 connector

Contact: TapeWorks, Fort Collins, CO, (800) 704-1997 or (303) 224-1709; E-mail: cse@tapeworks.com.

Circle 1326 on Inquiry Card.

LAN-CABLE TESTER

A portable LAN-cable tester, the LANtek Pro XL (\$4495) grades the reliability of network cabling by testing line mapping, Dual Next, signal attenuation, DC loop resistance, mutual capacitance, cable length, and attenuation to cross-talk radio. In addition to testing Ethernet and Token Ring network frequencies, the LANtek Pro XL tests attenuation and two-way Next to 100 MHz. In addition, you can store your test

results in the LANtek
Pro XL's internal
memory, download
them to a PC, or
print them. With
the optional FiberKit (\$895), the
LANtek Pro XL
can display optical power loss
through fiber cable, splices, and
connectors.
Contact:

Wavetek, San Diego, CA, (800) 854-2708 or (619) 279-2200; E-mail: madaras@ wavetek.com.

Circle 1132 on Inquiry Card.

CONTROL GPIB INSTRUMENTS WITH YOUR MAC

With the GPIB-232CT-A/Mac, an external RS-232-to-GPIB controller, you can control GPIB instruments from your Mac's printer/modem port. The device (\$595) implements a normal and extended Talker and Listener, serial and parallel polling, service requests, pass- and receive-control functions, and remote-programming functions.

Contact: National Instruments, Austin, TX, (800) 433-3488 or (512) 794-0100; E-mail: info@natinst.com.

Circle 1331 on Inquiry Card.

30-INCH TRINITRON MONITOR

A high-resolution monitor with a 16-to-9 aspect ratio, the GWM-3000 (\$21,900) incorporates a

30-inch Trinitron tube with a 28-inch-diagonal viewing area and noninterlaced resolution of 1920 dots by 1080 lines, or more than 2 million pixels. The monitor can display characters as small as 0.1 inch high from corner to corner anywhere on the screen. Digital Alignment technology allows precise display adjustments; Auto Calibration optimizes user-selected color bal-

ance

Contact: Sony Component and Computer Products Group, San Jose, CA, (800) 352-7669 or (408) 432-0190.

Circle 1133 on Inquiry Card.



The ABP940 SCSI host adapter connects up to seven drives to a single PCI slot in PCs, workstations, and servers. The plug-and-play adapter (\$379) comes with the AdvanSys universal SCSI software driver, which replaces up to seven software drivers in a single computer.

Contact: AdvanSys, San Jose, CA, (800) 525-7443 or (408) 383-9400; E-mail: louw@ advansys.com.

Circle 1342 on Inquiry Card.

ISDN REMOTE-LAN ACCESS

KNX's three ISDN remote-LAN-access products include the KNX Access Server Basic. or ASB: the KNX Access Server as an NLM, or AS-NLM; and the KNX Remote LAN Workstation, or RLW. The ASB (\$1595; expansion kit, \$795) provides remote access to the corporate network across ISDN. The AS-NLM (\$1195; expansion kit, \$795) allows remote access from Novell NetWare file servers and provides ISDN support for thirdparty applications. The RLW (\$795; analog telephone interface, \$200), designed for a single-user/single-device environment, lets you remotely connect to corporate LANs to access files, mail, or databases or to obtain embedded access in point-of-sale equipment or credit-card authorization.

Contact: KNX, San Francisco, CA, (800) 569-5267 or (415) 764-1700.

Circle 1330 on Inquiry Card.

MULTIMEDIA KEYBOARDS

The Platinum Sound Multimedia Audio and Stereo Keyboard is available in two different models. The MAK-100 Multimedia Audio Keyboard (\$129.95) features a built-in omnidirectional microphone; 4-inch magnetically shielded, 16-W, full-audiorange speakers; external micro-

phone and headphone jacks; and a volume-control knob. In addition to the features of the MAK-100 Keyboard, the MSK-200 Multimedia Stereo Keyboard (\$229.95) provides separate volume, bass, treble, and balance controls using soft sliding controls with center positions.

Contact: SC&T International, Phoenix, AZ, (800) 408-4084 or (602) 470-1334.

Circle 1338 on Inquiry Card.

ANALOG SIGNAL-CONDITIONING MODULES

The 5B isolated analog signalconditioning modules (\$150 to \$205) are for frequency input, voltage output, four-wire RTD input, resistive input, narrowbandwidth strain-gauge input, two-wire transmitter interfacing, and servo/motor control.

Contact: Intelligent Instrumentation, Tucson, AZ, (800) 685-9911 or (602) 573-0887.

Circle 1328 on inquiry Card.

DISPLAY FOR SPARC WORKSTATIONS SAVES SPACE

Weighing only 17½ pounds, the Integrix subsystem for SPARCbased workstations includes the 13-inch N209 true-color flat-panel display, which offers a resolution of 1280 by 1024 pixels, a refresh rate of 60 Hz, and display of 256 colors from a palette of 16.7 million. Also included are a TGX125 graphics accelerator card with 2 MB of video memory, 1.7 million 2-D vectors per second, and 560,000 3-D vps; and a six-foot cable. Cost for the subsystem is \$16,995; sold separately, the TGX125 card costs \$1995.

Contact: Integrix, Newbury Park, CA, (800) 300-8288 or (805) 375-1055; E-mail: sales@integrix.com.

Circle 1332 on Inquiry Card.



ETHERNET ADAPTER ▲ FOR PORTABLES

The EtherChain Network Adapter lets you connect laptop PCs anywhere on a 10Base-T Ethernet network. You simply connect the adapter (\$349) to a PC's parallel port and daisy-chain the PC into the network at any point. The printer port pass-through lets you continue printing automatically to your local printer. Contact: Apexx Technology, Boise, 1D, (800) 767-4858 or (208) 336-9400; E-mail: 71043.2403@compuserve.com.

Circle 1137 on Inquiry Card.


What's New Hardware

MULTIPLATFORM **PRINTER SERVER**

Designed for Ethernet networks, NetQue Mate (\$399) allows users to share one printer or plotter from up to 30 different operating environments, including Microsoft LAN Manager, Novell NetWare, IBM LAN Server, Apple EtherTalk, Windows NT, and Unix TCP/IP.

Contact: Emulex, Costa Mesa, CA, (800) 854-7112 or (714) 662-5600: E-mail: literature@ emulex.com.

Circle 1334 on Inquiry Card.



Circle 1335 on Inquiry Card.

stereo sound at up to 44 kHz.

Contact: PDO Peripherals,

Santa Clara, CA, (800) 737-

E-mail: pdqperiph@aol.com.

7462 or (408) 727-2600;

INTERNAL SURGE SUPPRESSOR

Designed for installation inside your PC, the Defender/OVP (\$39.95) protects your PC's voltage-sensitive hardware components against damage caused by lightning, power-line surges, switching artifacts, static dis-

> failures. Upon detection of an overvoltage condition, the Defender/OVP shuts down the power supply's outputs, in effect turning the computer off and protecting it from damage.

Contact: IsoBlock, Decatur, GA, (404) 325-8282.

Circle 1336 on Inquiry Card.

FLAT-PANEL COLOR MONITOR

The Model 460 (\$7950; with options, \$8995) flat-panel color monitor is a 14.2-inch active-matrix display that is only 3 inches deep. The screen supports 16.7 million colors for precise color presentations and offers optional touchscreen and video capabilities.

Contact: PixelVision. Acton. MA, (508) 264-9443.

Circle 1344 on Inquiry Card.

MULTIMEDIA MODULE FOR PCS

The PDQ Mobile Multi-Media Module, or M4, lets you play audio and multimedia CDs on most notebook and desktop PCs via the parallel port. A self-contained unit, the PDQ M4 (\$149) contains a power supply and a multifunction PCB that provides a Sound Blaster-compatible sound controller and SCSI, IDE, speaker, microphone, and printer passthrough ports. The volume control is software programmable and supports 16-bit mono and

NETWORK FAXING

FaxPress 3000 lets LAN and enterprise-wide network users send and receive faxes directly from their workstations. The self-contained server features increased processor speed; concurrent support for four outgoing lines at 14.4 Kbps; 10Base-T/BNC with auto-selection; and 1 MB of

memory, upgradable to 8 MB. The FaxPress 3000 is available for Ethernet (two-line version, \$3995; four-line version, \$4795) and Token Ring (two-line version, \$4295; fourline version, \$4995) LANS.

Contact: Castelle, Santa Clara, CA. (800) 289-7555 or (408) 496-0474: E-mail: sales@ castelle.com.

Circle 1337 on Inquiry Card.

DIRECT-INWARD-DIALING **NETWORK FAX-SERVER BOARD**

Faxination DID routes incoming faxes from the fax server, through the LAN, and directly to users' workstations. Operating at a 14.4-Kbps V.17 fax-transmission rate and using Modified Read data compression, Faxination DID (two-port version, US\$1845; four-port version. US\$3245) supports T.30 subaddress routing and provides automatic trunk-busy out, trunk-loop back test, diagnostic tools, power-fail support, and DTMF and pulse-dial decoding.

Contact: PureData, Richmond Hill, Oniario, Canada, (905) 731-6444; E-mail: stephen-Iwan@puredata.com.

Circle 1339 on Inquiry Card.

ENTERPRISE-WIDE TAPE BACKUP

The DLT20 is a digital linear tape drive that uses half-inch cartridge streaming tape in a 51/4inch full-height case. The drive (\$2999.95; data and cleaning cartridges, \$45.95 each) can pack up to 20 GB of data on a DLT CompacTape II data cartridge and feeds data at rates of up

to 110 MB per minute. Contact: APS Technologies, Kansas City, MO, (800) 235-2753 or (816) 483-6100: E-mail: sales@apstech.com. Circle 1341 on Inquiry Card.

AMPLIFIER/ SPEAKER PACKAGE >

The TC 1490SP package consists of a high-power/ zero-footprint amplifier and a pair of high-out-




put speakers that enhance the audio performance of most PCor Mac-based multimedia systems. The package (\$249.95) includes a 40-watt-per-channel integrated amplifier, two SP 510 speakers, a five-band graphic equalizer, an LED level meter, and tone-defeat control. The built-in FET microphone and variable microphone-mixing circuitry enable you to use the package with voice-recognition software.

Contact: Micro Multimedia Labs. Reisterstown, MD. (410) 429-4300.

Circle 1329 on Inquiry Card.

NETWORK-TRANSPARENT GREEN PCS

Two Energy Star-compliant PCs, the Preferred 5/100E PCI ESP (from \$2998) and the Preferred 5/100 PCI ESP (from



Contact: CSS Laboratories, Irvine, CA, (714) 852-8161.

Circle 1324 on inquiry Card.



Official BYTE Merchandise for Technology Experts.









CERAMIC MUG.

11 oz. ceramic mug with gold band and 3-color, 2-sided logo. BYT 8. \$4.50.

MOCK TURTLENECK.

Outer Banks 100% cotton mock turtleneck with 20th Anniversary logo embroidered on left chest. White. Sizes: M-XL. M-BYT 4, L-BYT 5, XL-BYT 6. \$25.85.



MOUSE PAD.

Hard top mouse pad. 4-color with 20th anniversary logo and tag line and repeating text background. 7.5" x 8.5" x 3/16".

BYT 7. \$5.25.





BALL CAP.

Soft brushed cotton free-form ball cap with adjustable Velcro closure back and 20th Anniversary logo embroidered on front. Black. BYT 11. \$14.75.



SWEATSHIRT.

11 oz. cross grain Lee sweatshirt with 20th Anniversary logo embroidered on left chest, features generous athletic cut and side gussets. 95% cotton, 5% polyester. Ash. Sizes: M-XL. M-BYT 1, L-BYT 2, XL-BYT 3. \$31.20.



Parker Vector Sport Roller Ball Pen. Black with 3-color BYTE logo repeated on barrel and cap. BYT 10. S6.25.



Parker Insignia ball point pen. Laque black with 3-color BYTE logo on clip emblem. BYT 9, S34.50.



T-SHIRT.

100% Cotton Oneita Power-J. White with 1-color "technology" print on both sides and 4-color 20th anniversary logo on front. Sizes: L-XL. L-BYT 13, XL-BYT 14, S8.00.

COMPUTER TOOL KIT.

Deluxe computer service tool kit in black vinyl zipper case features: 2 nut drivers, 3 prong ports retriever, tweezers, torx driver, IC Extractor, one Phillips and 2 slotted screwdrivers. 1-color 20th Anniversary logo.

BYT 12. \$20.10.



Ordering: Credit card phone orders: Call 1-800-676-HALO (4256) (in IL, call 708/647-4902). We accept VISA, MasterCard, American Express and Discover. Merchandise in stock will skip within 2-3 husiness days of receipt. If an item is out of stock, the costomer will be notified and given the option to backorder, substitute or cancel the item. Rush orders can be shipped the same day received if the order is placed by 2:00 p.m. CST. Rush orders will incur a \$10 additional charge and express freight charges will be billed at cost.

Shipping: Include the following amounts for shipping via U.P.S. Ground. Up to \$50.00-add \$5.75, \$50.01 to \$100.00-add \$7.75, over \$100.00-add 8% to total. Air freight is additional.

Shipping charges apply to domestic US orders only. International orders will incur a \$12 documentation charge and will be billed at actual cost plus ossociated duties and taxes. F.O.B Point:
Niles, 11 60714

Sales Tax: We are expected to collect applicable sales tax on all purchases, including shipping and bundling charges, sent to CO, FL, GA, MI, NM, NC, TN, TX, WI and on purchase totals only in CA, IA, IL, IN, OH, SC, and VA. Sales Tax Chart: CA 7.75%, CO 3.8%, FL 6%, GA 6%, IA 6%, IL 8.25%, IN 5%, MI, 6%, NC 6%, NM 5.82%, OH 7%, SC 6%, TN, 8.25%, TX 8.25%, VA 4.5%, and WI 5.5%.

What's New Software



CREATE AUDIOVISUAL PRESENTATIONS

ScreenCam for Windows release 2.0 (\$99) includes captioning, 2-to-1 sound-compression, and editing functions. You can store up to 15 minutes of ScreenCam movies (without audio, using captions) on a floppy disk and save and distribute the movies as stand-alone executable files or as embedded OLE objects in documents. In addition, you can send ScreenCam presentations over a network via Lotus cc:Mail, Lotus Notes, Microsoft Mail, or Novell

GroupWise and post them on BBSes, the Internet, on-line services, or in a Notes database.

Contact: Lotus Development, Cambridge, MA, (800) 343-5414 or (617) 577-8500. Circle 1271 on Inquiry Card.

WINDOWS ACCESS FOR BLIND PC USERS

ScreenPower for Windows provides blind people with access to Windows applications. The program identifies every icon, button, scroll bar, and command element and makes them easy to find and operate. SPWin (\$995) comes in Braille- and speechonly versions and is compatible with more than 30 speech synthesizers.

Contact: TeleSensory, Mountain View, CA, (800) 286-8484 or (415) 960-0920; E-mail: tele@netcom.com.

Circle 1276 on Inquiry Card.

32-BIT OS/2 IMAGE EDITOR ▼

ColorWorks for OS/2 (\$495), a 32-bit multitasking application with a configurable tool architecture, yields thousands of possible drawing tools and a flexible way to define floated images. You can configure the drawing tools to allow you to draw with a color, an effect, or combinations

Constant for 17. Total Constant for 18 and 1

of effects and use the tools to define masks for effects and transformations.

Contact: SPG, Miami Lakes, FL, (305) 362-6602; E-mail: 74723.3437@compuserve.com. Circle 1275 on Inquiry Card.

MEMORY TECHNOLOGY FOR THE MAC OS

With OptiMem RAM Charger (\$129), memory use becomes more efficient, flexible, and reliable. Applications open using smaller initial blocks, and an application's size in memory can grow and shrink after it is open. Contact: Jump Development Group, Pittsburgh, PA, (800) 586-7622 or (412) 681-2692; E-mail: jumpdevgrp@aol.com. Circle 1284 on Inquiry Card.

PRODUCTIVITY TOOLS FOR VISUAL BASIC

A set of 10 productivity tools, ToolThings (\$179) takes the work out of developing Visual Basic applications. Each tool automates a common development task, so you can visually design windows, message boxes, and Windows common dialog boxes; precisely position, align, group, and resize controls; set the tab order for all controls on a form in one dialog box; indent lines of code; change blocks of procedural code to comments and vice versa; identify and remove unused routines, variables, and constants from your code;

and call up a visual diagram of a user-defined function, userdefined type, or variable declaration and assign values to each element.

Contact: Pinnacle Publishing, Kent, WA, (800) 231-1293 or (206) 251-1900.

Circle 1290 on Inquiry Card.

WORDPERFECT DOCUMENT SPLITTER

SplitVu allows you to simultaneously view and edit two parts of a WordPerfect document. The program (\$34.95) creates two window panes, each containing a separate view of the active document. You can separately scroll, search, edit, or work on the text in each pane, and all changes you make in either pane are reflected in the original document.

Contact: Bramblebush Software, New Canaan, CT, (800) 893-1117 or (203) 966-0198; E-mail: 73541.3470@ compuserve.com.

Circle 1280 on inquiry Card.

INCORPORATE YOUR BUSINESS

Incorporate takes you step-bystep through the process of incorporating. Based on forms and procedures obtained from state government offices, the Windows-based program (\$69) creates valid documents for the 10 states in which more than 70 percent of all new corporations are formed. Incorporate also includes an introduction to corporate law. Contact: Unabridged Software, Bellaire, TX, (800) 248-7630 or (713) 661-0044.

Circle 1281 on inquiry Card.

WINDOWS-BASED DATA ACQUISITION SOFTWARE

When you use the Hydra Logger for Windows software with the Hydra data acquisition unit, you can control such functions as scanning, signal conditioning, sensor linearization, alarm sounding, nonvolatile memory, and trend plotting. An optional Trending package controls how the Hydra unit displays data. Hydra Logger for Windows' (\$595; with Trending software, \$995) Trending package can also calculate basic statistics and create x-bar charts and x,y scatter diagrams. It also lets you import data into a spreadsheet, zoom in on and isolate the desired data, and export only that portion to the designated spreadsheet. Contact: Fluke, Everett, WA. (800) 443-5853 or (206) 356-5500.

Circle 1282 on Inquiry Card.



ENGINEERING VISUALIZATION

MicroStation Masterpiece provides photo-realistic rendering, animation, advanced ray tracing, radiosity, engineering animation, and other visualization capabilities. The program (\$1450), which is available in Windows, NT, Unix, and Power Mac versions, works with MicroStation Modeler, MicroStation V5, and MicroStation Review.

Contact: Bentley Systems, Exton, PA, (800) 778-4274 or (610) 458-5000; E-mail: sales@bentley.com.

Circle 1278 on Inquiry Card.



WINDOWS SPREADSHEET VERSION MANAGER

CCC QuikTrak automatically keeps track of the changes you make to a spreadsheet, why you made the changes, and how to get back to any prior version you choose. The program also provides comparison capabilities that allow you to quickly compare changes between versions and identify the impact of those changes. In addition, CCC Quik-Trak (\$99) saves disk-storage space by storing only the changes made between spreadsheet versions rather than duplicate copies of the entire file.

Contact: Softool, Goleta, CA, (800) 763-8665 or (805) 683-5777; E-mail: info@softool.com.

Circle 1283 on Inquiry Card.

ANALYZE AND MANAGE SERVER SPACE

A server-space analysis and management tool, FileWizard 3 has a Native Windows front end, Hierarchical Storage Management, and support for NetWare file servers with PC and Mac clients. The program (single server, \$695) automatically migrates files ac-

*

Pite

cording to a rule-based system and makes all migrated files available to users. Transparent access to the archive server lets users find and retrieve a file as though it were still

in the primary location. Contact: Knozall Systems, Chandler, AZ, (800) 333-8698 or (602) 545-0006; E-mail:

gaill@tesi.com. Circle 1285 on inquiry Card.

IMPROVE YOUR ADA PROGRAMS

Asta's TCMON and

TBGEN software-analysis and test systems improve the quality and performance of software programs written in Ada. The products (licenses, from \$2300) identify performance bottlenecks, test coverage, and automatically test Ada Unix programs.

Contact: Asta, Nashua, NH, (800) 350-2782 or (603) 889-2230; E-mail: asta@delphi.com.

Circle 1298 on Inquiry Card.


MULTIPLATFORM SECURITY FOR UNIX

SeOs combines operating-system-level interception of security-sensitive events with an access-rules database. The program (server, \$999; each client, \$150) features a Kerberized Single Sign-On to the mainframe, which

eliminates the transmission of passwords over a network, and lets you protect root ID and defend against Trojan horses and back doors.

Contact: Memco Software, New York, NY, (800) 862-2602 or (212) 286-8820; E-mail: dorin@memco.com.

Circle 1277 on Inquiry Card.



SOLVE EQUATIONS A

Theorist 2 for Windows 3.1 and NT provides numeric and symbolic computational tools, which it displays in real mathematical notation, for equation solving and mathematical exploration. More than a calculator, Theorist 2 (US\$299) also handles algebraic equations and expressions and 2-D and 3-D graphing. The program is also available for Macs and Power Macs.

Contact: Waterloo Maple Software, Waterloo, Ontario, Canada, (800) 267-6583 or (519) 747-2373; E-mail: info@maplesoft.com.

Circle 1288 on Inquiry Card.

Software Update

Conversions Plus 3.0, a Windows utility that lets you use Mac disks in your PC and convert files back and forth, includes new translators, enhanced graphics capabilities, and a file-preview feature. \$149.

Contact: DataViz, Trumbull, CT. (800) 733.0030 ar (203)

Contact: DataViz, Trumbull, CT, (800) 733-0030 or (203) 268-0030; E-mail: d0248@ applelink.apple.com.

Circle 1300 on Inquiry Card.

With SafE Mail 1.02 for DOS,

you can safely encrypt or decrypt information in almost any format. The program creates output files with Internet-format compatibility and provides an electronic signature protocol, which is for exchanging presigned mail, and distortion protection that you can increase for low-quality transmission facilities. Single copy, \$199; two-user pack, \$349; four-user pack, \$599. Contact: Pinnacle Systems International, Cary, NC,

Circle 1301 on Inquiry Card.

(919) 469-9002.

SCSI-Share 2.0, which lets you share SCSI devices over AppleTalk LANs, features completely overhauled emulation for virtual devices and full support of Apple's SCSI Manager 4.3. \$89.

Contact: Stalker Software, Mill Valley, CA, (800) 262-4722 or (415) 383-7164; E-mail: info@stalker.com. Circle 1305 on Inquiry Card.

ManagePro 3.0 for Windows,

a program that helps managers set goals and deadlines, organize work, and manage people more effectively, offers customized reporting, job-specific templates, and Software Update expanded project and action management. \$279.

Contact: Avantos Performance Systems, Emeryville, CA, (800) 282-6867 or (510) 654-4600; E-mail: avantos@ america.online.com.

Circle 1303 on Inquiry Card.

TRACK DOWN 6000 VIRUSES

Dr. Solomon's Anti-Virus Toolkit 7 (single-user Windows version, \$125; single-user OS/2 version, \$149) detects more than 6000 computer viruses, including complex encrypted and polymorphic viruses. The program scans inside files you've archived and compressed with PKZip, ARJ, PKLite, and LZExe. A Net-


Ware NLM version offers NetWare 4 compatibility, optional server-based scanning, and administration from either the server console or a Windows client on a workstation.

Contact: S&S Software International, Burlington, MA, (617) 273-7400. Circle 1272 on Inquiry Card.

Remove this disk before re-bushing!
Close everything down normally, then
any John Evens on automain 253

QK

What's New Software



ENTRY-LEVEL ACCOUNTING A

The Peachtree First Accounting program (\$169) includes general-ledger, accounts-receivable, invoicing, accounts-payable, item-tracking, checking-account-reconciliation, job-tracking, and business-reporting features. It also lets you enter and print payroll checks and import data from Quicken. Peachtree First's Setup Checklist tells you how to customize your books to best fit your business's needs.

Contact: Peachtree Software, Norcross, GA, (800) 228-0068 or (404) 564-5700.

Circle 1292 on Inquiry Card.

DEVELOP NEURAL-NETWORK SOLUTIONS

NeuralWorks Predict 1.0 (\$995) uses fuzzy logic, genetic algorithms, dynamic hill climbing, Kalman filtering, and conjugategradient methods to help you develop sophisticated neural-

network solutions. Once you develop a model, Predict provides facilities for testing it, running it within Microsoft Excel for Windows, and deploying it as a C, Visual Basic, or FORTRAN program.

Contact: NeuralWare, Pittsburgh, PA, (412) 787-8222; E-mail: sales@nware.com. Circle 1279 on inquiry Card.

NEW APPROACH TO PROJECT MANAGEMENT


Artemis ResourceView (call for prices), a client/server-based resource management tool, consists of two modules: Requester and Allocator. Requester allows you to define new work requests and send them to the appropriate managers for scheduling and commitment. You can directly enter work requests into Artemis ResourceView or import them from Artemis Prestige or Microsoft Project. The Allocator module allows managers to assign approved tasks to resources.

Contact: Lucas Management Systems, Fairfax, VA. (800) 477-6648 or (703) 277-1050; E-mail: cfinch@lucasmgt.com.

Circle 1289 on inquiry Card.

GAUSS APPLICATIONS ▼

Constrained Maximum Likelihood's (Unix version, \$995; PC version, \$495) features include the ability to solve general maximum-likelihood problems using the sequential quadratic programming method; linear and nonlinear constraints on parameters; equality and inequality constraints on parameters; confidence limits for constrained



problems; bootstrapping with histogram and surface-plot output; likelihood-profile trace plots; weight observations; and the ability to profile *t* plots and fix selected parameters.

Constrained Optimization (Unix version, \$495; PC version, \$245) solves standard nonlinear programming problems using the sequential quadratic programming method and provides the capability of adding linear, nonlinear, equality, and inequality constraints on parameters.

Contact: Aptech Systems, Maple Valley, WA, (206) 432-7855; E-mail: info@aptech.com.

Circle 1293 on inquiry Card.

Software Update

StarManager Advanced 4.0.

a Windows program for salesterritory design and mapping, supports more data formats, including ODBC, and mapping and realignment down to the individual account level; it also provides up to 20 user-definable variables in the Star-Manager database, up to 20 layers of map detail, and a drag-and-drop feature that lets you quickly grab and realign territory geography and accounts. From \$995.

Contact: TTG, Woburn, MA, (617) 932-6500.

Circle 1302 on Inquiry Card.

The 32-bit version of the Formula One spreadsheet component includes the ability to create and format objects on worksheets; an enhanced calculation engine; worksheet zooming; print scaling; the ability to read and write Microsoft Excel 4.0 worksheets; special classes for C++ developers to handle worksheet and window creation and manipulation, message routing, and events; and window-manager functions for C developers. \$249.

Contact: VisualTools, Lenexa, KS, (800) 884-8665 or (913) 599-6500.

Circle 1306 on Inquiry Card.

Software Sentry 2.0, a networkindependent license-metering and software-asset management tool, comes with a virus checker and the ability to automatically load the TSR into expanded memory. Alerts notify the LAN administrator of low-license conditions and help-desk requests. Multilingual client support provides international user-intercept messages and end-user help text in English, French, German, Italian, or Spanish. Per server: 50 users, \$295; 100 users, \$595; 250 users, \$895.

Contact: Microsystems Software, Framingham, MA, (800) 489-2001 or (508) 879-9000; E-mail: info@microsys.com.

Circle 1307 on inquiry Card.


Low-Cost Windows Publishing Suite



An all-in-one desktop publishing and graphics solution, Serif Publishing Suite helps you produce professional-quality black-and-white or color-separation newsletters, ads, brochures, catalogs, and greeting cards. The package (\$199) includes PagePlus, a desktop publisher with Pantone Color Matching, text wrapping, and three levels of operation (Intro, Publisher, and Professional); WritePlus, a word processor; DrawPlus, a vector illustration module for creating and editing WMF clip-art files; PhotoPlus, an image-effects module for TWAIN and Kodak Photo CD files; TypePlus, for text effects and logo creation; TablePlus, for table

editing and mini-spreadsheets; and Fonts & Clipart, a library of typefaces and images.

Contact: Serif, Nashua, NH, (800) 697-3743 or (603) 889-8650; E-mail: serif@mv.mv.com. Circle 1273 on Inquiry Card.



Contact: Modatech Systems, Vancouver, BC, Canada, (800) 804-6299 or (604) 736-9666; E-mail: brn@ modatech.com. Circle 1295 on Inquiry Card.

GRAPHICAL DATA ANALYSIS A

DADiSP 4.0 (PC version, \$1895; workstation version, \$2995), a graphical data-analysis package. includes native GUI standards; DDE and other interprogram communications; and SPL (Series Programming Language), which provides user-defined functions, looping and iteration, conditional statements, array references, and variables. SPL also includes Hot Variables, which can contain complex numbers, real numbers, integers, and strings, as well as data series and matrices.

Contact: DSP Development, Cambridge, MA, (800) 424-3131 or (617) 577-1133; E-mail: dspdev@world.std.com. Circle 1297 on Inquiry Card.

CONTACT MANAGEMENT

The OLE support in Maximizer 3.0 for Windows enables you to attach objects, such as spreadsheets and documents, to clients and contacts. Once they're linked, you can modify, print, search, and archive objects from within Maximizer. In addition to printing documents, reports, labels,

and envelopes, Maximizer 3.0 (\$249) can print in popular address- and calendar-book formats. The software's new scheduling features include conflict checking. a find-free-time feature, and an option to add a follow-up task or appointment.

MULTIMEDIA NOTES ANYWHERE

A Windows-based annotation utility, E•Glue 2.0 lets you annotate documents and Windows applications with electronic stick-on notes that can contain text, sound, video, graphics, and animations. Version 2.0 (singleuser version, US\$69.95) features templates, pop-up notes, and a self-resizing notepad. The program's network compatibility lets you send notes to other users with Microsoft Mail or cc:Mail using your existing post office. Contact: The Plant Software, North Vancouver, BC, Canada, (604) 986-6121; E-mail: info@ theplant.com.

Circle 1291 on Inquiry Card.

ENGLISH/SPANISH ACCOUNTING

The Business Accountant Gold integrates receivables, payables, and payroll into one system. The DOS-based program also helps in budgeting, financial planning, decision making, and tax preparation. The program (\$99) saves each transaction to your disk and closes your books as soon as you enter a transaction, keeping your books always up-to-date. From any menu, you can switch from Spanish to English or from English to Spanish.

Contact: Brilliant Nite Software, McLean, VA. (800) 991-1997 or (703) 883-3700; E-mail: dmr@netcom.com. Circle 1286 on Inquiry Card.

SCHEMATIC DESIGN TOOL FOR WINDOWS 3.1 AND NT

You can design schematics with WinDraft (\$750), a 32-bit application that lets you scale components using the Plus or Minus key before placement and automatically places junctions when you end a wire on another wire. You can also edit any part's pin name from the schematic editor without having to go through the library editor.

Contact: Ivex Design International, Beaverton, OR, (503) 531-3555; E-mail: info@ ivex.com.

Circle 1296 on Inquiry Card.

Software Update

VToolsD 1.1 for Windows 3.1. a VxD (virtual device driver) toolkit for C and C++, lets you build VxDs targeted for Windows for Workgroups 3.11; supports the WFW 3.11 features that will be implemented in Windows 95; and introduces PELE, a utility that lets you create VxDs with the 32-bit Borland C++ compiler. \$495.

Contact: Vireo Software, Bolton, MA, (508) 779-8352; E-mail: vireo@vireo.com. Circle 1308 on Inquiry Card.

PICS 1.5 provides doubled speed of the hierarchical listbox, a TimeEdit control that automatically starts and stops time, international date/calendar control, and numeric edit control. The Percent Bar control displays the percent-completed status of an ongoing process, and the Volume Dial control lets you turn a knoblike stereo control to increase or decrease a parameter. \$149; source code version. \$495; PICS NT version, \$495: source code NT version, \$995.

Contact: ProtoView Development, Dayton, NJ, (800) 231-8588 or (908) 329-

Circle 1319 on Inquiry Card.

Electronics Workbench 4.0

lets you simulate analog, digital, and mixed-mode circuits; in addition, you can create larger and more complex circuits with components in multiple parts bins and over 350 real-world models. The program also provides A/D and D/A converters; variable resistors, capacitors, and inductors; encoders, decoders, multiplexers, and demultiplexers: and 74xx and 74xxx ICs. \$299.

Contact: Interactive Image Technologies, Toronto, Ontario, Canada, (800) 263-5552 or (416) 977-5550; E-mail: ewb@interactiv.com. Circle 1310 on Inquiry Card.

INTERACTIVE ON-LINE SOFTWARE

Worldgroup (\$795) unifies messaging, workgroups, customer service, sales, support, EDI, and the Internet. For callers, Worldgroup offers E-mail, group-messaging forums, file libraries, multiuser teleconferencing, polls, and questionnaires. The client software can access the server over a dial-up modem

or through the internet. From inside a company, Ø 481 the employees can log on through a LAN using Novell IPX/SPX or TCP/ IP protocols.

Contact: Galacticomm, Fort Lauderdale, FL, (800) 328-1128 or (305) 583-5990: E-mail: sales@gcomm.com.

Circle 1274 on Inquiry Card.



Having trouble keeping up with the ever-changing world of technology? Quatech can help. We are committed to providing our customers with quality products and exceptional service and support. We manufacture a complete line of communication and data acquisition products for PC/XT, PC/AT, PS/2, and PCMCIA systems. Just tell us your application, and we'll find the solution that's right for you.

Quatech's communication and data acquisition PCMCIA cards provide maximum flexibility for your application. Communication PC cards include single and dual channel RS-232 and RS-422/485, EPP, and synchronous adapters. Data acquisition PC cards provide 12 and 16-bit analog input, 8 channel analog output, and 24 digital I/O. Add PCMCIA capability to your desktop computer with our Internal Interface Adapters. Each adapter supports Type I, II and III PC cards, and is available in several configurations.

Communication boards for ISA and Micro Channel meet synchronous, asynchronous, serial, and parallel communication requirements with protocols such as RS-232, RS-422, RS-485, Current Loop, and IEEE-488. Intelligent and coprocessor adapters are also available. Data acquisition products add analog to digital, digital to analog conversions, and digital I/O capabilities in 8 to 16-bit resolution. Other boards provide the capabilities for digital multimeters, digital frequency synthesizers, arbitrary waveform synthesizers, and IEEE-488 GPIB interfaces.



Foreign Distributor Inquiries Welcome

For more information and a free 1995 Handbook, call a Quatech sales representative today at 800-553-1170.

Quatech, Inc. 662 Wolf Ledges Parkway, Akron, OH 44311. International Distributors: Australia/Interworld Electronics & Computer 61-3-9563-5011, Australa/ Megadata 43-1-523 42 12, Belgiumi/Acal NV/SA 32-27-205983, Brazil (Sao Paulo)/Intercomp 55-11-8532733, Brazil (Rio de Janeiro)/Medusa Sistemas e Automacao 55-21-2394955, Canada(Westem)/Interworld Electronics 800-663-6001(Toronto office 800-465-0164), China/Quatech China 86-1-205-9030, Denmark/Jes Rasmussea Aps. 45-4281-6838, Finland/Lab Hi-Tech OY 358-0-682-1255, France/Elexo 33-1-69302880, Germany/Jupiter Electronic Systems GMBH 49-61-8175041, Hong Kong/Brio Technology Ltd. 852-581-1111, India/Comsquare Network Pvt. Ltd. 91-11-224-5159, Israel/Milivision Ltd. Div. 972-9-500623, Italy(Non-PCMCIA)/ N.C.S. Computer Italia 39-331-770016, Italy(PCMCIA Only)/Kernel Consulting S.r.l. 39-6-77207000, Japan/Nictrix Corp. (New Jersey) 201-947-2220, Korea/Sam Boo Systems 82-2-135-280, Netherlands/ACAL Auriema 31-40-502602, New Zealand/Advanced Portable Technologies 64-4-3852838, Pakistan/Rastek (PVT) Limited 92-21-4551881, Saudi Arabla/Integrated Computer Operations 966-3-895-1827, Singapore/Bliss Services Pte Ltd. 65-338-1300, South Africa/Eagle Technology 27-21-234943, Spain/Santa Barbara SA 34-3-418-81-16, Sweden/Systec 46-13-310140, Switzerland/Technosoftware 41-64-519040, Turkey/Logic Group 90-212-2747197. PC/XT, PC/AT, PS/2, and Micro Channel are registered trademarks of the IBM Corporation. All other trademarks are of their respective companies.

Circle 85 on Inquiry Card (RESELLERS: 86).



BYTE

BUYER'S GUIDE

Essential Products and Services for Technology Experts

Mail Order

Top mail-order vendors offer the latest hardware and software products at the best prices.

268

Hardware/Software Showcase

Your full-color guide to in-demand hardware and software products, categorized for quick access.

287

Buyer's Mart

The BYTE classified directory of computer products and services, organized by subject so you can easily locate the right product.

295

COMPUTER DISCOUNT WAREHOUSE

COMPUTER DISCOUNT WAREHOUSE™



bulky phone line adapters • User-upgradeable Flash memory
• Online help in ROM • Includes data and fax communications

OPTIMA 288 \$299.87 CDW 49664 .\$179.46 CDW 49665

TAIL?

CDW[®] Sells For Less



Zip disk 29ms seek time, up to 1.25MB/second austained transfer rate Parallel or SCS1 interface (SCS1 host adapter sold separately) Includes Zip Tools' software Compact and portable: 1.5" x 5.35" x 7.25", 1 lbs 1 year warranty

EPSON

PACKARD

MICROTEK

Summagraphics. Summasketch III 12 X 12 16 button ... Summasketch III 18 X 12 4 button ...

MONITORS

,,,499.00 ,1237.30

339.63 472.00 529.27

1073.62

487,44

,227.86 ,247.44

347.61

729.60

529.56 ...966.72 1929.85 ...626.40 1196.84

2447,48 .225.86

258.75

Parallel						
SCSI	\$1	9	9.	9	5	CDW 51390

ActionScanner ES600C...

ScanJet 3P ScanJet 3P document feeder ScanJet 3C WASA Interface .

ScarList BCX document feeder ScanJet HCX transparency adapt Scarulet fICX to

Scanmaker IIG grayscale ...
Scanmaker IISP color
Scanmaker IISP color
Scanmaker IIHR color

Mag Innovision DX15F

Mag Innovision DX15F
Mag Innovision DX15F
Mag Innovision DX17F
Mag Innovision MXP17F
Mag Innovision MXP17F
Mag Innovision MX21F
Magnavox CM2099 14* 28 NI
Magnavox CM2099 14* 28 NI

Magnavox CM2015 15° 1024 Magnavox CM2015 15° 1024 Magnavox CM4015 15° 1280 Magnavox CM4017 17° 31 Magnavox CM4018 17° 28 Magnavox CM4018 20°

NEC XV15 15" NEC XV17 17°

NEC XE15 15°

NEC XE17 17° NEC XE21 21° NEC XP15 18° NEC XP17 17°

NEC XP21 21"

Samsung 3 14"

nMaker III color..... nmaker 35T säde scanner

FS-1200-PmPC

HARDWARE, SOFTWARE & PERIPHERALS AT

NETWORKING PRODUCTS MNOVELL Netware V4.1 5 User CD.... 10 User CD... 25 User CD... 50 User CD... 100 User CD. Netware V3.12 3Com 3C503 Etherlink III coax. 3C509B Etherlink III coax. 3C509B Etherlink III coax. 3C509B Etherlink III 108T 50. 3C509B Etherlink III combo. 3C509B Etherlink III 3C500B 50. 3C579 Etherlink EISA 108T 3C79 Etherlink EISA 108T 3C1627 12 port Linkbuilder 1081 199.44 114.14 479.85 111.14 442.36 123.77 526.78 229.91 229.91 619.44 ARTISOFT NodeRunner 2000A NodeRunner 2000T NodeRunner 2000T NodeRunner 2000C NodeRunner SI 2000A NodeRunner SI 2000A NodeRunner SI 2000C LAMISSIS V6 0 Suson Krt. LAMISSIS V6 0 Suson Krt. Simply LAMISSIS starfer kit. T-Runner 8 port 108T T-Runner 12 port 108T 218.68 169.05 169.05 67.13 73.82 79.50 329.87 229.13 388.13 163.79 178.89 **ASP** Multiprotocol print server 108T HP MIO. Multiprotocol print server 108T pocket ... Multiprotocol 2 printer server combo Multiprotocol 4 printer server combo ... SNAP starter kit-2 computers, 1 printer... 118.10 IBM intها. EtherExpress PRO/100Mbps PCI EtherExpress PRO/100Mbps EISA EtherExpress PRO/100Mbps EISA EtherExpress PRO/10 Fish 108T ps EtherExpress PRO/10 Fish 108T ps EtherExpress PRO/10 Fish 108T ps EtherExpress FRO/10 Fish 108T ps EtherExpress 16 coat EtherExpress 16 coat EtherExpress 16 coat EtherExpress 16 loat EtherExpress 18 loat EtherExpress 18 combo Spk EtherExpress 18 combo Spk EtherExpress 18 combo Spk EtherExpress Flash 108T spk EtherExpress Flash 108T spk EtherExpress Flash combo Spk ItherExpress Flash combo 219.19 329.82 108.01 419.98 115.07 472.90 99.33 454.13 99.33 454.13 698.36

OF I WARE & PEI
NETWORKING PRODUCTS
SMC
Ultra 16 Ethernet coax Ultra 16 coax 694. Ultra 16 coax 694. 10 88. 10 88. 10 88. 10 88. 10 88. 10 88. 10 88. 10 88. 10 88. 10 88. 10 88. 10 88. 10 88. 10 10 10 10 10 10 10 10 10 10 10 10 10 1
THOMAS (DARAD
TC5143 Ethernet 108T 72.00 TC5143 Ethernet 108T 6ph. 38.04 TC6242 ARCNET 6-bit coax 50.00 TC6245 ARCNET 6-bot coax 77.00 TC6040 ARCNET passive 4 port hub coax 39.00 TC6055 Ethernet 8 port hub 108T 398.47 TC4045 Tolen Ring 164 20.00 CDW Carries the Complete Line of TCNS Products, Call for Desibil
TERMINALS
Link MC5 amber/green/white
Xircom
PE310BC pocket Ethernet coax
TAPE & REMOVABLE MEDIA DRIVES
COLORADO MENOR SISTEMS IN
Jumbo 250 internal
iomega
Zip cinve 100MB parallel interface
MICROSOLUTIONS Backpack 3.5* 1.44MB floopy parallel

Tape*Stor 250MB Internal	181.17 237.29 272.26 429.90
Mountain.	
FS8500 305MB fDE internal	.,300.44
MULTIMEDIA AND CD-RO	М
Creative Labo	204.45
Olgital School House CD 2X lut internal Edutainment CD 2X lut internal	435,14
Game Blaster CD 2X kit internal	388.64
Multimedia Home CD 4x kit internal	448.00
SoundBlaster Pro value edition	72.68
SoundBlaster 16 value edition	00.05
SoundBlaster 16 value edition	178.95
SoundBlaster 16 ASP MCD	178.95
SoundBlaster 16 ASP SCSI-2	198,95
SoundBlaster AWE32	296.95
Advent PP570 speakers 35W	245.07
Advent PP622 spkrs/subwoofer	,199.00
Chinon CDS535 CD-ROM kit internal	,240.73
Chinon CDX535 CD-ROM kit external Diamond 4000 Quad CD kit internal	.347.88
Diamond 5000 Quad CD kit internal	440.06
Ensoniq Soundscape wavetable	199.88
Jensen JPS35 speakers 5W	54.88
Logitech SoundMan Wave	119.48
Microsolutions 4X CD parallel	.357.65
NEC 2V Dehive	785.68
NEC 2V Deluxe	384.54
NEC 3Xp Plus Kit	450.93
NEC 4XI Kit	449.76
NEC 4Xe	479.85
NEC 4Xe Kri	.549.25
NEC 6Xp	547.58
Pioneer DRM604X 4X 6 dusc	.004.71
Pioneer DRM1804X 4X 18 disc Plexfor 4plex quad external	1879.28 589.85
Plextor 4olex guad internal	409.04
Plextor 6X Internal	.499.87
Sigma Designa RealMagic	279 88
Sigma Designs RealMagic CD Kit	650.41
Sony CDU-558 SCSI 2X Internal	166,07
Sun Moon Star CD 2X kit Internal	140.76
Teac SuperQuad 4X internal	200 25
Turtie Beach Monte Carlo	309.40
Tuetta Baach Tennas	07.85
Turtie Beach Tropez	67.85
Turtle Beach Monterey	
Turtle Beach Tropez. Turtle Beach Montorey DIGITIZERS & SCANNERS	
Turtle Beach Monterey	
Turtle Beach Montorey DIGITIZERS & SCANNERS CalComp DB III 12X12 4 busen	
Turte Beach Tropaz. Turte Beach Montorey DIGITIZERS & SCANNERS	

TAPE & REMOVABLE MEDIA DRIVES

CONNER

450.00		225.8
379.E		358.7
	Samsung 17GLs 17"	
470.8	Sonv CPD-1425 14*	310.2
548.2	Sony 15SF 15"	429.2
498.14	Sony 17SF1 17°	STR.4
	Sony 20SE1 20*	
6 disc	ViewSonic 15G 15'	
X 18 disc1879.2	ViewSonic 17G 17"	710 7
ternal	ViewSoric 21PS 21"	4.662 T
ernal409.6-	VANISOTIC 21P3 21	
490.8	VIDEO BOARDS	
lagic Lite	3	
fagic		134.6
fagic CD Kit 659.4	ADS YGA to TV Elde external	198.8
lemal119.8-	ATI Graphics Xpression ISA 2MB	
2X Internal	ATI Graphics Xpression VLB 2MB	208.4
Ç kit internal140.79	ATI Graphics Xpression PGI 2MB	200.4
Ckt internal w/sound	ATI Graphics Pro Turbo ISA 2MB	
mernal204.53	ATI Graphics Pro Turbo VLB 2MB	
X internal 309.86	ATI Graphics Pro Turbo PGI 2MB	
arlo	ATI Graphics Pro Turbo PCI 4MB	
193.6	Diamond SpeedStar Pro ISA 1MB	
y	Diamond SpeedStar 64 ISA 2MB	
	Diamond Stealth 64 VLB 2MB VRAM	
ERS & SCANNERS	Diamond Stealth 64 PCI 2MB VRAM	
	Hercules Dynamite Pro ISA 1MB	
CalComp	Hercules Dynamite Pro ISA 2MB	
1 carcomp	Hercules Dynamite Provise VLB 1MB	
340.9		
340.0		
pon		
2.4 button cordiess246.0	Intel Smart Video Recorder Pro	
8 CDW* TELI	EPHONE	1
HOU		JEES
11001		

If You Find a Better Price, Call CDW Before You Buy (800) 959-4CDW

MICRODYNE

Eagle NE2000+ coax... Eagle NE2000T+108T _ Eagle NE2000T-combo _ NE3200 EISA 108T _ NE3200 EISA coax _ IRMAdrac 4/16Mpbs ISA Convertible IRMAdrac 4/16Mpbs ISA Convertible IRMAdrac 4/16Mpbs ISA Convertible



BUY WITH CONFIDENCE CDW9 IS A NASDAQ TRADED COMPANY

No surcharge for credit card O VSA CHESTO

7:00-9:00 CDT Mon-Fri. 9:00-5:00 CDT Set. Tech Support for Custom 8:00-7:00 COT Mon-Fri.

SHIP THE SAME DAY

COMPUTER DISCOUNT WAREHOUSE



CREATIVE

Sound Blaster Multimedia Home 4x



Multimedia kit with Microsoft* Home software

✓ Internal tray-loading quad-speed CD-ROM drive ✓ IDE interface, 600KB/second data transfer rate, 250ms average access ✓ Sound Blaster 16 stereo sound card ✓ More than 20 best-selling multimedia titles, including 11 Microsoft Home titles—Encarta, Bookshelf, Cinemania, Publisher, Golf, Dangerous Creatures and much more V Includes stared speakers and microphone



\$449.00 CDW 51844

WHY SETTLE **FOR LESS?**

CDW® SERVICES YOU BETTER





17" diagonal (15.6" viewable)

flat square CRT .28mm dot pitch high-contrast anti-static screen Maximum resolution: 1280 x 1024, non-interlaced ✓ Refresh: up to 76Hz at 800 x 600, 76Hz at 1024 x 768, 60Hz at 1280 x 1024 x 768, 60Hz at 1280 x 1024 x 1024 x 768, which is the second of the second o



CDW® CARRIES OVER 20,000 PRODUCTS. IF YOU DON'T SEE IT.

COMPUTERS	
TOSHIBA	
T2100 DX2/50 250MB mono	1449.02
T2100CS DX2/50 330MB dual cir	2254.13
T2100CT DX2/50 330MB act color	3099.30
T2150CS DX4/75 500MB pas color CD	3599.81
T2150CT DX4/75 500MB act color CD	4896.22
T1960CT 200MB act color	2057.14
T1960CT 320MB act color	2246.49
T2400CS 250MB dual color	2272.10
T2400CS 320MB dual color	2442.14
T2400CT 320MB act color	2996.80
T2450CT 320MB act color	3343.40
T2450CT 500MB act color	3576.36
T3600CT 500MB act color	3709.20
T4800CT 500MB act color	3343.40
T4850CT 4/75 520MB act color	
T4900CT P75 772M8 act color	5448.20

AST.

Ascentia 910N 4/50D 340MB pas color	2459.73
Ascentia 910N 4/75 510MB pes color	2649.50
Ascentia 910N 4/75 510MB act color	3679.81
Ascentia 910N 4/75 710MB act color	
Advantage! 6066d 4/66 540MB CD	.,1095.06
Advantage! 6060p 5/60 540MB CD	.1624.79
Advantage! 8075p 5/75 1GB CD	
Advantage! 8090p 5/90 1GB CD	2139.63
Advantage! 8100p 5/100 1GB CD	
Bravo MST 5/90 540MB	2059.80

Canon va Media 4/66 420MB MT va Media 5/60 420MB MT

1199.90

IBM	
Aptiva 338 DX2/66 540MB	1274.87
Aptiva 350 DX2/66 540MB MT	
Aptiva 535 DX2/66 540MB	
ThinkPad Portables	
701CS DX2/50 360MB dual color	3790.00
701CS DX2/50 540MB dual color	4149.00
701CS DX4/75 360MB act color	5299.00
701CS DX4/75 540MB act color	5849.00
360C 4/33SX 340MB act color	1999.00
360CSE DX2/50 540MB pas color	
360CE DX2/50 340MB act color	
360CE DX2/50 540MB act color	

PC300 Series deaktop

PC300 Series desktops	
PC330 DX2/50 8MB, 364MB	1374.00
PC339 5/60 16MB, 540MB	2225.00
PC350 DX2/86 8MB, 540MB	
PC350 DX4/100 8MB, 540MB	
PC350 5/80 8MB, 364MB	1875.00

NEC

Versa V 4/50 250MB dual color	2382.25
Versa V 4/50 250MB act color	2802.80
Versa V 4/50 340MB act color	3047,57
Versa V 4/50 540MB act color	3426.27
Versa M 4/75 250MB dual cir	3033.07
Versa M 4/75 340MB dual cir	3142.00
Versa M 4/75 340MB act cir	
Versa M 4/75 340MB true cir	
Versa M 4/75 540MB act cir	
Versa M 4/75 540MB hi-res cir	
Versa M 4/100 340MB act color	
Versa M 4/100 810MB act color	
Versa M 4/100 540MB hi-res color	
Versa M 4/100 540MB true color	
Versa M 4/100 810MB hi-res cir	
Ready 4/33S 270MB CD	1336.21
Ready 4/66 340MB CD	
Ready 4/66M 420MB 2X CD	
Ready 5/50M 420MB 2X CD	

TEXAS INSTRUME	NIS
TM4000M 4/50SX 200MB dual color	
TM4000M 4/50DX 340MB dust cir	2137.72
TM4000M 4/50DX 455MB act cir	2409.44
TM4000M 4/75 344MB act color	2748.85
TM4000M 4/75 455MB dual co-or	2489.92
TM4000M 4/100 524MB act color	2839.57
TM5000 5/75 524MB dual cir	
TM5000 5/75 810MB active cir	5608.00

DOT MATRIX & LASER PRINTERS

	OKIE	DATA"
184 Turbo	219.14	ML591 579.12
ML320	299.88	Pacemark 3410 1213.96
ML321	427.40	OL400E 388.86
ML380	212.43	OL410E 539.8
ML395	966.07	
ML395C	1039.74	OL410E/PS759.80
ML520	366.77	OL810964.96
ML521		OL830 Plus1078.51
ML590		OL8501189.50

CAROR

	BJ100
	BJ200ex229.88 BJ230388.60

BJC4000 720dpl + color	

EPSON

AP2250	DFX5000 Plus 1384.01
AP3250146.45	DFX8000 2322.45
AP3260167.82	Stylus 300163.16
LIC300165.65	Stylus 400184.88
FX870288.45	Stylus 800+211.14
FX1170374.86	Stylus 1000 436.15
AP5000+229.71	Stylus Color509.53
LQ1070+375.25	ActionLaser 1100 383.62
LQ870454.44	ActionLaser 1400, 582.40
LQ1170	ActionLaser 1500 458.82
LQ2550965.00	ActionLaser 1600 765.75

TRM LEXMARK LASER PRINTERS

WnWriter 400 laser758.03
WirWriter 600 laser
ValueWriter 300 (4037 5E 5PPM)844.87
ValueWriter 600 laser
Optra R 600dpi laser1426.69
Execulet lic

1150				133.4
2023				
2130	**********	***********	177470mmmqmm v 178400000	204.4
2135 C				
KX1-595				498.41
4400 4				ASA W
KX-SP1	00 printer/fa:	x/oopier		798.8

TEXAS

microWriter PS23
microLaser 600
microLaper Pro 600 PS231197.0
microLaser Pro E
microLeser Power Pro 600 PS651029.0
TE HEWLETT

Office.Jet inkjet fax/copyer/prints	f 779.59
DeskJet 540	289.75
DookJet 660C	**************************************
DeskJet 1200C	
DeskJet 1200C PS	1599.49
LaserJet SP	
LaserJet 4 plus	
LanerJet 4SI	2900.95
LaserJet 4V	1967.36
LaserJet Color	5929.62
COSTAL	A .

LabelWriter XI, DOS/Win....... LabelWriter XL Plus DOS/Win.

HARD DRIVES & CONTROLLERS

INIEDGO	
270AB Fast-ATA 160.1 345AB SCSI-2 160.1	10
425MB Fast-ATA 1694 540MB Fast-ATA 1672	io.
Diomit Cast of Personal Property of the Personal	-
MICROPOLIS	
3221 2.1GB SCSI-21088.4	
3243 4.3GB SCSI-2 1608.7	7
1936 3GB SCSI-21278.1	17

CCHNER

425MB (DE	
540MB (DE235.00	
850MB Fast-ATA297.48	
1.27GB Fast-ATA	
LE/OD FERMIN	

Seagate

429MB Fast-ATA
545MB Fast-ATA189.89
722MB Fast-ATA2286.46
1GB Fast-ATA2
1.0GB SCSI-2584.36
WESTERN DIGITAL

	•	AFOI FULL DIO	100	
Cavin	540MB EID	DE	21	2.60
Cavia	730MB EIC	Æ		5.75
Cavia	IGB EIDE.			5.61
Cavia	1.2GB EID	E	***************************************	4.14

CONTROLLERS
Acculogic SIDE-3+ w/on-board BIOS
Acculogic SIDE-4+ w/per, 2ser, game35.06
Acculogic SIDE-4VL EIDE, 16550 serial89.78
Acculogic ISApport SCSI-2
Adaptec AVA1505 SCSI-2 CD Kit
Adaptec AHA1542CF SCSI-2285.45
Adaptec AVA2825 VLB SCSI-2/EIDE166.87
Adaptec 2842 VLB SCSI-2
Promise 2300+ EIDE VLB

MODEMS & COMMUNICATIONS

Robotics

SPORTSTER MODEMS

V.34 28.6K Internal wifax	
V.34 28.6K external w/fax242	LÓ
14.4K internal w/fax	
14.4K external w/fax111	ø
COURIER MODEMS	

Haves

ACCURA 144 Internal w/tax93.99
ACCURA 144 external w/lax
ACCURA 288 V 34 Internal w/fax188.13
ACCURA 286 V.34 external w/fax218.86
OPTIMA 144 external w/fax374.30
OPTIMA 144 pocket w/fax
OPTIMA 288 V.34 internal w/fax
OPTIMA 288 V.34 external wrtax

PRACTICAL

	14.4 internal witax
	14.4 Mini Tower wifax108.8
Ì	V.34 28.8 internal wfax196.8
	V.34 28.6 Mini Tower w/fax
	BOCA

Online Express 14.4 external w/fax

MICROCOM				
Dealgorte	ES 14 4	146.		
Dealgorite	Fast ES V.FC 28.8	179		
Deskoorte	Fast EP V.FC 28.8	385		

	Power Conversion
BackUPS 280	
BackUPS 400	144.2
BackUPS 450	175.8
BackUPS 600	243.00
BackUPS 800	345.70
	449.21
	299.60
	362.3
Smart IPS 900	514.6
	644.2
Surrea Arraict Methorski	33.29
Surrant Pen	29.4
Cuena Armet Biotunele .	Phone 49.90

Tripp Lite

BC25094.9	7
BC400138.9	п
BC500173.0	ė
BC500 LAN177.5	Ĭ
BC600 LAN	۵
BC750 LAN288.0	ä
BC900 LAN 327.5	×
9C1250 LAN 436.1	ä

SMART UPS SERIES NEW

SMART 250 LAN	8.30
SMART 400 LAN	
SMART 500 LAN	
SMART 600 LAN	
SMART 750 LAN	
SMART 900 LAN48	
SMART 1400 LAN56	
Isobar 4 OUTLET	
Isobar 6 OUTLET	6.38

PCMCIA CARDS

3Com Etherlink IIIB combo	214.2
Hayes EZJack 14.4 w.fax	179.4
Hayes EZJack V.34 wfax	290.8
IBM Token Ring 16/4	390.9
Linksys Ethernet combo	165.7
Megahertz 14,4K data/fax	179.4
Megahertz XJech 14.4 data/tax	188.5
Megahertz XJack Gold 14.4 data/fax	196.8
Megahertz V.34 XJack data/fax	353.0
New Media Bus Toaster SCSI-2 host	199.8
New Media Wave Jammer sound card	229.4
New Media Multimedia Combo	439.8
Simple Tech 14.4K data/fax modern	145.5
Simple Tech 14 4K modem + voice	143.0
Simple Tech Ethernet 10BT adapter	140.8
Simple Tech SCSI adapter	145.5
Simple Tech 130VIB hard drive	359.1
Simple Tech 170MB hard drive	404.6
Adaptec APA1480 SCSI-2	211.8
Turtle Beach Audio Advantage	129.3
USR Sportster 14.4K	178.9
USR Sportster V.34	348.7
Xircom Ethernet 10BT	158,6
Xircom Ethernet combo	
Xircom Ethernet-modern 10BT	449.8
Xircom Ethemet+modern combo	
Xircom Token Ring 16/4	436.1

INTEL OVERDRIVE

Intel OverDrive	CX2/50	129.68	
Intel OverDrive	0X2/66	160.67	
	DX4/75		
Intel OverDrive	DX4/100	297.74	
Intel OverDrive	Pentium 63MHz	396.48	
MEMORY UPGRADES			

simple Lifetime Warranty

AST Ascentia 910N 4MB	CAL
AST PowerExec 4/33SL 4MB	CAL
AST PowerExec 4/33SL 16MB	
HP LeserJet 4L 'MB	CAL
HP LaserJet 4P 4MB	CAL
HP LaserJet 4 4MB	CAL
HP LaserJet 4 8MB	
IBM ThinkPad 500 4MB	CAL
IBM ThinkPad 500 8MB	CAL
IBM ThinkPad 755 4MB	
IBM ThinkPad 755 8MB	
Toshiba 1900-4600 4MB	
Toshiba 1900-4600 8MB	CAL
Toshiba 1900-4600 16MB	CAL
Toshiba 4700/4800 32MB	
NEC Versa 4MB	
NEC Versa 8MB	

Call today for current pricing and avail

FREE TECHNICAL SUPPORT FOR CDW® CUSTOMERS

CDW° Sells for Less and Services You Better!

FAX (708) 465-6800

CALL FOR FREE CDW® CATALOG

The Databrick...

Now with PCMCIA option!

The newest addition to Datalux's family of space-saving computer products! This 1.4kg unit measures only 26x12x5cm (10"x5"x2"), yet is powerful — 486SX to 486 DX2/66 with local bus video. Intended for situations where space saving is

> most important, it provides a rugged, portable, flexible PC solution, bridging the gap between a laptop and a desktop PC. Databrick drives both VGA and Datalux LCD monitors, making it ideal for industrial control, vehicle, POS, institutional and presentation systems. It can be configured as a diskless unit

(booting from PCMCIA devices or from a network) or a stand-alone system with hard disk, powerful enough for today's CAD or desktop publishing programs. Hinged lid is removable.

> Orders and Information: 1 800-DATALUX 24-hour faxed data sheets: 703 662-1675

Space-Saver Keyboards



The popular 1.0kg desk and .4kg portable flat models save 60% of the normal desk space, with full-travel, tactilly responsive keys. Footprint is only 28 x 16 cm (11x6"), but the 100 keys have standard left-to-right spacing. Both models are XT/AT/PS2 compatible and are available in many languages.

LCD Monitors

Datalux stand-alone monitors are available in both 1.8 kg. desk/wall (which folds for portability) and 2.7 kg mobile/industrial, 64-grey shade, mono or 256 color DUAL SCAN versions. Both are 9.4" diagonal 640 x 480 VGA and can be fitted with optional touch screen with integrated touch controller. The mobile/industrial unit (pictured with swive)

mount) is in a rugged aluminum housing with sealed front bezel and controls. All models plug directly into the Databrick or are supplied with a 16-bit ISA bus controller.



Desk/Wall Package

The Databrick combined with our LCD monitor is an ideal solution when you need a complete, compact PC and screen in a single unit. When folded or mounted on a wall, this 4 kg unit measures only 29x24x11cm (4.5x9.5x11") and is rugged enough to survive as a touch system in harsh environments such as kitchens or factories.

TALUX

American Made **Space-Saving Computer Products**

DATALUX Corporation 155 Aviation Drive Winchester, VA 22602 Phone (703) 662-1500 Fax (703) 662-1682

Datalux International, LTD Euro House Curtis Road, 11 Old Water Yard Dorking, Surrey, UK RH41EJ Phone 44 + [0] 306-876718 Circle 132 on Inquiry Card. Fax 44 + [0] 306-876742

Control PC, Macintosh, and Sun Computers from 1 Console!

- Supports any mixture of PC/Macintosh computers and Sun workstations up to 4 in all
- Any platform's peripherals work with any type of computer in the system

 Full multimedia capabilities; keyboard, mouse, video, microphone, speakers, and serial port available

Multiple users can access different computers simultaneously

■ Convenient desktop size unit





COMMANDER 100° T

Cybex Corporation 4912 Research Drive Huntsville AL 35805 USA (205) 430-4000 (205) 430-4030 fax



PC is a registered trademark of International Business Machines Corporation. Macintosh is a registered trademark of Apple Computer, Inc. Sun is a trademark of Sun Microsystems. Cybex, Commander, AutoBoot, and 1xP are trademarks of Cybex Corporation.



GUIDE

SHIBA

T2150 as low as \$3539



T2100

- Integrated Accupoint small, accurate & easy to use
- Built-in AC adapter small, sleek design & reduced weight
- 10.4" Dual Scan display

Processor	Screen	HD	Price
486DX2/50	9.5" Mono	250MB	\$1439
486DX2/50	10.4" Dual Scan	330MB	2249
486DX2/50	8.4" Active	330MB	3099

T2150

- Built-in CD-ROM Drive
- Built-in 16-bit sound, microphone, speaker & MIDI
- 10.4" Active & Dual Scan
- Built-in AC adapter small, sleek design & reduced weight
- Integrated Accupoint small, accurate & easy to use

Processor	Screen	HD	Price
486DX4/75	10.4" Dual Scan	500MB	\$3539
486DX4/75	10.4" Active	500MB	4679





T4900CT

- 75MHz Pentium for blazing performance
- 10.4" Active Matrix display
- Built-in 16-bit sound, microphone. speaker & MIDI

Processor	Screen	HD	Price
Pentium 75	10.4" Active	772MB	\$5499

© PCs Compleat. All prices subject to change and do not include shipping. All products or brand names are trademarks of their respective companies. PCs Compleat, 34 St. Martin Drive, Mariborough, MA 01752. Phone (508) 624-6400. Not responsible for typographical errors.



T4800 as low as \$3559

Other Notebooks from Toshiba


Processor	Screen	HD	Price
T4800	CT		
4B6DX4/75	9.5" Active	500MB	\$3559
T4850	CT		
486DX4/75	10.4" Active	500MB	S3889
486DX4/75	10.4" Active	772MB	4099
T3600			
486DX2/50	8.4" Active	500MB	\$3719

NEC

Versa M

- High Res. displays available 800x600 res. on notebook
- True color displays available-16.7 million colors on notebook
- Removable/Reversible display
- Replace floppy w/ 2nd battery for 6-10 hrs. Versa battery life
- Replace floppy w/ Versa Bay Add extra **PCMCIA**
- Built-in 16-bit sound, microphone & speaker
- Úpgradable hard drive easily add more storage

ı	THOIC Stor	uge .		
١	Processor	Screen	HD	Price
Ì	486DX4/75	9.5" Dual Scan	250MB	\$3049
ŀ	486DX4/75	9.5" Dual Scan	340MB	3119
ľ	486DX4/75	9.5" Active	340MB	3739
ı	486DX4/75	9.5" Active	540MB	3999
ľ	486DX4/75	9.5" True Color	340MB	3999
l	486DX4/75	9.5" High Res.	540MB	4399
ŀ	486DX4/100	9.5" Active	340MB	4069
l	486DX4/100	9.5" True Color	540MB	4629
ĺ	486DX4/100	9.5" Active	810MB	4729
ŀ	486DX4/100	9.5" High Res.	540MB	4729
ĺ	486DX4/100	9.5" High Res.	810MB	5099




Versa P

- 75MHz Pentium for blazing performance High Res. displays available - 800x600 res.
- on notebook (10.4" on selected models) Removable/Reversible display
- Replace floppy w/ 2nd battery for 6-10 hrs. battery life
- Replace floppy w/ Versa Bay Add extra PCMCI. Built-in 16-bit sound, microphone & speaker
- Upgradable hard drive easily add more storage

Processo	Screen	HD	Price
Pentium 75 Pentium 75	9.5" Active	340MB	\$4349
Pentium 75	9.5" Active	540MB	4629
Pentium 75	9.5" Active	810MB	4999
Pentium 75	9.5" High Res.	540MB	4999
Pentium 75	9.5" High Res.	BIOMB	5389
Pentium 75	10.4" Active	540M8	499
Pentium 75	10.4" Active	BIOMB	5389
Pentium 75	10.4" High Res.	BIOMB	576


TEXAS ISTRUMENTS



TravelMate 400

- Brilliant color display
- 16-bit sound card
- Integrated pointing device
- 2 Type II or 1 Type III PCMCIA slot

Processor	Screen	HD	Pric
486DX2/50	9.5" Dual Scan	340MB	\$211
486DX2/50	8.4" Active	455MB	237
486DX4/75	9.5" Dual Scan	455MB	245
486DX4/75	8.4" Active	340MB	272
486DX4/75	8.4" Active	455MB	297
486DX4/100	9.5 Active	525M8	393



TravelMate 5000

TravelMate 5000

- 10.4" Active Matrix display w/ 2MB Video RA 10.5" Dual Scan display with 2MB Video RAY
- 65K colors on notebook display
- Built-In Dual Lithium Ion Batteries
- 16-bit Sound Card, Speaker, Microphone & MIDI
- User Replaceable 772MB Hard Drive (Active User Replaceable 500MB
- Hard Drive (Dual Scan) Infrared port for wireless connections

Processor	Screen	HD	Price
Pentium 75	10.5" Dual Scon	500MB	
Pentium 75	10.4" Active	772MB	

CALL for Guaranteed Lowest **Price!**







Ascentia 910N

- 10.4" Active & 10.3" Dual Scan Lithium Ion battery technology
- Intelligent power management to
- maximize performance
- Integrated Smartpoint small, accurate & easy to use

Processor	Screen	HD	Price
486DX2/50	10.3" Dual Scan	340MB	\$2559
486DX4/75	10.3" Dual Scon	510MB	2749
486DX4/75	10.4" Active	510MB	3829
486DX4/75	10.4" Active	700MB	4129



Ascentia 810N

- 486DX2/66 processor to speed through your applications
- 10.4" Dual Scan display
- Replace floppy w/ 2nd battery for 4-6 hrs. battery life

Processor	Screen	HD	Price
486DX2/66	10.4" Dual Scan	250MB	\$1969
486DX2/66	10.4" Duai Scan	340MB	2109
486DX2/66	10.4" Dual Scan	510MB	2259

AST, AST logo are trademarks of AST Research, Inc. All rights reserved.





ThinkPad 755C

ThinkPad 755CE, CSE & CD

- Built-in CD-ROM Drive (755CD models only)
- Built-in 16-bit sound, microphone, speaker (MIDI on 755 CD models)
- 10.4" Active (65K colors) & 10.4" Dual Scan
- 14.4 fax/modem, speaker phone, answering machine & voice mail
- Built-in infrared


	Processor	Streen	HD	Price
	486DX4/100	10.4" Dual Scan	340MB	S4099
	486DX4/100	10.4" Dual Scan	540MB	4449
	486DX4/100	10.4" Dual Scan	810MB	4899
	486DX4/100	10.4" Active	340MB	4999
k	486DX4/100	10.4" Active	540MB	5349
4	486DX4/100	10.4" Active	810MB	5799
Į	486DX4/100	10.4" Active	540MB	6349*
	4B6DX4/100	10.4" Active	810MB	6799"
D	*Fe	atures Built-In CD-R	OM drive	

More IBM® Notebooks

Processor Screen **IBM ThinkPad 360 & 360E** 486SL/33 8.4" Activ 8.4" Active 340MB \$1999 486DX2/50 9.5" Dual Scan 340MB 2699 9.5" Dual Scan 486DX2/50 540MB 3049 486DX2/50 8.4" Active **340MB** 3099 486DX2/50 **540MB** 8.4" Active

(5			
Processor	Screen	HD	Price
IBM Thi	nkPad® 70	1	
486DX2/50	10.4" Dual Scan	360MB	S3799
486DX2/50	10.4" Dual Scan	540MB	4149
486DX2/50	10.4" Active	360MB	4799
486DX2/50	10.4" Active	540MB	5149
486DX4/75	10.4" Dual Scan	360MB	4399
486DX4/75	10.4" Dual Scan	540MB	4749
486DX4/75	10.4" Active	360MB	5299
486DX4/75	10 4" Active	540MB	5649

COMPAQ



Contura 410

- Upgradable hard drive easily add more storage
- 32-bit local bus with 1MB video RAM
- Extended life NiMH battery technology Compaq, 3-year worldwide warranty

Processor	Screen	HD	Price
486DX2/50	9.5" Dual Scan	350MB	
486DX2/50	8.4" Active	350MB	



LTE Elite

- 10.4" Active Matrix display
- Fast 486DX4/75 processor
- Built-in AC adapter small, sleek design & reduced weight
- Upgradable hard drive easily add more storage

Processor	Screen	HD	Price
486DX4/75	9.5" Dual Scan	340MB	\$3129
486DX4/75	9.5" Dual Scan	510MB	3499
486DX4/75	10.4" Active	510MB	5029
486DX4/75	10.4" Active	810MB	5389
		By	te 6/95

HEWLETT® PACKARD

1019.99

More Hewlett-Packard Products

Processor	Screen	HD	Price
	niBook 6	00	
Notebo 486DX2/50	8.5" Dual Scan	170MB	S2549
486DX2/50	8.5" Dual Scan	260MB	2829
486DX4/75 486DX4/75	8.5" Dual Scan 8.5" Dual Scan	170MB 260MB	3099

HP LaserJet Printers
HP LaserJet 5P printer (IBM, 600dpi)
HP LaserJet 5MP printer (IBM&MAC, 600dpi)
1039.99 HP LaserJet 4L printer (IBM, 300dpi) \$499.99

HP LoserJet 4ML printer (IBM&MAC, 300dpi)

HP InkJet Printers HP DeskJet 320 printer (portable) \$299.99 HP DeskJet 320 printer w/feeder 359.99 HP DeskJet 540 printer HP DeskJet 560C printer 289.99 479.99 HP DeskJet 1200C printer 979.99 HP OfficeJet 769.99



HP OmniBook 4000 Notebook PC

HP OmniBook 4000

- 10.4" Active & 10.3" Dual Scan
- Built-in 16-bit sound, microphone & speaker
- Replace floppy w/ 2nd battery for 5-7 hrs. battery life
- Built-in infrared for no hassle printer connections


Processor	otreen	ND	Price
486DX2/50	10.3" Dual Scan	260MB	\$2499
486DX2/50	10.3" Dual Scan	340MB	2829
486DX2/50	10.3" Dual Scan	520MB	3199
486DX2/50	10.4" Active	340MB	3769
486DX2/50	10.4" Active	520MB	4129
486DX4/100	10.3" Dual Scan	340MB	3619
486DX4/100	10.3" Dual Scan	520MB	3999
486DX4/100	10.4" Active	340MB	4489
486DX4/100	10.4" Active	520MB	4829

More Brand Names, peripherals and software available. If you don't see it, CALL!

International 508-624-6400 Internet: sales@pcscompleat.com Open 24 Hours weekdays. 8am—8pm weekends and holido

Powerful PC

SCSI Adapters from MEDPT



A DPT PCI SCSI Host Adapter is the smart way to tap into the power of PCI. DPT outperforms every major competitor right out of the box, and you can add optional hardware caching and RAID for even more power and flexibility. So why choose anything else? DPT - the smart choice!

You may be eligible for our "ULTIMATE DEAL" - a 50% savings on our full line of high-performance ISA, EISA, & PCI products! Call today.

















Limited Time Offer: Get EAGLE 16-bit version for:

Including Layout, Schematic, and Autorouter Module

With EAGLE 3.0 you get 32-bit power and all the functions you need in a single, affordable program. It includes schematic capture, layout editor, 100% autorouter, DRC, ERC, drivers, and libraries — plus copper pouring. There are no hidden fees or charges for maintenance and support. We'll even supply a conversion program that lets you transfer your current program's netlists into EAGLE's layout editor.

Install EAGLE 3.0 on a 386 or higher and you'll be productive from day one — because we've also eliminated the complexity that makes competitive programs so frustrating and time-consuming.

Call for a FREE INFO DISK today, and discover why EAGLE 3.0 is a value that soars above the rest.

800-858-8355



CadSoft Computer, Inc., 801 S. Federal Highway, Delray Beach, FL 33483 FAX (407) 274-8218, Hotline (407) 274-8355 In Germany: FAX: +49 8635 920

All product names are trademarks of their respective organizations

ANY ADVERTISED



4901 Morena Blvd Suite 1111 San Diego, CA 92117

Fax (619) 581-1439 Customer Service (619) 581-0125

> MODE 7420

7540

7850

TOLL FREE

credit cards



Qualified Firms



Call Us for Unbeatable Prices! Pacific Coast Micro specializes

in all your storage needs...If you see it advertised at a lower price, we will BEAT IT!

Nor Warra	M M	apdor	•
SIZE	SPEED	TYPE	PRICE
.420MB	10MS	3.5 IDE	\$175
,540MB	11M\$	3.5° 10E	189
SSIME	11MS	3 5' IDE	249

A A STREET, SQUARE	sample of the best of the section of	Giornell & Galacta processors	Married Lagrange	
-	Mar Harra	CC	MAIS	R
CFS420A	420MB	12MS	3.5° IDE	\$175
CF5540A	540MB	11MS	3.5° IDE	189
CFA850A.	850MB	10MS	3.5° IDE	255
CFA1275	1.2768	10MS	3.5° IDE	365

	3	Ling Wal		B.	Seag	ate	
5	T3660	_545MB	121/	\$	3.5" 10	E	\$190
	T3780A	_730MB	10N	Spirmon	3.51.10	E	,239
	T31220A	1.0868	10N	Š įseislauses	3.5° ID	Ē,,,,,,,,,	34

	WESTERN DIGITAL			
MODEL	SIZE	SPEED	TYPE	PRICE
2420	425MB	12MS	3.5° IDE	\$175
2540	540MB	12MS	3.5° IDE	199
2700	730MB	10MS	3.5° IDE	232
2850	850MB	10MS	3.5' IDE	265
AC31000	1Gig	10MS	3.5° IDE	359
	- Lour Man	Our	entrum	

540MB		3.5° IDE	\$182
SCS	DR!	YES	3
CFF1060S			
	DATE HARRAC E, 7200 RPM,	AUG	499
1 mo unon			\$1049

LASER PRINTER MEMORY HPII, IID, IIP, III, IIIP, IIID, & IIIP+ 2mb 4mh HP IIIsi, 4, 4m, 4si, 4simx

HP Deskjet 500, 500C, 550C, 256K42
HP LJ 4L 1mb54
IBM 4019, 4019E 2mb112
IBM 4029 Series 2mb98
Panasonic 4410, 4430, 4420, 4450i 2mb92
4mb168

MOTHERBOAR

INTEL 486 VLB

3VL, 5 ISA Slots, Ami Bios, Opti Chip Set, Ziffsocket, 256 K-Cache, 4-30 PIN/3-72 PIN Sockets 486 DX-33\$219 486 DX2-66 265 486 DX4-100 375 486 DX w/o CPU..... 95

8-30 PIN Sockets.......109

8 ISA Slots, Ami Bios, Opti Chip Set, 256K Cache, upgradeable to 486 DX CPU's, 8-30 PIN Sockets, 486 DLC 40\$165

SUPER MICRO P60, P66

2mg to 128mg, 4-72 pin Simms, 512K Cache, 4 PCI, 2 Vesa, 5 ISA, 60, 66 Selectable 8½ *x13 586 P60.....\$539 586 P66.....545 Pentium Board w/o CPU .. 219

Byte Magazine -"Best Overall" and
PC Magazine "Editor's Choice Award"

I PC SANA

CONNER.

\$7949906

2mg to 128mg, 4-72 pin

1 Vesa, 5 ISA, 75, 90, 100,	
Selectable 8½ 'x13	
P75\$	599
P90	899
P1001	059
MB w/o CPU	279



on all

MEMORY PRODUCT

INSTALLATION GUIDES INCLUDED

1X3-70 838 1X9-70 840

4X9-70 **8130**

16X9-70 8678

1X36-70 \$158 2X36-70 \$318

4X36-70 **\$489** 8X36-70 \$1089



Cirrus Logic	SVGA VLB 1-2, 1M8 Upgradeable to 2M3\$85
DI	AMOND PRODUCTS
SpeedStar24x	ISA, max. 1024x768 NI, 72MHz, 24-bit, 16.7 mi. colors
SpeedStarVL	VL-Bus, 16 mt. WinMark, 1MB, 16.7 Mil. Colors, 72MHz119
ViperVLB	VL-Bus, 74MHz, 2MG VRAM, Weiteck P9000, 60 Million WinMark, 2MB299
Steath 64 PCI or VLB	2MB279
	4M8399

CONTROLLER BOARDS

Adaptec 1542CK-ISA, SCSI Controller......199

Adaptec 2742T-EISA, SCSI Controller289

Adaptec 2940 PCI/SCSI Controller260

IDE/IO card, 2s/1p/1g15

IDE/IO-VLB, 2s/1p/1g27

IDE/IO VLB Enhanced35

Promise DC4030VL-VLB.

Promise 2300+ ...

Q Logic ISA SCSI...

IDE Caching Controller...

FAX MODEMS

14.4 Internal	\$59
14.4 Internal w/voice	
U.S. Robotics Sportst	er
	14.4 External
	28.8 External234

CD ROMS MITSUMI

FX001DE Int., double speed, FX400 Quadspin......189

TEAC.

CD-55A, QUADSPIN, 195MS. 600KB Transfer rate\$199

NEC

NEC 3XCDR-510 195MS Triple Spin\$255

TOSHIBA

QUAD Internal XM3501B.... .\$319

EXTERNAL TXM3501E 150MG

Transfer rate 600KB.

BAATU CO.

DAINE BEE C	כטי
83D8733	S25
83D8740	33
8358733	29

CPUs

1486DX2-66	5169
1486DX-33	718
CX486DLC-40	49
CX486DLC-33	42
586 P60	405
586 P66	
586 P90	
ARC DVA 100	

TAPE DRIVES

Conner 420\$1	65
Colorado Jumbo 2501	32
Colorado Jumbo 3501	
DC2120 Tapes	15
Tracker 2502	69
Tracker 3503	29



DISCOVERY 16

Soundblaster 16. 2 Labtec Speakers Double Speed CD ROM. Aldus Photostvier. The New Groller MutiMedia Encyclopedia

CO Bonus Pack

MONITORS

MAE Innevision DX15F-1 15", 28DPI, NI, 60Khz, Flat, MPRII (110 volt)\$335 DX17F 17' .26DPI, NI, 60Khz. Flat, MPRII.....

MX15F 15', .28DPI, NI, 60Khz, Flat MPRII.

ViewSonic*

15G 15" Monitor 1280x1024 NI, 60Hz, 26DP1 ... 17G 17" Monitor

1280x1024 NI, 60Hz, .28DPI ... 20G 20" Monitor

1600x1280 NI, 76Hz, 28DPI

IMPRESSION

3 14" .28 NI 1024x768 \$219 5 15' .28 NI 1280x1024....325 7 17' .28 NI 1280x1024....569

LOW COST SHIPPING RATES AVAILABLE HOURS: MON-FRI 7AM-5:30PM P.S.T. SAT. 10AM-1:30PM P.S.T. IABLe - No cancellations on special order ligns - 20% Restocking fee on refunds within 30 days - No refunds after 30 days - Warranty replacement only - All prices linal - P

ofter 30 days - Warraety replacement only 95, 385, 387, 287, 486, 5X are trademarks of intel, Cor Circle 147 on Inquiry Card.

Finish Out Your Rack with a Magnum Commander

- Control up to 96 file servers with just 1 keyboard, monitor and mouse
- Supports all 100% IBM compatible PCs and PS/2 or serial mice; integral Sun and optional Macintosh support available
- 3.5 " unit is designed for 19, 23, and 24" rack applications
- Each unit controls up to 16 file servers; cascade up to 6 units
- Control all computers locally, remotely, or both
- AutoBoot[™] feature boots all computers without user intervention
- Push-button and keyboard controlled scanning standard
- Rear peripheral access available





COMMANDER™

Dealer Program Available

Cybex Corporation 4912 Research Drive Huntsville AL 35805 USA (205) 430-4000 (205) 430-4030 fax





IBM, PC, and PS/2 are registered trademarks of International Business Machines Corporation. Macintosh is a registered trademark of Apple Computer, Inc. Sun is a trademark of Sun Microsystems. Cybex, Commander, and AutoBoot are trademarks of Cybex Corporation.

IBM

(THINKPAD STOCK

T/PAD 755C 50MHz 4/540MB......3275 T/PAD 755C 75MHz 4/340MB......3509 T/PAD 755C 75MHz 4/540MB......3850 T/PAD 360CS 33MHz 4/340MB..special T/PAD 360CSE 50MHz 4/340MB....2398 T/PAD 360CSE 50MHz 4/540MB....2719 T/PAD 360CE 50MHz 4/340MB.....2760 T/PAD 360CE 50MHz 4/540MB.....3079

SPECIAL

T/PAD 755 CSE DX4/100 540MB....4099 T/PAD 755 CSE DX4/100 810MB....4499 T/PAD 755 CE DX4/100 540MB.....4899 T/PAD 755 CE DX4/100 810MB.....5350

will

beat

any

price

on

IBM

syste

ms

NEW RELEASE PC 300 DX2/50 4/270MB..... PC 300 DX2/66 4/270MB..... PC 300 DX2/66 8/540MB..... PC 330 P60 8/540MB PCI.... PC 700 P/9016/540MB scsi. PC 700 P/90 16/1GBMB scsi PC 700 P/75 16/1GBMB scsi PC 700 P/7516/1GBMB scsi.

SERV ERS PC SERVER 300 SERIES PC SERVER 500 SERIES... PS/2 MODELS PS/2 9577ANG 66. 8/527MB....

PS/2 9577ONF 66 8/400MB...

APPLE P/PC 6100/60MHz.....call [/PC 7100/66MHz.....call P/PC 8100/80MHz.....call

BRAND NAME LOW PRICES LEADER **SINCE 1983**

We export with international warranty

HEWLETT PACKARD

DESKJET 320.....290 HP 4+/4M+.1350/1835 **DESKJET 560C...450 DESKJET 540....275** HP 4SIMX.....4140 HP 4SI.....2789 HP 4V/4MV.1835/save HP 1200C.....939

1200 C/ps.....call SCAN JET IIcx..880 HP 4L/4P.....489/915 HP 3c(new).....call HP 5P....(new).....call HP 660..(new).....4551 *All printer S T O C K

HEWLETT PACKARD COMPUTERS

OMNIBOOK 600C DX2/50 & 75MHz 4/170/250MB.......CALL OMNIBOOK 4000CT DX4/100 8/340/520MB......save/4650 Desktops/Towers VECTRA VL2/50 4/210MB VECTRA VL2/66e 8/340MB VECTRA XU 5/90 8/540MB. VECTRA XI 5/90C 16/1GB scsi+matrox. VECTRA XI 5/100C 16/1GB acal+matrox. SERVERS

NETSERVER LC SERIES...... NETSERVER LF SERIES **NETSERVER LM SERIES....**

BUNDLE DISCOUNT COMPLET PACKAGE

CONTURA 410 DX2/50MHz

dos, windows, pcmcia, tabworks, built in mouse

410c 340MB Passive color \$2345 410cx 340MB Active color \$ 2799

NOVELL

3.12 5/10 user.....call 25/50 ueer.....oall

4.02 5/10 user......call

COMPAQ

Notebooks

	1101000000
	CONTURA AERO 4/25 170MB999
	CONTURA AERO 4/33C 170 / 2501499/1699
	CONTURA 410 C 4/340MB2299
	CONTURA 410CX 4/340MB2799
	LTE Lite 4/40C 4/170MB2299
	LTE Lite 4/40CX MHz 170/340MB
	LTE Lite 4/75 MHz 340MB4599
	LTE Lite 4/75 MHz 510MB4899
	NEW Prolinea Series(PCI)
	PROLINEA DX2/66 8/420MB1499
	PROLINEA DX4/100 8/420MB1699
	PROLINEA PENTIUM 75 8/420MB1899
	PROLINEA PENTIUM 90 16/7202899
	PROLINEA PENTIUM 100 16/7203099
	Deskpro XL
Ī	DeskPro XL 4/66M, 8/535 MBSPECIAL
ı	Darles VI FICAL OFFICE

Deskpro XL 5/60M 8/525MB.....SPECIAL Deskpro XL 5/90 16/1gb......3885 Deskpro XL 5/100MCALL SERVERS Prosignia VS SERIES. BUNDLE Prosignia 300 SERIES.....(NEW)... DISCOUNT

Prosignia 500 SERIES..... Prollant 1000 & 2000 SERIES...... Prollant 1500 SERIES...(NEW)...... Prollant 4000 SERIES..... Prollant 1000 RACK SERIES.. Proliant 2000 RACK SERIES Prollant 4000 RACK SERIES......

COMPLET **PACKAGE**

COMPAQ PROLINEA DX2/66 CDS

Mid Tower case ,8MB rarn,420MB hard disk, 1.44MB floppy frive, dos, windows, mouse, tabwork, Double speed CD Drive Speakers, Sound card, Ms Works, Ms Money, Ms Encarts, Ms Golf and lot of other titles, COMPAQ 14" SVGA Monitor .28 1024X788.

Authorized Serverice Center For IBM, COMPAQ, TOSHIBA & HP Systems, All Parts in S T O C K Also sell & Service AST, NEC & ALL OTHER DESKOP & NOTEBOOK SYSTEMS

TOSHIBA NOTEBOOK

T1910 486SX/33 4/200MB..... 1910CS 486SX/33 4/200MB..... T1960CS DX2/50 200MB/340MB T1960CT DX2/50 200MB/340MB T2400CS DX2/50 200MB/320MB T2400CT DX2/50 200MB/320MB. T2450CT 75MHz 320/540MB. T4850 75MHZ 8/510MB 810M. T4900 75MHZ 8/810MB. T2100 DX2/50 MHZ 320MB. T2100 DX2/50 MHz 320MB

All Models Stock Stock call for new LOW **PRICES** OLD MODELS ALSO AVAILABLE

MODEMS SUPRA 14.4 FAX.....79 SUPRA 282.8 Internal 199 HAYES 14.44.....call INTEL SATISFAXION.....call J.s. Robotics 14.4/28.8....call

HP TONER HP 4P/4.....95/102 HP 4I /4p.....63/63 HP Deskjet color.....27 HP 3SI/4SI.....115 HP Deskjet black......22

OPTICAL DRIVES IBM, HP, PINNACLE, SONY, fUJITSU, PANASONIC ETC.

PIONEER ""call for prices & delivery"

Memory & Hard Drives for Compaq ,IBM, AST, Toshiba Desktop/tower

4MB/8MB /16MB......165/399/645 Notebooks

4MB/8MB /16MB.....220/420/840 HARD DRIVE FOR NOTE BOOKS 250MB/340MB/540MB.,299/399/552

PCMCIA PRODUCTS PCMCIA **NETWORK** PCMCIA FAX+ PCMCIA DRIVES. **PCMCIA SOUND**

CD CHANGER Ploneer 2X 6Disk859 Ploneer 4X 18Disk......2050 CD ROM KITS S Diamond 5000 kit..... C Mdia Valon 1100 kit..... Creative Edutainkit.....425Trakker250/350... E NEC 2vdx klt..... CD ROM DRIVES NEC 2X/4X.....185/399 N IE SONY 2X/2X SCSI.....149.191 SOUND CARDS

M.vision 3D..... S.blaster ecsl..... Turtule Monterey..... **Tape Back-Up Drives** Jumbo 120/250..... 113/159 Jumbo 350/700... CONNER 420/850.....185/285 Power Tape 2GB......call. Wangtek 525/1GB...

PRINTERS OKI ML320/321.....299/425

OKI ML 590/591	
OKI OL410e/410	645/520
OKI 810/830	880/107
Epson Stylus	SAVE
Canon BJC 600C	
BOARD & DR	IVES
IBM SLC2/66+ mat co	180
IBM BLC3/75+ math o	
INTEL90MHzcpu+boa	ırd945
INTEL DX2/66cpu+ bi	pard 325
420/540MB DISK	185/199
850/1GB MB DISK	
2GB FAST SCSI	980
IGB FAST SCSI	
call for quantity disco-	unts.

Computerlane Inc.

Corporate Accounts Volume Discounts Welcome


Outside California: 1-800- 526- 3482

Inside California: 818-884-8644 • Fax: 818-884-8253

7500 Topanga Cyn Blvd, Canoga Park, Ca 91303 Hours: Monday - Friday: 9 - 6 Sat: 10 - 5

Compaq is A Registered Trademark Of Compaq. BM is A Registered Trademark Of International Business Machines. All Quoted Prices Reflect A 5% Cash Discount, Visa, MasterCard And American Express , Wire Transfer Also Accepted. Prices Subject To Change Without Notice.

SciTech SOFTWARE Sest Sellers FOR SCIENCE of great prices!



MICROSOFT® FORTRAN **POWERSTATION**

Develop & run Fortran programs of virtually any size & complexity with Microsoft FORTRAN PowerStation family of 32-bit development systems! Migrate Fortran code from other platforms with little ar na modification! Get unparalleled price/performance!

Save time in cade development and maintenance using the Windows integrated development environment. Call NOW to order or request a FREE Test Drive Kit!

DOS & Windows price									a	.\$349
Windows NT price	a		٠	٠			•	•		.\$519



MICROSOFT® VISUAL C++


If you program in C or C++ and use MS DOS®, Windows® or Windows NT™. Microsoft Visual C++™ (version 2.0) is THE product to use. Visual C++ features an optimizing compiler and a state-of-the-art Integrated Development Environment that includes a

project manager, incremental linking; just in time debugging; books online and a whole lat more! Get outstanding value by enrolling in the subscription program.

Single product price				•						.\$399
Subscription price		۰	-							.\$499

MAPLE V


Mathematical (numeric, symbolic, graphical) computation system with extensive progromming facilities, more than 2,500 functions, 2D/3D calor graphics and animation. Displays and prints in standard math notation. Used world-wide by engineers, scientists and mathematicians. Includes math coprocessor support.



DOS, Mac,	Windows	price	 \$549
UNIX price	2		 \$1,195



and grophing program. No programmina language to learn, no syntax errars to puzzle with. Enter equations with the built-in outliner. Point and click structures from the palette. Rearrange your equations by "dragging." Version 2.0



Windows, Mac price\$279



JMP®3.1

Statistical Discovery Software from SAS Institute, Inc.

Statistics is not just data reduction and analysis, it's data discovery. JMP's unique graphical approach to statistics allows you to see your data from many different perspectives quickly, easily, JMP's ever-growing list of statistical features includes: extensive linear and

nonlinear model fitting, including regression, ANOVA, MANOVA, and random effects models. Statistical quality control analysis, extensive survival analysis, and exclusive integrated design of experiments. Available for Windows 2nd Quarter '95 - Call.



Specialized tools for drawing chemical structures as well as powerful general-purpose drawing and text tools. You can organize ChemDraw structures with ChemFinder or transfer them to Chem3D for molecular modelina

•
Mac, Windows price\$399
Academic price
Student price



STANFORD GRAPHICS

With Stanford Graphics' Graph Gallery of 171 groph types, you'll always find the right groph for your technical data. Error bar charts, X-Y plats, bubble plats, histograms, 3D surfaces and contours, and curve fitting are just a few of the graph types available. Link your Excel, Lotus 1-2-3 or ASCII files directly into a powerful 4-dimensional spreadsheet.



Windows	price								•			.\$395
Windows	NT price						٠	٠		+		.\$695

To order or for more information call

1.800.622.3345

ask for our free 116-page catalog with more than 1,850 products!

> See us on the Internet! Our URL is http://www.scitechint.com/scitech/

SciTech Tel 312.486,9191, Fax 312.486,9234
Rasellers and 1.800.622.3320 for a Confidential Reseller fract List

Circle 144 on Inquiry Card.

SCIENTIFIC. **ENGINEERING** & TECHNICAL SOFTWARE IS OUR SPECIALTY.

GET EXPERT TECHNICAL SUPPORT **BEFORE YOU** BUY.

CALL FOR MORE INFOR-MATION & **FREE DEMO** DISKS.

EXCELLENT SERVICE IS OUR MOST IMPORTANT GOAL.

GET **PERSONAL ATTENTION EACH TIME** YOU CALL.

310-539-0019 FAX: 310-539-5844

Prices & Availability Subject to Change Without Notice

CALL

TOLL FREE


-800=433-(US and Canada)

ESTAR 1985 **HOW OPEN** Mon-Fri, 8:00 a.m. to 5:00 p.m. PST Sat. 10:00 a.m. to 12:00 noon

22825 Lockness Avenue • Torrance, CA 90501

CALL ABOUT **WINDOWS 95** VERSION

Remotely Control PCs over LANs, the Internet or Phone Lines with



AVALAN

TECHNOLOGY

P.O. BOX 6888

HOLLISTON, MA 01746

TEL: (508) 429-6482 FAX: (508) 429-3179

IN THE U.K. CALL:

TEL: 01460 57001

FAX: 01460 57060 E MAIL: 75300.255@ compuserve.com

E MAIL: sales@avalan.com

DATASOFT

HORTON HOUSE, DITTON STREET ILMINSTER, SOMERSET TA19 080

Powerful, Fuli-Featured. Easy to Use and Fast!

Outperforms ReachOut. pcAnywhere and Carbon Copyl

Runs over TCP/IP via Windows Sockets, over Netware, Netbios, or Windows LANs and via modem seriai ports!

100% Windows DLL - requires no DOS TSR!

Uses less than 200K of Windows memory!

Very low RAM and disk requirements!

Automatically matches video color systems and resolutions!





REMOTELY POSSIBLE / DIAL -

for home and travel. Supports over 200 modems up to 230.4Kbps including V.34. PCMCIA and ISDN adapters. NASI, INT 14 and Telebit ACS support. Licensed for 2 PCs. \$199

REMOTELY POSSIBLE / LAN -

supports all networks including Novell, Netware, Windows for Workgroups and Netbios. Includes one Dial version. Competitive licensing starting at \$599 (200 users per site), includes 1 FREE Dial version.



"Intelligent" Remote Control, File Transfer,

software for all environments!

Chat and Remote Printing - True Windows DLL

REMOTELY POSSIBLE screen redraws, program leunches and file transfers were each symple, speedy and a joy to use!

REMOTELY POSSIBLE / SOCKETS - supports TCP/IP

via Windows Sockets, works over SLIP, PPP and the Internet. Prices start at \$298 (1 Host and 1 Viewer); add-on packs available.

Speed Crown Award

Best Overall Quality Award Ease of Use Award InfoWorld

INTRODUCTORY OFFER! SOCKETS Version only \$99 (Save \$199!) (800) 441-2281



Cail today for free catalog

- Print servers
- ◆ Data switches
- Keyboard/video control

800-333-9343

P.O. Box 742571 ◆ Houston, Texas 77274 TEL 713/933-7673 ◆ FAX 713/933-0044

Access up to 256 CPU's from a single keyboard, monitor, and mouse. ServeView is our best-selling switch, has every feature you can imagine, and installs in minutes. Compare price, features, performance, quality, and support and you'll find Rose can't be beat.

Call us to discuss your application or to receive your free information kit.





EPU'S &

SIMM MODULES 30 PIN SIMM MODULES 100NS 80NS 70NS

256X9	59	\$12	\$15	\$17
IMEGX3		\$36	\$39	\$41
IMEG X 9	\$34	\$40	\$42	\$46
4MEGX8	-		\$124	
4MEG X 9		\$129	\$139	\$148
16 MEG X 9 (3	6 CHIP		\$668	
1011001110		ADD \$5.00		
	2 PIN SI			
	a Pile all			
512X36 2MEG		\$88	\$94	8012
1X32			\$148	
IX36 4MEG		\$148	\$176	\$198
2X32			\$288	
2X36 8MEG		\$302	\$308	\$378
4X32		-	5468	
4X36 16MEG		\$518	\$538	\$598
8X32				2070
		\$518	\$548	
8X36 32MEG			\$1175	\$1275
16X36 64MEG			\$2695	
			-	

1	P	J'	S	
ir	ŧ.	J		

IIIIQI	
	\$70
	590
	\$138
1	
֡	ine.

CPU DOUBLERS



52 Caompatible. Uses Industry Standard Mati Chip. Easy To Install - About 15 Hintest

Cx486DRx-16/32	\$198
Cx486DRx3-25/50	\$228
CH486DR+131/55	
Cx4865Rx3-25/50	\$228
486DLC40	
486DLC33	

COPROCESSORS

REDUCED	" inte	
	IIIIA	ı
386 MACHINES:		
387-16 1/8-12		4

80387-16MHz	\$21
80387-20MHz	
80387-25MHz	43
80387-33M9-fz	
90387DX	
80387-SX16	671
80387-SX20	
80387-SX33 80387SL	-30
8088 MACHINES:	
8067-3 SMHz	\$3
8087-2 8MHz	\$41
	571
80286 MACHINES	
00497 - F E E	51
90287-8MHz	52
80287-10 MHz	34
80287-XL	54
90287-XLT	\$71

		3	7	K.		
-	4		4			
	-	-	_		-	*

D-RAM CHIPS

ı						
	Type	120NS	IDONS	80NS	70NS	40NS
	64 X 4	\$2.25	\$2.45	\$2.95		
ŀ	256 X 1	\$1.85	\$2.40	\$3.00	\$3.15	\$3,20
ļ	256 X 4		\$5.45	\$5.95	\$6,45	\$6.95
ı	IMEG X I	\$4.40	\$4.90	\$5.75	\$6.45	\$6.75
Į	IMEGX4			\$26.00	\$29.00	\$34.00
l	256X16 YRA	M (WE)			\$49,00	
١	SEAVIA VEN	MICHE			#76 AA	

Call Toll Free

800-982-2925

For U.S. and Gasedian Orders only
HOURS! M-F 7AM-SPM / SAT TOAM-3PM PST 4131-50-73

TECHNICAL & CUSTOMER SERVICE CALL:
(793) 294-9204
PURCHASE ONDERS & INTERNATIONAL ORDERS
FAX TO: (792) 294-1168

-

IBM Me		022	,
MODEL ME AMBRA Enterprise 386, Huro		PART#	PRICE
Artoria Enterprise 300, Huro	2MB	N/A	593
	8148	NA	\$328
AMBRA Enterprise 486, Huro			-
	4118	NIA	\$198
	BM61	NA	3648
PS/1 and 386/SX (2121)	2118		\$88
***	4M8	9259694	\$198
PS/2 30/286;25/286; Adot Brd 1497259	SI2K	30F5348	\$35
Adpt ard 1477239	2MB	30F5360	\$98
PS/2 355X, LS, 405X,70-E61;			370
6450609; 34F3011; 34F3077,			P70.
55LS, 65LS X Station120 & 13			\$39
	2MB	6450604	\$94
PS2 50, 50Z, 55SX, 60, 65SX			\$198
	2-16MB		\$368
PS/I Consultant, Essentials &			, x44 &
PS/Valuepoint all models exce			*100
		96F9290 96F9291	\$198
PS/2 70-A21; A61; B21; B61; 1			
Expert models x11, x13 & x1			
exhere moners with wing at Mi-		6450603	539
	2MB		\$89
PS/2 355X; LS, 405X, 555X; L	5, 65SX;		
		34F2933	5198
PS/2 90 XP, 95 XP, P75 (Pairs			
PS/1 Pro 2123		6450902	\$88
PSZ 90, 95 XP; P75 (Pains) 56.	57, (all)	PS/I Com	ultant,
Essential, Expert x11; x13 & x			
6000		6450128	\$198
PS2/2 355X: LS: 405X		6450129	\$338
PS2 70's and 80's		6450605	5297
		34F3077	5775.
		34F3011	\$310
PS/2 80-A21; A31; A61	4MB	6451060	\$188
PS/2,80-041		6450375	\$78
PS/2 80-111; 311; 121; 321; 0			
		6450379	394
4010 RISC/6000(16MB) \$			1598,
4036(64Mi			
IBM Lapto			
Thinkpad 300, Ambra Treka			\$128
Thinkpad 350, 350C, 360, PS/		33G92B9	\$368
1 Halidaga 130' 238-6' 790' 6.26		6060378	\$330
	4110	0000310	

CHARGES SOOT SALES IN THE	GITID	23127400	3140
100	- BMB	33G9289	\$368
hinkpad 350, 350C, 360, PS/	NOTE		
		6060378	\$330
	16149	6060379	\$647.
hinkpad 500, \$10CS, 2618	4P4B	8189098	\$198
	BMB	8189099	\$398
	16MB		5848
1.57500	4MB	07G1420	\$208
hinkpad 700, 700C, 720, 720	C. 750		
		07G1421	\$376
		6665109	\$89E
No. 2			TRIAN

	8M8	07G1421	\$378
	16MB	6645109	\$896
Thinkpad 710T	4145	N/A	\$188
	8148	N/A	\$31E
P5/Note N45SL	2MB	92F8804	\$106
PS/2, N51, SLC, SX	2M8	07G1826	-376
	4MB	07G1827	\$188
	8MB	07G1828	541E
Laptop N33SX, L40SX & PSN	NOTE II	92	
	2MB	7950999	\$98
	4MB	79F1000	\$184
L40SXL PSNOTE 182 ONLY	8MB	79F1001	\$358

MEMORY

MODEL#	MEMORY	PARTH	RICE
PREMIMIA	4MB	501159-001	\$188
	8M8	501159-002	\$368
	16MB	501159-003	\$768
ADVANTAGE 386SX/	20:25, PRO 5	X/25 BRAVO	3/335
	2MB	500962-001	\$88
	8MB	500962-002	·\$348
BRAVO NB486	4MB		\$198
72.15	16MB		\$798
ADVANTAGE PRO 48	6DX/33:5X/7	25. BRAVO LE	
255: 33: 335: 50D: 4'66		500987-00E	588
		500987-002	\$164
	16118	500987-004	\$578
DESCRIPTION OF THE PARTY AND IN	THE MARKET		100000

PREMIUM 386/25; 33: 33T II 386SX/		\$57
	500780-003	\$4
ADVANTAGE 486/25: 33.33P5X20	500780-002	\$4
25. PREMIUM 4/25, 33TE, SE 4/332N	18500718-004	
2MB	500780-005	\$61

	2148	500780-005	368
ADVANTAGE 486/25:33:33P	SX20.	POWER PRE	MUM
3/33.4 33: 335: 50D:66D: PRE	MIUM	386/33TE. 48	6'25:E
25TE: 33: 33TE PREMJUM # 3	186/25	: 33, 486/33,	4E6SX/
20PREMIUM SERVER SE 4/13	4MB	500780-004	\$178
	8MB	500780-001	\$398
AST LO	PIC	P	****
The second secon			

POWER EXEC 3/255I	3/255L C.EL	
	474B	\$178
	16MB	\$768
POWER EXEC 4/25SI	/33SL 4MB	\$178
	16MB	\$688
PREMIUM EXEC 286.	386SX/20:25:25C	
	4MB	\$178
BRAVO NB486	4848	8812
	16148	\$668

IG; UPS (19n. \$1.25) Shipping charges a d. COO and \$5.00 (Cadhirra check) CO

Compa	q Me	mory
MODEL PRICE	MEMORY	PART#
Deskpro 286E; 386-20	20E: 25: 25E	
, , , , , , , , , , , , , , , , , , , ,	IMB	113131-001 \$59
and the same	4M8	113132-001 \$188
Deskpro 386S	4MB Board	113634-001 \$254
Deskpro 386-20E; 258	4MB Module 4MB	112534-001 \$188 113645-001 \$238
Deskpro 386/33/33t: 4		
	2148	115144-001 \$108
	8M8	116561-001 \$378
(1900)	32148	116568-001\$1458
Systempro; Designo	6 SKT BRD W/2MB	116569-001 \$268
Coniced MF	2-64MB	129160-001 \$188
Deskpro 286N; 386N;		
Deskipro M. Systempe		
Signia		
	2MB	118689-001 \$84
	4MB 8MB	118690-001 \$168
Prolina 3/25 & 25Z	2148	141738-001 \$88
	8118	141742-001 \$318
Prolina 4/25si, 4/33, 4/		141683-001 \$94
	4MB Module	
	8MB Modulé	141685-001 \$338
Compaq Pro Signia	16MS -32MS	149320-001 \$684 149147-001\$1524
DeskPro 5/60, 5/66M	8MB	149911-001 \$388
Prosignia PC Server, 4		
4.0	EMAI	149320-001 \$648
1. 1.15	32MB	149147-001\$1498
Prosignia 5/60	16MB	149949-001 \$698
Proliant 100 5/60 Proliant 2000 4/30, 5/6	32MB 6 64MB	149912-00151398
Profant 4000 4/50, 5/6		149914-00154495
Compag La		
Concerno 486	4148	8812
	8118	\$358
	16668	\$698
Concurs 220, 325, C	27-18	139497-001 598
	4MB	139498-001 \$174
Contura 4/25CX	801B 401B	139499-001 \$318
CONTRACT TRESCA	8748	146521-001 \$338
0.00	16MB	146532-001 \$718
5LT/286	IMB	110235-001 \$75
Secretary 1997	4MB	110237-003 \$218
SUT386	IM8	[18303-00] \$79 [18304-00] \$108
	4118	118304-001 \$108 118305-001 \$198
Lco 286	(MB	117081-001 \$79
Carl College	2MB	117061-002 \$99
	4118	117081-004 \$178
Lee 386\$/20	IMB	[2] [25-00] \$98
Les Lice/20, 25, 25C	4M8 2M8	121125-002 \$208

129769-003 \$388 129769-004 \$808 129769-004 \$808 142337-002 \$178 142337-004 \$718 142337-004 \$718 190532-001 \$188 190597-001 \$358 **Laser Printer** Memory

BT18 16MB 4MB 8MB 16MB 4MB 8MB

LTE Lin 486/25C Auro Livole

HODULE	IMB	2748	3968.	448	SHE	2118
Canon LBP4, 4 Liss # 44		Site.				
Canon LBP-430		3178	1	3154		
Epson Action Later	23.	. \$1.40.	1973	-112		
II. 8000	400		dibo		5308	
Epson + 6000 and		320		1	100	
many more		4128	2.00	Camp.		
Eoson Action		9) 44		9130		
Laser 1000 & 1500		\$98	- 5	\$188		399
Fullow 7100		470.		3100	•	277
A 7200	6195	\$279				
HP Deskler 500.	****	40.				
500C, \$10, 550C						
and 560	\$18 /	256K)				
HP 2, 2D		\$78		5164		
HP 3, 3D, 3P, 2P,						
2P+		598		8812		
HP Laser Jet 4, 35L		-		4,00		
XL300, 1200C		\$84		S168	4	318
IBM Laser 4019.				-		
4019E (3.5MB)		\$114		\$164		
IBM Laser 4029		\$95		\$155		
NEC 90, 290		\$104				
NEC 95	588					
OKI 400	\$68	588				
Packard Ball PB9500	-	\$125		\$208		
Panasonic 4410/4430		\$118		\$174		
Parasonic 4420/4450		\$118		\$178	- 24	
Panasonic 4450		\$98			18	500
Parasonic 4400/5400		\$129		\$198		100
QMS 410		\$119	\$159		249	
Tosiba Page Laser 6		\$99		\$168		
TI XL/PS17/PS35		844	\$98			
rchee arders from University	os. Fore					-

\$198

In Touch with Tomorrow TOSHIBA Toshiba Memory

Inalling	N.H.C.III		
MODEL	MEMORY	PARTE	
PRICE			
T1000 SE/LE/XE		DI1EBA9	
T1000 SE/LE/XE		PA8312U	
T2000 / T2000SX		PASS17U	
T2000SX/T1000 LE		PA8314U	
	BMB	PA8315U	\$358
T1200 XE	2MB	PAB306U	598
T1600	2MB	PA8302U	\$98
T2000 SXE/T2200SX/T18	00 T1850, C		
		PA2000U	
	4MB	PA2001U	\$198
		PA2002U	
T2400, T2450, T3600 3.3\	/ 4MB	PA2019U	\$218
	8MB	PA2020U	\$398
	IAMB	PA2023U	\$798
T3100		PA7135E	
T3100 E	2MB	PASSHIU	\$108
T3100 SX	2MB	PA8306U	\$108
		PA8310U	
T3200 SX		PA8307U	
		PA8309U	
T3200 SXC		PA8318U	
		PA8319U	
T3200		PATI37U	
T3300SL		PA2006U	
		PA2007U	
		PA2008U	
		PA2009U	
T3400CT		PA2019V	
		PA2020V	
		PAZ02IV	
T4400 SX, SXC, T6400 SX	C. DXC		
4 1 1 1		PA2003U	\$125
		PA2004U	
		PA2005U	
		PAZOIOU	
	32/48		1546
T4500, T4600, T1900C		PA2012U	219
(3.3VOLTS) T4700		PA2013U	
The state of the s		PA2014U	
T3100		PA630IU	
T3200/T5200C/T8500/TS		PA8304U	
- Darwin Community Colour 10		DELEGAN	
MARIAN I			2710
MAJOR			
NOTEBOO	KME	MOR	Y
	ÉMORY.		
Acer New (All models)	4218		\$238

MODEL	MEMOR	Y PARTWE	RICE
Acer Nace (All models)	4218		\$238
	8148	Charles and	\$438
Canon Notejez 486	4fm		\$238
All stories	8148		\$418
Deli 320N, 212N	2148		\$98
NL25, NL20			
Dell Listoide	4MB		5198
	16MB		\$698
Dec Notebook 425/433	4418		\$198
	16MB		\$798
Epson Action Note	ZMB		\$122
	4148		\$218
Everex Tempo LX, LX20	2MB	.00160	\$98
Gattiway 2000	4MB		\$188
decaust 4000	16MB		\$1475
Gatiway 2000 486	4MB		\$188
GB(BHB) 2000 100	16MB		5781
HP Omnbook	2MB		296
TO CHIRICOUN	4MB		\$708
Packard Bell, Planswoon, Plicab		NIA	\$108
	4118		\$198
Panasonic CF170/270/374		CE-BA165	\$64
Pantsonic CESSO, V21P, V41	4MB		5218
	16118		3896
Sargo 17NB; 18NB & ZEOS		MBC-NBMEM2	
SHARP PC-7700, 7750	4MB	The Item Item	\$198
8150, 8650; 8660	I 6MB		\$698
SHARP PCB501	2MB		\$108
Ti Travelmate 2000	IMB	2568034-0011	588
TI Travelnam 1000SC WIND		2566996-0001	
Ti Travelmate 4000,			
WINDX/25 5X/16, 5X25	4948	2581245-001	\$188
DX2/50, DX2/40	16948	AVAILABLE	
	-		

CACHE MEMORY

BOXB #2ms	15ns	20ms	2.5ms
12X8 12.00	1.05	7.75	6.55
64x1	10.95	7.05	6.95
64x4	10.00	7.95	6.95
16x4	6.95	6.45	5.95
128x8	54.00	34.00	27.00
David Bergman		56 1 3 1 C. W	





RACK MOUNT PC SYSTEMS & ENCLOSURES

MULTIPLE DRIVE COMPUTER SYSTEMS AND ENCLOSURES



- ◆ Computers available with '386, '486, or Pentium processors
- ◆ 8 or 12 slots for Motherboards or passive backplanes
- ◆ All drive bays are shock mounted
- Accomodates full height & full length cards
- · Card retainer to firmly hold plug-in cards
- ◆ 250W power supply w/ front panel on/off switch
- ◆ Front panel keylock/reset switches & LED status displays

DC 24V and 48V power supplies available for systems & enclosures



SYSTEMS WITH 9" MONO & 10" SVGA COLOR MONITORS

- ◆ Computers available with '386, '486, or Pentium processors
- ♦ 8 or 12 slots for motherboards or passive backplanes
- ◆ Shock Mounted cage for three half-height front panel drives
- ◆ Internal hard drive bracket holds two half-height drives
- ◆ 9" MONO or 10" SVGA color monitors with front panel controls
- ◆ 250W power supply with front panel ON/OFF switch
- ◆ Front panel keylock/reset switches and LED status displays



Available in both 20" and 24" deep models



- 9" MONO & 10" SVGA color monitors
- ◆ Tinted Lexan shield for screen protection
- Power, Contrast & Brightness controls in front

RACK MOUNT MONITORS



- ◆ 14" SVGA & Multi-Sync color monitors
- Automatic degaussing
- · Standard 15-pin input connector



- ◆ 17" Ultra VGA 0.26 dot pitch color monitor
- Microprocessor controlled digital adjustments
- ◆ Energy-Star & MPR-II compliant



Call us for quotes on custom rack mount systems!

Ask us about Passive Backplanes and open-frame monitors!

RACK MOUNT KEYBOARDS AND ENCLOSURES



- Vertical rack mount or desktop
- Sealed membrane 101 kevs
- ◆ Selectable on/off audible tone
- XT or AT operation



- ◆ 101 K/B with mouse holder
- ◆ Full travel (4mm) keys
- Optional protective cover



- Standard 101 keyboard enclosure
- ◆ Storage space for K/B and mouse
- ◆ Slides for rack included

RACK MOUNT PRINTER



- ◆ Microline 184T dot matrix printer
- ◆ IBM compatible graphics characters
- ◆ All operator controls easily accessible
- Large storage for roll or fanfold paper
- Standard IBM parallel printer interface
- · Serial printer interface also available
- · Slides, power & signal cables included

In both

UniMod™ MODULAR COMPUTER SYSTEMS



- ◆ Independent self-contained 4 or 8 slot computer modules
- ◆ Individual module power supply and filtered cooling fan
- ◆ Available with '386 or '486 CPU's & various memory & hard drive sizes
- ◆ 7" TTL Mono or 7" VGA color or mono monitors available for further flexibility
- ◆ Multiple configurations can be combined in 7 inches of vertical rack space
- ◆ Available with either AC or DC power supplies

Call us for UniMod™ combinations and quotes

RECORTEC, INC.

1290 Lawrence Station Road, Sunnyvale CA 94089 Tel: (408) 734-1290 Fax: (408) 734-2140 RACKFAX™
(408) 734-9374
Fax-On-Demand System

800-729-7654


Call for free catalog





OVERNMENT, EDUCATIONAL, CORPO & INTERNATIONAL ORDER SPECIALI OGSO EXPRESS International Order Line
4640 EXPRESS Technical Support
0116 EXPRESS FAX: Domestic - International
6579 EXPRESS Order Line - TOLL FREE
ed to serving Purchasing Agents Worldwide
Foved Open Accounts for all Fortune 2000 WEST COLUMN **NO SURCHARGE**

CPU'S



. .

CACHE MEMORY

Serving you since 1979 JDR Microdevices *** **The control of the control of th

1850 SOUTH 10TH STREET, SAN JOSE CA 95112-4108



\$58,67

Special Prices Byte Buyers! Good Through 8/31/95

To receive these special prices, you must mention key code #1066

FREE JDR CATALOGS!

Fax/Modem/Phone Switch

Considering a separate phone line for your fax machine? Get a fax switch instead and save money! This fax switch lets you use just one telephone line for your phone, fax, modem and answering machine.

- Accepts tone or pulse access codes
- . User-programmable access codes and ring counter to control junk faxes

FAXM-SWITCH \$89.95

MCT's new internal 14,400 bps modem features voice capability, providing nine voice mail boxes, fax on demand, system access plus standard fax and data capabilities

14,400 bps Fax/Modem

IAL FOR BYTE CUSTOMERS ONLY!

AND ELECTRONIC COMPONENTS

PC PRODUCTS

CALL **TOLL-FREE**

1-800-538-5000



VESA Local Bus 486 Motherboards

These motherboards combine the power of the Intel 486 CPU with the performance of the VESA Local Bus.

- 100MHz Intel 80486DX4, 66MHz Intel 80486DX2 or 33MHz Intel 80486DX CPU with OPTi chip set
- Accepts four 256K x 9, 1M x 9 or 4M x 9 70ns 30-pin SIMMs and up to three 256K x 36, 512K x 36, 1M x 36, 2M x 36, 4M x 36 or 16M x 36 70ns 72-pin SIMMs totalling up to 128Mb

MCT-M486V-100	100MHz 486DX4	\$499.95
MCT-M486V-66	66MHz 486DX2	\$349.95
MCT-M486V-33	33MHz 486DX	\$249.95



SIP & SIMM Converters

Make use of your SIP or SIMM investment with these converters. All you need to do is make sure they are fast enough for your application.

SIP2SIMM S8.95
Converts 30-pin SIP devices into SIMMs
JH004T \$44.95 Converts four 30-pin SIMMs to one 2.1" high 72-pin SIMM
JH006T \$44.95
Four 30-pin SIMMs to one 1.3' high 72-pin SIMM, low profile
JH109T \$69.95 Converts eight 30-pin SIMMs to one 3.2" high 72-pin SIMM

OverDrive™ Processors

BOXDX40DP100
BOXDX40DPR100 \$289.95 Replaces 33MHz 486SX or 486DX CPU
80XDX40DP75 \$219.95 Plugs into 25MHz 486SX or 486DX
BOXDX40DPR75
BOXDX20DP-66 \$159.95 Plugs into 33MHz 486SX or 486DX
BOXDX20DPR-66\$159.95 Replaces 33MHz 486SX or 486DX CPU



JDR Price Guarantee

If you purchased any item from JDR Microdevices in the last 30 days and we've lowered our price, call us with the details and we'll promptly refund the difference

Dynamic RAM

DUE TO CURRENT MARKET CONDITIONS, CALL FOR CURRENT DRAM PRICES!

Part #	Size	Speed	Туре	Price
1MX9-80X3	1M x 9	80ns	SIMM	44.95
1MX9-60X3	1M X 9	60ns	SIMM	46.95
4MX9-80X9	4M X 9	80ns	SIMM	135.29
SPECIAL FOR E	YTE CUSTO	MERS ONLY	1	
16MX9-70X9	16M x 9	70ns	SIMM	699.00
1MX36-70	1M x 36	70ns	SIMM	184.95
2MX36-70	2M x 36	70ns	SIMM	379.95
4MX36-70	4M x 36	70ns	SIMM	619.00

Seagate Hard Drives

Upgrade to a new, high-quality, high-capacity Seagate hard drive.

	545Mb 14ms 120Kb IDE-Fast ATA	193.47
ST-5850A ST-31220A	850Mb, 11ms, 256Kb, IDE-Fast ATA	479.95
ST-5660N ST-31230N ST-32430N	545Mb, 12ms, 256Kb, Fast SCSI-2	569.00
ST-32550N ST-15150N	2.1Gb, 9ms, 512Kb, Fast SCSI-2	1249.00



Quad-Speed CD-ROM


This internal CD-ROM drive makes multimedia affordable

- 16-bit PC compatible IDE drive
- . 5-1/4" internal drive is MPC, Multisession Photo CD, High Sierra and ISO 9660 compatible

OROMI-4.

Connect 16 PCs to 1 Printer

Plug one transmitter in each of up to 16 PC compatible parallel printer ports.



- . Transfers up to 11,000 characters per second
- · Time-out independently adjustable on each transmitter to 5, 15 or 30 seconds

CEXT	Transmitter for PC	\$39.95
	Receiver for printer	\$38 95

16-Bit Sound Card

This low-cost sound card produces reduced-distortion 16-bit sound for CD-quality recording and reproduction.



. 16-bit PC compatible ISA card . 8/16-bit selectable stereo & mono sampling rates to 48KHz

4 watt per channel output using 4 ohm speakers


VGA to TV Conver

Use your big screen TV to play your favorite PC games, rather than your small VGA monitor!

- · Resolution up to 640 x 480 in 256 colors
- Composite NTSC output using RCA socket and using female S-Video connector







24-Hours-A-Day Local/International



FIRST SOURCE R MEMO

ALL YOU NEED TO KNOW IS THE NAME OF YOUR PC!

Our upgrade experte have detailed configuration information on thousands of computers and printers, from the oldest to the latest models. We provide you with an "Easy Upgrade" by providing you with the following information:

- 1. Your System Memory Features 2. How Much Memory You Really Need 3. Memory Products Available for Your System
- 4. The Most Cost Effective Upgrade Path for Your System 5. Your Systems Minimum and Maximum Memory Capabilities

First Source International takes the confusion out of your memory purchase. Take advantage of our service and the savings!

PERSONAL COMPUTER

AST COMPAQ HEWLETT-PACKARD	IBIVI
🖶 Premiuma GV, Prison, Prison	
will an area of the least and the second and the se	\$134 HAB H72 \$500
CUB foliation 5100" 6408 foliation of 1999 MARLET COM 5544 CUB 14755000 51619 ON 110744 5179 ON 110744 5466 64 Chapter 65	
Presented ATTE 56: 2510 509 1238 123974 5000 5152 618	74(129) 5276
total authorities 21 auth and labella 21 authorities 21 authoritie	ad 50 mindels
through all sing all design and the contract that the contract and the distance of the public and the contract at	51% tissel incores 55-re
17. 18 18 18 18 18 18 18 18 18 18 18 18 18	
and analytically and due desired all and all all and all all and all all all and all all all all all all all all all al	SHE INB HIPPING STATE
Brate 1/2% AUS 121764 5177 WHI DATE WALL THE PARTY	
Trill offi 10 100 Set 10 M 40 1000 2 10 4 10 10 10 10 10 10 10 10 10 10 10 10 10	\$179 KB 257(3) 15in
Administry Plan (4017/14 187-14) 187-140 187-1	nentral Expert models vet, vet
\$13 401164-001 5250 5738 403824-001 530, with	residely except CXX models
PAY BASIST, THE BASIS THE	4693.90 11
time analysis on home analysis 25.5	9619291 5609
Advantage Pers 4884 XXA & XX24	sserital. Expert mustels
Boson ULLUIT DE BON ULLUIT DE	Metal at 1 september 1 septemb
" the server on 1 254 4750 error on 2141	
19-71 and 24-10 (218) 400-04, 104- 2100 and 19-71 and 19	
Promition 90/25, 33, 547 and Prenstant II 50/55/16, 20, 25	KNTS VIO 5°N
	manus 6" at 3724 at 3764 305 x
Littlem and 18 April 10 Test 11 April 15 Test 10 Test	FeStation 300°
408 407 90404 519 1 X 3-70ns (3-dip/1MB). 36. 512 x 36-70ns (2MB)	521 Biol Ps/Valuquest to mylife
Aluenes - PVI Cartellani	sential Exect models
Proof Promas and Promasa TE all models 1 a. A. "One distant 1 a. A. "One distant 1 a. A. "One distant 1 a. A. The distant 1 a.	14 SOLOR 4040S pet
Philipson I and the second sec	ma92 23 26% At 7287 A

	AFNGAFIUT SIM
16 x 9-70ns (16xB) 365 4 x 36-70ns (16xB) 498 Instructional Instructional Post (SAL IS, 40	
Company of the control of the contro	
Described and Lot Books the second of the State of the St	PF4 (point) \$6.4" (all) PS4 Pm 112424
AND 100 CO.	\$10 SEPTED
1/310 Ha his case 16-6(20) 66-6(1) 66-	PTS (pure) St. 37 Lill (midcle)
Proceed to a substants of the analysis and the substants of the substant of the substants of the substant of the subst	ssential Expert models, PS/I Pm/1/2121
110 410 240 594 410 110-265 110 410 61-0128	\$169 XVIII 669030 5336
MIN CITY AND CITY 150 AND 150 AND CITY 180 AND 150 AND	[2] 42] del [6]
Performance 11 consists	114505772 5000
WARM THE THE THE TANK	436
[67][6] [125] 5549 (Second State St. 72)	6-4-210PD (1-6-1)
ZENITH PROGRAM Series 400-14 TEXTON MARIA normals and allowers first	fer 15v 1 1602% leaved models
2 die Zhanke Sh Sk de hit had be let and be	ha filtrem (the "Legan" > 500
2 th an an an 2 ch 57 2 255 2 245 m 51	
THE TAX TOO STY 15/18 THE 19 GALLY WITH THE TAX PROPERTY AND THE TAX PRO	THE RESIDENCE AND ADDRESS.
	for PS-2 90 000 Front models
24B 1956+1-001 5100 Panythin 900 CE 214B + 24B	topicon 520 +
Anna Harding San Art Asset 26	topicon 520 +
A control to the state of the s	topicon 520 +

							_						
Canon USP-4					A	ST		TEXAS IN	STRUME	NTS	CON	PAQ	
1396 074	5834	2118	19/3.	S159 W	Secrettia Milan, Stiller	+3384	SINS	TravelNate 4000 tall model	() IMB .	579	Existers Arro 4/25, 4/15c	4318	517)
Canco LBP-NI TIR	III					RT1B	5407	Tensel Vate 4000 tall model	801- 14	\$100		11.525	\$391
1//B	564- MI			5159		16/IB	56674		\$6128	5091	6 Europete 1/25, 4/45	4315	51"5
Etwen School poor 37	100. 150P				Acerdia Willia Milita	4135	5,305	Travelliate +Ontil), Foto	62(18)	,8194		COL	5165
\$1.55 mu	545	21/25	15.731	600		SUIR	5,590		10113	\$791	Contain USI VIS USC	438	\$140
Envir VotenLaws 1	195					1973B	56:051			_		131%	5,398
2016 reca	5105	4HIS	Info.	5150	Box n \B (Rt)	431E	4114	30000	V		debunille silinish	+119	\$1207
Low is School aury III		1-40				TATIN.	2.639	1 WH	Y ADD			83/8	5865
sNB mix	5.91	Elfa!	D'A	SHOP	America with the Ma	4738	313%			NA.		M	4-01
HP Loverlet 48.	3 -4	100.070	10 %	Ja al		16/1B	100	MORE /	NEMOR		C 16683 4 25 44250, 4 250	10	3.169
1183	02024%			Sell	Printer of Park	11/B	5104				C 1889 4 7 4 7 CC 4 7 4	2010	5,296
Mr Levelet 117 111 1				7401	VERSEAL EL	16/48	28/24		10140			19770	56.55
2505 554750	912	.1+D	15a B	SEMI	Proposition Edge.	4119	1140				GS CTÚ EUR	43/8	51"e
112 Laverlet () (10)	2.14	4.40	150 D	25501	MMV2F25, 24						THE PARTY OF THE P	831B	5115
Dis steed	.994	140	to tra	\$160	11	3M		62 ESJ	1			164B	5114
			(See 4)	21643	ThinkPad 259	4148	5,140				make by the See See		
IP Livetet (thy a d				42.	ThinkPad 2005	367 Ets	5107	AT			THE 19th 30 TH 295 SHE	4718	5 339
4381 (2063). 4381 (2063)	5 68		C.306+1	694	Third.Pad 300	MIB	55,09	*				10,19	6149
	5174		C2068A	5440	Think Paul 460 465 440 740	4/1B	5168	DEDE	DRMANCE			10718	5,34
📂 HP Liserlet 49: 4312						STATE	5 874	*	MININE		LTE Line 4 15c	4758	9 EM2
2018 L \$141A			1.41474	3174		16378	se-Lt	d 4 5	10 10	347		SQBI	\$ 694
🕶 IRP Residen form form		440E	507 4648		Thinkind 410	PATE PATE	\$194 \$150	Mant amilianti	ons run satisfac		1.00	14.268	54+19
164	13.8.8			5-0	DunkPad '00 "30 "55	BLE.	\$199				TOS	HIBA	
IBNI rumark Luce					and (2.575)	513B	5579		rut in the long ru	17	1,300 30065\. Slie	a LEB	\$16"
258 (04m24	1100		104114.	516"	Market A 16.5	16MB	5144	16MB is	recommended		TABLES V. TERROS Series	80703	157
IRUnamed Law-						12348	\$1,991				## T2400 T2496 2100 2290	45°28	5194
inti therer	585"		1064444	2120	Throid's	93E5	6979	"Henry alon, Wider				1949	5640
1894 Leverant Lawr						KNB	5415	"I Reducts your system's r			TEMPO FROM TRUM	red.	CW.
400 10000	\$1¢"	RUB	1439465	5319	149 Solebook	23/0	594	"I Wilce numerous & exte	ecoive applications at the so	other facine	THOUSA CHEST, SM.	23/08	5185
Olla aver 400						4728	\$170					+165	514"
ווד-וטל מווו	53/4	2318	tiv.t	50	THORY FIRST PROPERTY.	41/B	5114				144084	45	717
🖮 tikli per sitir. (Dr						sun	1291		NEC			47.28	100
TAN BAT	5117	4.UB	rich.	497	ZEI	HTIV	4	Average A	4,1B	\$141	Then Then	435B	5184
Old per 810, 810 Pl					Z-Acay 1501 to 127L	2500	544		NAB	2014		5-7214	5448
2VIB 1V2	3114		LA,T	2333		3030	5391	8 Insulate Serva S. SE P.	437B	83:01	iddean Sci Ohell Site	4/28	915
Partisonic Liberthirt					Z Nati 424 Series	47/12/15/5/5/1	3157		WHB	314	1 4 3 4 1 1 7 1 4 1 2 1 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1	NVB	5.539
TAR MY-LAI	2110		KT-PETT3	5204		#\$IB (4.5.5)	sun	fixed as 188 in 189	16540 (4.45)	5613		(618	5645
Parawelic LavePart				Wheel	2-sp.et 4,00x 4,55x	43/03	5 (30)	month at a 150	2/18	188	Tisky Taker Tools	43-35 (3-5.5)	51100
JAIR AND HA	2114	+14	15/2.	3,130	Z-apart 1355	4513	61/44		6/10	\$129	Ta'TO TAND TAND	WHILE \$ \$ \$ \$	5549
Panasonic Laserburt				Audi	Material Miss Stat State	25111	7,761	A Brown of a March and a Mellin	BUS	\$440	T4400	1640 13 13 1	2,10
2/8 (2-P-H		4/25	N.A.	\$\$16"	Materials Media	23.28	3315	1 Bord and 50,720 NO.2019	412B	582 675,4	TSAUT TSAUT TSAUT THEOR	2518	2.10
Tesus Instruments V	PERFECTION A			žel .	2 4	2VB	5504	Acres 50 - \$800.16	418	25.00	(1981) (128) 1528 1790)	7,18	et.

Call the Upgrade Experts ORDER TODAY! 8



WE SET THE STANDARD!

100% GUARANTEED

Memory Guaranteed - 100% Compatible in form, fit & function

LIFETIME WARRANTY

On all Paragon Memory products

EASY TO INSTALL

All products user installable, installation instructions included with most memory products

FREE SUPPORT

Free technical support & direct dial lines for immediate response

SPECIAL PRICING

Government & educational pricing, special volume pricing

PLUS . . .

Overnight delivery available No surcharge on credit cards Corporate PO's, APO/FPO's welcome

WHY SETTLE **FOR LESS!**





HOURS

Monday - Friday • 7am - 5pm, PST Saturday, 9am - 3pm (orders out)



MAIL OR FAX ORDERS TO:

(714) 448-7750 • FAX: (714) 448-7 Compuserve Address: MHS:SALES@1SOURCE First Source International 7 Journey • Aliso Viejo, California 92656




Circle 208 on Inquiry Card (RESELLERS: 209).









CONTROL **ALL YOUR PC SERVERS**

FROM ONE KEYBOARD, MONITOR AND MOUSE



with MasterConsole®

COMPARE QUALITY AND PRICE PERFORMANCE!

- Save Space, Cut Costs & Centralize Control with 100% Reliability
- "Plug and Play" Any Mix of PCs & All Video; Supports PS/2 & Serial Mouse
- Desktop or Rackmount Models for 2, 4, 8, 16 PCs, Expand to 64
- · Keyboard & Mouse Emulators for Error Free PC Operation and Autoboot
- AUTOSCAN™ to Monitor All PCs



800-RCI-8090 x 71

RARITAN COMPUTER, INC. 10-1 liene Court, Belle Mead, NJ 08502 Fax (908) 874-5274

30-DAY MONEY BACK GUARANTEE FULL 1-YEAR WARRANTY

See Us at PC Expo Booth #4764 INTERNATIONAL:

stacks up."

France: (33) 1-64 67 64 67 Germany: (49) 180-522-8222 Ireland: (353) 1-454-0589 Italy: (39) 2-66800548 Japan: (81) 3-3255-1517 United Kingdom: (44) 244-520222; (44) 344-424-333
INTERNATIONAL RESELLERS INQUIRIES WELCOME — CONTACT RCI (908) 874-4072

Korea: (82) 2-412-5775 Netherlands: (31) 10-4423313 Sweden: (46) 020-788850 Switzerland: (41) 22-7532200 Talwan: (886) 2-218-1117

Circle 181 on Inquiry Card (RESELLERS: 182).

Rhetorex **Voice Processing boards** make CTI a reality.

If you're asking "what's CTI," you're missing one of the hottest new technologies going.

Computer Telephony Integration links PCbased computer applications to the telephone network, providing voice/

fax mail, interactive voice response, voice/fax servers and more.

Interested? Maybe you're already developing a CTI application. Then it's time to discover Rhetorex."

For the best value in CTI technology-from our 2 and 4 port DSP-based voice and fax processing boards, to our 24-port platform-give Rhetorex a call. And start making CTI a reality today.

Rhetorex, Inc., 200 E. Hacienda Ave., Campbell, CA 95008-6617 Tel. (408) 370-0881; Fax (408) 370-1171

All trademarks identified by the ™ symbol are trademarks of Rhetorex, Inc. All other trademarks belong to their respective owners. © 1993 Rhetorex, Inc.

Circle 160 on Inquiry Card.

LET YOUR COMPUTER DO THE TALKING!

Integrated Voice/Fax Mail

Communications/Networking

integrates major voice/fax applications plus program control into one full-featured high performance software, PC-AT/386/486 based. Menu driven. Easy to use. Full support for Rhetorex, New Voice, Dialogic, Bicom, Pika, TTI and Intel voice and fax hardware. Supports Telemarketing up to 32 voice lines and up to 8 fax lines. Hardware + Software Kits 2 voice lines kit starts at Fax-on-Demand lines: 818-368-4566 or

818-368-8848 SigmaTech Software

Tel: (818) 368-6132 Fax: (818) 368-7859 10801 Bismarck Ave., Northridge, CA 91326 USA (Resellers/Dealers/OEMs/Private labels are welcome)

Automated Attendant

Unlimited Audiotex

Voice Mail

Talking Yellow pages

Fax Mail


Fax-on-Demand

Fax Broadcasting

■ Date/Party lines

Int'l Call Back

Circle 171 on Inquiry Card (RESELLERS: 172).



TurboPort/RA™ controllers

Delivering fast, reliable connections for high-speed modems, TurboPort serial I/O controllers supply the speed

you need for remote access. Supports Windows, NetWare, OS/2 and more.

Faster than standard serial ports

Supports data rates up to 460.8K bps-4 times faster than V.34 modems.

Maximizes modem speeds

Software-configurable. Offers automatic software/hardware flow control. Each port

serviced by a 16C650 UART. For ISDN terminal adapters or modems of all types-9600 bps, 14.4K bps, 28.8K bps and above.

Multiple-strike surge protection

The only serial board for remote PC users with complete ESD protection to every signal.

For more information, call 1-800-782-7428 VISA and MasterCard accepted.

Star Gate Technologies, Inc. 29300 Aurora Rd. · Solon, OH 44139 USA 216-349-1860 • Fax 216-349-2056

© 1995 Digl International Inc. ADIGI All rights reserved

Circle 170 on Inquiry Card.

List: \$89 to \$129

or 2 high-speed ports ISA 1/2 card format

5 year warranty

Free Tech Support



Communications/Networking • Computer Systems

GET THE MESSAGE – OR ELSE!



TALKING TECHNOLOGY, INC.
1125 Atlantic Avenue, Alameda, California, 94501
Voice: 510-522-3800 Fex: 510-522-5556

Circle 162 on Inquiry Card.





Circle 197 on inquiry Card.

World's Fastest A/D Cards

Data Acquisition • Diagnostic Equipment



√ 250 MSPS, 8 bit

√ 60 MSPS, 12 bit

√ Up to 16M Memory **Multi-Card Systems**

Drivers in C, BASIC, LabVIEW, LabWindows


> CSL ITTE 8 bit, 100MSPS C92126 8 bit. 250 MSP5 C81012 12 bt. 20MSPS

1-800-567-GAGE

Gage Applied Sciences Inc.

5465 Vanden Abeele, Montreal, QC, Canada H4S 1S1 From outside North America, call +1-514-337-6893 Fax: (514) 337-8411, BBS: (514) 337-4317

Circle 149 on Inquiry Card.



The Intelligent Solution For Data Acquisition



VRX Custom Control

DAP 3200e14 Data Acquisition Processor

Analog I/O to 769K samples per second Digital I/O to 1.6M samples per second Up to 512 analog inputs on one DAP198 Up to 128 digital inputs on one DAP Up to 66 analog outputs on one DAP Up to 1024 digital outputs on one DAP

On-hoard 486: SX SX2, DX2, or DX4 Real-Time Data Acquisition-Windows or OS/2 Real-Time Process Control-Windows or OS/2 On-board FFT, FIR, PID, and more MICROSTAR

Ask for FREE catalog and demo diskette. 206-453-2345 / fax 206-453-3199 e-mail to info@mstarlabs.com

2265 116th Avenue NE Bellevue, WA 98004

LABORATORIES

Circle 154 on Inquiry Card.

Rackmount Solutions

RACKMOUNT COMPONENTS – OTY 25 PRICING Rackmount Chassis 19'x7'x17' Rackmount VGA Monitor Rackmount Monitor Shelf \$113 Rackmount Cherry Keyboard Drawer \$200

RACKMOUNT PLATFORMS - 0ty 1 Pricing

RMS486DX-33 \$1136

RMS386SX-33 \$915

RMS486DX-33 \$1136

RACKMOUNT CHASSIS - 15 Models up to 20 Board Slots MACKMOUNT CHASSIS - 15 MOGES UP to 20 BOAR 5101 SLOT CPU BOARDS - EISA/ISA 486, 486SX, 386, 385X, RACKMOUNT MONITORS - Super VGA & Monochrome RACKMOUNT KEYBOARDS - High Quality Cherry KB RACKMOUNT SWITCH - VIGEO/KB UP to 12 CPUS RACKMOUNT CABINET - Modular from 21' to 96' high

Exclusive International Distributor Program now Available



2468 Armstrong Street, Livermore CA 94550 (510) 447-2030 FAX: (510) 447-4559




Circle 166 on Inquiry Card.

FREE CATALOG

Offers tools, tool kits, test and diagnostic products for the support of computers, telecommunications, and integrated networks. Features the latest from Jensen, Fluke, Tektronix, Landmark, Ultra-X and many other leading manufacturers. Also wire, cable, connectors and everything else you need for network installation and support, plus technical charts and selection guides.





Jensen Tools Inc. 7815 S. 46th St. • Phoenix, AZ 85044 (602) 968-6231 • Fax (800) 366-9662



Circle 177 on Inquiry Card.

Terminate SCSI Problems!

SCSI Vue™ Terminator

- Active Regulation
- Status Indicators Gold Contacts

Benefits:

- Improves SCSI Bus Performance
- Less Errors; More Reliable Data Transfer





High- Performance Active Diagnostic · DOS · MAC · UNIX ·

Features:

- Diagnostic Indicators
- · Large Ferrite Filters
- Triple Shielding Double Gold 20u"
- Plated Connectors Extra Heavy 26
- Gauge Wire Benefits:
- No Loss Of Important Data
- Faster Performance Test Cable Integrity



SCSI Vue™ Gold Cables




3101 Whipple Rd., Union City, CA. 94587 Ph: 510-471-6442 Fax 510-471-6267

Circle 173 on Inquiry Card (RESELLERS: 174).

Keyboards

REMOVABLE STORAGE MODULES



FEATURES & OPTIONS:

- ➤ Supports most 3.5" hard
- > IDE, or SCSI interfaces
 - Hot removability
 - Key lock ON/OFF security
 - Fan cooling option
- > Built-in SCSI ID selector switch aption
- Ruggedized aluminum or low-cost plastic version
- Power/Drive activity LEDs
- > Patent protected

RUGGED RACKMOUNT KEYBOARDS



- > 19" reckmount keyboards
- 1U or 1.75° space
- > 25 models
- > Full travel and membrane types
- > IBM PC XT/AT, PS2 compatible
- > US and Intl. versions
- Spring-lock front panel
- Serial output 16mm, 2 button trackball

Call Elma at

510-656-3400



ELMA Electronic Inc. 44350 Grimmer Blvd. Fremont, CA 94538 Tel: (510) 656-3400 Fax: (510) 656-3783

Circle 185 on Inquiry Card (RESELLERS: 186)

CUSTOMIZE YOUR KEYBOARD

- Custom Key Imprinting all brands!
- Custom Colored keys for IBM®, DEC®, Wyse, Key Tronic, Cherry and more!
- Custom and stock keytop label kits for software support & languages.
- Full color keyboard templates made to
- your exact specifications. Word Perfect Keyboards.
- · Cyrillic, Arabic, Hebrew, etc. Keyboards





Cottonwood, AZ 86326 520 634-7515 FAX 520 634-4620

Circle 150 on Inquiry Card.



Turns a tape drive into a DOS "disk"

- Supports SCSI DAT/DDS-2, 8MM, QIC
- · Backup & Secondary storage.
- · Read/write files directly from/to tape.
- · Fast system crash recovery.
- · Less than \$5.00 per Gigabyte.
 - PSM software included (\$79.00 value) Works with WINDOWS 95



Call 800-827-3372 Voice 715-235-3388

FAX 715-235-3818



TAPEDISK Corporation \$249.95

Circle 183 on Inquiry Card (RESELLERS: 184).

Laptop/Notebook UPGRADE

CPU and Hard-drive Upgrades for all major brands.

- 486SLC2 clock-doubled CPU upgrades for 286/386SX's - IBM 486SLC2 (with 16KB cache) for true 486 performance.
- 386DX to IBM 486BL3 clock-tripled CPU upgrades.
- i486SX/DX to i486DX4 clock-tripled CPU upgrades.
- Upgrade-packages (CPU & hard-drive) from \$495.00 - Packages include installation, file transfer & return shipping.

Request our new Upgrade Guide Now available! 486 upgrades for most IBM PS/2 models

CORPORATE Upgrades, Inc.

(800) 240-6190


US/Canada: 3el: (916)536-3710 Pax; (916)536-3719 PO Box 289, Fair Oaks, CA 95628 Tel: (+46) 8-751-7668 Fax: (+46) 8-751-4601 Box 1189, Kista, Sweden All trademarks are the property of their respective owners.

Circle 279 on Inquiry Card (RESELLERS: 280).

The LIGHTEST desktop-to-go PC

HEWLETT PACKARD





- 2 PCMCIA card slots
- Full-size keyboard
- Pop-up mouse
- Only 3.8 lbs!

CALL TODAY FOR PRICING & CATALOG 800-713-6525

Circle 178 on Inquiry Card.

EduCALC 27953 Cabot Road Laguna Niguel, CA 92677 Fax: 714-582-1445

Save \$100s in memory when upgrading to newer PC Systems! SimmVerter™ converts your old 30 pin SIMMs to 36 bit, 72 pin connector SIMMs...

...for only \$19

- Converts four 1MRv9 SIMMs to one 1MRv36 SIMM (4MR) Converts four 4MBx9 SMMs to one 4MBx36 SMM (16MB)
- Guaranteed to work in any system using 36 bit memory. Works along with other 36 bit and even 32 bit SIMMs.
- Up to 4 adapters can be installed side by side
- 4 models to choose from to fit any system.
 Patented and designed in the USA.



To Order call 1-800-440-7466

OEM, dealer & distributor inquiries welcome !

Price per adapter. Add \$5 for shipping and handling and sales tax where applicable

Ph. 408-937-0390 Fax. 408-937-0391

Circle 206 on Inquiry Card (RESELLERS: 207).

Bright color. Bright price.

\$2,299.

The New BOXLIGHT ColorShow 1200 Projection Panel. Call now and order our brightest true-color LCD

> panel at the special introdutory price of only \$2,299. It's an unbeatable valueguaranteed.

- Compact & portable
- 640 x 480 resolution
- · PC and MAC compatible
- Free remote and cables

Your direct source for all the bright answers.

- Widest selection
- · Instant availability
- Overnight shipping
- 30-day guarantee

Call Today 1-800-762-5757

Circle 195 on Inquiry Card (RESELLERS: 196).



Now you no longer need to bring your stereo set to your computer. We do it for you!

2x10 Watt Speaker Output. Bass, Treble, Balance and Volume control in 32 steps. \$110 5 Line Audio Input.

4 bit Digital Input.

12-bit DOLL™ (Digital One Line Link)
Interface for 5, 12, 110 or 220 volt
switching technique. Switch
boxes are available from \$59

worldwide

incl. Windows software

DTC Electronics Hungary CALL or FAX us today Sport utca. 2; P.o.Box 14.
2112 Veresegyház - HUNGARY
Distributors wanted WORLDWIDE 35.27 387.292 for more information

Circle 192 on Inquiry Card (RESELLERS: 193).

VIDEO FRAME GRABBER / ACCELERATED SVGA DISPLAY HIGH PERFORMANCE, SINGLE SLOT, PCI / VL BUS

IMASCAN "/Chroma

NTSC PAL, SECAM, Y/C (S-VIDEO) RS-170 MONO (640X480)

IMASCAN/Mono-D

RS-170 MONO (5 MHz - 20 MHz) 8 / 16 BIT (40 MHz) DIGITAL INPUT

IMASCAN/RGB

16 / 24 BIT RGB (5 MHz- 15 MHz)

IMASCAN PRODUCTS INCLUDE:

- . PCI and VI. Bus Architecture
- 2 MB Shared Frame Buffer Design
 Transfer Rate to 25 MB/Second, Qual Port Transfer

- Iransfer Hate to 2.5 MM/Second, Qual POR Transfer
 Sub-Pixel Clock Alignment, Programmable Gain/Offset, DC Restoration
 Real-time Video in Window with Continuous Scale and Zoom
 24/16/8 Bit Color Display up to 1280 x 1024 at 70 Hz
 Orivers for Windows 3.X, Windows NT, Video for Windows, IBM 05/2
 Application Drivers for Image-Pro Prus and Optimas Available



III IMAGRAPH

11 Elizabeth Drive Chelmsford, MA 01824 USA (508) 256-4624

(508) 250-9155

Circle 175 on Inquiry Card (RESELLERS: 176).



ACE-925T: -40VDC to -57VDC





Only Micro/sys delivers embedded PCs this easy

through 486. All ready-to-run. On-board

firmware loads .EXE files into RAM for

FREE! 284 pg. Catalog (818) 244-4600 • FAX (818) 244-4246

at \$235. Qty 1.

MICRO/SYS

to use. CPU, RAM, FLASH, serial ports, I/O. V40

debug, or into flash for your final system. No hidden development costs. Save time

& money - right out of the box. Starting



Circle 198 on Inquiry Card.

your hardware to lock out intruders.


ADVANCED ENGINEERING CONCEPTS, INC.



250W/-48VDC Input DC-to-DC Converter

Contact us for +12VDC input model!!

Circle 203 on Inquiry Card (RESELLERS: 204).



250W/+24VDC Input

1801 South Street Lafayette, IN 47904

7 4 2 - 6 8 0 9

With support for expanded and extended memory, HiWIRE II can handle your most demanding schematic and PCB designs. The unique HiWIRE II editor allows you to display and edit schematics and PCBs simultaneously, using the same commands for each. HiWIRE II is \$995, and is guaranteed.

HIWIRE® II Schematic and PCB Software

> Call (800) 742-6809 or (317) 448-1903

Circle 164 on Inquiry Card.



Don't miss out on the best special we have ever offered! You get all of the following for only \$9900!

PCBoard Bulletin Board Software - 2 Node Version The PCBoard Programming Language Compiler Internet/UUCP EMail and Usenet News Gateway

Fildo Technology Mailer & Tosser Credit Accounting System dBASE III+ File Access (database & index files) Local/LAN and Remote/Modern Access PCBMail for Microsoft Windows

System management programs & utilities Free software upgrades for a full year Unlimited voice technical support for a full year

Don't wait! This special offer expires on June 30, 1995!

Try PCBoard for yourself! call our BBS at 801.261.8976 or Telnet to 199.67.41.2 Call Now 800.356.1686

PCBoard. Clark Development Company, Inc.

Circle 194 on Inquiry Card.



24 Hour Fax-Back Info 310-597-7145

HARDWARE/SOFTWARE SHOWCASE



New Windows Instrumentation Programming Tools

A new series of application notes outlining development tools and techniques for instrumentation programming under Windows is now available. Subjects covered include advanced GUI development and event-driven programming techniques, interactive C development, execution, and debugging tools designed specifically for instrumentation programmers using C under Windows.

National Instruments

6504 Bridge Point Parkway, Austin, Texas 78730-5039 Tel: (512) 794-0100 (800) 433-3488 (U.S. and Canada) Fax: (512) 794-8411

Circle 155 on Inquiry Card.

BYTE

Breaks the 4-Color Price Barrier with the Hardware/Software Showcase

See how affordable it is to advertise to BYTE's 500,000 computer professionals in this section!

Call for more advertising information: (603) 924-2695 or (603) 924-2598

Educational

Full and Part-Time Graduate Studies in Computer and Information Science



New Jersey Institute of Technology A Public Research University

University Heights Newark, New Jersey 07102-1982

Specializations in:

- · Advanced Computer Architecture
 - · Artificial Intelligence
 - Collaborative Systems
- · Communications and Networking
 - · Computer and Information Systems in Management
- · Data and Knowledge Management
 - · Image Processing and Pattern Recognition
 - · Multimedia and Hypermedia Information Systems
- · Parallel and Distributed Processes
 - Programming Environments and Tools
 - · Real-Time Computing
 - · Software Engineering
- · System Simulation and Modeling
 - · Theory of Computing

Off-campus programs:

Drew University at Madison and the Technology Education Center at Burlington. Distance learning programs available.

For information,

call (201) 596-3366 or e-mail csgrad@cis.njit.edu

NJTT does not discriminate on the basis of sex, sexual orientation, race, handicap, veteran's status, national or ethnic origin or age in the administration of student programs

Circle 205 on Inquiry Card.



Featuring the best-selling Novell's CNE Study Guide plus the complete So You Wanna Be a CNE?! video series

- Prepare for the Novell CNE exams.
- Train all your LAN managers for one low price.
- Study in the convenience of your home or office.
- · Learn at your own pace.
- Save hundreds of dollars compared to live instruction!

Required Courses Covered: DOS / Microcomputer Concepts • NetWare 3.1x Administration • NetWare 3.1x Advanced Administration • NetWare 3.1x Installation & Configuration • Novell's new Networking Technologies • Novell's new Service and Support.

Three months free on-line support from live instructor via BBS included.

CALL 1-800-877-4889 ext. 28

United Education Centers

50 South Main, Pleasant Grove, UT 84062 801-785-7900 ext. 28

Circle 199 on Inquiry Card.

Programming Languages/Tools • Windows • Recruitment


$\mathbb{C}(\mathbb{H})$ for MS Windows

The Computer Graphics Metafile is the ISO/ANSI standard for the system independent storage of vector and raster based graphical information. Our Windows solutions give you easy access to this technology.

MetaPrint: The CGM printer driver for MS Windows. Installs and functions as a standard MS Windows printer driver. MetaPrint gives you immediate print to CGM capability from any application that uses the GDI print function.

HSIview: The CGM interpreter for MS Windows, Views and prints CGM and WMF files and also translates CGM to/from

WMF. HSIvlew was developed for Microsoft for use with Word, Powerpoint, etc. and is available as both an enduser application and a developer DLL



Besides CGM EMATEK supports other ISO/ANSI standards as well. Based on the Graphical Kernel System (GKS) and Computer Graphics Interface (CGI) standards our GSS graphic tools enable you to develop portable, device independent graphic applications. Call for an info pack today.




EMATEK GmbH Subbelrather Straße 17 D-50823 Cologne, Germany Phone: +49-221-512074 Fax: +49-221-529666

Circle 187 on Inquiry Card.



For High-Quality Scientific Publishing. use PCT_FX Typesetting Software.



Make all your documents and math formulas look their best! For a free brochure & demo disk, call 800/808-7906

Personal TeX, Inc. 12 Madrona Street, Mill Valley, CA 94941

Fax: 415/388-8865 E-mail: pti@crl.com

Circle 158 on Inquiry Card.



Create FORMS for Windows or DOS applications

Integrate forms, logos, fonts, graphics, signatures, into Visual Basic, C/C++, FoxPro, Clipper, Clarion, programs. Visual Forms, in a Windows environment, creates PCL or metafile. Use Template Maker to position your X,Y coordinates for your data fields.

Custom and stock forms available. Digitized logos, signatures.



(914) 354-8666

BUSINESS SYSTEMS, INC.

5C Medical Park Dr.

Pomona, NY 10970

Circle 167 on Inquiry Card.

Learn C++ & Windows Based Programming... Simply, Quickly!

With the OML Learning Series™ you can learn C/C++, object technology and Windows"-Based programming quickly and conveniently in the privacy of your home or office. The OML Learning Series features:

Visual Series", C/C++ Series" OOA/OOD Series". **OLE Series**

Each series: \$249° (reg. \$400) Arry 2 series: \$399* (reg. \$750) Any 3 series: \$549* (reg. \$1050) All 4 series: \$649* (reg. \$1300) LAN version: Call

800-6789-OML

Call us for information. and FREE Demo

Softwar 30-

> OBJECT MANAGEMENT LABORATORY TEL: 805-373-8111 FAX: 805-373-8116

Circle 191 on Inquiry Card.



Conventional spreadsheets can't cope with uncertain or fuzzy numbers.

But now there's FuziCalc. This Windows spreadsheet uses revolutionary fuzzy math technology to achieve breakthrough performance.

Call now for FREE information.

800-472-6183

FuziWare, Inc. (615) 588-4144

Circle 188 on Inquiry Card.





Data Analysis

Data Acquisition

The Origin Data Acquisition System is an integrated software package that provides a complete solution for data collection, instrument control, data analysis and creating publication graphics.



Call For Free Demo 1-800-969-7720

Microcal Microcal Software, Inc., One Roundh se Plaza, Northampton, MA 01060, Fax (413) 585-0126

Circle 168 on Inquiry Card (RESELLERS: 169).

Windows Software Development

• C++ • X88A8M • Chicago • WinSDK • OLE 2.X • Win85 • MFC • • Networking Protocols & APIs • TCP/IP • GUIS • Client/Server •

• Windows Sockets • Win32 • MAPI • WWW • DLLs •

Imagine working with the latest Microsoft technology developing the hottest PC Networking products for the rapidly expanding TCP/IP market. Imagine working for an industry leader and feeling like you're working for a start-up. Imagine Sun East. We have openings in Boston for talented Windows Engineers, SQA Engineers and Windows UI Designers:

Email: staffing@east.sun.com FAX: (508) 442-0011, US Mail: Sun Staffing East, Dept. ELN, 2 Elizabeth Drive, Cheimsford, MA 01824

All products or service names mentioned herein are trademarks of their respective owners. We are an equal opportunity employer and encourage women and diversity candidates to apply. No Agency/ Recruiter fees paid.



THE BUYER'S MART

A DIRECTORY OF PRODUCTS AND SERVICES

THE BUYER'S MART is a unique classified section organized by product category to help readers locate suppllers. Each ad has Inquiry numbers to aid readers requesting information from advertisers.

AD FORMAT: Each ad will be designed and typeset by BYTE. Do NOT send logos or camera-ready artwork. Advertisers should furnish typewritten copy. 2"x11/s" ads can include headline (23 characters maximum), descriptive text (300 characters is the maximum recommended) plus company name, address, telephone and fax number. 2"x2%" ad has more space for descriptive text (850 characters is the maximum recommended)

DEADLINE: Ad copy is due approximately 2 months prior to issue date. For example: November issue closes on September 8. Send your copy and payment to: THE BUYER'S MART, BYTE Magazine, 1 Phoenix Mill Lane, Peterborough, NH 03458. For more information call: Ellen Perham at 603-924-2598 or Mark Stone at 603-924-2695. FAX: 603-924-2683.

		3-5 Issues	6-11 Issues	12 issues
	1 ad	\$731	\$701	\$614
2"x11/6"	2 ads/Issue	-	-	584
	3 ads/issue	-	_	556
	1 ad	\$1,462	\$1,402	\$1,228
2"x2"/4"	2 ads/issue	-	-	1,169
	3 ads/issue	-	-	1,111
	-COLOR -	Add \$1	00	

RATES (Jan. 1995)

ACCESSORIES

KEYBOARD, VIDEO, MOUSE, AUDIO

Extend signals from PC with EXTENDER
Split signals with COMPANION/PC EXPANDER Switch signals among PCs with COMMANDER

Boosts signals up to 600 feet. Control up to 96 PCs with one keyboard, monitor and mouse.

CYBEX CORPORATION

4912 Research Dr., Huntsville, AL 35805 Phone: 205-430-4000 Fax: 205-430-4030

Inquiry 651.

STABILANT 22 CONTACT ENHANCER

"Highly recommended..." Jeny Pourn

rignay recommended... Jeny Pounelle
A long-term environmentally-safe, resident contact
treatment; Stabilant 22 substantially improves the reliability
of connectors and contacts for computers, bio-medical
electronics, telecom, avionics, process control, CATV, video,
audio, and automotive equipment.

D.W. Electrochemicals Ltd.

Newkirk Road (North) Unit 3, Richmond H Ontario L4C 3G4, Canada (905) 508-7500

Inquiry 652.

VGA Splitters

- Connect 2, 4, or more monitors to your computer Bright and crisp presentation simulteneously on all monitors Gueranteed Works with all VGA, SVGA, and RGB monitors Supports 1280 x 1024 MADE IN USA Special VGA extension cables to 250 ft

HALL RESEARCH

800-959-6439 Santa Ana, CA (714) 641-6807

Inquiry 653.

BAR CODE

Bar Code Readers

For PC, XT, AT, PS/2, Macintosh and Serial Terminals

- * Attaches as 2nd Keyboard, no software changes
- * Reads 2of5, 128, UPC/EAN, Code 39, etc.
- * External or Internal attachment on PC
- * Wand, CCD, Slot Badge, Magstripe or Laser
- * Supports DOS, Novell, UNIX, Mac OS, etc.
- ★ 100+ Configurable Options
- * Supports USA & International Keyboards
- * 2 Year Warranty, 30 Day \$ Back Guarantee
- ★ Direct From Manufacturer
- * Top Rated by Independent Review
- * Complete with CCD Scanner \$624
- Complete with Laser Scanner \$784
- ★ Complete Wand only Reader-\$329

Worthington Data Solutions

3004 Mission Street - Santa Cruz, CA 95060 408-458-9938 800-345-4220

BAR CODE

Portable Reader

- * AA Battery Operated, 64K or 256K
- * Display messages and optional voice messages tell operator what to do. Messages are easily recorded (like answering machine) in any language. This unit is EASY!
- ★ Double duty as Non-portable Reader
- * 4x20 Supertwist LCD Display, 35 Rubber Keys
- ★ 2 Built-In Inventory Programs or create custom
- . Download tables and Pick Lists
- * Wand, CCD, or Laser Scanner Input
- * Serial Interface and Keyboard Interface
- ★ Reads 2of5, UPC/EAN, 128, Code 39, etc.
- ★ 2 year Warranty on Reader & Wand
- * 30 Day Money Back Guarantee
- * 64K Complete with Steel Wand \$799
- * Small Size and very long battery life

Worthington Data Solutions

3004 Mission Street • Santa Cruz, CA 95060 408-458-9938 FAX 408-458-9964 800-345-4220

Labeling Software

For DOS and Windows with dot-matrix, LaserJet or DeskJet. Easy WYSIWYG design. Any format/size. Mix big text, bar codes, and PCX graphics. Formats for AIAG, KMart, Sears, MiL-STD, Penneys, WalMart. File Input. LabelRIGHT for DOS-\$279. LabelRIGHT for Windows-

30 Day Money Back Guarantee

Worthington Data Solutions (408) 458-9938 800-345-4220

Cordless RF Wand and Laser

A cordless RF bar code wand or laser with a range of 100 feet. Plug-N-Play. No software needed. Attaches as 2nd keyboard. For IBM and Macintosh or any serial device. Complete Cordless Wand - \$695. Complete Cordless Laser - \$1775. Optional range extenders \$200 per 100' added.

Worthington Data Solutions

(800) 345-4220 (408) 458-9938

Windows Bar Code Fonts

Add bar codes to any font based Windows program. Fonts designed for dot matrix, DeskJet and LaserJet. Print Codabar, 2 of 5, Code 128, UPC/EAN and Code 39 inside your Windows program. TrueType fonts, bitmaps and metafile support included. Only \$199.

Worthington Data Solutions

(408) 458-9938 (800) 345-4220

BAR CODE

FREE BARCODE CATALOG

Full of barcode tips and advice

FREE BARCODE SOFTWARE

Scanners from \$49

VISA 800,478,8644 Dealers welcome **Abraham Technical Services** 110 Hamel Road, Medina, MN 55340 THE BARCODE SOURCE

Inquiry 654.

Portable Bar Code Reader

- ➤ Use as a PORTABLE, WEDGE, or SERIAL
- > 9V Battery Operation with Lithium Backup
- ➤ 2x16 Supertwist LCD Display
- > 54 Key Keyboard with Separate Numeric Keys
- ➤ Real-time Clock Supports Date & Time Stamps
- ➤ Reads all Popular Bar Codes (16 types)
- ➤ Wand, CCD, Laser, or Serial Input Devices
- ➤ Built-In Program Generator
- ➤ Create Your Own Custom Programs
- ➤ 6 Built-In Inventory Programs
- ➤ Up to 250 Programs Can Reside in Memory
- ➤ Create up to 250 Data Files per Program
- ➤ Up to 250 Look-Up Files in Memory
- ➤ Built-In Calculator
- ➤ Supports HAYES Compatible Moderns
- 64K Memory with Data Compression
- ➤ 30-day \$\$ Back Guarantee 1 Year Warranty
- ➤ Complete Unit with WAND Scanner \$795

AMERICAN MICROSYSTEMS

2190 Regal Parkway, Euless, TX 76040 (800) 648-4452 (817) 571-9015 FAX (817) 685-6232

BAR CODE READERS

For PC, XT, AT, PS/2, & Serial Terminals

- ➤ Emulates Keyboard: Works With Any Software
- ➤ Data Appears as Keyboard Input
- ➤ Uses Enhanced Decoding Algorithms
- Accepts Wand, Slot/Badge, CCD, Laser, Magnetic Stripe Reader, & RS232 Serial Input
- ➤ Reads All Popular Bar Codes (16 types)
- > Reads HIGH, MEDIUM, & LOW density codes
- ➤ Auto-Discriminates Between Bar Code Types
- ➤ Easily Programmed with a Bar Code Menu ➤ Over 140 User Configurable Options
- ➤ Dalsy Chain Up to 96 Readers
- ➤ Supports NOVELL Networks
- ➤ Supports US & INTERNATIONAL Keyboards
- ➤ Direct From Manufacturer
- > 30-day \$\$ Back Guarantee, 1 Year Warranty
- ➤ Complete Unit with LASER Scanner \$1095
- ➤ Complete Unit with WAND Scanner \$299

MERICAN MICROSYSTEMS 2190 Regal Parkway, Euless, TX 76040

(800) 648-4452 (817) 571-9015 FAX (817) 685-6232

'HE BUYER'S MAR

BAR CODE

Bar Code Printing Software LabelWorks for Windows

- > Prints all Popular Bar Code Types (19 Types)
- Desktop Publishing Features: WYSIWYG. Scalable Fonts, Rulers, Guides, Lines, Shapes, Page Zooms (25%-400%), Templates
- Rotates Text, Bar Codes, and Graphics
- Supports Windows Compatible Fonts
- Choose From Over One Hundred Popular Label Formats or Design Your Own
- > Rich Text Support: Mix Styles, Types, & Sizes
- Automatically Prints Serial Numbers
- Imports & Exports Graphic Files TIFF, GIFF, BMP, PCX, WPG, WMF, TARGA
- Supports Virtually all Windows Compatible Printers (PostScript, Laser, & Dot Matrix)
- > 30-day Money-Back Guarantee, \$295
 - *** CALL FOR FREE DEMO SOFTWARE ***

AMERICAN MICROSYSTEMS 2190 Regal Parkway, Euless, TX 76040

(800) 648-4452 (817) 571-9015 FAX (817) 685-6232

BARCODE & MAG. STRIPE SYSTEMS

- Keyboard Wedge with HP Stainless Steel Wand/Mag. Stripe Reader \$249
- Keyboard Wedge with SYMBOL LS2000 or SP400 Laser & Mag. Stripe Reader
- Keyboard Wedge with PSC QuickScan
- Laser/Mag. Stripe Reader
- Software Wedge Decoder with HP Stainless Steel
 Wand or Laser Scanner (pos & with Rs-232 or parallel) \$189 4
- All Wedge Packages include a Wand or Laser Holder
- Mag. Stripe Encoder/Reader (3 Trks) w/Software
- \$1099 Printing Software (DOS, WIN, UNIX...) \$1494
- Portable Data Terminals (129K-4.2MB) \$599 + Complete POS System: 486 40M/tz, S1:

 4MB RAM, monitor, POS Software, SP212 Receipt Printler,
 M-S Cash Drawer, pole display, HP stainless steel wand
 and magnetic stripe reader with decoder \$1999
- Application Software: Inven, Asset, Tools, Time & Attend_
- Radio Frequency Terminals (spread spectrum/narrow band)
- · Bar Code Printing Software (DOS) included with each purchase
- Made in the USA 30 Day \$\$ Back Spanish Dept. Avail. Direct from Mfg.

BARCODE INTERNATIONAL SYSTEMS (BIS)

12140 Severn Way, Riverside, CA 92503 (909) 270-0016 Int'l (800)653-4252 US • (800)219-5178 CAN • FAX (909) 270-0920

Inquiry 655.

BAR CODE PRINTERS

Only \$1,495!

Reseller Pricing Available Impeccable Print Quality, Rugged Performance!

THARO SYSTEMS, INC.

P.O. Box 798, Brunswick, OH 44212-0798 216-273-4408 Fax: 216-225-0099

Inquiry 656.

CAD

Circuit Design Software for Windows Easy-to-use schematic entry, PCB design, and simulation software, starting at \$149 each. Complete PCB package with schematics, autorouter, and layout for 2-layer circuit boards, \$399. Enhanced version with autoplacement, more symbol libraries, and up to 16 layers, \$649. CAM file outputs.

Mental Automation, Inc.

5415 136th Place, SE-Bellevue WA 98006 (206) 641-2141 FAX (206) 649-0767 BBS (206) 641-2846

Inquiry 657. 296 BYTE JUNE 1995

CAD/CAM

CONTOURING MOTION CONTROL

FROM A PRINTER PORT! \$249

NEW

- VERSION 3

 Controls up to six step motors simultaneously.
 Inear and Circular Interpolation.
 New features to accommodate machine control
- Easy-to-use DOS device driver. Super Manual.
 CAD-CAM interface available.

Ability Systems

Corporation, 1422 Arnold Ave Roslyn, PA 19001 (215) 657-4338 FAX: (215) 657-7815

Inquiry 658.

CD-ROM

We Buy, Sell & Trade

CD-ROMS & MEMORY CHIPS

Resellers Wanted

Call or write for a free product update

Consolidated CDROM, Inc.

515 67th Ave Philadelphia PA 19126 USA +1-215-276-3657 / +1-215-276-3854 fax

1-800-8-CDROMS

Inquiry 659.

INTERNET on CDROM!

ľ	LINUX Developers Resource 3 CD Set
	CICA Windows 3 CD Set
	INTERNET Tools CD-ROM
	BSDisc (NetBSD & FreeBSD)
	USENET 2 CD Set\$25 comp.sources & alt. sources + many FAQ's from other groups
	SOURCE CODE CD-ROM
	PERL & TCL/TK CD-ROM
	STANDARDS 2 CD Set
	MS-DOS 2 CD Set (SimTel Archive)
	4 000 000 0040

MC, VISA & AMEX

1-800-800-6613 tel: +1-602-526-9565

InfoMagic fax: +1-602-526-9573

P.O. Box 30370, Flagstaff, AZ 86003-0370 info@infomagic.com

Inquiry 660.

CD ROM TOWERS & JUKEBOX SERVERS FOR ALL OPERATING SYSTEMS!

No Device Drivers/ MSCDEX needed. Complete Kit Networks CD Roms, unlimited user license, DISCPORT.

"JES, NONE BETTER AT ANY PRICE"

Call NOW: 1 (800) 482-1866 305-271-0076

Inquiry 661.

\$13 \$12 Charlie Chaplin 517 The Holy Bible W.C. Fields My Talking Dictionary 3D-ttl A Plus K-12 Plus \$12 \$38 SysOps Plus The Civil War \$12 Complete Algebra \$14 \$45 Grey Wolf Computer Aremator News Yesterday, Today & Tomorr Middle School Suite \$14 517

CALL OR WRITE FOR A FREE PRICE LIST



44 Maple Street, Suite 7, Danvers, MA 01923 800-334-8666 (orders only) Fax: 508-774-5811 MASTER CARD - VISA - COD - PREPAID

Inquiry 662.

New and Updated CDROM Titles

Cica MS Windows CDROM, Thends of Windows prgrms.	\$29.95
Giga Games CDROM, Games for DOS/Windows	\$39.95
Space and Astronomy, Thends NASA images/data	\$39.95
C User Group Library, C source code Dec 93	\$49.95
Simtel MSDOS CDROM, DOS Shareware/Freeware	\$29.95
QRZ Ham Radio CDROM, FCC Callsign Db & Shrwar	\$29.95
Hobbes OS/2 CDROM, OS/2 Shareware/Freeware	\$29.95
Source Code CDROM, 650 Mb source, DOS/Unix	\$39.95
Gutenberg Project, Literature and docs	\$39.95
Linux Operating Sys, 386/486 OS, X11, full src	\$49.95
FreeBSD Operating Sys., Ver 1.0, kml src, X/GNU	\$39.95
Libris Britannia, MSDOS Tech/Scl/Engineer	\$69.95
X11R5/Gnu CDROM, Full src, SPARC binaries	\$39.95
Nebula for NeXTSTEP, Prgms for Intel NeXTSTEP	\$59.95
Ada Programming CDROM, Compilers, source, docs	\$39.95
Aminet CDROM, Amiga Shareware/Freeware	\$29.95
CDROM Caddles, Lifetime Guarantee	\$4.95
T	lum d

Top quality CDROMs. 100% satisfied or full refund.

WALNUT CREEK CDROM

4041 Pike Lane, Ste D-212, Concord, CA 94520 1-800-786-9907 Visa/MC AMEx. Fax: 1-510-674-0821

Inquiry 663.

COMMUNICATIONS

Frame Relay, X.25, BSC, HDLC, SDLC

Use our rock solid, compilant, linexpensive and robust synchronous products for your PC project. On board protocol support reduces PC overhead.

Support for MS-DOS, Windows, Unox, OS/2, Netware and others.

- · CCITT and ISO compliant X.25, HDLC.
- Frame Relay blanket certified for any application.
 Test and datascope programs for easy debugging.
- Sangoma Technologies Inc.

1-800-388-2475 905-474-1990

Fax 905-474-9223

Share Modems & Phone Lines!

Modern Assist PLUS is a full featured, non-dedicated modern server for IPX or NetBIOS networks. Data rates to 115,200 with serial ports or multiport boards. Use ANY Windows fax or communication software or DOS programs which support INT 14 or NASI. \$249 two ports, \$749 unlimited. Free 30-day trial on 8BS.

SYNERGY SOLUTIONS, INC.

2150 South Country Club, Suite 1, Mesa, AZ 85210 (602)545-9797 FAX (602)545-9827 BBS (602)545-0232

Inquiry 664.

COMPUTER BOOKS

COMPUTER BOOKS ONLINE

Easy online ordering at our Internet, CompuServe. & NIFTYServe stores. 15% off most books from 140 publishers for computer professionals. GO CBK, www.compubooks.com/books.html, or tip info.txt from ftp.compubooks.com. Worldwide shipping. E-mail to info@compubooks.com for information.

CompuBooks

AR1 Box 271D 512-321-9652 Cedar Creek TX 78612 USA Fax 512-321-4525

Order line 800-880-6818

COMPUTER INSURANCE

INSURES YOUR COMPUTER

SAFEWARE Computerowner's coverage provides replacement of hardware, media and purchased software. As little as \$49 a year covers accidents, theft, power surges and more. One call does it all.

1-800-800-1492

SAFEWARE, The Insurance Agency Inc. PO Box 02211, 2929 N. High St., Columbus, OH 43202 Now available in Ontario!!!

Inquiry 665.

COMPUTER TELEPHONY

Write your own Voice Mail software

Create advanced, multi-line voice/tax mail systems with VOS™, the Editors' Choice. Complete language for computer/telephone integration. VOS supports databases, LANs, voice recognition, text-to-speech, conferencing.

Call for free booklet Get into Interactive Voice.

Parity Software

US: 415-989-0330 fax: 415-989-0441 Europe: +45-3940.8803 fax: +45-3940-7803

CREDIT CARD PROCESSING

Take Charge!

PC-Credit makes It easy to add credit card, debit card and check guarantee services to your DOS or Windows applications. Our products include Libraries, DLLs, TSRs and easy to interface programs that will provide the solutions to your most demanding single or multi-user applications.

Go Software, Inc.

31 Sherborne Rd., Savannah, GA 31419 (800)-725-9264 (912) 925-4048 Fax (912) 927-0214

Inquiry 666.

CROSS ASSEMBLERS

PC BASED DEVELOPMENT TOOLS

We offer low-cost efficient CROSS ASSEMBLERS and a superb line of SIMULATOR-DEBUGGERS with full built-in superb line of SMULATOR-DEBUGGERS with full bull-in DISASSEMBLERS for Intel's MCS-48, 51, 85 and 96, and for the Z80 tamilies of embedded controllers. Our new eim-ulators for the 80C196KB and 80C196KC are unique in the market, and have been received with rave reviews. The price of our software includes unlimited free upgrade privileges!

Lear Com Company

2440 Kipling St., Ste. 208, Lakewood, CO 80215 (303) 232-2226 FAX (303) 232-8721

Inquiry 667.

DATA RECOVERY

Recover Repair Restore All EVERLOCK

All SMARTCAM

Is your software attached to your computer with Everlock EV31.SYS & EV32.SYS? Any Everlock software (even damaged) can be recovered & run on any computer you own.

Did your Smartcam hard drive crash? Did you try to move Smartcam? No problem! You can repair Smartcam to run on any computer you own. Safe & easy to use even for novices.

CODYWARD VISAMC/AMEX 905-830-1961 FAX 905-830-5064

We Can Save It! All Platforms - All Storage Devices

Proprietary techniques so advanced we rescue data others simply abandon.

DRIVESAVERS

Restoring data since 1985

1-800-440-1904

415-883-4232

Inquiry 669.

The Leader in Data Recovery

- Expertise in virtually every operating system and media storage device.
- 24-Hour support & emergency services available.
- Call for a FREE consultation!

ONTRACK DATA RECOVERY

MN: 1-800-872-2599 · CA: 1-800-752-7557 Europe: +44 (0)181 974 5522 • Japan: (0429) 32-6365

Inquiry 670.

DATA/DISK CONVERSION

THE #1 CHOICE In disk & tape conversion

for many leading corporations, government agencies, law firms, and companies in every industry-world-wide.

Free test . Satisfaction guaranteed Graphics Unlimited Inc.

3000 Second St. North, Minneapolis, MN 55411 (612) 588-7571 FAX: (612) 588-8783 1-800-745-7571

Inquiry 671.

CONVERSION SERVICES

Convert any 9-track magnetic tape to or from over 6000 formats including 3½", 5½", 8" disk formats & word processors. Disk-to-disk conversions also available. Introducing CD-ROM conversions, Call for more info.

Pivar Computing Services, Inc.

165 Arlington Hgts. Rd., Dept. #B, Buffalo Grove, IL 60089 (800) Convert (708) 459-6010

Disk & Tape Conversion Services

Or do it yourself with The File Analysti it overcomes all file translation and transfer problems. Analyzes unknown files! Makes old files into perfectly structured import or client/server files! Search, remove å replace data/codes. Convert between any format, any database, any report generator. ASCII, delimed, EBCDIC, spit, scan, verify, å more. Commercial and Professional editions used dally all

THE FILE ANALYST "The Ultimate File Analyzer & Reformatter"

RALPH GARNER ASSOCIATES, INC. 99 Madison Ave., New York, NY 10016 Tel 212-779-7667

Inquiry 672.

WE WROTE THE BOOK!

Deal direct with the company who developed Deal airect win the company who developed the systems that most others use... SHAFFSTALL! Tape/Diskette Transfer/Conversion/Duplication. PC/Minl/Mainframe/Workstation Tape Transfer. WP to WP Document Conversion Services.

1-800-357-6250

317-842-2077

Shaffstall Corporation

(Fax) 317-842-8294

Inquiry 673.

EDUCATION

B.S. & M.S. In COMPUTER SCIENCE

B.5. & M.5. In COMPUTER SCIENCE
The American Institute For Computer Sciences offers an indopth home study program to earn your Bachelor of Science
at home. B.5. subjects covered are: MS/DOS, BASIC,
PASCAL, C, C++, Data File Processing, Data Structures &
Operating Systems. Ms. program includes subjects in
Software Engineering and Artificial Intelligence. Ada and
using Windows courses also available. Accredited Momber:
World Association of Universities and Colleges.

AMERICAN INST. for COMPUTER SCIENCES

2101-BY Magnolia Ave., Suite 200, Birmingham, AL 35205

1-800-767-2427 1-205-323-6191

FLOPPY DISKETTE

We are a manufacturer licensed by Sony Corporation.
Our disks are all 100% Tested and Detrified Error Free with guarantee Chipping for disker: HM, 200, video tape, CO leverity box.
Our own brand MEGA, DEM or both pack are also available.
Outpicators & wholesalers are welcome.
YHC Cassette Ind. Ltd.
75 Saintsbury Square Scarborouph, Ont.
WIMMARK IND. LTD.
14 Man Frong Industrial Blig.
7 Cheurg Lee Street.
Oral Wan Horny Kong.
IEI: (416) 321-1479
Fax: (416) 321-18451
Fax: (8522) 5882203
Fax: (8522) 8973700

Inquiry 674.

FLOW CHARTS

COBOL STRUCTURE CHARTS

The new PowerStructure for Windows generates incredible structure charts DIRECTLY from your COBOL source – STRUCTURED or NOT! Forget manual flowcharting. PowerStructure will diagram your spaghetti code, do it in seconds, and free programmers for more important work. Now just \$149.

CyberMetrics

5541 S. Marine Drive., Tempe, AZ 85283 (602) 838-3310

Inquiry 675.

WINDOWS FLOWCHARTER \$129

RFFlow 3.0 is a professional drawing tool for flowcharts & org. charts. Requires Microsoft Windows; 500 shapes auto adjust in size; diagonal lines and curves; auto line routing and re-routing; OLE server; click on a shape to bring up a sub-chart; import/export bitmaps and metafiles; Call for free trial disk.

RFF ELECTRONICS

1053 Banyan Court, Loveland, CO 80538 Phone: (970) 663-5767 FAX: (970) 669-4889

FOREIGN LANGUAGES

OVER 150 LANGUAGES

Translation, Language Learning Tutorials, Fonts, Dictionaries and Language Systems for DOS, Mac and Windows. Japanese, Chinese, Spanish speaking staff. Call us first for best prices and expert support.

Character Language Resources

2130 Sawtelle Blvd. 304A, Los Angeles, CA 90025 800-569-2099 FAX 310-996-2303

Inquiry 676.

HARDWARE

Pre-Owned Electronics, Inc™

THE Independent Provider, serving the Dealer, Professional, Corporate, Government, and Educational Buyer since 1985.

APPLE II® & MACINTOSH® SYSTEMS • PARTS • EXCHANGE REPAIRS

Call for a Catalog...800-274-5343 INT'L: 617-275-4600 • FAX: 617-275-4848 205 BURLINGTON ROAD • BEDFORD, MA 01730

Inquiry 677.

HEWLETT-PACKARD

Buy - Sell - Trade ColorPro

LaserJet DraftPro DraftMaster DeskJet RuggedWriter Electrostatic Plotters DesignJet HP 9000 Workstations and Vectras also available.

Ted Dasher & Associates

4117 Second Ave., S. Brringham, Al. 33222 Phone: (205) 591-474 Fax: (205) 591-1108 (800) 638-4833 E-mail: sales@dasher.com

Inquiry 678.

LANS

Little Big LAN

The most flexible network

- Peer to Peer LAN to 250 nodes
- \$75 total software cost, not per node! Link via serial, parallel, or Moderns Also via Ethernet or Archet, or mix!
- Typically only 40k of RAM

Information Modes 817-387-3339 / P.O. Drawer F, Denton TX 76202 Fax 817-382-7407 Orders 800-628-7992

Inquiry 679.

HE BUYER'S MAR

LASER CHECKS

LASER CHECKS

PERSONALIZED WITH YOUR NAME AND LOGO IN SAFETY BACKGROUND CALL (714) 773-5811 OR TOLL FREE 1-800-252-6427 Fax 1-800-439-0158

FOR SAMPLE (ETC.) :MAGNETIC ENCODING:

MICR-COMP, Inc. 689 S. State College Blvd., Suite A Fullerton, CA 92631

Inquiry 680.

LOCALIZATION

DON'T MISS OUT!

Reach millions of European customers now. A team of localization experts can seamlessly adapt all aspects of your software or multimedia product: Documentation, GUI, sound, packaging etc.

Get it right the first time!

Contact OVERSYS today.

In France: 33-67 59 30 62 - Fax 33-67 59 30 26

100276.2103@compuserve.com

Inquiry 681.

MANUFACTURING SOFTWARE

Manufacturing Software

E-Z-MRPTM is complete material requirements planning software for the PC, includes bill of materials, material planning make/buy calculation, capacity planning, purchase orders, labor distribution, job costing, physical inventory, AutoCAD interface, and more. The best entry-level manufacturing solution. Complete for \$2.995 Special Lite version for \$995, Call for information.

Alliance Manufacturing Software

1-800-490-2520

Inquiry 682.

MEMORY

WE'LL PAY YOU FOR YOUR OLD MEMORY

Siltens Dips Laser Printer, 1 Megic9, 4 Megic9, DRam Chi-- ANY MEMORY -

Men ory Has Value! Don't of your

Call or fax what you have available

1-800-718-7755 THE MEMORY LIQUIDATORS

The company that buys memory back

531 Main St. Ste. 1174, El Segundo, CA 90245-3060 Ph. 310-676-3074 Fax 310-676-3076

Inquiry 683.

PROGRAMMING TOOLS

dBASE file access from C++, Basic

CodeBase gives complete database management with multi-user dBASE, FoxPro or Clipper file compatibility from C, C++, Basic or Pascal. Get visual design software and royalty free client-server. Unconditional money back guarantee!

Call Sequiter Software Inc. for details! FAX 403-436-2999 403-437-2410

Inquiry 684.

SECURITY

Leaders in Software Security

EVERLOCK and EVERKEY If copy protection. Features include – Encryption, Serialization, Remotely resettable access flags, date limits, execution counts and network user limits -and much more! Free demo available.

Call today and ask about our low cost Trial Kits!

Az-Tech Software, Inc. 201 East Franklin St., Richmond, MO 64085-1883 (880) 227-0644 (816) 776-2700 FAX (816) 776-8398

Inquiry 685. 298 BYTE JUNE 1995

SECURITY

THE ULTIMATE SOFTWARE SECURITY

- THE ULIMATE SOFT WAKE SECURITY
 STOPCOPY family UNCOPIABLE copy protection
 STOPVIEW software encryption
 NETLIMIT network license metering
 DOS, Windows, Macintosh, OS/2, support
 No source code changes required for ANY of our products in ANY environment
 Our products destroy ALL of our competition
 Call for FREE domo disk, or to discuss our products'
 MANY onlines

BBI Computer Systems, Inc. 14105 Heritage Lane, Silver Spring, MD 20906 800/TRY-ABBI • 800/879-2224 • 301/871-1094 • FAX:301/460-7545

Inquiry 686.

CRYPKEY SOFTWARE LICENSING SYSTEM

"Hardware key protection without the hardware key"

CrypKey is a software protection tool, offering

- complete security from any disk copy program
 complete compatibility with any MS-DOS
- or MS WINDOWS based machine
- · complete invisibility no disk key, no hardware key, less support calls
- · instant disaster recovery
- · protect programs distributed on CD-ROM, BBS, or Internet!

CrypKey is a sales tool, allowing you to sell your program by increments - enable the options the customer purchased

by number of runs - e.g., sell 100 calculations for \$100.00 time period - e.g., lease or demo your program for 60 days

CrypKey uses a numeric key that can be transmitted by phone. fax, or email. Self your customers more options, more copies, more time or more runs instantly, just by making a telephone call. (great for overseas customers or distributors) CrypKey is produced by Kenonic Controls Ltd. - engineering and software since 1972.

> Kenonic Controls Limited 7175-12th Street South East Calgary, Alberta, Canada T2H 2S6 (403) 258-6200 • fax: (483) 258-6201

Inquiry 687.

Cop's CopyLock II

Professional software protection with TRUE Machine Install, Option Board safe. DOS, OS2, Networks, Windows, Trace 3000. DialCOPS Access Control for mass distribution via CD-ROM or Internet. Known and used world-wide since 1984.

LINK Data Security Int'l: + 45 3123-2350 Fax: + 45 3123-8448

KEY-LOK™ SECURITY

KEY-LOK SECURITY

Piracy survival 11 years proves effectiveness of powerful multilayered security. Algorithmic response. Programmable memory. Economical, Transparent to PARALLEL/SERIAL port, Counters/Real-Timo-Clock, Multi product/teature licensing. DOS/NT/UNIX/OS2. Access control systems and disk drive locks.

MICROCOMPUTER APPLICATIONS

3167 E. Otero Circle, Littleton, CO 80122 1-800-4KEYLOK (303) 770-1917 FAX: (303) 770-1863

Inquiry 688.

SOFTWARE PACKAGING

FREE SOFTWARE

PACKAGING CATALOG Everything you will need to Package, Distribute, and Ship You Softwarell From manuals and binders to mailers and shippers

LABELS . LABELS . LABELS For your diskettes, plain or custom printed dot matrix or laser printer ... free samples

· · · FREE CATALOG · · · Hice & Associates 8586 Monticello Dr., West Chester, OH 45069

Phone/Fax: 513-779-7977

Inquiry 689.

SOFTWARE REGISTRATION

REGISTRATION MANAGER is a powerful utility that provides for the automatic remote registration of your software. It can significantly (up to 100%) increase response rates. You select the level oncouragement, from gentle reminder to full copy protection. Also includes a database manager to keep track of your user demographics.

StanBrite SOFTWARE

124 Country Club, Stansbury Park, UT 84074 (801) 882-3546 fax +801-882-3017 E-mail: 72723.1157@compuserve.com

Inquiry 690.

SOFTWARE/BUSINESS

DATA ENTRY SOFTWARE

Full featured, heads-down data entry with two-pass verification, edit language, operator stats, much more! Designed for the PS/2®, PC, XT, AT or compatibles.

PCs from \$395 LAN version available FREE 30 day trial

Computer Keyes 21929 Makah Rd., Tel: 206/776/6443 206/776-7210 Woodway, WA 98020 LISA: 800/356-0203

SOFTWARE/ENGINEERING

Analog/Digital Simulation!! • Model Libraries, RF, Po • More Than 5000 parts

- Windows, NT, DOS
 Power Mac, Macintosh
 ISSPC4 Real Time SPICE
 Mixed Mode Simulation
 Waveform Analysis
 Full SPICE programs

Schematic Entry starting at \$95. Complete
New AHDL Modeling Kit!! systems, \$595-\$2595 P.O. Box 710 San Pedro, CA 90733-0710 (310)833-0710, FAX (310)833-9658 intusoft

Call for your Free Demo and information kit.

Inquiry 691.

ALLTED-All Technology Designer Electronics-Hydraulics-Pneumatics-Mechanics-Control

From schematic entry to optimum design in single or mixed technology • Steady state, Transient, Frequency, Fourier and MonteCarlo analyses • Plus high level operations of multivariant, worst case, sensitivity, optimal

tolerance assignment, multiple criteria optimization

Component libraries wicons, functions and parameters

Modular configuration + MORE • Cali for Demo

Tatum Labs, Inc. 1287 N. Sila Ridge, Ann Arbor, MI 48108 -8810 FAX 313-663-3640 313-663-8810

Inquiry 692.

SOFTWARE/GRAPHICS

New Version! AccuSoft Image Format Library 5.0

Programmers: Add support for 36 raster file formats instantly!

TIFF, JPEG, PCX, TARGA, DIB, DCX, GIF, BMP, WMF, PICT, WPG, EPS, Group 3, Group 4 New Formats: Photo CD, PhotoShop, ASCII, KoFax, RLE, LaserData, CALS, ATT, CLP, XWD, IMG, IFF, SUN, XBM, ICO, IOCA, CX2, XPM, CUT, Brooktrout, MAC, MSP.

Guaranteed to read all raster images in existence in the listed formats!

- Import, export, scanning, conversion, compression
 Printing, display, image processing

- Supports all languages
 Fax formats and multi-page images
- * Rolate, zoom, scale, color reduction
- ★ Thumbnails, sharpen, special-effects
 ★ Windows, NT, WinPro Gold 32, VBX, VBX32
 ★ Watcom, OS/2, MAC, UNIX, Clipper, FoxPro

AccuSoft Corp. Call 800-525-3577 TEL (508) 898-2770 FAX (508) 898-9662

Inquiry 693.

SOFTWARE/GRAPHICS

Autodesk's DWG OEM

- Programmers' Toolkit to Read/Write AutoCAD DWG & DXF Files.
 Object oriented, modular, database-like access to
- CAD data. View, Print, Plot and Pick Modules.
- ◆ Available for C/C++ for DOS, X-DOS, Windows, Sun, and other Unix systems

Autodesk OEM Sales

1301 Marina Village Parkway, Alameda, CA 94501 Phone: (510) 337-7203 Fax: (510) 523-2880

Inquiry 694.

DbCAD dev 1.3 DLLs
Create, select, edit, import (DXF, DWG), all the
AutoCAD 2D vector entities, in a graphics database
(DBF). Display raster images (RLC, RLE, BMP) on
which you can overlay vector drawings (DWG, WMF,
graphic DBF). Manage a graphic window (pan,
zoom, overview, pick). Print by using Windows
driver and fonts.

Channel inc. U.S.A. +617-863-0068

Inquiry 695.

CAD Developers Kit

TG-CAD Professional 5.5, a 'C' Win/DOS SDK. Read/Write/View PCX/GIF files & DXF to R12. Create onts & text. Ray Tracing & Shading. Hundreds of 2D & 3D routines. Comes as DOS Lib., Win Lib. & Win DLL. Source available. Free Technical White Paper available. Call or write today.

Disk Software, Inc., Box 941152 Plano, TX USA 75094-1152 800-635-7760, Fax 214-423-7288

Inquiry 696.

"LEADTOOLS does image manipulation and does it right!" BYTE Me

Discover what Kodak, Corel, Delrina and over 2500 developers, publishers and OEMs already know: LEAD offers the fastest and most complete image compression and manipulation SDK on the market.

Three Toolkits In Onei

Introducing LEADTOOLS version 5, offering three toolkits for the price of one: 1) image format support, conversion and compression, 2) image processing and, 3) all NEW BITONAL toolkit. Includes royalty-free runtime, virtual memory management for unlimited image size, free technical support, online help, sample programs with source code, over 40 image processing functions, and CMP, the virtually lossless image

Call today for FREE imaging application built with LEADTOOLS 5!

800-637-1835



900 Baxter Street • Charlotte NC 28204 • 704-332-5632 Fax 704-372-8161

Inquiry 697.

SOFTWARE/SCIENTIFIC

VT_FX Scientific Desktop Publishing

- Scalable Fonts Font effects Typeface customization
 Equations Tables Graphics Foreign languages
 Multi-lingual spell & hyphenation IDE On-line help
 Dos, Dos-32 and Windrows versions From \$199
 TEX of Tomorrow"—Notices of AMS, March 1991
 Call now for a FREE DEMO DISK

MicroPress, Inc. 68-30 Harrow Street, Forest Hills, NY 11375

Tel (718) 575-1816 Fax (718) 575-8038

Inquiry 698.

SOFTWARE/SCIENTIFIC

EXPERIMENTAL DATA FITTING

SCIENTIST™ is the leader in experimental data fitting. Fit combinations of user-defined algebraic and differential equations or Laplace transforms also splines and interpolating functions. Includes 3D plotting and a scientific worksheet. Requires Windows. \$395. Model libraries also available.

MicroMath Scientific Software 1-800-942-6284 Fax: (801) 943-0299

Inquiry 699.

SOFTWARE/VOICE/FAX

Computer Telephony 'C' Libraries Multi-Voice V4.0 and Multi-Fax V2.0 Toolkits give you the most powerful solution to integrate telephony to your 'C' applications. Unique design based on multi-tasking: DOS Extender; Supports most major voice and fax boards; Commented source code; Royalty free; Best value. Also available: Windows based application generator

ITI SOFTWARE

Tel: 514-835-3124 Fax: 514-835-4772 BBS: 514-835-5945 Fax-On-Demand: 514-835-2216, E-mail: ggagnon@cam.org Check our home page: http://www.cam.org/~ggagnon

UNIX FOR PCS

INUX

RELEASE 1.1

32 bit Unix compatible OS for 386, 486, 586's

Includes C, C++, Oby C, Pascal, smalltalk, Perl,X11 R6, TCP/IP, There is a summary of the state of the state

Linux Systems Labs, 49884 Miller Ct. Chesterfield, MI 48017 (800) 954-2938, (810) 716-1700, fax (810) 716-1703

Inquiry 700.

VIDEO CARDS

VANTED

RASTEROP 1425 TC 24-BIT FRAMEBUFFER CARDS

new or used

Contact: Linda Greene 800-323-4449 In Europe Contact: Doris Baschek 41-64-54 0154

WINDOWS

*FREE INTERNET 217-322-1111

Full Access 14.4K 8/N/1 All Nodes Service is FREE 'You Pay L.D. Charge

Voice Help 1-217-322-1212

Inquiry 701.

THE ULTIMATE BBS FREE FREE FREE FREE FREE FREE

Latest Windows and DOS Utils, Pgms, Source Code, Lively CHAT, online games, Internet Access and more and all FREE. Call from home or office up to 14.4K and download for FREE. (n/8/1)

217-792-3663

Customer Service 415-281-4429

Inquiry 702.

A Message to Our **Subscribers**

rom time to time we make the BYTE subscriber list available to other companies whose products or services would be of interest to our readers. We take great care to screen these companies, choosing only those who are reputable.

Furthermore, subscriber names are made available for direct mail purposes only; telemarketing calls are strictly prohibited.

Many BYTE subscribers appreciate this carefully managed program, and look forward to receiving information of interest to them via the mail. While we believe this information is of benefit to our subscribers, we firmly respect the wishes of any subscriber who does not want to receive promotional literature. Should you wish to restrict the use of your name, please send your request (including your magazine mailing label, name, address, and subscription account number) to:

BYTE Magazine Subscriber Services PO Box 555 Hightstown, NJ 08520



Because the Experts decide.

ADVERTISER CONTACT INFORMATION

To order products or request FREE information, call advertisers directly or send in the response card by mail or fax! Let them know you saw it in BYTE!

inquir	y No. P	age No.	Phone No.	inquiry	No. Pag	go No.	Phone No.	Inquiry	No. Pag	e No.	Phone No.
	A						ext 3080		W.T. 0000		ext 3507
203-204	ACI	292	800-983-1177	67	COREL STOCK PHOTO LIBRARY	35	613-728-0826	l :	INTEL CORP	8-9	800-538-3373
				land.			ext 3080		INTEL CORP	119	800-538-3373
546	ACTION	40IS 22	+886-3-4520697**	68	COREL VENTURA 5	61	613-728-0826	402-403	INTERGRAPH CORP	200DM 2	800-345-4856
198	ADVANCED ENGINEERING	202	240 270 4400				ext 3080	515-516	INTERGRAPH CORP (INT'L)	65	205-730-5499
404 400	CONCEPTS	292	310-379-1189		CORPORATE UPGRADES	291	800-240-6190	151	IO TECH	289	216-439-4091
	ADVANCED MICRO DEVICES (N	•	800-222-9323	554	CPU & MEMORY				IPS-INTERACTIVE PRODS & SER!	V 141	800-555-1205
	AERONICS INC	17	512-258-8040)	EXCHANGE CLUB	280NE 2	408-654-9090	98-99	ITERATED SYSTEMS	86	800-437-2285
61	ALADDIN KNOWLEDGE SYSTI		800-223-4277	556	CPU & MEMORY						
549	ALTEX ELECTRONICS	280NE 3	800-531-5369		EXCHANGE CLUB	28050 2	408-654-9090		J		
551	ALTEX ELECTRONICS	280SO 1	800-531-5369	100	CREATIVE LABS INC	58	800-998-5227		JDR MICRODEVICES	285	800-538-5000
•	AMERICA ONLINE (U.S.)	40A-B	800-827-6364	257	CREATIVE MINDS	124	800-701-0689	152	JENSEN TOOLS	289	602-968-6231
	AMERICAN LUNG ASSOC	280NE 4		128-129	CYBEX CORP	271	205-430-4030**	132	DEMOCIN TOOLS	200	002-300-0231
	AMERICAN LUNG ASSOC	280SO 4		130-131	CYBEX CORP	277	205-430-4030**		K		
9	AMERICAN POWER CONVERS			505-508	CYBEX CORP (INT'L)	CIII	205-430-4030**	450			
62	AMERICAN POWER CONVERS		800-800-4APC					153	KILA	289	303-444-7737
-	TIME TOTAL CONTENT	31011 82.00	dept A2		D			73-74	KINGSTON TECHNOLOGY	90	800-435-0670
208-209	ANDOR	287	800-750-4650	267	DALLAS SEMICONDUCTOR	176	800-258-5061		KINGSTON TECHNOLOGY	184	800-251-9058
,	ANTHRO CORP	126	800-325-3841		DATA COMMUNICATIONS (INT'L		000 250 5001	408	KL GROUP	200DM B	800-863-4723
	APPLE COMPUTER INC	103	800-909-0260		DATA COMMUNICATIONS (INT'L						
409				1 .			000 007 0004		L		
	ARTECON	200DM 22	800-872-2783			DM 18A-B	800-637-8034	145-146	L A TRADE	280	800-433-3726
261-262	ATTACHMATE	170	800-426-6283			200DM 17	800-537-8034	221-222	LAHEY COMPUTER SYSTEMS	162	800-548-4778
	17.7.0.00.00		ext 322	132	DATALUX CORP	270	800-DATALUX	245	LANSOURCE TECHNOLOGY	140	416-535-3555
110	AT&T GLOBAL INFO	40.44	000 417 110		DATAPRO ON FAX	178			LEXMARK	69	800-891-0399
	SOLUTIONS (N.A.)	48-49	800-447-1124	•	DATAPRO (INT'L)	48-49	800-328-2776				8x1 232
140	AVALAN TECHNOLOGY		ext 1050	216-217	DATAPRODUCTS	117	800-980-0374	271	LIIKKUVA SYSTEMS INT'L	181	916-676-0676
140	AVALAN TECHNOLOGY	281	508-429-3179**	260	DATASONIX	110	800-328-2779		LUNAR ENERGY CO	40IS 20	817-387-MOON
	R			•	DELL COMPUTER CORP	98-99	800-247-5531				220,
000	DARKED ADMINISTED				DELL COMPUTER CORP (N.A.)	CVI	800-433-2973	1	M		
268	BADGER COMPUTER	183	800-3-BADGER		DELL COMPUTER CORP (N.A.)	CVII	800-733-2782	533-534		ADIC 3	+49-7254-983290**
112	BBN SOFTWARE PRODUCTS	(N.A.) 87	800-331-2266		DELL COMPUTER CORP (N.A.)	CVIII	800-433-3498				
	25115 - 112155555 - 111		ext 130		DELL COMPUTER CORP	0.141	000 400 0430	517	MAGIC / MSE (INT'L)	109	+972-3-751-1901"
406-407	BEAME & WHITESIDE S/W	200DM 15	800-216-8450	I	(N.A., F1000)	CVI	800-225-4898	120-121	MAXTECH / GVC (N.A.)	229	201-579-3630
63-64	BELL & HOWELL INC (INT'L)	37	708-675-7600		DELL COMPUTER CORP	0	000 EED 4030		MCGRAW-HILL BOOKSTORE	252	212-512-4100
63-64	BELL & HOWELL INC (N.A.)	37	800-SCAN-494	1	(N.A., F1000)	CVIII	800-437-0210		MCGRAW-HILL ON-LINE (INT'L)	129	
450	BIX	305	800-695-4775	218	DELPHI INTERNET SERVICES	172	800-695-4005	•	MCGRAW-HILL		
195-196		291	800-762-5757	69	DELRINA WIN FAX PRO	70	800-268-6082		PUBLICATIONS (INT'L)	128	
526	BTC (INT'L)	166	+886-2-523-3114**		DIGIBOARD	200DM 5		250	MEGAHERTZ CORP (N.A.)	109	800-LINKING
114	BTG	238	703-876-1920**				800-551-4794	251	MEGAHERTZ CORP (N.A.)	111	800-LINKING
	BUSINESS WEEK (INT'L)	43			DIGITAL INFO SERVICE (EUROP			111	MENAI CORP	253	800-GAMELON
•	BYTE 20TH ANNIVERSARY	257		529	DISTINCT CORP	40IS 14	408-366-8933	265	MICRO 2000	175	800-864-8008
	BYTE BACK ISSUES (INT'L)	42		133	DISTRIBUTED PROCESSING TE		800-322-4378	263-264	MICRO SOLUTIONS COMP PROD	179	800-295-1214
	BYTE BACK ISSUES (WORLD)			192-193	DTC ELECTRONICS HUNGARY	291	+36-27-387-292**	168-169	MICROCAL SOFTWARE INC	294	800-969-7720
	BYTE EDITORIAL SURVEY	196			=			223-224	MICROGRAFX	133	800-877-3040
	BYTE EURODECK (INT'L)	104			E			266	MICRO-INTERNATIONAL INC	180	800-967-5667
	BYTE MOBILE OFFICE	104		521	ECEL (DIGICOM) (INT'L)	123	+886-2-772-3407°°	101	MICRON COMPUTER	CII-1	208-465-3434
	SWEEPSTAKES (U.S.)	199		522	ECEL (DIGICOM) (INT'L)	125	+886-2-772-3407**		MICROSOFT CORP	2-3	800-719-5577
283	BYTE ON CD ROM	248		178	EDUCALC	291	800-713-6525		morrosor i com	2.0	ext NYY
203			200 004 0505	507	ELIASHIM MICROCOMPUTERS	40/5 21	813-744-5177	154	MICROSTAR LABORATORIES	289	206-453-2345
	BYTE REPRINTS (WORLD)	40IS 19	603-924-2525	185-186	ELMA ELECTRONIC	290	510-656-3400		MICROWAY	151	508-748-7341
	BYTE SUB MESSAGE	299		187	EMATEK GMBH	294	+49 221 529666	202	MICRO/SYS	292	818-244-4600
	BYTE WAREHOUSE	261			EUROSOFT TECHNOLOGY		+44 1635 582 660	518			+49-511-7404-401
	BYTE WINBOOK SWEEPSTAK			508	EUTRON	40IS 12		274	MINOLTA GMBH (EUROPE)		
167	BYTECH BUSINESS SYSTEMS	294	914-354-8666	70-71	EXABITE CORP	19			MIPS DATALINE AMERICA INC	178	800-898-8560
	C			70-71	EXIDITE COM	10	000 17010111	525	MITAC INTERNATIONAL CORP (P	41 L) /5	+886-2-5018231
	•				F			225	MITSUBISHI MOTOR		200 551 (170)
143	CADSOFT COMPUTER INC	275	407-274-8355	507 COn	E & LL CILEU ATIONS (INTEL)	44	91 19 197 5161		SALES OF AMERICA (N.A.)	104-105	800-55MITSU
282	CALIFORNIA DIGITAL	174	310-217-1944		F & H SIMULATIONS (INT'L)		+31 13 427 516"	76	MKS / MORTICE KERN SYSTEMS	250	519-884-2251
105	CALIFORNIA PC PRODUCTS I		800-394-4122		FAST HARDLOCK		+49-89-539800-20	226	MOTOROLA	142-143	800-894-7353
542-543	CALLUNA TECHNOLOGY LTD	40IS 18	+44(0)1592 630920**		FAST MULTIMEDIA		+49-89-50206-199**		M		
206-207	CAMELEON TECHNOLOGY IN	C 291	800-440-7466	275	FEDCO ELECTRONICS	176			1		
122-123	CANON (N.A.)	42-43	800-962-2708	520	FIRST INTERNATIONAL COMP	40tS 8		•	NANAO USA CORP (N.A.)	164	310-325-5202
524	CARDIFF SOFTWARE	40IS 20	619-259-6445		FIRST SOURCE INT'L	286		155	NATIONAL INSTRUMENTS	293	512-794-0100
501	CHERRY			535	FISKARS POWERS SYSTEMS (II		+358 0 452661		NEVADA COMPUTER	282	800-982-2925
	MIKROSCHALTER GMBH	4015 15-17	+49-9643-18-206	186	FUZIWARE INC	294	800-472-6183	256	NEXGEN	163	408-435-0202
194	CLARK DEVELOPMENT CO IN	C 292	800-356-1686		•			78	NIKKEI BUSINESS PUB	186	610-941-9600
•	COLORADO MEMORY SYSTE		800-451-0907		G			227-228	NORTON-LAMBERT	137	805-964-6767
540-541	COMBYTE INC (INT'L)	CIV	303-229-0660	149	GAGE APPLIED SCIENCES INC	289	514-337-6893	77	NSTL	233	610-941-9600
65	COMPAQ (N.A.)	12-15	222 220 0000	•	GATEWAY 2000	25-27	800-846-4289	550		280NE 1	800-996-DATA
213	COMPAQ (N.A.)	128-129	800-853-9518		GATEWAY 2000	120-121	800-846-2058	205	N.J.I.T.	293	201-596-3366
	COMPEX INC (INT'L)	87	714-630-7302	173-174	GRANITE DIGITAL	290			_	200	201 000-0000
214	COMPUSERVE (CD)	155	800-487-0952	511	GREY MATTER LTD (INT'L)	111			0		
214					GVC CORP (INT'L)		+886-2-704-0338*	191	OBJECT MANAGEMENT LAB	294	800-6789-OML
617	COMPUSERVE (INTL)	155	614-529-1349	Out-state		104		131	OBJECT WORLD (CD & INT'L)	199	+49-6173-2852
24.6	COMPUSERVE (U.S. & CD)	154A-B	555 457 155		Н			106	OBJECTS INC	44	
214	COMPUSERVE (U.S.)	155	800-487-4838		HEWLETT-PACKARD	31	800-964-1066				508-777-2800
281	COMPUTER ASSOCIATES	73	800-434-REAL	;	HEWLETT-PACKARD	55		513	OLIVETTI S.P.A. (INTL)	12-13	+39-2-45361
C.C.	REALIA		dept 26500		HOOLEON CORP			512	OLIVETTI S.P.A. (INTL)		+39-2-4836-2920
66	COMPUTER ASSOCIATES/	21	800-225-5224	150		290		523	ON TIME MARKETING	40IS 23	+49-40-437472
	VISUAL OBJECT	UP BY	dept 14500	530	HYPERSYSTEMS	4015 23	+39-11-434-2350	156-157	OPUS SYSTEMS	287	408-562-9340
204 225			800-438-5336		I .			•	ORACLE CORP	80-81	800-492-9870
284-285	COMPUTER DISCT WAREHSE		800-959-4CDW	1	•						ext 4981
126	COMPUTER DISCOUNTERS	28050 3	301-595-0500	•	IBM	56-57	800-IBM-4FAX	272-273	ORCHESTRA MULTISYSTEMS	182	800-237-9988
126 553		200DM 21		113	IBM (N.A.)	38-39	800-IBM-3333		OSBORNE MCGRAW-HILL	152-153	800-822-8158
126 553	COMPUTER MUSEUM		*** *** ***				ext FA101		_		
126 553	COMPUTER QUICK	40IS 13	415-861-8330								
126 553		40IS 13 278	800-526-3482	412-413	ICL (EMBLA)	200DM 7	703-648-3326**		P		
126 553 •	COMPUTER QUICK		800-526-3482		ICL (EMBLA) ICONOVEX INC (N.A.)	200DM 7 75		147	PACIFIC COAST MICRO	276	619-581-6040
126 553 504 127	COMPUTER QUICK COMPUTERLANE UNLTD COMPUTING MCGRAW-HILL	278 221	800-526-3482 212-512-4100	108-109				147 79	-	276 203	
126 553 504 127 75	COMPUTER QUICK COMPUTERLANE UNLTD COMPUTING MCGRAW-HILL CONNER PERIPHERALS (N.A.	278 221) 63	800-526-3482 212-512-4100 800-6-CONNER	108-109	ICONOVEX INC (N.A.)	75	800-943-0292 508-256-4624		PACIFIC COAST MICHO		619-581-6040 800-742-8086 ext PD
126 553 504 127 75 115	COMPUTER QUICK COMPUTERLANE UNLTD COMPUTING MCGRAW-HILL	278 221	800-526-3482 212-512-4100	108-109 175-176	ICONOVEX INC (N.A.) IMAGRAPH CORP	75 291	800-943-0292 508-256-4624		PACIFIC COAST MICHO PANASONIC COMMUNICATIONS		800-742-8086

ADVERTISER CONTACT INFORMATION

Inquir	y No.	Page No.	Phone No.	Anquitry	No. I	age No.	Phone No.	Inquir	y No.	Page No.	Phone No.
80	PERSOFT INC	247	800-368-5283	161	SEALEVEL SYSTEMS INC	287	803-843-4343	237-238	UNLIMITED SYSTEMS	138	619-622-140
158	PERSONAL TEX	294	800-808-7906	179-180	SHAFFSTALL CORP	292	800-248-3475		11		
519	PHILIPS MONITORS (INT'L)	22-23	431 40 73 39 83"°	171-172	SIGMA TECH SOFTWARE	288	818-368-6132		V		
81-82	PINNACLE MICRO	7	714-727-3300	•	SILICON GRAPHICS (N.A.)	67	800-800-7441	163	VIDEX INC	287	503-758-052
83	PKWARE INC	214	414-354-8699				ext D440	239-240	VIEWSONIC	139	800-888-8583
84	PKWARE INC	251	414-354-8699		SILICON WAREHOUSE	287	800-347-4887		***		
•	PROFOUND (N.A.)	123	800-688-5583	197	SILICONRAX	289	800-700-8560		W		
241-242	PROXIMA CORP	130	800-447-7694	88	SOFTWARE SECURITY	46	203-656-3932**		WALKER, RICHER & QUINN	47	206-217-7100
107	PSI (N.A.)	65	800-PSI-0852		SOFTWAY AMERICA INC	46	303-670-5345	94	WATCOM C/C++10.0	29	519-886-3700
		-	PC#00140		SOLID COMPUTER GMBH		+49-89-3159146**	269-270	WIBU (INT'L)	181	+49-721-93172-22**
	0				SPSS INC	205	800-543-5835	269-270	WIBU (U.S.)	181	301-570-3497
				170	STAR GATE TECHNOLOGIES	288	800-782-7428	102	WINBOOK (N.A.)	- 11	
229	ONX SOFTWARE SYSTEMS I	TD 158	800-676-0566	210-211	STARTECH COMPUTER PRO	288	800-265-1844	164	WINTEK CORP	292	
			ext 1006				ext 231	142	WORLDWIDE TECHNOLOGIE	S 284	
159	QUALSTAR CORP	292	800-468-0680	91	STATSOFT	193	918-583-4149		1.00	-	C10 0LL 0110
		200DM 8A-B	800-824-5545		SUN MICROSYSTEMS	294	508-442-0011**		X		
	QUANTUM CORP	200DM 9	800-624-5545	96-97	SYMANTEC	93	800-488-9914 ext 5518	544-545	XEROX IMAGING SYSTEMS (INT'L) 63	+44 1734 261913**
	QUARTERDECK OFFICE SYS		310-392-9851	96-97	SYMANTEC	95	800-628-4777		_		
85-86	QUATECH INC	266	800-553-1170	30-31	SIMALUES	33	ext 9AP2		Z		
	R				-			95	ZEOS INTERNATIONAL	88-89	800-554-5226
					I			165	Z-WORLD ENGINEERING	292	916-757-3737
	RACAL AIRTECH (CD & INT'L)		+44-(0)1844-201832**	243-244	TADPOLE TECHNOLOGY	161	800-232-6656				
87	RAINBOW TECHNOLOGIES	53	800-852-8569	200-201	TALKIE	293	800-TALKIE-4	* Corres	pond directly with company.		
414	RAVE COMPUTER ASSOC	2000M 18	800-966-RAVE	162	TALKING TECHNOLOGY INC	289	800-685-4884		ntes FAX Number		
181-182	RCI	288	800-RCI-8090	183-184	TAPEDISK CORP	290	800-827-3372		al Edition Definitions:		
	05000000		ext 71	552	TELEDAPTER SYSTEMS INC	280SO 3	800-997-7762		is only appear in Canada Editio		
141	RECORTEC INC	283	800-729-7654	234-235	TEXAS INSTRUMENTS	112-113	800-TI-TEXAS		ts only appear in Demographic		
160	RHETOREX INC	288	408-370-0881	254-255	TEXAS MICRO	146	713-541-8200		E - Ads only appear in Europe		
138-139	ROSE ELECTRONICS	281	800-333-9343	236	TOSHIBA AMERICA INC	134-135	800-457-7777		- Ads only appear in Internation		
404-405	ROSS TECHNOLOGY INC	2000M 15	800-774-7877	166	TRI VALLEY TECHNOLOGY IN	C 289	510-447-2030	MW-A	ds only appear in Midwest Reg	on Edition	
	S			410-411	TRITEAL CORP	200DM 13	800-874-8325		ds only appear in North Americ		
258-259	SAMSONITE (N.A.)	166	800-955-4001		U				ls only appear in Northeast Reg Is only appear in Pacific Coast I		_
	SAMTRON DISPLAYS INC (N.		310-537-7000	199	UNITED EDUCATION CTRS	293	800-877-4889		is only appear in Pacific Coast i Is only appear in Southern Reg		
	SCEPTRE TECHNOLOGIES	144	800-788-2878	199	ONITED EDUCATION CIRS	253	eut 28		ds only appear in U.S. Edition	UTI LUNUUTI	
144	SCITECH INTERNATIONAL	279	800-622-3345		UNDOWORLD OPEN	200006 19	044 20		- Ads only appear in World Ed	ition	

BYTE ADVERTISING SALES STAFF

Diane Lieberman, Director, Sales Operations, One Phoenix Mill Lane, Peterborough, NH 03458, Tel. (603) 924-2518, Fax: (603) 924-2683

NEW ENGLAND
ME. NH, Upstate NY, VT, MA, FI, CT,
ONTARIO
CANADA & EASTERN CANADA
Sanford L. Fibish (617) 860-6344
Merie Middle (617) 860-6221
McGraw-Hill Publications

EAST COAST NY, NYC, NJ, DE, DC, MD, PA, VA Michael Feinberg (212) 512-4811 Susan Rasbellini (617) 860-6265 McGraw Hill Publications 1221 Avenue of Americas—28th Floor New York, NY 10020 FAX: (212) 512-2075

SOUTHEAST
NC, SC, GA, FL, AL, TN, MS, AR, LA, KY, W/
MaryAnn Goulding (404) 843-4782
Maryot L. Swanson (603) 924-2651
McGraw-Hill Publications
4170 Asthord-Dunwoody Rd., Suite 520
Attachs, GA 30319

MIDWEST IL, MO, KS, IA, ND, SD, MN, WI, NE, IN, MI, OH Lon Salversien (614) 899-4908 Ed Ware (603) 924-2664 McGraw-Hill Publications 921 Eastwind Drive, Suite 118 Westerville, OH 43081

SOUTHWEST, ROCKY MOUNTAIN CO, OK, TX Jonnifer Walker (214) 701-8496 Kevin Lary (603) 924-2527 McGraw-Hill Publications 14850 Quorum Dr., Suite 380

MORTH PACIFIC NORTHERN CA, OR, ID, MT, WY, UT Roy J. Kops (415) 513-6861 James Bail (603) 924-2662 SILICON VALLEY, HI, WA, AK, W. CANADA Susan Werner (415) 513-6862 James Bail (603) 924-2662 McGraw-Hill Publications 1900 O'Farrell Street, Suite 200 San Mateo, CA 94403

SOUTH PACIFIC ORANGE COUNTY SAN DIEGO COUNTY Beth Dudas (714) 753-8140 Mark Sperso (714) 753-8140 Brad Duxon (603) 904-2574 McGraw-Hill Publications 15635 Alton Pixey, Suite 290 Invine, CA 92718 FAX: (714) 753-8147

Peterborough, NH Office: Inside Sales FAX: 603-924-2683 Advertising FAX: 603-924-7507

BYTE Deck Brian Higgins (603) 924-2596 BYTE Publications One Phoenix Mill Lane Peterborough, NH 03458

EURO-DECK Joseph Mabe (603) 924-2533 BYTE Publications One Phoenix Mill Lane Peterborough, NH 03458

INTERNATIONAL ADVERTISING SALES STAFF

Gary Lucas, European Sales Director, 34 Dover Street, London W1X 4BR, England, Tel. +44 171 4956780, Fax: +44 171 4956734

UNITED KINGDOM, BENELUX Gary Lucas (+44 171 495 6790) Jorathan McGowan (+44 171 495 5781) McGraw Hill Inc. McGraw-Hill Inc. 34 Dover St. London W1X 4BR England FAX: +44 171 4956734

GERMANY, SWITZERLAND, AUSTRIA AUSTRIA
Jürgen Heise
McGraw-Hill Inc.
Liebigstrasse 19
D-60323 Frankfurt
Germany
Tel: +49 69 7140 7140
FAX: +49 69 7140 7146

Subscription Customer Service

For a New Subscription U.S. 1-800-257-9402 Outside U.S. +1-609-426-5526

U.S. 1-800-232-2983

Outside U.S. +1-609-426-7676

ITALY, FRANCE, SPAIN, PORTUGAL, SCANDENAYIA Zena Coupé, Amanda Blaske A-Z International Sales Ltd. 70 Chalk Farm Road London NW1 BAN England Tel: +44 171 2843171 FAX: +44 171 2843174

Dan Aronovic DARA International 41 Ravutski Ra'anana 43220 Israel Tel: +972 9 919544 FAX: +972 9 981934 TAIWAN Talwan
Janet Wang
Third Wave Publishing Corp.
2nd FL, No. 19-2, Lane 231
Fu Hsing North Road
Taipei 105
Teiwan R.O.C.

HONG KONG Zoe Yen Third Wave Publishing Corp. Unit 2, 6F Hing Wah Center 82-84 To Kwa Wan Road Kowtoon, Hong Kong Tet: +852 784 3830 FAX: +852 764 3857

JES Moda Internations 6th FL, Donghye Bidg. 47-16, Myungil-Dong Kangdong-Gu Seoul 134-070, Korea Tel: +82 2 4813411 FAX: +82 2 4813414

JAPAN Masaid Mori Transworld Media Inc. 702, 2-26-3 Nishigotanda Shiragawa-ku, Tokyo 141 Japan Tel: +81 3 33887466 FAX: +81 3 37880674

A. Suzuld Nexus, Inc. 2-35-8, Unoki, Ota-ku Tokyo 146 Japan Tel: +81 3 37573721 FAX: +81 3 37572268

AUSTRALIA Phil Bush National Advertising Services 7-13 Parraween Street Cremorne NSW 2090, Tel: +61 2 908 9329

SINGAPORE, INDIA, INDONESIA, PAKISTAN, PHILIPPINES, OTHER ASIAN AND PACIFIC COUNTRIES AMD PACERIC COUNTERES Jenny Kao Third Wave Publishing Corp. 2nd Fl., No. 19-1, Lane 231 Fu Hsing North Road Taipei 105, Taiwan R.O.C. Tel: +886 2 7136959 ext. 226 FAX: +886 2 7189467

H.K. Lim Servex (Malaysia) Sdn. Bhd. 5th Floor, Bena Tower 160, Jalan Ampang 50450 Kuala Lumpur Malaysia Tel: +60 3 2624592

INDEX TO ADVERTISED PRODUCTS

For FREE product information from individual advertisers, circle the corresponding inquiry numbers on the response card!

To receive information for an entire product category, circle the category number on the response card!

	ry Ne.		Catego	•		Catego		
Inquiry	No. F	Page No.	Inquiry	No.	Page No.	Inquiry	No.	Page No
		_	156-157	OPUS SYSTEMS	287	525	MITAC INTERNATIONAL CORP (INT'L)	7
Н	ARDWARE		147	PACIFIC COAST MICRO	276	148	PC'S COMPLEAT	272-27
	AND WAILE		148	PC'S COMPLEAT	272-273	246-247	SCEPTRE TECHNOLOGIES	14
			414	RAVE COMPUTER ASSOCIATES	200DM 18	243-244	TADPOLE TECHNOLOGY	16
1	ACCESSORIES/SUPPLIE	ES	141	RECORTEC INC	283	234-235	TEXAS INSTRUMENTS	112-113
103-104	AERONICS INC	17		SILICON GRAPHICS (N.A.)	67	236	TOSHIBA AMERICA INC	134-135
208-209	ANDOR	287	197	SILICONRAX	289	102	WINBOOK (N.A.)	11
	ANTHRO CORP	126	243-244	TADPOLE TECHNOLOGY	161	95	ZEOS INTERNATIONAL	88-81
275	FEDCO ELECTRONICS	176	166	TRI VALLEY TECHNOLOGY INC	299	-		00-0
258-259	SAMSONITE (N.A.)	166	95	ZEOS INTERNATIONAL	88-89	14	MAIL ORDER	
230-233	SAMSONITE (N.A.)	100	33	ZEOG HATEHIANTIONAL	00-03	549	ALTEX ELECTRONICS	280NE :
2	ADD-IN BOARDS		6	DATA ACQUISITION		551	ALTEX ELECTRONICS	280SO
206-207	CAMELEON TECHNOLOGY INC	291	149	GAGE APPLIED SCIENCES INC	289	126	COMPUTER DISCOUNT WAREHOUSE	268-266
400-401	DIGIBOARD	200DM 5	175-176	IMAGRAPH CORPORATION	291	127	COMPUTERLANE UNLTD	271
192-193	DTC ELECTRONICS HUNGARY	291	151	IO TECH	289	226	MOTOROLA	142-14
175-176	IMAGRAPH CORPORATION	291	154	MICROSTAR LABORATORIES	299	136-137	NEVADA COMPUTER	283
156-157	OPUS SYSTEMS	287	85-86	QUATECH INC	266	148	PC'S COMPLEAT	272-27
85-86			254-255	TEXAS MICRO	146	142	WORLDWIDE TECHNOLOGIES	284
	QUATECH INC	266	234-233	TEXAS MICHO	140	192		
161	SEALEVEL SYSTEMS INC	287	53	DIAGNOSTIC EQUIPI	MENT	15	MEMORY/CHIPS/UP	GRADES
189-190	SILICON WAREHOUSE	287	152	JENSEN TOOLS	289	124-125	ADVANCED MICRO DEVICES	22-2
170	STAR GATE TECHNOLOGIES	288	265	MICRO 2000	175	206-207	CAMELEON TECHNOLOGY INC	291
162	TALKING TECHNOLOGY INC	289	203			554		280NE 2
3	BAR CODING		7	DISK & OPTICAL DR	IVES	556	CPU & MEMORY EXCHANGE CLUB	280NE 2
		100	409	ARTECON	2000M 22		CPU & MEMORY EXCHANGE CLUB	
163	VIDEX INC	297	403	COLORADO MEMORY SYSTEMS		134-135	FIRST SOURCE INT'L	280
					195		INTEL CORPORATION	8-0
4	COMMUNICATIONS/		115	CONNER PERIPHERALS (N.A.)	63	219-220	KINGSTON TECHNOLOGY	184
			177	CONTROL CONCEPTS INC	290		L A TRADE	280
	NETWORKING		173-174	GRANITE DIGITAL	290	256	NEXGEN	163
549	ALTEX ELECTRONICS	280NE 3	73-74	KINGSTON TECHNOLOGY	90	404-405	ROSS TECHNOLOGY INC	2000M 10
551	ALTEX ELECTRONICS	290SO 1	219-220	KINGSTON TECHNOLOGY	184	142	WORLDWIDE TECHNOLOGIES	284
261-262	ATTACHMATE	170	263-264	MICRO SOLUTIONS COMP PROD	179			
213	COMPAQ (N.A.)	128-129	79	PANASONIC COMMUNICATIONS & SYS	STEMS 203	16	MISCELLANEOUS	
216-217	DATAPRODUCTS	117	81-82	PINNACLE MICRO	7		HARDWARE	
192-193	DTC ELECTRONICS HUNGARY	291		QUANTUM CORPORATION	2000M 9			
•	IBM	56-57	8	DICKETTER (DUDI IO	ATORC	282	CALIFORNIA DIGITAL	174
219-220	KINGSTON TECHNOLOGY	184	8	DISKETTES/DUPLICA	410K5	105	CALIFORNIA PC PRODUCTS INC	254
250	MEGAHERTZ CORPORATION (N.A.)	109	103-104	AERONICS INC	17	553	COMPUTER DISCOUNTERS	280SO 3
251	MEGAHERTZ CORPORATION (N.A.)	111				72	INTEGRAND RESEARCH	213
550	NYNEX MOBILE COMMUNICATIONS	280NE 1	10	GRAPHICS TABLETS	/MICE/	147	PACIFIC COAST MICRO	270
156-157	OPUS SYSTEMS	287		PEN INPUT	,,	17	MODEME /MILLTIDLES	VODE
181-182		288				11	MODEMS/MULTIPLE)	LUKS
160	RHETOREX INC		•	IPS-INTERACTIVE PRODUCTS & SERV	ICES 141	•	JDR MICRODEVICES	285
138-139	ROSE ELECTRONICS	288	11	KEYBOARDS		120-121	MAXTECH / GVC (N.A.)	225
		281				250	MEGAHERTZ CORPORATION (N.A.)	109
171-172	SIGMA TECH SOFTWARE	288	526	BTC (INT'L)	166	251	MEGAHERTZ CORPORATION (N.A.)	111
252-253	SOLID COMPUTER GMBH	157	501	CHERRY MIKROSCHALTER GMBH	40IS 16-17	170	STAR GATE TECHNOLOGIES	281
170	STAR GATE TECHNOLOGIES	288	132	DATALUX CORPORATION	270	552	TELEDAPTER SYSTEMS INC	280SO :
	STARTECH COMPUTER PRODUCTS	288	185-186	ELMA ELECTRONIC	290	237-238	UNLIMITED SYSTEMS	138
162	TALKING TECHNOLOGY INC	289	150	HOOLEON CORPORATION	290	40	MONITORE & TERLET	
237-238	UNLIMITED SYSTEMS	138	183-184	TAPEDISK CORPORATION	290	18	MONITORS & TERMIN	IALS
5	COMPUTER SYSTEMS		10	LAN HADDWADE		546	ACTION	40IS 22
_			12	LAN HARDWARE		282	CALIFORNIA DIGITAL	174
110	AT&T GLOBAL INFO SOLUTIONS (N.A.)	48-49	502-503	COMPEX INC (INT'L)	87	132	DATALUX CORPORATION	270
114	BIG	238	128-129	CYBEX CORPORATION	271	531-532	GVC CORP (INT'L)	164
66	COMPAQ (N.A.)	12-15	130-131	CYBEX CORPORATION	277		MAXTECH/GVC (N.A.)	225
213	COMPAQ (N.A.)	128-129	505-506	CYBEX CORPORATION (INT'L)	CIN		NANAO USA CORP (N.A.)	164
132	DATALUX CORPORATION	270	134-135	FIRST SOURCE INT'L	286	272-273	ORCHESTRA MULTISYSTEMS	182
•	DELL COMPUTER CORP	98-99	550	NYNEX MOBILE COMMUNICATIONS	280NE 1	519	PHILIPS MONITORS (INT'L)	22-23
•	DELL COMPUTER CORP (N.A.)	CIII					SAMTRON DISPLAYS INC (N.A.)	125
•	DELL COMPUTER CORP (N.A.)	CIV	13	LAPTOPS & NOTEBO	UKS		VIEWSONIC	139
538-539	DIGITAL INFORMATION SERVICE (EUROPE)	40IS 7		APPLE COMPUTER INC	103	-	The state of the s	
	GATEWAY 2000	26-27	268	BADGER COMPUTER	183	19	MULTIMEDIA/CD-RON	VI .
•	GATEWAY 2000	120-121	279-280	CORPORATE UPGRADES	291	195-196	BOXLIGHT CORPORATION	291
	IBM	56-57	521	ECEL (DIGICOM) (INT'L)	123	100	CREATIVE LABS INC	58
113	IBM (N.A.)	38-39	522	ECEL (DIGICOM) (INT'L)	125		DTC ELECTRONICS HUNGARY	291
113	INTEGRIX INC (INT'L)	229	178	EDUCALC	291		FAST MULTIMEDIA	100
	INTEL CORPORATION	8-9	275	FEDCO ELECTRONICS	176		IMAGRAPH CORPORATION	29
514								
514		289	520	FIRST INTERNATIONAL LANGUITED			DDOVINA CODDODATION	
514 153	KILA	289 C#-1	520	FIRST INTERNATIONAL COMPUTER	40IS 8	241-242	PROXIMA CORPORATION	130
514 * 153 101	KILA MICRON COMPUTER	CH-1		INTEL CORPORATION	119	241-242	PROXIMA CORPORATION SILICON GRAPHICS (N.A.)	67
514 153 101 256	KILA		•			57		

INDEX TO ADVERTISED PRODUCTS


anquay.	ry No.	Page No.	Catego		Page No.	Catego		Page No.
					-			
20	PRINTERS/PLOTTERS		227-228	NORTON-LAMBERT	137	523	ON TIME MARKETING	40IS 23
282	CALIFORNIA DIGITAL	174		ORACLE CORPORATION	80-81	96-97	SYMANTEC	93
122-123	CANON (N.A.)	42-43	80	PERSOFT INC	247	96-97	SYMANTEC	95
216-217	DATAPRODUCTS	117	200-201	TALKIE	293	94	WATCOM C/C++10.0	29
•	HEWLETT-PACKARD	31		WALKER, RICHER & QUINN	47	41	SECURITY	
•	HEWLETT-PACKARD	55	28	DATA ACQUISITION		61	ALADDIN KNOWLEDGE SYSTEMS	82
	LEXMARK	69	155	NATIONAL INSTRUMENTS	293	267	DALLAS SEMICONDUCTOR	176
518	MINOLTA GMBH (EUROPE)	408S 19			250	507	ELIASHIM MICROCOMPUTERS	40IS 21
513	OLIVETTI S.P.A. (INT'L)	12-13	29	DATABASE		508	EUTRON	40IS 12
			281	COMPUTER ASSOCIATES/REALIA	73	509-510	FAST HARDLOCK	40IS 5
21	PROGRAMMABLE		530	HYPERSYSTEMS	40IS 23	557-558	RACAL AIRTECH (CD & INT'L)	213
			517	MAGIC / MSE (INT'L)	109	87	RAINBOW TECHNOLOGIES	53
	HARDWARE			ORACLE CORPORATION	80-81	88	SOFTWARE SECURITY	46
509-510	FAST HARDLOCK	40IS 5				269-270	WIBU	181
•	JDR MICRODEVICES	295	30	EDUCATIONAL		4=	HAIIV	
202	MICRO / SYS	292	205	N.J.I.T.	293	45	UNIX	
87	RAINBOW TECHNOLOGIES	53	199	UNITED EDUCATION CENTERS	293	406-407	BEAME & WHITESIDE SOFTWARE	200DM 15
269-270	WIBU	181	24	ENGINEEDING (COIEN	TIFIO	•	DATA FOCUS	200DM 17
165	Z-WORLD ENGINEERING	292	31	ENGINEERING/SCIEN	IIFIC	529	DISTINCT CORPORATION	40IS 14
=0	DAID DOUG ADDANG		536-537	EUROSOFT TECHNOLOGY	401S 24	402-403	INTERGRAPH CORPORATION	200DM 2
56	RAID DRIVE ARRAYS		527-528	F&H SIMULATIONS (INT'L)	11	515-516	INTERGRAPH CORPORATION (INT'L)	55
133	DISTRIBUTED PROCESSING TECH	274	511	GREY MATTER LTD (INT'L)	111	408	KL GROUP	200DM 8
20	COANNEDC (OOD (DIE	ITITEDE	98-99	ITERATED SYSTEMS	86	116-117	SOFTWAY AMERICA INC	46
22	SCANNERS/OCR/DIG		158	PERSONAL TEX	294	410-411	TRITEAL CORPORATION	200DM 13
63-64	BELL & HOWELL INC	37	20	PAITPOTAINMENT		46	UTILITIES	
52	SECURITY		32	ENTERTAINMENT				
			257	CREATIVE MINDS	124	61	ALADDIN KNOWLEDGE SYSTEMS	82
198	ADVANCED ENGINEERING CONCEPTS	292	-	OD A DIMOC		257	CREATIVE MINDS	124
501	CHERRY MIKROSCHALTER GMBH	40ES 16-17	33	GRAPHICS		265	MICRO 2000	175
507	ELIASHIM MICROCOMPUTERS	40IS 21	215	COREL FLOW	127	83	PKWARE INC	214
509-510	FAST HARDLOCK	408S 5	67	COREL STOCK PHOTO LIBRARY	35	84	PKWARE INC	251
87	RAINBOW TECHNOLOGIES	53	68	COREL VENTURA 5	61	230-231	QUARTERDECK OFFICE SYSTEMS	114
269-270	WIBU	181	187	EMATEK GMBH	294	183-184	TAPEDISK CORPORATION	290
00	TARE DOUGE		223-224	MICROGRAFX	133	47	WINDOWS	
23	TAPE DRIVES		274	MIPS DATALINE AMERICA INC	178			-
103-104	AERONICS INC	17	•	NANAO USA CORP (N.A.)	164	112	BBN SOFTWARE PRODUCTS (N.A.)	87
540-541	COMBYTE INC (INT'L)	CIV	241-242	PROXIMA CORPORATION	130	529	DISTINCT CORPORATION	40IS 14
284-285	COMPUTER CONNECTIONS INT BV	156	-	******		188	FUZIWARE INC	294
115	CONNER PERIPHERALS (N.A.)	63	35	MAIL ORDER		412-413	ICL (EMBLA)	200DM 7
260	DATASONIX	110	126	COMPUTER DISCOUNT WAREHOUSE	268-269	108-109	ICONOVEX ING (N.A.)	75
70-71	EXABYTE CORPORATION	19	504	COMPUTER QUICK	40IS 13	111	MENAI CORPORATION	253
263-264	MICRO SOLUTIONS COMP PROD	179				168-169	MICROCAL SOFTWARE INC	294
159	QUALSTAR CORP	292	36	MATHEMATICAL/			NANAO USA CORP (N.A.)	164
179-180	SHAFFSTALL CORP	292	30			102	WINBOOK (N.A.)	11
183-184	TAPEDISK CORPORATION	290		STATISTICAL		48	WORD PROCESSING	DTP
04	UDC /DOW/FD MANAG	FRAFAIT	511	GREY MATTER LTD (INT'L)	111	108-109	ICONOVEX INC (N.A.)	75
24	UPS/POWER MANAG	EMENI	158	PERSONAL TEX	294		XEROX IMAGING SYSTEMS (INT'L)	63
203-204	ACI	292	276-278	SPSS INC	205	311313	ACTION INVICTION (INVICT)	
62	AMERICAN POWER CONVERSION	32-33	91	STATSOFT	193			
535	FISKARS POWERS SYSTEMS (INT'L)	67	-	MARKET LANGOUS COL	-	11 67	ENERAL	
547-548	LUNAR ENERGY CO	40IS 20	37	MISCELLANEOUS SOI	TWARE			
		_	523	ON TIME MARKETING	40tS 23	49	DOONE (BURLIOATION	16
	OFTWARI		38	ON-LINE SERVICES		49	BOOKS/PUBLICATION	13
	ULIVANI						BUSINESS WEEK (INT'L)	43
			•	AMERICA ONLINE (U.S.)	40A-B	•	BYTE 20TH ANNIVERSARY	257
	BUSINESS		450	BIX	305	•	BYTE BACK ISSUES (WORLD)	40IS 7
25			214	COMPUSERVE	155		BYTE BACK ISSUES (INT'L)	42
25		97		DES DE DE PRESENTA DE LA COMPANIONE DE L			BYTE EURODECK (INT'L)	
112	BBN SOFTWARE PRODUCTS (N.A.)	87	218	DELPHI INTERNET SERVICES	172	•		104
112 524	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE	40IS 20	218	PROFOUND (N.A.)	123	283	BYTE ON CD ROM	248
112 524 271	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIKKUVA SYSTEMS INTERNATIONAL	40tS 20 181					BYTE ON CD ROM COMPUTING MC GRAW-HILL	
112 524 271 533-534	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIBRUVA SYSTEMS INTERNATIONAL MACON	40IS 20 181 40IS 2	218	PROFOUND (N.A.) PSI (N.A.)	123 65	283		248
112 524 271 533-534 223-224	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIIIGUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX	40IS 20 181 40IS 2 133	218	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS	123 65	283	COMPUTING MC GRAW-HILL	248 221
112 524 271 533-534 223-224 241-242	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIIKGUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION	40IS 20 181 40IS 2 133 130	218 • 107 39	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICROSOFT CORPORATION	123 65 2-3	283	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INT'L)	248 221 14-15
112 524 271 533-534 223-224	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIIKGUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION	40IS 20 181 40IS 2 133	218 • 107 39 • 229	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICROSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD	123 65 2-3 158	283	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INT'L) DATA COMMUNICATIONS (N.A.)	248 221 14-15 105
112 524 271 533-534 223-224 241-242	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIBRUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INT'L)	40IS 20 181 40IS 2 133 130	218 • 107 39 • 229 230-231	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICROSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD QUARTERDECK OFFICE SYSTEMS	123 65 2-3 158 114	283	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INT'L) DATA COMMUNICATIONS (N.A.) DATAPRO (INT'L)	248 221 14-15 105 48-49
112 524 271 533-534 223-224 241-242 544-645	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIBRUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INTL) CAD/CAM	40IS 20 181 40IS 2 133 130 63	218 • 107 39 • 229	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICROSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD	123 65 2-3 158	283	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INT'L) DATA COMMUNICATIONS (N.A.) DATAPRO (INT'L) MCGRAW-HILL BOOKSTORE	248 221 14-15 105 48-49 252
112 524 271 533-534 223-224 241-242 544-545 26 143	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIIKQUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INT'L.) CAD/CAM CADSOFT COMPUTER INC	40IS 20 181 40IS 2 133 130 63	218 107 39 229 230-231 410-411	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICHOSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION	123 65 2-3 158 114	283	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INT'L) DATA COMMUNICATIONS (N.A.) DATAPRO (INT'L) MCGRAW-HILL BOOKSTORE MCGRAW-HILL ON-LINE (INT'L)	248 221 14-15 105 48-49 252 129
112 524 271 533-534 223-224 241-242 544-645	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIBRUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INTL) CAD/CAM	40IS 20 181 40IS 2 133 130 63	218 • 107 39 • 229 230-231	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICROSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD QUARTERDECK OFFICE SYSTEMS	123 65 2-3 158 114	283	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INT'L) DATA COMMUNICATIONS (N.A.) DATAPRO (INT'L) MCGRAW-HILL BOOKSTORE MCGRAW-HILL ON-LINE (INT'L) MCGRAW-HILL PUBLICATIONS (INT'L)	248 221 14-15 105 48-49 252 129
112 524 271 533-534 223-224 241-242 544-545 26 143 154	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIKKUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INTL) CAD/CAM CADSOFT COMPUTER INC WINTEK CORP	40IS 20 181 40IS 2 133 130 63	218 107 39 229 230-231 410-411	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICHOSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION PROGRAMMING	123 65 2-3 158 114 2000M 13	283 75	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INT'L) DATA COMMUNICATIONS (N.A.) DATAPRO (INT'L) MCGRAW-HILL BOOKSTORE MCGRAW-HILL ON-LINE (INT'L) MCGRAW-HILL PUBLICATIONS (INT'L) OSBORNE MCGRAW-HILL SUN MICROSYSTEMS	248 221 14-15 105 48-49 252 129 128 152-153
112 524 271 533-534 223-224 241-242 544-545 26 143	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIIKQUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INT'L.) CAD/CAM CADSOFT COMPUTER INC	40IS 20 181 40IS 2 133 130 63	218 107 39 229 230-231 410-411	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICHOSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION PROGRAMMING LANGUAGES/TOOLS	123 55 2-3 158 114 2000M 13	283	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INT'L) DATA COMMUNICATIONS (N.A.) DATAPRO (INT'L) MCGRAW-HILL BOOKSTORE MCGRAW-HILL ON-LINE (INT'L) MCGRAW-HILL PUBLICATIONS (INT'L) OSBORNE MCGRAW-HILL SUN MICROSYSTEMS MISCELLANEOUS	248 221 14-15 105 48-49 252 129 128 152-153 294
112 524 271 533-534 223-224 241-242 544-545 26 143 154	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIKKUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INTL) CAD/CAM CADSOFT COMPUTER INC WINTEK CORP	40IS 20 181 40IS 2 133 130 63	218 107 39 229 230-231 410-411 40	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICHOSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITTEAL CORPORATION PROGRAMMING LANGUAGES/TOOLS BEAME & WHITESIDE SOFTWARE	123 65 2-3 158 114 2000M 13	283 75	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INTL) DATA COMMUNICATIONS (IN.A.) DATAPRO (INTL.) MCGRAW-HILL BOOKSTORE MCGRAW-HILL OH-LINE (INTL.) MCGRAW-HILL PUBLICATIONS (INTL.) OSBORNE MCGRAW-HILL SUN MICROSYSTEMS MISCELLANEOUS AMERICAN LUNG ASSOCIATION	248 221 14-15 106 48-49 252 129 129 152-153 294
112 524 271 533-534 223-224 241-242 544-545 26 143 164	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIIKUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INT'L.) CAD/CAM CADSOFT COMPUTER INC WINTEK CORP COMMUNICATIONS/ NETWORKING	40IS 20 181 40IS 2 133 130 63 275 282	218 107 39 229 230-231 410-411 40 406-407 167	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICROSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION PROGRAMMING LANGUAGES/TOOLS BEAME & WHITESIDE SOFTWARE BYTECH BUSINESS SYSTEMS	123 65 2-3 158 114 2000M 13	283 75	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INT'L) DATA COMMUNICATIONS (INT'L) DATAPRO (INT'L) MCGRAW-HILL BOOKSTORE MCGRAW-HILL ON-LINE (INT'L) MCGRAW-HILL ON-LINE (INT'L) OSBORNE MCGRAW-HILL SUN MICROSYSTEMS MISCELLANEOUS AMERICAN LUNG ASSOCIATION AMERICAN LUNG ASSOCIATION	248 221 14-15 105 48-49 252 129 128 152-153 294 280NE 4 280SO 4
112 524 271 533-534 223-224 241-242 544-545 26 143 164 27	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIBRUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INTL) CAD/CAM CADSOFT COMPUTER INC WINTEK CORP COMMUNICATIONS/ NETWORKING ATTACHMATE	40(\$\frac{20}{181}\$ 40(\$\frac{2}{2}\$ 133 130 63 275 292	218 107 39 229 230-231 410-411 40 406-407 167 66	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICROSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION PROGRAMMING LANGUAGES/TOOLS BEAME & WHITESIDE SOFTWARE BYTECH BUSINESS SYSTEMS COMPUTER ASSOCIATES/VISUAL OBJECT	123 65 2-3 158 114 2000M 13 2000M 15 2000M 15 294 CTS 21	283 75	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INT'L) DATA COMMUNICATIONS (N.A.) DATAPRO (INT'L) MCGRAW-HILL BOOKSTORE MCGRAW-HILL ON-LINE (INT'L) MCGRAW-HILL PUBLICATIONS (INT'L) OSBORNE MCGRAW-HILL SUN MICROSYSTEMS MISCELLANEOUS AMERICAN LUNG ASSOCIATION AMERICAN LUNG ASSOCIATION BYTE EDITORIAL SURVEY	248 221 14-15 105 48-49 252 129 128 152-153 294 280NE 4 280SO 4
112 524 271 533-534 223-224 241-242 544-545 26 143 164 27	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LINKUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INTL) CAD/CAM CADSOFT COMPUTER INC WINTEK CORP COMMUNICATIONS/ NETWORKING ATTACHMATE AVALAN TECHNOLOGY	40(S 20 181 40(S 2 2 133 130 63 275 292	218 107 39 229 230-231 410-411 40 406-407 167 66 187	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICHOSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD QUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION PROGRAMMING LANGUAGES/TOOLS BEAME & WHITESIDE SOFTWARE BYTECH BUSINESS SYSTEMS COMPUTER ASSOCIATES/VISUAL OBJECT EMATEK GMBH	123 65 2-3 158 158 2000M 13 2000M 15 294 CTS 21 294	283 75	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INTL) DATA COMMUNICATIONS (INA.) DATAPRO (INTL.) MCGRAW-HILL BOOKSTORE MCGRAW-HILL ON-LINE (INTL.) OSBORNE MCGRAW-HILL SUN MICROSYSTEMS MISCELLANEOUS AMERICAN LUNG ASSOCIATION AMERICAN LUNG ASSOCIATION BYTE EDITORIAL SURFVEY BYTE MOBILE OFFICE SWEEPSTAKES (I	248 221 14-15 105 48-49 252 128 152-153 294 280NE 4 280SO 4 196
112 524 271 533-534 223-224 241-242 544-545 26 143 164 27 251-262 140 405-407	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LINKUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INTL.) CAD/CAM CADSOFT COMPUTER INC WINTEK CORP COMMUNICATIONS/ NETWORKING ATTACHMATE AVALAN TECHNOLOGY BEAME & WHITESIDE SOFTWARE	40IS 20 181 40IS 2 133 130 63 275 282 170 281 2000M 15	218 107 39 229 230-231 410-411 40 406-407 167 66 187 511	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICHOSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION PROGRAMMING LANGUAGES/TOOLS BEAME & WHITESIDE SOFTWARE BYTECH BUSINESS SYSTEMS COMPUTER ASSOCIATES/VISUAL OBJECT EMATEK GAMBH GREY MATTER LTD (INTL)	123 65 2-3 158 114 2000M 13 2000M 15 294 CTS 21 294	283 75	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INTL) DATA COMMUNICATIONS (IN.A.) DATAPRO (INTL) MCGRAW-HILL BOOKSTORE MCGRAW-HILL OH-LINE (INTL) MCGRAW-HILL PUBLICATIONS (INTL) OSBORNE MCGRAW-HILL SUN MICROSYSTEMS MISCELLANEOUS AMERICAN LUNG ASSOCIATION BYTE EDITORIAL SURVEY BYTE MOBILE OFFICE SWEEPSTAKES (I BYTE REPRINTS (WORLD)	248 221 14-15 106 48-49 252 128 152-153 294 280NE 4 280SO 4 196 U.S.) 199
112 524 271 533-534 223-224 241-242 544-545 26 143 164 27 261-262 140 406-407 194	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LIIKQUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INTL.) CAD/CAM CADSOFT COMPUTER INC WINTEK CORP COMMUNICATIONS/ NETWORKING ATTACHMATE AVALAN TECHNOLOGY BEAME & WHITESIDE SOFTWARE CLARK DEVELOPMENT CO INC	40IS 20 181 40IS 2 133 130 63 275 292 170 281 20004 15	218 107 39 229 230-231 410-411 40 406-407 167 66 187 511 118-119	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICROSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION PROGRAMMING LANGUAGES/TOOLS BEAME & WHITESIDE SOFTWARE BYTECH BUSINESS SYSTEMS COMPUTER ASSOCIATES/VISUAL OBJECT EMATEK GMBH GREY MATTER LTD (INTL.) INTEK TECHNOLOGIES	123 65 2-3 158 114 2000M 13 2000M 15 294 21 294 111 79	283 75	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INTL) DATA COMMUNICATIONS (IN.A.) DATAPRO (INTL) MCGRAW-HILL BOOKSTORE MCGRAW-HILL ON-LINE (INTL) MCGRAW-HILL ON-LINE (INTL) MCGRAW-HILL PUBLICATIONS (INTL) CSBORNE MCGRAW-HILL SUN MICROSYSTEMS MISCELLANEOUS AMERICAN LUNG ASSOCIATION AMERICAN LUNG ASSOCIATION BYTE EDITORIAL SURVEY BYTE MOBILE OFFICE SWEEPSTAKES (I BYTE REPRINTS (WORLD) BYTE SUB MESSAGE	248 221 14-15 105 48-49 252 129 128 152-153 294 280NE 4 280SO 4 196 40IS 19 299
112 524 271 533-534 223-224 241-242 544-545 26 143 164 27 261-262 140 406-407 194 502-503	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LINKUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INT'L) CAD/CAM CADSOFT COMPUTER INC WINTEK CORP COMMUNICATIONS/ NETWORKING ATTACHMATE AVALAN TECHNOLOGY BEAME & WHITESIDE SOFTWARE CLARK DEVELOPMENT CO INC COMPEX INC	40IS 20 181 40IS 2 133 130 63 275 282 170 281 2000M 15 282	218 107 39 229 230-231 410-411 40 406-407 157 66 187 511 118-119 221-222	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICROSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION PROGRAMMING LANGUAGES/TOOLS BEAME & WHITESIDE SOFTWARE BYTECH BUSINESS SYSTEMS COMPUTER ASSOCIATES/VISUAL OBJECT EMATEK GIMBH ORDER ORDER OFFICE OF TOOLS LANGUAGES	123 65 2-3 158 114 2000M 13 2000M 15 294 CTS 21 294 111 79	283 75	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INT'L) DATA COMMUNICATIONS (INT'L) DATAPRO (INT'L) MCGRAW-HILL BOOKSTORE MCGRAW-HILL ON-LINE (INT'L) MCGRAW-HILL PUBLICATIONS (INT'L) OSBORNE MCGRAW-HILL SUM MICROSYSTEMS MISCELLANEOUS AMERICAN LUNG ASSOCIATION BYTE EDITORIAL SURIVEY BYTE MOBILE OFFICE SWEEPSTAKES (I BYTE REPRINTS (WORLD) BYTE SUB MESSAGE BYTE WAREHOUSE	248 221 14-15 105 48-49 252 129 128 152-153 294 2800NE 4 280S 14 96 J.S.) 199 40IS 19 299 261
112 524 271 533-534 223-224 221-242 544-645 26 143 164 27 261-262 140 406-407 194 502-503 69	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LINKUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INTL) CAD/CAM CADSOFT COMPUTER INC WINTEK CORP COMMUNICATIONS/ NETWORKING ATTACHMATE AVALAN TECHNOLOGY BEAME & WHITESIDE SOFTWARE CLARK DEVELOPMENT CO INC COMPEX INC DELRINA WIN FAX PRO	40IS 20 181 40IS 2 133 133 63 275 292 170 281 2000M 15 292	218 107 39 229 230-231 410-411 40 406-407 167 66 187 511 118-119	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICHOSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION PROGRAMMING LANGUAGES/TOOLS BEAME & WHITESIDE SOFTWARE BYTECH BUSINESS SYSTEMS COMPUTER ASSOCIATESVISUAL OBJECT EMATEK GAMBH GREY MATTER LTD (INT'L) INTEK TECHNOLOGIES LAHEY COMPUTER SYSTEMS MAGIC / MSE (INT'L)	123 65 2-3 158 198 2000M 13 2000M 15 294 217 294 111 79 162 109	283 75 	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INTL) DATA COMMUNICATIONS (INTL) DATAPRO (INTL) MCGRAW-HILL BOOKSTORE MCGRAW-HILL DUBLICATIONS (INTL) MCGRAW-HILL PUBLICATIONS (INTL) MCGRAW-HILL PUBLICATIONS (INTL) MCGRAW-HILL PUBLICATIONS (INTL) MCGRAW-HILL SUN MICROSYSTEMS MISCELLANEOUS AMERICAN LUNG ASSOCIATION AMERICAN LUNG ASSOCIATION AMERICAN LUNG ASSOCIATION BYTE EDITORIAL SURVEY BYTE MOBILE OFFICE SWEEPSTAKES (I BYTE REPRINTS (WORLD) BYTE SUB MESSAGE BYTE WAREHOUSE BYTE WINBOOK SWEEPSTAKES (U.S.)	248 221 14-15 105 48-49 252 129 128 152-153 294 280NE 4 280SO 4 196 U.S.) 199 40IS 19 299 261 213
112 524 271 533-534 223-224 241-242 544-545 26 143 164 27 261-262 140 405-407 194 502-503 69 529	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LINKUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INTL.) CAD/CAM CADSOFT COMPUTER INC WINTEK CORP COMMUNICATIONS/ NETWORKING ATTACHMATE AVALAN TECHNOLOGY BEAME & WHITESIDE SOFTWARE CLARK DEVELOPMENT CO INC COMPEX INC DELRINA WIN FAX PRO DISTINCT CORPORATION	40IS 20 181 40IS 2 133 130 63 275 292 170 281 2000M 15 292 87 70 40IS 14	218 107 39 229 230-231 410-411 40 406-407 167 66 187 511 118-119 221-222 517	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICHOSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION PROGRAMMING LANGUAGES/TOOLS BEAME & WHITESIDE SOFTWARE BYTECH BUSINESS SYSTEMS COMPUTER ASSOCIATES/VISUAL OBJECT EMATEK GAMBH GREY MATTER LTD (INTL) INTEK TECHNOLOGIES LAHEY COMPUTER SYSTEMS MAGIC / MSE (INTL) MICHOWAY	123 65 2-3 158 114 2000M 13 2000M 15 294 211 79 162 109 151	283 75 	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INTL) DATA COMMUNICATIONS (INTL) DATAPRO (INTL) MCGRAW-HILL BOOKSTORE MCGRAW-HILL DUBLICATIONS (INTL) MCGRAW-HILL PUBLICATIONS (INTL) SUBORNE MCGRAW-HILL SUN MICROSYSTEMS MISCELLANEOUS AMERICAN LUNG ASSOCIATION AMERICAN LUNG ASSOCIATION BYTE EDITORIAL SURVEY BYTE MOBILE OFFICE SWEEPSTAKES (I BYTE REPRINTS (WORLD) BYTE SUB MESSAGE BYTE WAREHOUSE BYTE WINBOOK SWEEPSTAKES (U.S.) MITSUBISHI MOTOR SALES OF AMERICA	248 221 14-15 105 48-49 252 129 128 152-153 294 280NE 4 280SO 4 196 40IS 19 299 261 (N.A.) 104-105
112 524 271 533-534 223-224 241-242 544-545 26 143 164 27 251-262 140 406-407 194 502-503 69 134-135	BBN SOFTWARE PRODUCTS (N.A.) CARDIFF SOFTWARE LINKUVA SYSTEMS INTERNATIONAL MACON MICROGRAFX PROXIMA CORPORATION XEROX IMAGING SYSTEMS (INTL) CAD/CAM CADSOFT COMPUTER INC WINTEK CORP COMMUNICATIONS/ NETWORKING ATTACHMATE AVALAN TECHNOLOGY BEAME & WHITESIDE SOFTWARE CLARK DEVELOPMENT CO INC COMPEX INC DELRINA WIN FAX PRO	40IS 20 181 40IS 2 133 133 63 275 292 170 281 2000M 15 292	218 107 39 229 230-231 410-411 40 406-407 167 66 187 511 118-119 221-222	PROFOUND (N.A.) PSI (N.A.) OPERATING SYSTEMS MICHOSOFT CORPORATION ONX SOFTWARE SYSTEMS LTD OUARTERDECK OFFICE SYSTEMS TRITEAL CORPORATION PROGRAMMING LANGUAGES/TOOLS BEAME & WHITESIDE SOFTWARE BYTECH BUSINESS SYSTEMS COMPUTER ASSOCIATESVISUAL OBJECT EMATEK GAMBH GREY MATTER LTD (INT'L) INTEK TECHNOLOGIES LAHEY COMPUTER SYSTEMS MAGIC / MSE (INT'L)	123 65 2-3 158 198 2000M 13 2000M 15 294 217 294 111 79 162 109	283 75 	COMPUTING MC GRAW-HILL DATA COMMUNICATIONS (INTL) DATA COMMUNICATIONS (INTL) DATAPRO (INTL) MCGRAW-HILL BOOKSTORE MCGRAW-HILL DUBLICATIONS (INTL) MCGRAW-HILL PUBLICATIONS (INTL) MCGRAW-HILL PUBLICATIONS (INTL) MCGRAW-HILL PUBLICATIONS (INTL) MCGRAW-HILL SUN MICROSYSTEMS MISCELLANEOUS AMERICAN LUNG ASSOCIATION AMERICAN LUNG ASSOCIATION AMERICAN LUNG ASSOCIATION BYTE EDITORIAL SURVEY BYTE MOBILE OFFICE SWEEPSTAKES (I BYTE REPRINTS (WORLD) BYTE SUB MESSAGE BYTE WAREHOUSE BYTE WINBOOK SWEEPSTAKES (U.S.)	248 221 14-15 105 48-49 252 129 128 152-153 294 280NE 4 280SO 4 196 U.S.) 199 40IS 19 299 261 213

EDITORIAL INDEX

For more information on any of the companies covered in articles, columns, or news stories in this issue, circle the appropriate inquiry number on the response card. Each page number refers to the first page of the article or section in which the company name appears.

Inqui	ry No.	Page No.	Inquiry No.	Page No.	Inquiry	No.	Page No.	Inquity	No.	Page No.
	A		Dense-Pac N		1022	Logitech	40IS 15	1020	Psion Dacom	40IS 17
	Advanced Micro D	levices 24, 187	1327 Diamond Mu	Itimedia 258	1264	Los Altos	200DM 23	1339	PureData	260
1342		259	Systems Digicash	71	1001	Technologies Lotus Development	34, 215		Q	
	AER Energy Reso			ory Assistance 249	1260.	Lucas Management	264.	978	QNX Software Sys	tems 83
1005	Alcatel SEL	4015 3		ment 30, 131, 201,	1289		200DM 23		R	
1025 1265			-0	239, 40IS 3		M			Racotek	107
1205	American Technolo Labs	Ugy 2000M 23	Digital Resea		1012	Macon	40IS 9		RadioMail	107, 147
1138		a 217		mmunications 249	1032	Mannesmann Tally	40IS 18		Radius	25
1033			Display Tech		1013	Mapinfo	40IS 9		RAM Mobile Data	107
	Apex Data	159	1297 DSP Develop		10.0	Market Intelligence Res		1152	RSA Data Security	249
1137	Apexx Technology	259	DTK Duracell	201 131		MathWorks	34		S	
	Apple Computer	25, 59, 115,		131		Matra Telecommunicat	ion 40IS 3	1272	S&S Software Inte	mational 263
	131, 147, 243, 40		E			Matrox	25, 187	1338	SC&T International	259
1341			1334 Emulex	260	1118	Maxtech/GVC	234	1034	Scene Double	40IS 20
1293	Aptech Systems Archelon	264 36		wer Systems 131	1157	Medio Multimedia	40	1004	Scitor	214
1105		234	Epson 1146 EuroPak Inte	mational 171	1157,	Megahertz 159	9, 234, 249	1273	Serif	264
1028			_	inguonai iri	1277	Memco Software	263	1014	Sharp Electronics Siemens Nixdorf	40IS 9
	Ardis	107, 147	F	V		MetaCase Consulting	40IS 3	1014	Silicon Video	115
	Arithmos	115	FED	115	1119,	Microcom	234	1283	Softool	263
1149			First Data/No		1348			1141	Software AG of No	
1298		263	First Virtual	71 262, 200DM 23		Micrografx	34		America	
1150		mation 173	1267, Huke 1282	EUE, EUULMI ES		Micro International	201	1133	Sony Computer &	259
4000	Solutions Attanna Design	045	1048 Frax	40IS 22	1329	Micro Multimedia	260		Peripheral Produ	
1002	Athena Design ATI Technologies	215 25	Fujitsu Micro		4000	Micron Display Techno		,===	Sony Electronics	147
1343				ms Europe 40IS 18	1037	MicroProcessor	40IS 23	1266	Sophos	200DM 23
10-10	Austin Direct	201	Futaba	115		Engineering Microsoft 30, 34, 3	6, 41, 145,	1275	SPG	262
1259			FuziWare	34		147, 215, 241			Spry Staktek	28 197
	Technologies		G		1307	Microsystems Software		1305	Stalker Systems	263
1303		nce 263	1274 Galacticomm	265		MLL Software &	40IS 3	1010	Strategic Mapping	
	Systems		1155 Gateway 200			Computer Industries			Stylus Innovations	
	AVM Computersys	steme 40IS 3	General Mag		1295	Modatech Systems	265	1026	Summagraphics E	
	В		GeoWorks	147		Motif	100, 115	1258	Sun Microsystems	
	BellSouth Cellular	115	H				0, 107, 115			M 3, 200DM 23
	Benchmarq Micros		1111, Hayes Micro	computer 234	1120	Motorola ISG	234	1038	SuperMemo World	
1278		262	1112, Products	DOMPOLD LOT	1122	M-Systems Multi Tech Systems	187 234.	1124	Supra	234
1106			1113, 1346		1122, 1261, 1		200DM 23		SystemSoft	131
1107		234	1000, Hewlett-Paci		1201,	**	LUGUIN LU		T	
1108 1280		234 ware 262	1322	209, 258, 200DM 3		N		977,	Tadpole Technolog	gy 165,
1286			Hitachi Amer		1331	National Instruments	259	1005,		167, 40IS 15
1340			1269 Hummingbird			National Semiconducto NEC	30	1326	TapeWorks	258
1139		217	Communica Huntington A		1148	Network General	245	1333	Tatung Science &	258
	C		Huntington A Technology		1279	NeuralWare	264	1351	Technology TDK Systems	234
	_	20 115 124	HyperLogic	34	1	New World Media	28	1331	Tektronix	28
	Canon Computer Systems	28, 115, 131	· · · / porcogra	•	1	NexGen	24	1125.		234, 200DM 23
1109		gies 234	4444 (DM	E EO 100 107 100		Nielsen Media Research		1262		
	Casio	147	1114, IBM 2 1115	5, 50, 100, 107, 169, 234, 200DM 3		Northern Telecom	30	1276	TeleSensory	262
1337		260	IBM PC	30, 131	1255	Novell 215, 200DM 3,	200DM 23	1254	Tenon Intersystem	
	Centennial Techno	ologies 187	In Focus Sys			0			Texas Instruments	
	CE Software	107	Innovative Sc			Ocean Information Sys	tems 187	1006	3D/Eye	34
1011		40IS 9	1268, Integrix	259, 200DM 23		Oki Telecom	159	1006	Toshiba America	187, 201
1154 1031		249	1332			Open Market	71	1302	TTG	264
1031	Clarity Systems Coloray	40IS 17 115		24, 30, 131, 187, 241		Opti Computer	131		U	204
	Communication Int			strumentation 259	976	Optrex America Oracle 50	115 0, 107, 207	4004	_	
	Compaq Computer		1310 Interactive In Technologie		210		, 107, 207	1281	Unabridged Softwa Unlimited Systems	
	CompuServe	28	1027 Interlink Elec			P		1126,	U.S. Robotics	159 234
1046	Computers Unlimit	ted 40IS 24	1140 IQ Software	217	1024	Pacific Image Electroni		1127,		234
1147			1336 IsoBlock	260		Palm Computing	147		V	
	ConnectSoft	107	1296 Ivex Design I			Panasonic	131			
1156		249	1257 IXI	200DM 23	1335	Communications & Sy PDQ Peripherals	260	1308	Vireo Software	265
	Corel	34	J		1292	Peachtree Software	264	1306	VisualTools	264
	CPSI CPV Stollmann	115 40/S 3	1039 Joosen Softv	rare 40IS 24	1043	Phase One Denmark	40IS 23		W	
	Cray Research	197	Developme			Phoenix Technologies	131	1288	Waterloo Maple So	
1324				pment Group 262	1290	Pinnacle Publishing	262	4400	Wave Systems	71
	Cubic Memory	197	K		1301	Pinnacle Systems	263	1132 1040	Wavetek Wollongong Intern	259 ational 40/S 23
1110		234	Kingston Tec	hnology 197		International	445	1040	WordPerfect	34 abonai
	Cybercash	71	1270 The KL Grou		1344	Pixel International	115			34
	Сугіх	24	1285 Knozali Syste		1344	PixelVision Planar America	260 115		X	
	D		1330 KNX	259	1159	Plantronics	249	1036	Xara	40IS 21
	Dassault	40IS 3	Kopin	115	1291	The Plant Software	265		Xcelinet	107
	Telecommunicati	ion	Kyocera	115	1023	Plextor	40IS 15		Xerox	50
	Dataquest Europe		L			Positive Technologies	115		Z	
1325		258	1116 Lectron Prag	matic 234	1123,	Practical Peripherals	234	1128,	Zoltrix	234
1300		263	Lexmark	28	1350			1129	7	
	Dell Computer Delrina	131, 159 34	1153 Lexmark Inte		1319	ProtoView	265 147	1130 1263	Zoom Telephonics Zzyzx	234 200DM 23
			1117 Logicode Tec	chnology 234		Psion				

BIX: Your Coach to the Internet!



Give BIX a try with our new 5 for Free Offer! Join BIX today and get 5 hours of evening and weekend access for free! Take the rest of the calendar month to explore BIX, and then continue for our standard \$13 monthly membership fee. Further details and complete rate information are provided during registration. Using any communications program, dial 1-800-695-4882. At the "logon" prompt enter bix. Then at the "name?" prompt enter bix.byte39. If you have any questions, call us at 1-800-695-4775 (voice). Or fax us at 617-491-6642.

Send Internet mail to info@bix.com. Windows users can order BIXnav, our graphical interface for BIX, for easy point and click access. Details are available during registration.

The Internet connects you with more than 10 million people, at universities, companies, and other online services. Now, get full access to the Internet free of charge when you subscribe to BIX! You'll also get expert assistance from BIX moderators who can help you find your way around the Internet.

These experts can guide you through the many services and features available, and help you find the information you're looking for. Anytime you need help, just join our special 'internet' conference and get fast answers to your questions.

As you become more familiar with the Internet, you'll be able to download files from all over the world using FTP, connect to other sites and services through telnet, read and reply to Usenet Newsgroups, access utilities like finger and whois, and much more! BIX and the Internet together provide the largest and most effective technical resource for computing professionals.

And with over 600 local access numbers in the U.S., plus telnet access via the Internet, BIX makes it easy to connect. Try BIX today through our special 5 for Free offer - and become part of the top technical team!



ATM = After the Millennium

Are you holding your breath waiting for this next big thing? Better have a medical technician standing by.

re you getting as sick as I am of the daily announcements about ATM (asynchronous transfer mode) products? Or even worse, ATMenabled products, whatever they might be. I mean, is anyone except a few universities and corporate pioneers actually using this stuff now, for real-world applications, all the time?

Doesn't this look like déjà vu all over again? It's just like when ISDN was announced in the early 1980s. When everyone was talking breathlessly about the integration of the computer and the telephone. When IBM boughtand then divested-Rolm.

Lest we believe that ATM is right around the corner, think first of the problems of moving to ATM, or for that matter to any other all-encompassing megatechnology. Interoperability issues are huge (we still have major interoperability issues with ISDN after 10 years of a supposedly established standard).


The cost of the ATM stuff is disproportionately high, and so are the connection and transport prices (all of which have been major issues stalling ISDN). Skills in installing, using, maintaining, and debugging ATM are nonexistent in the marketplace at large and will be for many years (just like ISDN again, even in the telephone companies themselves). Add to that the complexity of ATM-only networks, let alone heterogeneous networks, including everything from X.25 to video-on-demand.

In any case, why do normal people need ATM anyway? Isn't there more than enough of a choice out there? Frame relay, fast Ethernet, SMDS (Switched Multimegabit Data Service), not to mention ISDN. Unless you're transferring the entire MGM film library to every branch office in the world every day, aren't these older technologies going to cover just about everything you expect to do over the next few years? Is ATM a solution in search of a problem?

Even if ATM finds that killer problem this week, how long is it going to take to become a well-established standard? The telephone companies haven't done that with ISDN in 10 years. Let's be optimistic and say the pace of change has doubled-it will still be five years at least before ATM is established.

So why do we need ATM now? Is it the new corporate MIS status symbol to show that we're with it? Is ATM just the latest shot in the eternal class war, this time played out in that new frontier called cyberspace?

In the real world, the success of a technology is not a function of its engineering elegance. Witness the Concorde 20 or so years on. Ultimately, the test is whether or



not the technology is appropriate-something we technofreaks tend to forget. ATM is clever. ATM is elegant. But is it appropriate? Right now it isn't.

What with the Internet, on-line services, and lots of PC-based communications methods and standards, cyberspace is fast becoming a protocol soup, where no one communications protocol dominates and newcomers are even less likely to do so. No one delivery protocol is going to take over the world of communications, nor should we want it to. We already have a delicious protocol soup with lots of ingredients that please many different palates. Some are gourmet, some are more basic. ATM is going to be just another, albeit gourmet, ingredient of the protocol soup, something to be enjoyed and savored by the technoliterati and the corporate titans while the peasants get by with the meat and potatoes of frame relay and ISDN.

The protocol soup that is communications today and tomorrow reflects a wide variety of demands and needs that the soup is by and large meeting. New ingredients will also be added: faster and longer Ethernets, ATM Lite, Son of Frame Relay, SMDS for TV, broad-ISDN, and so on. Each will meet the different needs of different users.

So you shouldn't just blindly jump on the ATM bandwagon. There's more to communications than fashion. Figure where you stand in the spectrum of needs and plan accordingly. Take into account the rich variety of existing methods that fit many needs very well and much more cheaply than ATM will. Leave the hard ATM stuff to others. Wait until it forms a real part of the communications environment and isn't just another brilliant but expensive technology waiting for its time in the sun.

Ted Prince is president of Perth Ventures and publisher of Technology Fundamentalist, a newsletter that covers "winners and losers in information technology." You can reach him on CompuServe at 74073,1236 or on the Internet or BIX at editors@bix.com.

BATTERY.

NOW ONLY


Dell[®] Latitude XP[™] IntelDX4™ 100MHz System

Business Lease : \$122/Mo.

- 9.5" Dual Scan Color
- 8MB RAM (36MB Max RAM)
- 340MB Removable Hard Drive (810MB Max)
- Smart Lithium Ion Battery with Advanced Power Management
- · 32-bit Local Bus Video, 1MB Video RAM

- 2 Type II/1 Type III PCMCIA Expansion Slots
- Preloaded Communications Software
- 5.9 Pounds
- 3-year Warranty
- · 30-day Money-back Guarantee'
- Optional Advanced Port Replicator Available
- **★Upgrade to 16MB RAM** for only \$499 more.

Order Code #600025



WORK LONGER WITH LITHIUM IN YOUR SYSTEM

It's amazing what a little lithium can do.

The Dell Latitude XP notebook is the first full-size notebook to introduce the smart lithium ion battery. This vastly superior technology instantly provides up to 30% more energy for the same weight as other batteries. Perhaps that's why Computerworld recently stated about the XP, "We have seen the future, and it's Lithium."

But our incredible battery life story goes beyond lithium ion. Our battery includes its own microprocessor that communicates with the CPU to optimize energy usage. You can fast charge in 1½ to 2 hours, even while you're using the Dell Latitude XP. And you never have to drain the battery before recharging.

Call today to order this sleek little six-pound notebook. You'll work such extended hours, your boss just might have you tested.

TO ORDER, CALL NOW.

Mon-Fri 7am - 9pm CT • Sat 10am - 6pm CT • Sun 12pm - 5pm CT In Canada; Call 800-668-3021 http://www.us.dell.com/

Keycode #01020

WORKS FAST PHONE NUM



Dell's featured computer artist is Daniel Fenelon.

NEW P120c WORKSTATION

Dell Dimension P120c

A Pentium^e Processor-based 120MHz System

- Updated Pentium Chip
- Mini Tower Model 16MB EDO Memory
- 1GB EIDE Hard Drive (10ms)
- 512KB Pipeline Burst Cache
- 17LS Monitor (17° CRT, NI)
- 9FX Motion PCI 2MB VRAM Video 4X Multi-session FIDE CD-ROM Drive
- Sound Blaster 16 Sound Card
- Altec Lansing ACS-5 Speakers MS Office 4.3, MS Bookshelf.
- Visio Express for MS Office

30 Days Free Support

- · 3.5" Diskette Drive
- Spacesaver Keyboard/Mouse MS-DOS 6.2/Microsoft Windows 3.1/

Business Lease: \$133/Mo. Order Code #500080

NEW P120c BEST BUY

Dell Dimension XPS P120c

A Pentium Processor-based 120MHz System

- Updated Pentium Chip
- Mini Tower Model
- 16MB EDO Memory
- 1GB EIDE Hard Drive (10ms)
- 256KB Pipeline Burst Cache
- 15LS Monitor (15" CRT, NI)
- 64-Bit PCI 1MB DRAM Video Card
- 4X Multi-session EIDE CD-ROM Drive MS Office 4.3, MS Bookshelf. Visio Express for MS Office
- 3.5° Diskette Drive
- Spacesaver Keyboard/Mouse
- MS-DOS 6.2/Microsoft Windows 3.1/ 30 Days Free Support

Business Lease: \$111/Mo. Order Code #500092

XPS P100c BEST BUY

Dell Dimension XPS P100c A Pentium Processor-based

100MHz System

- Updated Pentium Chip
- Mini Tower Model 8MB RAM
- . 1GB EIDE Hard Drive (10ms)
- 256KB Pipeline Burst Cache
- . 15LS Monitor (15" CRT, NI)
- 64-bit PCI 2MB DRAM Video Card
- 4X Multi-session EIDE CD-ROM Drive
- 3.5" Diskette Drive
- Spacesaver Keyboard/Mouse
- MS-DOS 6.2/Microsoft Windows 3.1/ 30 Days Free Support
- ★Add a Conner 200/400MB Tape Backup Unit for \$199 more.

P75 MULTIMEDIA OFFICE

Dell Dimension P75 A Pentium Processor-based

75MHz System

- Updated Pentium Chip
- Mini Tower Model
- · RMR RAM
- . 1GB EIDE Hard Drive (10ms)
- 256KB Writeback Cache
- 15LS Monitor (15" CRT, NI)
- 64-bit PCI 1MB DRAM Video
- 4X Multi-session EIDE CD-ROM Drive Sound Blaster 16 Sound Card
- Altec Lansing ACS-5 Speakers
- · MS-Office 4.3, MS Bookshelf,
- Visio Express for MS Office
- 3.5" Diskette Drive
- · Spacesaver Keyboard/Mouse
- MS-DOS 6.2/Microsoft Windows 3.1/ 30 Days Free Support

P90 WORKSTATION

Dell Dimension P90 A Pentium Processor-based 90MHz System

- Updated Pentium Chip
- Mini Tower Model
- 540MB Hard Drive (12ms)
- 256KB Writeback Cache
- 15LS Monitor (15" CRT, NI)
- 64-bit PCI 1MB DRAM Video
- 4X Multi-session EIDE CD-ROM Drive
- 3.5" Diskette Drive
- Spacesaver Keyboard/Mouse
- MS-DOS 6.2/Microsoft Windows 3.1/ 30 Days Free Support
- ★Increase your available resolution upgrade to 2MB DRAM for \$59 more.

P75 WORKSTATION

Dell Dimension P75

A Pentium Processor-based 75MHz System

- Updated Pentium Chip
- Mini Tower Model
- 8MB RAM
- 540MB Hard Drive (12ms)
- 256KB Writeback Cache
- 15LS Monitor (15° CRT, NI)
- 64-bit PCI 2MB DRAM Video
- 3.5" Diskette Drive
- Spacesaver Keyboard/Mouse
- MS-DOS 6.2/Microsoft Windows 3.1/ 30 Days Free Support
- ★Add a 3COM ELINK III Network Interface Card for \$124 more.

Business Lease: \$87/Mo.

Business Lease: \$81/Mo. Order Code #500084

Business Lease: \$70/Mo. Order Code #500085

Business Lease: \$61/Mo. Order Code #500086



Pricing is not discountable. "Guarantees available in the U.S. only for registered owners of Dell Dimension systems purchased after 8/1/93 and Dell Latitude systems purchased after 8 site service may not be available in certain remote lications. OBusiness leasing arranged by Leasing Group, Inc. *Prices and specifications valid in the U.S. only and subject to char Microsoft Corporation. FORTUNE 500 is a registered trademark and FORTUNE GLOBAL 500 is a trademark of the Time Inc. Magazine Corp. Back cover screen visual ©1995 E

R. COSTS LESS. ER AT BOTTOM.

XPS P100c WORKSTATION

Dell Dimension XPS P100c A Pentium Processor-based

- 100MHz System
- Updated Pentium Chip
 Mini Tower Model
- 16MB EDO Memory
- 1GB EIDE Hard Drive (10ms)
- 256KB Writeback Cache
- 15LS Monitor (15" CRT, NI)
- 64-Bit PCI 1MB DRAM Video Card
- 4X Multi-session EIDE CD-ROM Drive
- Sound Blaster 16 Sound Card
- Altec Lansing ACS-31 Speakers
- 3.5" Diskette Drive
- Spacesaver Keyboard/Mouse
- MS-DOS 6.2/Microsoft Windows 3.1/ 30 Days Free Support

\$2749

Business Lease: \$102/Mo. order Code #500093

466D WORKSTATION

Dell Dimension 466D IntelDX2™ 66MHz System

- 8MB RAM
- 365MB Hard Drive (12ms)
- . 15LS Monitor (15° CRT, NI)
- Accelerated Local Bus Video with 1MB DRAM
- 3.5" Diskette Drive
- Spacesaver Keyboard/Mouse
 MS-DOS 6 2/Microsoft Windows 3
- MS-DOS 6.2/Microsoft Windows 3.1/ 30 Days Free Support
- ★Add a 14.4 Fax/Modem for only \$99 more.

\$1299

Business Lease: \$48/Mo.

100MHz ONLY \$3299



Dell Latitude XP IntelDX4 100MHz System

- 9.5" Dual Scan Color
- 8MB BAM (36MB Max BAM)
- 340MB Removable Hard Drive (810MB Max)
- Smart Lithium Ion Battery with Advanced Power Management
- 32-bit Local Bus Video, 1MB Video BAM
- 5.9 Pounds
- · 3-year Warranty[†]
- 30-day Money-back Guarantee*
- Expansion Options Available

\$3299

Business Lease: \$122/Mo. Order Code #600025

ACTIVE MATRIX 100MHz

Dell Latitude XP IntelDX4 100MHz System

- 9.5" Active Matrix Color
- 8MB RAM (36MB Max RAM)
- 340MB Removable Hard Drive (810MB Max)
- Smart Lithium Ion Battery with Advanced Power Management
- 32-bit Local Bus Video, 1MB Video RAM
- 6.1 Pounds
- 3-year Warranty
- 30-day Money-back Guarantee
- · Expansion Options Available

\$4199

Business Lease: \$151/Mo.

75MHz COLOR UNDER \$2000



Dell Latitude[™] IntelDX4 75MHz System

- 9.5" Dual Scan Color
- 4MB RAM (20MB Max RAM)
- 260MB Upgradeable Hard Drive (524MB Max)
- \$99 more for 2nd NIMH Battery (Slides into floppy drive to achieve extended battery life)
- 32-bit Local Bus Video, 1MB Video RAM
- 6 Pounds
- 1-year Warranty[†]
- · 30-day Money-back Guarantee

\$1999

Business Lease: \$74/Mo. Order Code #600035

NEW 75MHz POWER

Dell Latitude

IntelDX4 75MHz System

- 9.5° Dual Scan Color
- 8MB RAM (20MB Max RAM)
- 524MB Upgradeable Hard Drive
- \$99 more for 2nd NiMH Battery (Slides into floppy drive to achieve extended battery life)
- 32-bit Local Bus Video, IMB Video RAM
- 6 Pounds
- 1-year Warranty
- 30-day Money-back Guarantee

\$2499

Business Lease: \$92/Mo.

DELL SPECS

Dell is a \$3.5 billion company and is a member of the FORTUNE GLOBAL 500.™ As a global company, we've sold over 3 million systems in over 120 countries. And 80% of the FORTUNE 500' and 50% of the FORTUNE GLOBAL 500 companies have done business with Dell.

For \$199, Dell's SelectCare program offers you 3-year, on-site service on all Dell Dimension desktops. That's 3 full years of next-business-day, at-your-desk, parts-and-labor (monitor, mouse and keyboard included) service...guaranteed.

100% money-back guarantee. If you're not fully satisfied, return within 30 days for a full refund of purchase price.

Dell's U.S. and European factories have both earned the ISO 9002 registration, ensuring consistent quality.

TO ORDER, CALL NOW.

800-433-2973

Mon-Fri 7am-9pm CT • Sat 10am-6pm CT Sun 12pm-5pm CT

In Canada*, Call 800-668-3021 In Puerto Rico*, Call 800-805-8030 (In Spanish and English) http://www.us.dell.com/

Keycode #01021



394. For a complete copy of our Guarantees or Limited Warranties, please write Dell Computer Corp., 2214 W Braker Lime, Building 3, Austin, TX 78758. Mon-site service provided by BancTec Service Corp. Onte without nonce. The Intel Inside logo and Pentium are registered trademarks and IntelDX2 and IntelDX4 are trademarks of Intel Corporation. MS-DOS, MS, Windows and Microsoft are registered trademarks of exercic Image, Inc. ©1995 Dell Computer Corporation. All rights reserved.

TECHNOSPEAK: 120MHz Pentium processor 16MB EDO memory 512KB pipeline burst SRAM cache 9FX Motion Video 4 PCI and 3 ISA slots

4x CD-ROM

To put it succinctly, it rips, sir

INTRODUCING
THE DELL DIMENSION
XPS P120c.

\$3699

Dell Dimension™ XPS P120c

A Pentium® Processor-based 120MHz System

Business Lease⁰: \$133/Mo.

- Updated Pentium Chip
- Mini Tower Model
- 16MB EDO Memory
- 1GB Enhanced IDE Hard Drive (10ms)
- 512KB Pipeline Burst SRAM Cache
- 17LS Monitor (17" CRT, NI)

- 9FX Motion PCI Graphics Accelerator with 2MB VRAM
- 4X Multi-session EIDE CD-ROM Drive
- Sound Blaster 16 Sound Card
 Altec Lansing ACS-5 Speakers
- MS* Office 4.3, MS Bookshelf, Visio Express for MS Office
- 3.5* Diskette Drive
- Spacesaver Keyboard/Mouse
- MS-DOS® 6.2/Microsoft®
- Windows 3.1/ 30 Days Free Support

Order Code #500080

512 R

The Dell Dimension XPS P120c combines a 120MHz Pentium chip with a 512k pipeline burst SRAM cache for spine-tingling throughput. Yes, cybernauts around the globe will have speed and

video performance rarely seen by beings in this vector. Which means desktop publishing, multimedia projects, database creation, spreadsheets, even code creating endeavors get done way fast. So just give the boss some bigwig mumbo-jumbo about enhanced Q3 profit margins or something. And then procure one, fellow traveler.

TO ORDER, CALL NOW.

800-433-3498

Mon-Fri 7am-9pm CT • Sui 10am-6pm CT • Sui 12pm-3pm CT In Canada, Call 800-668-3021 http://www.us.dell.com/

Keycode #01019

